EHRM INFRASTRUCTURE UPGRADES

1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

PROJECT #: 581-22-700



1 LOCATION MAP
NOT TO SCALE

2 FACILITY SITE PLAN
1" = 20'-0"

BUILDING TYPE

BUILDING 01S - LEVEL 00B - ADMIN
BUILDING 01S - LEVEL 00G - HEALTHCARE
BUILDING 01S - LEVEL 01 - HEALTHCARE
BUILDING 01S - LEVEL 02 - HEALTHCARE
BUILDING 01S - LEVEL 03 - HEALTHCARE
BUILDING 01S - LEVEL 04 - HEALTHCARE
BUILDING 01S - LEVEL 05 - HEALTHCARE
BUILDING 01S - LEVEL 06 - HEALTHCARE
BUILDING 01W - LEVEL 00B - ADMIN
BUILDING 01W - LEVEL 00G - ADMIN
BUILDING 01W - LEVEL 01 - HEALTHCARE
BUILDING 01W - LEVEL 02 - HEALTHCARE
BUILDING 01W - LEVEL 03 - HEALTHCARE
BUILDING 01W - LEVEL 04 - ADMIN
BUILDING 02 - LEVEL 00B - ADMIN
BUILDING 02 - LEVEL 01 - ADMIN
BUILDING 02 - LEVEL 02 - ADMIN
BUILDING 03 - LEVEL 01 - ADMIN
BUILDING 03 - LEVEL 02 - ADMIN
BUILDING 04 - LEVEL 00 - ADMIN
BUILDING 04 - LEVEL 01 - ADMIN
BUILDING 04 - LEVEL 02 - ADMIN
BUILDING 05 - LEVEL 00 - HEALTHCARE
BUILDING 05 - LEVEL 01 - HEALTHCARE
BUILDING 05 - LEVEL 02 - HEALTHCARE
BUILDING 06 - LEVEL 00 - HEALTHCARE
BUILDING 06 - LEVEL 01 - HEALTHCARE
BUILDING 06 - LEVEL 02 - HEALTHCARE
BUILDING 07 - LEVEL 00 - HEALTHCARE
BUILDING 07 - LEVEL 01 - HEALTHCARE
BUILDING 07 - LEVEL 02 - HEALTHCARE
BUILDING 07 - ATTIC - HEALTHCARE
BUILDING 08 - LEVEL 00 - ADMIN
BUILDING 08 - LEVEL 01 - ADMIN
BUILDING 08 - LEVEL 02 - ADMIN
BUILDING 08 - ATTIC - ADMIN
BUILDING 09 - LEVEL 00 - HEALTHCARE
BUILDING 09 - LEVEL 01 - HEALTHCARE
BUILDING 09 - LEVEL 02 - HEALTHCARE
BUILDING 12 - LEVEL 00G - ADMIN
BUILDING 12 - LEVEL 01 - ADMIN
BUILDING 12 - LEVEL 02 - ADMIN
BUILDING 20 - LEVEL 01 - ADMIN
BUILDING 20 - LEVEL 02 - ADMIN
BUILDING 23R - LEVEL 00B - HEALTHCARE
BUILDING 23R - LEVEL 00G - HEALTHCARE
BUILDING 23R - LEVEL 01 - HEALTHCARE
BUILDING 23R - LEVEL 02 - HEALTHCARE
BUILDING 25 - LEVEL 01 - ADMIN
BUILDING 25 - LEVEL 02 - ADMIN
BUILDING 25 - LEVEL 03 - ADMIN
BUILDING 25 - LEVEL 04 - ADMIN
BUILDING 25 - LEVEL 05 - ADMIN
BUILDING 28 - LEVEL 01 - ADMIN
BUILDING 34 - LEVEL 00 - ADMIN
BUILDING 34 - LEVEL 01 - ADMIN
BUILDING TR1 - LEVEL 01 - ADMIN
BUILDING TR2 - LEVEL 01 - ADMIN
BUILDING TR3 - LEVEL 01 - ADMIN
BUILDING TR4 - LEVEL 01 - ADMIN
BUILDING TR5 - LEVEL 01 - ADMIN

PROJECT INFORMATION

CODE ANALYSIS

STATE:	WEST VIRGINIA
COUNTY:	CABELL
JURISDICTION:	HUNTINGTON
OWNER:	DEPARTMENT OF VETERANS AFFAIRS

ICRA CLASS REQUIREMENTS

REQUIREMENTS DEPENDENT ON EACH INDIVIDUAL ROOM LOCATION, CLASS II, III AND IV.

APPLICABLE BUILDING

BUILDING 1, 2, 3, 4, 5, 6, 7, 8, 9, 12, 20, 23, 23R, 25, 28, 34, TRAILER 1, TRAILER 2, TRAILER 3, TRAILER 4, TRAILER 5, DATA CENTER

PROJECT DESCRIPTION

THE PROPOSED DESIGN SHALL IMPROVE, RECONFIGURE, EXPAND AND RENOVATE EXISTING SPACES, CONSTRUCT NEW EXTERIOR ROOMS FOR NEW TELECOMMUNICATION ROOMS, AND TO CONSTRUCT NEW DATA CENTER IN REPLACEMENT OF THE EXISTING IN THE INTERIOR COURTYARD.

DESIGN TEAM

CIVIL

WSP USA, INC.
33301 9TH AVENUE SOUTH
FEDERAL WAY, WA 98003-2600
PHONE: (206) 431-2300

MECHANICAL

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S. SUITE 300
KENT, WA 98032
PHONE: (206) 590-2118

ARCHITECTURAL

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S. SUITE 300
KENT, WA 98032
PHONE: (206) 590-2118

ELECTRICAL

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S. SUITE 300
KENT, WA 98032
PHONE: (206) 590-2118

STRUCTURAL

WSP USA, INC.
33301 9TH AVENUE SOUTH
FEDERAL WAY, WA 98003-2600
PHONE: (206) 431-2300

GENERAL NOTES

1. COORDINATE WORK WITH ALL CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO DRAWINGS & SPECIFICATIONS.
2. SPECIFICATIONS SHALL SUPERSEDE DRAWINGS IN THE CASE OF ANY CONFLICTING INFORMATION. BRING TO THE AWARENESS OF AND VERIFY WITH VA COR PRIOR TO PROCEEDING.
3. THE CONTRACTOR AND ANY SUB CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH EXISTING CONDITIONS AND PROJECT REQUIREMENTS PRIOR TO SUBMITTING A BID OR BEGINNING WORK. NO ALLOWANCES WILL BE MADE ON BEHALF OF THE CONTRACTOR OR SUB-CONTRACTORS FOR FAILURE TO VISIT THE SITE.
4. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS BEFORE BEGINNING WORK. ANY CONFLICTS BETWEEN EXISTING CONDITIONS AND THE CONTRACT DOCUMENTS SHALL BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE COR.
5. ALL WORK SHALL BE PERFORMED WITH A HIGH-LEVEL OF WORKMANSHIP.
6. THE CONTRACTOR SHALL VERIFY ALL PRODUCT TYPES AND QUANTITIES DURING SITE WALK THROUGH, PRIOR TO PURCHASING ANY MATERIALS, EQUIPMENT, PRODUCTS OR LABOR.
7. THE CONTRACTOR SHALL VERIFY AND COORDINATE WITH ALL INSTALLERS TO ENSURE COMPLIANCE WITH THE CONTRACT DOCUMENTS.

Revisions: | Date:

CONSULTANT
ENGINEERING DISCIPLINE:

ARCHITECT/ENGINEER OF RECORD
A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S. SUITE 300
KENT, WA 98032
SPEESDESIGNBUILD

STAMP
10000 REGISTERED ARCHITECT
JAMES M. KING
STATE OF WASHINGTON
9/3/2025

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
COVER SHEET	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700

Building Number: -

Approved:

Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn
09/03/2025	JW/MA	RB

Drawing Number: G-001

VA FORM 08 - 6231

BIM 360://581-22-700 VAHuntington EHRM/GENERAL SHEETS.rvt
26/08/2025 8:58:05 am

DRAWING INDEX

PAGE #		SHEET #	SHEET NAME
GENERAL			
1	OF 693	G-001	COVER SHEET
2	OF 693	G-002	DRAWING INDEX
3	OF 693	G-003	DRAWING INDEX
CIVIL			
4	OF 693	C-001	CIVIL SHEET INDEX AND GENERAL NOTES
5	OF 693	C-002	GENERAL NOTES AND LEGEND
6	OF 693	CS100	OVERALL CIVIL SITE PLAN
7	OF 693	CG100	OVERALL EROSION CONTROL PLAN
8	OF 693	CG101	EROSION CONTROL GENERAL NOTES AND DETAILS
9	OF 693	CU250	CIVIL UTILITY CONSTRUCTION DETAILS
10	OF 693	CU300	OVERALL FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
11	OF 693	CU301	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
12	OF 693	CU302	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
13	OF 693	CU303	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
14	OF 693	CU304	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
15	OF 693	CU305	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
16	OF 693	CU306	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
17	OF 693	CU307	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
18	OF 693	CU500	COMMUNICATION DUCTBANK DETAILS
19	OF 693	CU501	COMMUNICATION TRENCHING DETAILS
20	OF 693	CU502	BUILDING CONNECTION DETAILS
STRUCTURAL			
21	OF 693	S-001	STRUCTURAL GENERAL NOTES
22	OF 693	S-002	STRUCTURAL GENERAL NOTES
23	OF 693	S-003	ABRREVIATIONS AND SYMBOLS
24	OF 693	S-101	STRUCTURAL PLANS -TOWER T1
25	OF 693	S-102	STRUCTURAL PLANS -TOWER T2
26	OF 693	S-103	STRUCTURAL PLANS -TOWER T3
27	OF 693	S-104	STRUCTURAL PLANS -TOWER T4
28	OF 693	S-105-1B	FOUNDATION PLAN -DATA CENTER -PHASE 1
29	OF 693	S-106-2B	FOUNDATION PLAN -DATA CENTER -PHASE 2
30	OF 693	S-107	STRUCTURAL PLANS -BUILDING TR1
31	OF 693	S-115-1B	ROOF FRAMING PLAN -DATA CENTER -PHASE 1
32	OF 693	SD105	DEMOLITION PLAN -DTATA CENTER
33	OF 693	S-116-2B	ROOF FRAMING PLAN -DATA CENTER -PHASE 2
34	OF 693	S-301	BUILDING SECTIONS -DATA CENTER
35	OF 693	S-501	TYPICAL CONCRETE DETAILS
36	OF 693	S-502	FOUNDATION DETAILS
37	OF 693	S-503	FOUNDATION DETAILS
38	OF 693	S-504	TYPICAL PENETRATIONS IN EXISTING STRUCTURE
39	OF 693	S-511	TYPICAL STRUCTURAL STEEL DETAILS
40	OF 693	S-512	TYPICAL STRUCTURAL STEEL DETAILS
41	OF 693	S-515	TYPICAL STRUCTURAL STEEL DETAILS
42	OF 693	S-525	TYPICAL COLD-FORMED STEEL DETAILS -SHEET 1
43	OF 693	S-526	TYPICAL COLD-FORMED STEEL DETAILS -SHEET 2
44	OF 693	S-527	TYPICAL COLD-FORMED STEEL DETAILS -SHEET 3
45	OF 693	S-528	TYPICAL COLD-FORMED STEEL DETAILS -SHEET 4
46	OF 693	S-541	MECHANICAL ANCHORAGE DETAILS
47	OF 693	S-542	TYPICAL DETAILS-CABINET TO CFS FRAMED WALL
48	OF 693	S-543	TYPICAL DETAILS-CABINET TO WOOD FRAMED WALL
49	OF 693	S-544	TYPICAL DETAILS-CABINET TO CONCRETE AND CMU WALL
ARCHITECTURAL			
50	OF 693	A-001	ARCHITECTURAL SYMBOLS & ABBREVIATIONS
51	OF 693	AS101	ICRA DETAILS
52	OF 693	AD101-1B	DATA CENTER -PHASE 1B -DEMO FLOOR PLAN
53	OF 693	AD102-1B	DATA CENTER -PHASE 1B -DEMO RCP
54	OF 693	AD103-1B	DATA CENTER -PHASE 1B -DEMO ROOF
55	OF 693	AE104-1B	DATA CENTER -PHASE 1B -FLOOR PLAN
56	OF 693	AC105-1B	DATA CENTER -PHASE 1B -RCP
57	OF 693	AE106-1B	DATA CENTER -PHASE 1B -ROOF
58	OF 693	AD107-2A	DATA CENTER -PHASE 2A -DEMO FLOOR PLAN
59	OF 693	AD108-2A	DATA CENTER -PHASE 2A -DEMO RCP
60	OF 693	AE109-2A	DATA CENTER -PHASE 2A -FLOOR PLAN
61	OF 693	AC110-2A	DATA CENTER -PHASE 2A -RCP
62	OF 693	AD111-2B	DATA CENTER -PHASE 2B -DEMO FLOOR PLAN
63	OF 693	AD112-2B	DATA CENTER -PHASE 2B -DEMO RCP
64	OF 693	AD113-2B	DATA CENTER -PHASE 2B -DEMO ROOF
65	OF 693	AE114-2B	DATA CENTER -PHASE 2B -FLOOR PLAN
66	OF 693	AC115-2B	DATA CENTER -PHASE 2B -RCP
67	OF 693	AE116-2B	DATA CENTER -PHASE 2B -ROOF
68	OF 693	AE301	BUILDING SECTIONS
69	OF 693	AE501	DETAILS
70	OF 693	AE401	INTERIOR ELEVATIONS
71	OF 693	01AS100B	BUILDING 01, 02, 12, 23 & 23R -LEVEL 00B -OVERALL PLAN
72	OF 693	01AS100G	BUILDING 01, 02, 12, 23 & 23R -LEVEL 00G -OVERALL PLAN
73	OF 693	01AS101	BUILDING 01, 02, 12, 23 & 23R -LEVEL 01 -OVERALL PLAN
74	OF 693	01AS102	BUILDING 01, 02, 12, 23 & 23R -LEVEL 02 -OVERALL PLAN
75	OF 693	01AS103	BUILDING 01, 02, 12, 23 & 23R -LEVEL 03 -OVERALL PLAN
76	OF 693	01AS104	BUILDING 01, 02, 12, 23 & 23R -LEVEL 04 -OVERALL PLAN
77	OF 693	01AS105	BUILDING 01, 02, 12, 23 & 23R -LEVEL 05 -OVERALL PLAN
78	OF 693	01SAS100B	BUILDING 01S -LEVEL 00B -PHASING PLAN
79	OF 693	01SA-100B	BUILDING 01S -LEVEL 00B -DEMO, FLOOR PLANS & RCPS
80	OF 693	01SAS100G	BUILDING 01S -LEVEL 00G -PHASING PLAN
81	OF 693	01SA-100G	BUILDING 01S -LEVEL 00G -TOWER T1 -DEMO, FLOOR PLANS & RCPS
82	OF 693	01SA-200G	BUILDING 01S -LEVEL 00G -TOWER T4 -DEMO, FLOOR PLANS & RCPS
83	OF 693	01SAS101	BUILDING 01S -LEVEL 01 -PHASING PLAN
84	OF 693	01SA-101	BUILDING 01S -LEVEL 01 -TOWER T1 -DEMO, FLOOR PLANS & RCPS
85	OF 693	01SA-201	BUILDING 01S -LEVEL 01 -TOWER T4 -DEMO, FLOOR PLANS & RCPS
86	OF 693	01SAS102	BUILDING 01S -LEVEL 02 -PHASING PLAN
87	OF 693	01SA-102	BUILDING 01S -LEVEL 02 -TOWER T1 -DEMO, FLOOR PLANS & RCPS
88	OF 693	01SA-202	BUILDING 01S -LEVEL 02 -TOWER T4 -DEMO, FLOOR PLANS & RCPS
89	OF 693	01SAS103	BUILDING 01S -LEVEL 03 -PHASING PLAN
90	OF 693	01SA-103	BUILDING 01S -LEVEL 03 -TOWER T1 -DEMO, FLOOR PLANS & RCPS
91	OF 693	01SA-203	BUILDING 01S -LEVEL 03 -TOWER T4 -DEMO, FLOOR PLANS & RCPS
92	OF 693	01SAS104	BUILDING 01S -LEVEL 04 -PHASING PLAN
93	OF 693	01SA-104	BUILDING 01S -LEVEL 04 -TOWER T1 -DEMO, FLOOR PLANS & RCPS
94	OF 693	01SA-204	BUILDING 01S -LEVEL 04 -TOWER T4 -DEMO, FLOOR PLANS & RCPS
95	OF 693	01SAS105	BUILDING 01S -LEVEL 05 -PHASING PLAN
96	OF 693	01SA-105	BUILDING 01S -LEVEL 05 -TOWER T1 -DEMO, FLOOR PLANS & RCPS
97	OF 693	01SA-205	BUILDING 01S -LEVEL 05 -TOWER T4 -DEMO, FLOOR PLANS & RCPS
98	OF 693	01SAS106	BUILDING 01S -LEVEL 06 -PHASING PLAN
99	OF 693	01SA-106	BUILDING 01S -LEVEL 06 -DEMO, FLOOR PLANS & RCPS
100	OF 693	01SA-105c	TR TOWER 1 -EXTERIOR ELEVATIONS
101	OF 693	01SA-105d	TR TOWER 4 -ELEVATIONS
102	OF 693	01SA-105e	TR TOWER 1 -BUILDING SECTIONS
103	OF 693	01SA-105f	TR TOWER 4 -BUILDING SECTIONS
104	OF 693	01S-A-511	EXTERIOR DETAILS -TR TOWER T1
105	OF 693	01S-A-512	EXTERIOR DETAIL -TR TOWER T1
106	OF 693	01S-A-513	EXTERIOR DETAILS -TOWER T4
107	OF 693	01S-A-514	TYPICAL ROOF DETAILS
108	OF 693	01S-AE451	TR TOWER 1 -WALL SECTIONS
109	OF 693	01S-AE452	TR TOWER 4 -WALL SECTIONS
110	OF 693	01SA-106a	TOWER T1 -ROOF PLAN
111	OF 693	01SA-206	TOWER T4 -ROOF PLAN
112	OF 693	01WAS100G	BUILDING 01W -LEVEL 00G -PHASING PLAN
113	OF 693	01WA-100G	BUILDING 01W -LEVEL 00G -DEMO, FLOOR PLANS & RCPS
114	OF 693	01WAS101	BUILDING 01W -LEVEL 01 -PHASING PLAN
115	OF 693	01WA-101	BUILDING 01W -LEVEL 01 -DEMO, FLOOR PLANS & RCPS
116	OF 693	01WAS102	BUILDING 01W -LEVEL 02 -PHASING PLAN
117	OF 693	01WA-102	BUILDING 01W -LEVEL 02 -DEMO, FLOOR PLANS & RCPS
118	OF 693	01WAS103	BUILDING 01W -LEVEL 03 -PHASING PLAN
119	OF 693	01WA-103	BUILDING 01W -LEVEL 03 -DEMO, FLOOR PLANS & RCPS
120	OF 693	01WA-103b	TR TOWER 2 -EXTERIOR ELEVATIONS
121	OF 693	01WA-103c	TR TOWER 2 -BUILDING SECTIONS
122	OF 693	01W-AE451	WALL SECTIONS
123	OF 693	01WA-104	BUILDING 01W -ROOF PLAN
124	OF 693	01W-AE511	EXTERIOR DETAILS
125	OF 693	02AS100B	BUILDING 02 -LEVEL 00B -PHASING PLAN
126	OF 693	02A-100B	BUILDING 02 -LEVEL 00B -DEMO, FLOOR PLANS & RCPS
127	OF 693	02AS100G	BUILDING 02 -LEVEL 00G -PHASING PLAN
128	OF 693	02A-100G	BUILDING 02 -LEVEL 00G -DEMO, FLOOR PLANS & RCPS
129	OF 693	02A-100Gb	TR TOWER 3 -EXTERIOR ELEVATIONS
130	OF 693	02A-100Gc	TR TOWER 3 -BUILDING SECTIONS
131	OF 693	02A-100R	BUILDING 02 - ROOF PLAN
132	OF 693	02A-501	TR TOWER T3 MECH SHAFT DETAILS
133	OF 693	02A-511	EXTERIOR DETAILS
134	OF 693	02A-512	EXTERIOR DETAILS
135	OF 693	02AE-451	WALL SECTIONS
136	OF 693	03AS101	BUILDING 03 -LEVEL 01 -PHASING PLAN
137	OF 693	03A-101	BUILDING 03 -LEVEL 01 -DEMO, FLOOR PLANS, & RCPS
138	OF 693	03AS102	BUILDING 03 -LEVEL 02 -PHASING PLAN
139	OF 693	04AS100	BUILDING 04 -LEVEL 00 -PHASING PLAN
140	OF 693	04A-100	BUILDING 04 -LEVEL 00 -DEMO, FLOOR PLAN & RCPS
141	OF 693	04AS101	BUILDING 04 -LEVEL 01 -PHASING PLAN
142	OF 693	04AS102	BUILDING 04 -LEVEL 02 -PHASING PLAN
143	OF 693	05AS100	BUILDING 05 -LEVEL 00 -PHASING PLAN
144	OF 693	05A-100	BUILDING 05 -LEVEL 00 -DEMO, FLOOR PLAN & RCPS
145	OF 693	05AS101	BUILDING 05 -LEVEL 01 -PHASING PLAN
146	OF 693	05AS102	BUILDING 05 -LEVEL 02 -PHASING PLAN
147	OF 693	06AS100	BUILDING 06 -LEVEL 00 -PHASING PLAN
148	OF 693	06AS101	BUILDING 06 -LEVEL 01 -PHASING PLAN
149	OF 693	06A-101	BUILDING 06 -LEVEL 01-DEMO, FLOOR PLANS & RCPS
150	OF 693	06AS102	BUILDING 06 -LEVEL 02 -PHASING PLAN
151	OF 693	07AS100	BUILDING 07 -LEVEL 00 -PHASING PLAN
152	OF 693	07A-100	BUILDING 07 -LEVEL 00 -DEMO, FLOOR PLAN & RCPS
153	OF 693	07AS101	BUILDING 07 -LEVEL 01 -PHASING PLAN
154	OF 693	07AS102	BUILDING 07 -LEVEL 02 -PHASING PLAN
155	OF 693	07AS103	BUILDING 07 -ATTIC -PHASING PLAN
156	OF 693	07A-103	BUILDING 07 -ATTIC LEVEL -DEMO, FLOOR PLAN, & RCPS
157	OF 693	08AS100	BUILDING 08 -LEVEL 00 -PHASING PLAN
158	OF 693	08A-100	BUILDING 08 -LEVEL 00 -DEMO, FLOOR PLAN & RCPS
159	OF 693	08AS101	BUILDING 08 -LEVEL 01 -PHASING PLAN
160	OF 693	08AS102	BUILDING 08 -LEVEL 02 -PHASING PLAN
161	OF 693	08AS103	BUILDING 08 -ATTIC -PHASING PLAN
162	OF 693	08A-103	BUILDING 08 -ATTIC -DEMO, FLOOR PLANS, & RCPS
163	OF 693	09AS101	BUILDING 09 -LEVEL 01 -PHASING PLAN
164	OF 693	09AS102	BUILDING 09 -LEVEL 02 -PHASING PLAN
165	OF 693	09A-102	BUILDING 09 -LEVEL 02 -DEMO, FLOOR PLANS & RCPS
166	OF 693	20AS101	BUILDING 20 -LEVEL 01 -PHASING PLAN
167	OF 693	20A-101	BUILDING 20 -LEVEL 01 -DEMO, FLOOR PLANS & RCPS
168	OF 693	20AS102	BUILDING 20 -LEVEL 02 -PHASING PLAN
169	OF 693	20A-102	BUILDING 20 -LEVEL 02 -DEMO, FLOOR PLANS & RCPS
170	OF 693	23RAS100B	BUILDING 23 & 23R -LEVEL 00B -PHASING PLAN
171	OF 693	23RA-100B	BUILDING 23R -LEVEL 00B -DEMO, FLOOR PLANS & RCPS
172	OF 693	23RA-100C	BUILDING 23R -LEVELS 01 & 02 -DEMO, FLOOR PLANS & RCPS
173	OF 693	25AS101	BUILDING 25 -LEVEL 01 -PHASING PLAN
174	OF 693	25A-101	BUILDING 25 -LEVEL 01 -DEMO, FLOOR PLAN & RCPS
175	OF 693	28AS101	BUILDING 28 -LEVEL 01 -PHASING PLAN
176	OF 693	28A-101	BUILDING 28 -LEVEL 01 -DEMO, FLOOR PLANS, & RCPS
177	OF 693	34AS100	BUILDING 34 -LEVEL 00 -PHASING PLAN
178	OF 693	34A-100	BUILDING 34 -LEVEL 00 -DEMO, FLOOR PLANS, & RCPS
179	OF 693	34AS101	BUILDING 34 -LEVEL 01 -PHASING PLAN
180	OF 693	TR1AS101	BUILDING TR1 -LEVEL 01 -PHASING PLAN
181	OF 693	TR1A-101a	BUILDING TR1 -LEVEL 01 -DEMO, FLOOR PLANS, & RCPS
182	OF 693	TR1A-101b	BUILDING TR1 -LEVEL 01 -SECTION AND DETAIL
183	OF 693	TR2AS101	BUILDING TR2 -LEVEL 01 -PHASING PLAN
184	OF 693	TR3AS101	BUILDING TR3 -LEVEL 01 -PHASING PLAN
185	OF 693	TR3A-101	BUILDING TR3 -LEVEL 01 -DEMO, FLOOR PLAN & RCPS
186	OF 693	TR4AS101	BUILDING TR4 -LEVEL 01 -PHASING PLAN
187	OF 693	TR4A-101	BUILDING TR4 -LEVEL 01 -DEMO, FLOOR PLAN & RCPS
188	OF 693	TR5AS101	BUILDING TR5 -LEVEL 01 -PHASING PLAN
189	OF 693	TR5A-101	BUILDING TR5 -LEVEL 01 -DEMO, FLOOR PLAN & RCPS
190	OF 693	A-601a	ROOM FINISH SCHEDULE
191	OF 693	A-601b	ROOM FINISH SCHEDULE
192	OF 693	A-602	DOOR SCHEDULE AND DETAILS
193	OF 693	A-603	DETAILS -WALL TYPES
194	OF 693	A-604	DETAILS
195	OF 693	AW001	IN-03.01 -ROOM NUMBER SIGN & SIGNAGE SCHEDULE
MECHANICAL			
196	OF 693	M-001	FIRE PROTECTION, PLUMBING, AND MECHANICAL GENERAL NOTES
197	OF 693	M-002	FIRE PROTECTION, PLUMBING, AND MECHANICAL GENERAL NOTES
198	OF 693	01-M-101	BUILDING 01S -BASEMENT -OVERALL PLAN -AREA A
199	OF 693	01-M-102	BUILDING 01S -LEVEL 00 -OVERALL PLAN -AREA A
200	OF 693	01-M-103	BUILDING 01S & 01W -LEVEL 00 -OVERALL PLAN -AREA B
201	OF 693	01-M-104	BUILDING 01S -LEVEL 01 -OVERALL PLAN -AREA A
202	OF 693	01-M-105	BUILDING 01S & 01W -LEVEL 01 -OVERALL PLAN -AREA B
203	OF 693	01-M-106	BUILDING 01S -LEVEL 02 -OVERALL PLAN -AREA A
204	OF 693	01-M-107	BUILDING 01S & 01W -LEVEL 02 -OVERALL PLAN -AREA B
205	OF 693	01-M-108	BUILDING 01S -LEVEL 03 -OVERALL PLAN -AREA A
206	OF 693	01-M-109	BUILDING 01S & 01W -LEVEL 03 -OVERALL PLAN -AREA B
207	OF 693	01-M-110	BUILDING 01S -LEVEL 04 -OVERALL PLAN -AREA A
208	OF 693	01-M-111	BUILDING 01S -LEVEL 04 -OVERALL PLAN -AREA B
209	OF 693	01-M-112	BUILDING 01S -LEVEL 05 -OVERALL PLAN
210	OF 693	01-M-113	BUILDING 01S -LEVEL 06 -OVERALL PLAN
211	OF 693	01S-M-401	BASEMENT FLOOR PLAN -MECHANICAL AND PLUMBING PIPING TO TR TOWER 1
212	OF 693	01S-M-402	PIPE BASEMENT FLOOR PLAN -MECHANICAL PIPING TO TR TOWER 4
213	OF 693	01S-M-403	BUILDING 01S -BASEMENT -FIRE PROTECTION AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
214	OF 693	01S-M-404	BUILDING 01S -LEVEL 00 -MECHANICAL PIPING -FLOOR PLAN
215	OF 693	01S-M-405	BUILDING 01S -T1 -LEVEL 00 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
216	OF 693	01S-M-406	BUILDING 01S -T4 -LEVEL 00 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
217	OF 693	01S-M-407	BUILDING 01S -LEVEL 01 -MECHANICAL PIPING -FLOOR PLAN
218	OF 693	01S-M-408	BUILDING 01S -T1 -LEVEL 01 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
219	OF 693	01S-M-409	BUILDING 01S -T4 -LEVEL 01 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
220	OF 693	01S-M-410	BUILDING 01S -T1 -LEVEL 02 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
221	OF 693	01S-M-411	BUILDING 01S -T4 -LEVEL 02 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
222	OF 693	01S-M-412	BUILDING 01S -T1 -LEVEL 03 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
223	OF 693	01S-M-413	BUILDING 01S -T4 -LEVEL 03 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
224	OF 693	01S-M-414	BUILDING 01S -T1 -LEVEL 04 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
225	OF 693	01S-M-415	BUILDING 01S -T4 -LEVEL 04 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
226	OF 693	01S-M-416	BUILDING 01S -T1 -LEVEL 05 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
227	OF 693	01S-M-417	BUILDING 01S -T4 -LEVEL 05 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
228	OF 693	01S-M-418	BUILDING 01S -LEVEL 06 -MECHANICAL -FLOOR PLAN
229	OF 693	01W-M-401	BASEMENT FLOOR PLAN -MECHANICAL PIPING -MECHANICAL PIPING TO TR TOWER 2
230	OF 693	01W-M-402	BUILDING 01W -T2 -LEVEL 00 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
231	OF 693	01W-M-403	BUILDING 01W -T2 -LEVEL 01 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
232	OF 693	01W-M-404	BUILDING 01W -T2 -LEVEL 02 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
233	OF 693	01W-M-405	BUILDING 01W -T2 -LEVEL 03 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
234	OF 693	M-301-2B	PHASE 2B -LVL 00 -DATA CENTER -HVAC DUCT -SECTION VIEW
235	OF 693	M-302-2B	PHASE 2B -LVL 00 -DATA CENTER -HVAC DUCT & ERV -SECTION VIEW
236	OF 693	MD401-1A	PHASE 1A -ROOF -DATA CENTER -DEMOLITION ROOF PLAN
237	OF 693	MH402-1A	PHASE 1A -ROOF -DATA CENTER - ROOF PLAN
238	OF 693	FD403-1B	PHASE 1B -LVL 00 -DATA CENTER -FIRE PROTECTION -DEMOLITION RCP
239	OF 693	MD404-1B	PHASE 1B -LVL 00 -DATA CENTER -HVAC DUCT -DEMOLITION FLOOR PLAN
240	OF 693	MD405-1B	PHASE 1B -LVL 00 -DATA CENTER -DEMOLITION RCP
241	OF 693	FX406-1B	PHASE 1B -LVL 00 -DATA CENTER -FIRE PROTECTION -FLOOR PLAN
242	OF 693	MP407-1B	PHASE 1B -LVL 00 -DATA CENTER -HVAC PIPING -FLOOR PLAN
243	OF 693	MH408-1B	PHASE 1B -LVL 00 -DATA CENTER -HVAC DUCT -FLOOR PLAN
244	OF 693	MH409-1B	PHASE 1B -LVL 00 -DATA CENTER -RCP
245	OF 693	MH410-1B	PHASE 1B -ROOF -DATA CENTER -ROOF PLAN
246	OF 693	PP411-1B	PHASE 1B -LVL 00 -DATA CENTER -PLUMBING PIPING -FLOOR PLAN
247	OF 693	MP412-2A	PHASE 2A -LVL 00 -DATA CENTER -HVAC PIPING -FLOOR PLAN
248	OF 693	MH413-2A	PHASE 2A -ROOF -DATA CENTER -ROOF PLAN
249	OF 693	MD414-2B	PHASE 2B -LVL 00 -DATA CENTER -HVAC PIPING -DEMOLITION FLOOR PLAN
250	OF 693	MD415-2B	PHASE 2B -LVL 00 -DATA CENTER -HVAC DUCT -DEMOLITION FLOOR PLAN
251	OF 693	MD416-2B	PHASE 2B -LVL 00 -DATA CENTER -PLUMBING PIPING
252	OF 693	MD417-2B	PHASE 2B -LVL 00 -DATA CENTER -DEMOLITION ROOF FLOOR PLAN
253	OF 693	FD418-2B	PHASE 2B -LVL 00 -DATA CENTER -FIRE PROTECTION -DEMOLITION RCP
254	OF 693	FX419-2B	PHASE 2B -LVL 00 -DATA CENTER -FIRE PROTECTION -FLOOR PLAN
255	OF 693	MP420-2B	PHASE 2B -LVL 00 -DATA CENTER -HVAC PIPING -FLOOR PLAN
256	OF 693	MH421-2B	PHASE 2B -LVL 00 -DATA CENTER -HVAC DUCT -FLOOR PLAN
257	OF 693	MH422-2B	PHASE 2B -ROOF -DATA CENTER -ROOF PLAN
258	OF 693	PP-423-2B	PHASE 2B -LVL 00 -DATA CENTER -PLUMBING PIPING
259	OF 693	02-M-101	BUILDING 02 -BASEMENT -OVERALL PLAN
260	OF 693	02-M-102	BUILDING 02 -LEVEL 00 -OVERALL PLAN
261	OF 693	02-M-401	BASEMENT FLOOR PLAN -MECHANICAL PIPING TO TR TOWER 3
262	OF 693	02-M-402	BUILDING 02 -T3 -BASEMENT -FIRE PROTECTION, PLUMBING, AND MECHANICAL -FLOOR PLAN & RCP
263	OF 693	02-M-403	BUILDING 02 -T3 -LEVEL 00 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -FLOOR PLAN & RCP
264	OF 693	03-M-101	BUILDING 03 -LEVEL 01 -OVERALL PLAN
265	OF 693	03-M-401	BUILDING 03 -LEVEL 01 -PLUMBING AND MECHANICAL -FLOOR PLAN
266	OF 693	04-M-101	BUILDING 04 -LEVEL 00 -OVERALL PLAN
267	OF 693	04-M-401	BUILDING 04 -LEVEL 00 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
268	OF 693	04-M-402	BUILDING 04 -LEVEL 01 -MECHANICAL PIPING -FLOOR PLAN
269	OF 693	05-M-101	BUILDING 05 -LEVEL 00 -OVERALL PLAN
270	OF 693	05-M-401	BUILDING 05 -LEVEL 00 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
271	OF 693	05-M-402	BUILDING 05 -LEVEL 01 -MECHANICAL PIPING -FLOOR PLAN
272	OF 693	06-M-101	BUILDING 06 -LEVEL 01 -OVERALL PLAN
273	OF 693	06-M-401	BUILDING 06 -LEVEL 01 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
274	OF 693	06-M-402	BUILDING 06 -ROOF PLAN
275	OF 693	07-M-101	BUILDING 07 -LEVEL 00 -OVERALL PLAN
276	OF 693	07-M-102	BUILDING 07 -LEVEL 01 -OVERALL PLAN
277	OF 693	07-M-103	BUILDING 07 -LEVEL ATTIC -OVERALL PLAN
278	OF 693	07-M-401	BUILDING 07 -LEVEL 00 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
279	OF 693	07-M-402	BUILDING 07 -LEVEL 01 -MECHANICAL PIPING -FLOOR PLAN
280	OF 693	07-M-403	BUILDING 07 -LEVEL 02 -FLOOR PLAN
281	OF 693	07-M-404	BUILDING 07 -LEVEL ATTIC -FIRE PROTECTION, PLUMBING, AND MECHANICAL -FLOOR PLAN & RCP
282	OF 693	08-M-101	BUILDING 08 -LEVEL 00 -OVERALL PLAN
283	OF 693	08-M-102	BUILDING 08 -LEVEL ATTIC -OVERALL PLAN
284	OF 693	08-M-401	BUILDING 08 -LEVEL 00 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
285	OF 693	08-M-402	BUILDING 08 -LEVEL ATTIC -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
286	OF 693	09-M-101	BUILDING 09 -LEVEL 02 -OVERALL PLAN
287	OF 693	09-M-401	BUILDING 09 -LEVEL 00 -MECHANICAL PIPING -FLOOR PLAN
288	OF 693	09-M-402	BUILDING 09 -LEVEL 01 -FLOOR PLAN
289	OF 693	09-M-403	BUILDING 09 -LEVEL 02 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
290	OF 693	20-M-101	BUILDING 20 -LEVEL 01 -OVERALL PLAN
291	OF 693	20-M-102	BUILDING 20 -LEVEL 02 -OVERALL PLAN
292	OF 693	20-M-401	BUILDING 20 -LEVEL 01 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
293	OF 693	20-M-402	BUILDING 20 -LEVEL 02 -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
294	OF 693	20-M-403	BUILDING 20 -ROOF PLAN
295	OF 693	23R-M-101	BUILDING 23R -BASEMENT -OVERALL PLAN
296	OF 693	23R-M-401	BUILDING 23R -BASEMENT -FIRE PROTECTION, PLUMBING, AND MECHANICAL -DEMOLITION, FLOOR PLANS & RCPS
297	OF 693	25-M-101	BUILDING 25 -LEVEL 01 -OVERALL PLAN
298	OF 693	25-M-401	BUILDING 25 -LEVEL 01 -FIRE PROTECTION AND MECHANICAL -FLOOR PLAN & RCP
299	OF 693	28-M-101	BUILDING 28 -LEVEL 01 -OVERALL PLAN
300	OF 693	28-M-401	BUILDING 28 -LEVEL 01 -PLUMBING AND MECHANICAL -FLOOR PLAN
301	OF 693	34-M-101	BUILDING 34 -LEVEL 00 -OVERALL PLAN
302	OF 693	34-M-401	BUILDING 34 -LEVEL 00 -PLUMBING AND MECHANICAL -FLOOR PLAN
303	OF 693	TR1-M-101	BUILDING TR1 -LEVEL 01 -OVERALL PLAN
304	OF 693	TR1-M-401	BUILDING TR1 -LEVEL 01 -PLUMBING AND MECHANICAL -FLOOR PLAN
305	OF 693	TR3-M-101	BUILDING TR3 -LEVEL 01 -OVERALL PLAN
306	OF 693	TR3-M-401	BUILDING TR3 -LEVEL 01 -MECHANICAL -FLOOR PLAN & RCP
307	OF 693	TR4-M-101	BUILDING TR4 -LEVEL 01 -OVERALL PLAN
308	OF 693	TR4-M-401	BUILDING TR4 -LEVEL 01 -MECHANICAL -FLOOR PLAN & RCP
309	OF 693	TR5-M-101	BUILDING TR5 -LEVEL 01 -OVERALL PLAN
310	OF 693	TR5-M-401	BUILDING TR5 -LEVEL 01 -MECHANICAL -FLOOR PLAN & RCP
311	OF 693	M-501	MECHANICAL DETAILS I
312	OF 693	M-502	MECHANICAL DETAILS II
313	OF 693	M-503	MECHANICAL DETAILS III
314	OF 693	M-504	MECHANICAL DETAILS IV
315	OF 693	M-505	TR TOWER HYDRONIC RISER DIAGRAMS
316	OF 693	M-601	MECHANICAL SCHEDULES I
317	OF 693	M-602	MECHANICAL SCHEDULES II
318	OF 693	M-603	MECHANICAL SCHEDULES III
319	OF 693	M-701	MECHANICAL CONTROLS I
320	OF 693	M-702	MECHANICAL CONTROLS II
321	OF 693	M-703	MECHANICAL CONTROLS III
322	OF 693	M-704	MECHANICAL CONTROLS IV
ELECTRICAL			
323	OF 693	E-001	ABBREVIATIONS, GENERAL NOTES, AND SHEET INDEX
324	OF 693	E-002	ELECTRICAL LEGENDS
325	OF 693	ES101	ELECTRICAL FACILITY SITE PLAN
326	OF 693	01EP100G	BLDG 01 -LEVEL 00G -ELECTRICAL PLAN
327	OF 693	01AEP100G	BLDG 01A -LEVEL 00G -ELECTRICAL PLAN
328	OF 693	01SEP100B	BLDG 01S -LEVEL 00B -ELECTRICAL PLAN
329	OF 693	01SEP100G	BLDG 01S -LEVEL 00G -ELECTRICAL PLAN
330	OF 693	01SEP101	BLDG 01S -LEVEL 01 -ELECTRICAL PLAN
331	OF 693	01SEP105	BLDG 01S -LEVEL 05 -ELECTRICAL PLAN
332	OF 693	01SEP106	BLDG 01S -LEVEL 06 -ELECTRICAL PLAN
333	OF 693	01WEP100G	BLDG 01W -LEVEL 00G -ELECTRICAL PLAN
334	OF 693	01WEP103	BLDG 01W -LEVEL 03 -ELECTRICAL PLAN
335	OF 693	02EP100B	BLDG 02 -LEVEL 00B -ELECTRICAL PLAN
336	OF 693	03EP101	BLDG 03 -LEVEL 01 -ELECTRICAL PLAN
337	OF 693	04EP100	BLDG 04 -LEVEL 00 -ELECTRICAL PLAN
338	OF 693	04EP101	BLDG 04 -LEVEL 01 -ELECTRICAL PLAN
339	OF 693	05EP101	BLDG 05 -LEVEL 01 -ELECTRICAL PLAN
340	OF 693	06EP100	BLDG 06 -LEVEL 00 -ELECTRICAL PLAN
341	OF 693	06EP102	BLDG 06 -LEVEL 02 -ELECTRICAL PLAN
342	OF 693	06EP103	BLDG 06 -ATTIC -ELECTRICAL PLAN
343	OF 693	07EP100	BLDG 07 -LEVEL 00 -ELECTRICAL PLAN
344	OF 693	07EP101	BLDG 07 -LEVEL 01 -ELECTRICAL PLAN
345	OF 693	07EP102	BLDG 07 -LEVEL 02 -ELECTRICAL PLAN
346	OF 693	07EP103	BLDG 07 -LEVEL 03 -ELECTRICAL PLAN
347	OF 693	08EP100	BLDG 08 -LEVEL 00 -ELECTRICAL PLAN
348	OF 693	08EP101	BLDG 08 -LEVEL 01 -ELECTRICAL PLAN
349	OF 693	08EP102	BLDG 08 -LEVEL 02 -ELECTRICAL PLAN
350	OF 693	08EP103	BLDG 08 -LEVEL 03 -ELECTRICAL PLAN
351	OF 693	09EP100	BLDG 09 -LEVEL 00 -ELECTRICAL PLAN
352	OF 693	09EP101	BLDG 09 -LEVEL 01 -ELECTRICAL PLAN
353	OF 693	20EP101	BLDG 20 -LEVEL 01 -ELECTRICAL PLAN
354	OF 693	20EP103	BLDG 20 -LEVEL 03 -ELECTRICAL PLAN
355	OF 693	23REP100B	BLDG 23R -LEVEL 00B -ELECTRICAL PLAN
356	OF 693	23REP100G	BLDG 23R -LEVEL 00G -ELECTRICAL PLAN
357	OF 693	25EP101	BLDG 25 -LEVEL 01 - ELECTRICAL PLAN
358	OF 693	TR1EP101	BLDG TR1 -LEVEL 01 -ELECTRICAL PLAN
359	OF 693	TR3EP101	BLDG TR3 -LEVEL 01 -ELECTRICAL PLAN
360	OF 693	TR4EP101	BLDG TR4 -LEVEL 01 -ELECTRICAL PLAN
361	OF 693	TR5EP101	BLDG TR5 -LEVEL 01 - ELECTRICAL PLAN
362	OF 693	01EL400Ga-1B	DATA CENTER -LIGHTING PLAN -PHASE 1B (1 OF 2)
363	OF 693	01EL400Gb-1B	DATA CENTER -LIGHTING PLAN -PHASE 1B (2 OF 2)
364	OF 693	01EL400Gc-2A	DATA CENTER -LIGHTING PLAN -PHASE 2A (1 OF 2)
365	OF 693	01EL400Gd-2A	DATA CENTER -LIGHTING PLAN -PHASE 2A (2 OF 2)
366	OF 693	01EL400Ge-2B	DATA CENTER -LIGHTING PLAN -PHASE 2B (1 OF 2)
367	OF 693	01EL400Gf-2B	DATA CENTER -LIGHTING PLAN -PHASE 2B (2 OF 2)
368	OF 693	01EP400Ga-1B	DATA CENTER -ELECTRICAL PLAN -PHASE 1B (1 OF 3)
369	OF 693	01EP400Gb-1B	DATA CENTER -ELECTRICAL PLAN -PHASE 1B (2 OF 3)
370	OF 693	01EP400Gc-1B	DATA CENTER -ELECTRICAL PLAN -PHASE 1B (3 OF 3)
371	OF 693	01EP400Gd-2A	DATA CENTER -ELECTRICAL PLAN -PHASE 2A (1 OF 3)
372	OF 693	01EP400Ge-2A	DATA CENTER -ELECTRICAL PLAN -PHASE 2A (2 OF 3)
373	OF 693	01EP400Gf-2A	DATA CENTER -ELECTRICAL PLAN -PHASE 2A (3 OF 3)
374	OF 693	01EP400Gg-2B	DATA CENTER -ELECTRICAL PLAN -PHASE 2B (1 OF 3)
375	OF 693	01EP400Gh-2B	DATA CENTER -ELECTRICAL PLAN -PHASE 2B (2 OF 3)
376	OF 693	01EP400Gi-2B	DATA CENTER -ELECTRICAL PLAN -PHASE 2B (3 OF 3)
377	OF 693	01EP400Gj-1A	DATA CENTER -ROOF PLAN -PHASE 1A (1 OF 2)
378	OF 693	01EP400Gk-1A	DATA CENTER -ROOF PLAN -PHASE 1A (2 OF 2)
379	OF 693	01EP400Gl-1B	DATA CENTER -ROOF PLAN -PHASE 1B (1 OF 2)
380	OF 693	01EP400Gm-1B	DATA CENTER -ROOF PLAN -PHASE 1B (2 OF 2)
381	OF 693	01EP400Gn-2A	DATA CENTER -ROOF PLAN -PHASE 2A (1 OF 2)
382	OF 693	01EP400Go-2A	DATA CENTER -ROOF PLAN -PHASE 2A (2 OF 2)
383	OF 693	01EP400Gp-2B	DATA CENTER -ROOF PLAN -PHASE 2B (1 OF 2)
384	OF 693	01EP400Gq-2B	DATA CENTER -ROOF PLAN -PHASE 2B (2 OF 2)
385	OF 693	01EF400Ga-1B	DATA CENTER -FIRE ALARM PLAN -PHASE 1B (1 OF 2)
386	OF 693	01EF400Gb-1B	DATA CENTER -FIRE ALARM PLAN -PHASE 1B (2 OF 2)
387	OF 693	01EF400Gc-2A	DATA CENTER -FIRE ALARM PLAN -PHASE 2A (1 OF 2)
388	OF 693	01EF400Gd-2A	DATA CENTER -FIRE ALARM PLAN -PHASE 2A (2 OF 2)
389	OF 693	01EF400Ge-2B	DATA CENTER -FIRE ALARM PLAN -PHASE 2B (1 OF 2)
390	OF 693	01EF400Gf-2B	DATA CENTER -FIRE ALARM PLAN -PHASE 2B (2 OF 2)
391	OF 693	01EG400Ga-1B	DATA CENTER -GROUNDING PLAN -PHASE 1B (1 OF 2)
392	OF 693	01EG400Gb-1B	DATA CENTER -GROUNDING PLAN -PHASE 1B (2 OF 2)
393	OF 693	01EG400Gc-2A	DATA CENTER -GROUNDING PLAN -PHASE 2A (1 OF 2)
394	OF 693	01EG400Gd-2A	DATA CENTER -GROUNDING PLAN -PHASE 2A (2 OF 2)
395	OF 693	01EG400Ge-2B	DATA CENTER -GROUNDING PLAN -PHASE 2B (1 OF 2)
396	OF 693	01EG400Gf-2B	DATA CENTER -GROUNDING PLAN -PHASE 2B (2 OF 2)
397	OF 693	01EP400Gr	BLDG 01 -LEVEL 00G -ENLARGED ELECTRICAL PLANS
398	OF 693	01EP400Gs	BLDG 01 -LEVEL 00G -ENLARGED ELECTRICAL PLANS
399	OF 693	01SEP400Ba	BLDG 01S -LEVEL 00B -ENLARGED ELECTRICAL PLANS
400	OF 693	01SEP400Bb	BLDG 01S -LEVEL 00B -ENLARGED ELECTRICAL PLANS
401	OF 693	01SEP400Bc	BLDG 01S -LEVEL 00B -ENLARGED ELECTRICAL PLANS
402	OF 693	01SEP400Ga	BLDG 01S -LEVEL 00G -ENLARGED ELECTRICAL PLANS
403	OF 693	01SEP400Gb	BLDG 01S -LEVEL 00G -ENLARGED ELECTRICAL PLANS
404	OF 693	01SEP401	BLDG 01S -LEVEL 01 -ENLARGED ELECTRICAL PLANS
405	OF 693	01SEP402	BLDG 01S -LEVEL 02 -ENLARGED ELECTRICAL PLANS
406	OF 693	01SEP403	BLDG 01S -LEVEL 03 -ENLARGED ELECTRICAL PLANS
407	OF 693	01SEP404	BLDG 01S -LEVEL 04 -ENLARGED ELECTRICAL PLANS
408	OF 693	01SEP405	BLDG 01S -LEVEL 05 -ENLARGED ELECTRICAL PLAN
409	OF 693	01SEP406	BLDG 01S -LEVEL 06 -ENLARGED ELECTRICAL PLANS
410	OF 693	01SEP407	BLDG 01S -LEVEL 07 -LIGHTNING PROTECTION PLANS
411	OF 693	01WEP400Ga	BLDG 01W -LEVEL 00G -ENLARGED ELECTRICAL PLANS
412	OF 693	01WEP400Gb	BLDG 01W -LEVEL 00G -ENLARGED ELECTRICAL PLANS
413	OF 693	01WEP401	BLDG 01W -LEVEL 01 -ENLARGED ELECTRICAL PLANS
414	OF 693	01WEP402	BLDG 01W -LEVEL 02 -ENLARGED ELECTRICAL PLANS
415	OF 693	01WEP403	BLDG 01W -LEVEL 03 -ENLARGED ELECTRICAL PLANS
416	OF 693	02EP400B	BLDG 02 -LEVEL 00B -ENLARGED ELECTRICAL PLANS
417	OF 693	02EP400Ga	BLDG 02 -LEVEL 00G -ENLARGED ELECTRICAL PLANS
418	OF 693	02EP400Gb	BLDG 02 -LEVEL 00G -ENLARGED ELECTRICAL PLANS
419	OF 693	03EP401	BLDG 03 -LEVEL 01 -ENLARGED ELECTRICAL PLANS
420	OF 693	04EP400a	BLDG 04 -LEVEL 00 -ENLARGED ELECTRICAL PLANS
421	OF 693	04EP400b	BLDG 04 -LEVEL 00 -ENLARGED ELECTRICAL PLANS
422	OF 693	04EP401	BLDG 04 -LEVEL 01 -ENLARGED ELECTRICAL PLANS
423	OF 693	05EP400	BLDG 05 -LEVEL 00 -ENLARGED ELECTRICAL PLANS
424	OF 693	06EP400	BLDG 06 -LEVEL 00 -ENLARGED ELECTRICAL PLANS
425	OF 693	06EP401	BLDG 06 -LEVEL 01 -ENLARGED ELECTRICAL PLANS
426	OF 693	07EP400	BLDG 07 -LEVEL 00 -ENLARGED ELECTRICAL PLANS
427	OF 693	08EP400	BLDG 08 -LEVEL 00 -ENLARGED ELECTRICAL PLANS
428	OF 693	09EP402	BLDG 09 -LEVEL 02 -ENLARGED ELECTRICAL PLANS
429	OF 693	20EP401	BLDG 20 -LEVEL 01 -ENLARGED ELECTRICAL PLANS
430	OF 693	20EP402	BLDG 20 -LEVEL 02 -ENLARGED ELECTRICAL PLANS
431	OF 693	23REP400Ba	BLDG 23R -LEVEL 00B -ENLARGED ELECTRICAL PLANS
432	OF 693	23REP400Bb	BLDG 23R -LEVEL 00B -ENLARGED ELECTRICAL PLANS
433	OF 693	23REP400G	BLDG 23R -LEVEL 00G -ENLARGED ELECTRICAL PLANS
434	OF 693	25EP401a	BLDG 25 -LEVEL 01 -ENLARGED ELECTRICAL PLANS
435	OF 693	25EP401b	BLDG 25 -LEVEL 01 -ENLARGED ELECTRICAL PLANS
436	OF 693	28EP401	BLDG 28 -LEVEL 01 -ENLARGED ELECTRICAL PLANS
437	OF 693	34EP400	BLDG 34 -LEVEL 00 -ENLARGED ELECTRICAL PLANS
438	OF 693	TR1EP401	BLDG TR1 -LEVEL 01 -ENLARGED ELECTRICAL PLANS

Revisions: Date:

CONSULTANT

ENGINEERING DISCIPLINE:

ARCHITECT/ENGINEER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S. SUITE 300
KENT, WA 98032

SPEESDESIGNBUILD

STAMP

10000 REGISTERED ARCHITECT
...ES M. KING
STATE OF WASHINGTON
9/3/2025

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title
DRAWING INDEX

Approved:

Phase
100% CONSTRUCTION DOCUMENTS

Project Title
EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON

Project Number
581-22-700

Building Number
-

Location
VA HUNTINGTON
1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date 09/03/2025 | **Checked** JW/MA | **Drawn** RB

Drawing Number
G-002

BIM 360://581-22-700 VAHuntington EHRM/GENERAL SHEETS.rvt
27/06/2025 10:20:54 am

VA FORM 08 - 6231

DRAWING INDEX

PAGE #		SHEET #	SHEET NAME
439	OF 693	EP501	ELECTRICAL DETAILS
440	OF 693	EP502	ELECTRICAL DETAILS
441	OF 693	EP503	ELECTRICAL DETAILS
442	OF 693	EP504	ELECTRICAL DETAILS
443	OF 693	EP505	ELECTRICAL DETAILS
444	OF 693	EP506	ELECTRICAL DETAILS
445	OF 693	EP507	ELECTRICAL DETAILS
446	OF 693	EP508	ELECTRICAL DETAILS
447	OF 693	EP509	ELECTRICAL DETAILS
448	OF 693	EF601	FIRE ALARM RISER DIAGRAM
449	OF 693	EG601	TELECOMMUNICATIONS BONDING RISER DIAGRAMS
450	OF 693	EG602	TELECOMMUNICATIONS BONDING RISER DIAGRAMS
451	OF 693	EG603	TELECOMMUNICATIONS BONDING RISER DIAGRAMS
452	OF 693	EG604	TELECOMMUNICATIONS BONDING RISER DIAGRAMS
453	OF 693	01EP601	BLDG 01 -PARTIAL ONE-LINE DIAGRAM -EXISTING (1 OF 2)
454	OF 693	01EP602	BLDG 01 -PARTIAL ONE-LINE DIAGRAM -EXISTING (2 OF 2)
455	OF 693	01EP611	BLDG 01 -PARTIAL ONE-LINE DIAGRAM -REVISED (1 OF 2)
456	OF 693	01EP612	BLDG 01 -PARTIAL ONE-LINE DIAGRAM -REVISED (2 OF 2)
457	OF 693	01EP601-1A	DATA CENTER -ONE-LINE DIAGRAM -PHASE 1A (1 OF 2)
458	OF 693	01EP602-1A	DATA CENTER -ONE-LINE DIAGRAM -PHASE 1A (2 OF 2)
459	OF 693	01EP603-1B	DATA CENTER -ONE-LINE DIAGRAM -PHASE 1B
460	OF 693	01EP604-2A	DATA CENTER -ONE-LINE DIAGRAM -PHASE 2A (1 OF 2)
461	OF 693	01EP605-2A	DATA CENTER -ONE-LINE DIAGRAM -PHASE 2A (2 OF 2)
462	OF 693	01EP606-2B	DATA CENTER -ONE-LINE DIAGRAM -PHASE 2B (1 OF 4)
463	OF 693	01EP607-2B	DATA CENTER -ONE-LINE DIAGRAM -PHASE 2B (2 OF 4)
464	OF 693	01EP608-2B	DATA CENTER -ONE-LINE DIAGRAM - PHASE 2B (3 OF 4)
465	OF 693	01EP609-2B	DATA CENTER -ONE-LINE DIAGRAM -PHASE 2B (4 OF 4)
466	OF 693	01SEP601	BLDG 01S -PARTIAL ONE-LINE DIAGRAM -EXISTING (1 OF 3)
467	OF 693	01SEP602	BLDG 01S -PARTIAL ONE-LINE DIAGRAM -EXISTING (2 OF 3)
468	OF 693	01SEP603	BLDG 01S -PARTIAL ONE-LINE DIAGRAM -EXISTING (3 OF 3)
469	OF 693	01SEP611	BLDG 01S -ONE-LINE DIAGRAM -REVISED (1 OF 4)
470	OF 693	01SEP612	BLDG 01S -ONE-LINE DIAGRAM -REVISED (2 OF 4)
471	OF 693	01SEP613	BLDG 01S -ONE-LINE DIAGRAM -REVISED (3 OF 4)
472	OF 693	01SEP614	BLDG 01S -ONE-LINE DIAGRAM -REVISED (4 OF 4)
473	OF 693	01WEP601	BLDG 01W -ONE-LINE DIAGRAM -EXISTING (1 OF 3)
474	OF 693	01WEP602	BLDG 01W -ONE-LINE DIAGRAM -EXISTING (2 OF 3)
475	OF 693	01WEP603	BLDG 01W -ONE-LINE DIAGRAM -EXISTING (3 OF 3)
476	OF 693	01WEP611	BLDG 01W -ONE-LINE DIAGRAM -REVISED (1 OF 4)
477	OF 693	01WEP612	BLDG 01W -ONE-LINE DIAGRAM -REVISED (2 OF 4)
478	OF 693	01WEP613	BLDG 01W -ONE-LINE DIAGRAM -REVISED (3 OF 4)
479	OF 693	01WEP614	BLDG 01W -ONE-LINE DIAGRAM -REVISED (4 OF 4)
480	OF 693	02EP601	BLDG 02 -PARTIAL ONE-LINE DIAGRAM -EXISTING (1 OF 2)
481	OF 693	02EP602	BLDG 02 -PARTIAL ONE-LINE DIAGRAM -EXISTING (2 OF 2)
482	OF 693	02EP611	BLDG 02 -ONE-LINE DIAGRAM -REVISED (1 OF 3)
483	OF 693	02EP612	BLDG 02 -ONE-LINE DIAGRAM -REVISED (2 OF 3)
484	OF 693	02EP613	BLDG 02 -ONE-LINE DIAGRAM -REVISED (3 OF 3)
485	OF 693	03EP601	BLDG 03 -ONE-LINE DIAGRAM -EXISTING
486	OF 693	03EP611	BLDG 03 -ONE-LINE DIAGRAM -REVISED
487	OF 693	04EP601	BLDG 04 -ONE-LINE DIAGRAM
488	OF 693	05EP601	BLDG 05 -ONE-LINE DIAGRAM
489	OF 693	06EP601	BLDG 06 -ONE-LINE DIAGRAM -EXISTING
490	OF 693	06EP611	BLDG 06 -ONE-LINE DIAGRAM -REVISED
491	OF 693	07EP601	BLDG 07 -ONE-LINE DIAGRAM
492	OF 693	08EP601	BLDG 08 -ONE-LINE DIAGRAM -EXISTING
493	OF 693	08EP611	BLDG 08 -ONE-LINE DIAGRAM -REVISED
494	OF 693	09EP601	BLDG 09 -ONE-LINE DIAGRAM
495	OF 693	15EP601	BLDG 15 -ONE-LINE DIAGRAM
496	OF 693	20EP601	BLDG 20 -ONE-LINE DIAGRAM
497	OF 693	23REP601	BLDG 23R -ONE-LINE DIAGRAM -EXISTING
498	OF 693	23REP611	BLDG 23R -ONE-LINE DIAGRAM -REVISED
499	OF 693	25EP601	BLDG 25 -ONE-LINE DIAGRAM
500	OF 693	28EP601	BLDG 28 -ONE-LINE DIAGRAMS
501	OF 693	34EP601	BLDG 34 -ONE-LINE DIAGRAMS
502	OF 693	52EP601	BLDG 52 -ONE-LINE DIAGRAM
503	OF 693	TR12EP601	BLDG TR1&2 -ONE-LINE DIAGRAM
504	OF 693	TR345EP601	BLDG TR3,4,&5 -ONE-LINE DIAGRAM
505	OF 693	EP701	TYPICAL ELECTRICAL SCHEDULES
506	OF 693	EP702	ELECTRICAL SCHEDULES
507	OF 693	01EP701	BLDG 01 -ELECTRICAL SCHEDULES
508	OF 693	01EP702	BLDG 01 -ELECTRICAL SCHEDULES
509	OF 693	01EP703	BLDG 01 -ELECTRICAL SCHEDULES
510	OF 693	01EP704	BLDG 01 -ELECTRICAL SCHEDULES
511	OF 693	01SEP701	BLDG 01S -ELECTRICAL SCHEDULES
512	OF 693	01SEP702	BLDG 01S -ELECTRICAL SCHEDULES
513	OF 693	01SEP703	BLDG 01S -ELECTRICAL SCHEDULES
514	OF 693	01SEP704	BLDG 01S -ELECTRICAL SCHEDULES
515	OF 693	01SEP705	BLDG 01S -ELECTRICAL SCHEDULES
516	OF 693	01WEP701	BLDG 01W -ELECTRICAL SCHEDULES
517	OF 693	01WEP702	BLDG 01W -ELECTRICAL SCHEDULES
518	OF 693	01WEP703	BLDG 01W -ELECTRICAL SCHEDULES
519	OF 693	02EP701	BLDG 02 -ELECTRICAL SCHEDULES
520	OF 693	02EP702	BLDG 02 -ELECTRICAL SCHEDULES
521	OF 693	03EP701	BLDG 03 -ELECTRICAL SCHEDULES
522	OF 693	04EP701	BLDG 04 -ELECTRICAL SCHEDULES
523	OF 693	05EP701	BLDG 05 -ELECTRICAL SCHEDULES
524	OF 693	06EP701	BLDG 06 -ELECTRICAL SCHEDULES
525	OF 693	07EP701	BLDG 07 -ELECTRICAL SCHEDULES
526	OF 693	08EP701	BLDG 08 -ELECTRICAL SCHEDULES
527	OF 693	09EP701	BLDG 09 -ELECTRICAL SCHEDULES
528	OF 693	20EP701	BLDG 20 -ELECTRICAL SCHEDULES
529	OF 693	23REP701	BLDG 23R -ELECTRICAL SCHEDULES
530	OF 693	25EP701	BLDG 25 -ELECTRICAL SCHEDULES
531	OF 693	28EP701	BLDG 28 -ELECTRICAL SCHEDULES
532	OF 693	34EP701	BLDG 34 -ELECTRICAL SCHEDULES
533	OF 693	TR1EP701	BLDG TR1 -ELECTRICAL SCHEDULES
534	OF 693	TR3EP701	BLDG TR3 -ELECTRICAL SCHEDULES
TELECOMMUNICATIONS			
535	OF 693	TNG000	SHEET INDEX
536	OF 693	TNG001	ABBREVIATIONS AND GENERAL NOTES
537	OF 693	TNG002	TELECOMMUNICATIONS LEGENDS
538	OF 693	TNG003	TELECOMMUNICATIONS FIBER GENERAL NOTES
539	OF 693	01TN100G	BLDG 01 -LEVEL 00G -TELECOMMUNICATIONS PLAN
540	OF 693	01TN101	BLDG 01 -LEVEL 01 -TELECOMMUNICATIONS PLAN
541	OF 693	01TN102	BLDG 01 -LEVEL 02 -TELECOMMUNICATIONS PLAN
542	OF 693	01TN103	BLDG 01 -LEVEL 03 -TELECOMMUNICATIONS PLAN
543	OF 693	01TN104	BLDG 01 -LEVEL 04 -TELECOMMUNICATIONS PLAN
544	OF 693	01ATN100G	BLDG 01A -LEVEL 00G -TELECOMMUNICATIONS PLAN
545	OF 693	01ATN101	BLDG 01A -LEVEL 01 -TELECOMMUNICATIONS PLAN
546	OF 693	01ATN102	BLDG 01A -LEVEL 02 -TELECOMMUNICATIONS PLAN
547	OF 693	01ATN103	BLDG 01A -LEVEL 03 -TELECOMMUNICATIONS PLAN
548	OF 693	01ATN104	BLDG 01A -LEVEL 04 -TELECOMMUNICATIONS PLAN

DRAWING INDEX

PAGE #		SHEET #	SHEET NAME
549	OF 693	01STN100B	BLDG 01S -LEVEL 00B -TELECOMMUNICATIONS PLAN
550	OF 693	01STN100G	BLDG 01S -LEVEL 00G -TELECOMMUNICATIONS PLAN
551	OF 693	01STN101	BLDG 01S -LEVEL 01 -TELECOMMUNICATIONS PLAN
552	OF 693	01STN102	BLDG 01S -LEVEL 02 -TELECOMMUNICATIONS PLAN
553	OF 693	01STN103	BLDG 01S -LEVEL 03 -TELECOMMUNICATIONS PLAN
554	OF 693	01STN104	BLDG 01S -LEVEL 04 -TELECOMMUNICATIONS PLAN
555	OF 693	01STN105	BLDG 01S -LEVEL 05 -TELECOMMUNICATIONS PLAN
556	OF 693	01STN106	BLDG 01S -LEVEL 06 -TELECOMMUNICATIONS PLAN
557	OF 693	01WTN100B	BLDG 01W -LEVEL 00B -TELECOMMUNICATIONS PLAN
558	OF 693	01WTN100G	BLDG 01W -LEVEL 00G -TELECOMMUNICATIONS PLAN
559	OF 693	01WTN101	BLDG 01W -LEVEL 01 -TELECOMMUNICATIONS PLAN
560	OF 693	01WTN102	BLDG 01W -LEVEL 02 -TELECOMMUNICATIONS PLAN
561	OF 693	01WTN103	BLDG 01W -LEVEL 03 -TELECOMMUNICATIONS PLAN
562	OF 693	01WTN104	BLDG 01W -LEVEL 04 -TELECOMMUNICATIONS PLAN
563	OF 693	02TN100B	BLDG 02 -LEVEL 00B -TELECOMMUNICATIONS PLAN
564	OF 693	02TN100G	BLDG 02 -LEVEL 00G -TELECOMMUNICATIONS PLAN
565	OF 693	02TN101	BLDG 02 -LEVEL 01 -TELECOMMUNICATIONS PLAN
566	OF 693	02TN102	BLDG 02 -LEVEL 02 -TELECOMMUNICATIONS PLAN
567	OF 693	03TN101	BLDG 03 -LEVEL 01 -TELECOMMUNICATIONS PLAN
568	OF 693	03TN102	BLDG 03 -LEVEL 02 -TELECOMMUNICATIONS PLAN
569	OF 693	04TN100	BLDG 04 -LEVEL 00 -TELECOMMUNICATIONS PLAN
570	OF 693	04TN101	BLDG 04 -LEVEL 01 -TELECOMMUNICATIONS PLAN
571	OF 693	04TN102	BLDG 04 -LEVEL 02 -TELECOMMUNICATIONS PLAN
572	OF 693	05TN100	BLDG 05 -LEVEL 00 -TELECOMMUNICATIONS PLAN
573	OF 693	05TN101	BLDG 05 -LEVEL 01 -TELECOMMUNICATIONS PLAN
574	OF 693	05TN102	BLDG 05 -LEVEL 02 -TELECOMMUNICATIONS PLAN
575	OF 693	06TN100	BLDG 06 -LEVEL 00 -TELECOMMUNICATIONS PLAN
576	OF 693	06TN101	BLDG 06 -LEVEL 01 -TELECOMMUNICATIONS PLAN
577	OF 693	06TN102	BLDG 06 -LEVEL 02 -TELECOMMUNICATIONS PLAN
578	OF 693	07TN100	BLDG 07 -LEVEL 00 -TELECOMMUNICATIONS PLAN
579	OF 693	07TN101	BLDG 07 -LEVEL 01 -TELECOMMUNICATIONS PLAN
580	OF 693	07TN102	BLDG 07 -LEVEL 02 -TELECOMMUNICATIONS PLAN
581	OF 693	07TN103	BLDG 07 -LEVEL 03 -TELECOMMUNICATIONS PLAN
582	OF 693	08TN100	BLDG 08 -LEVEL 00 -TELECOMMUNICATIONS PLAN
583	OF 693	08TN101	BLDG 08 -LEVEL 01 -TELECOMMUNICATIONS PLAN
584	OF 693	08TN102	BLDG 08 -LEVEL 02 -TELECOMMUNICATIONS PLAN
585	OF 693	08TN103	BLDG 08 - LEVEL 03 -TELECOMMUNICATIONS PLAN
586	OF 693	09TN100	BLDG 09 -LEVEL 00 -TELECOMMUNICATIONS PLAN
587	OF 693	09TN101	BLDG 09 -LEVEL 01 -TELECOMMUNICATIONS PLAN
588	OF 693	09TN102	BLDG 09 -LEVEL 02 -TELECOMMUNICATIONS PLAN
589	OF 693	12TN100G	BLDG 12 -LEVEL 00G -TELECOMMUNICATIONS PLAN
590	OF 693	12TN101	BLDG 12 -LEVEL 01 -TELECOMMUNICATIONS PLAN
591	OF 693	12TN102	BLDG 12 -LEVEL 02 -TELECOMMUNICATIONS PLAN
592	OF 693	20TN101	BLDG 20 -LEVEL 01 -TELECOMMUNICATIONS PLAN
593	OF 693	20TN102	BLDG 20 -LEVEL 02 -TELECOMMUNICATIONS PLAN
594	OF 693	23RTN100B	BLDG 23R -LEVEL 00B -TELECOMMUNICATIONS PLAN
595	OF 693	23RTN100G	BLDG 23R -LEVEL 00G -TELECOMMUNICATIONS PLAN
596	OF 693	23RTN101	BLDG 23R -LEVEL 01 -TELECOMMUNICATIONS PLAN
597	OF 693	23RTN102	BLDG 23R -LEVEL 02 -TELECOMMUNICATIONS PLAN
598	OF 693	25TN101	BLDG 25 -LEVEL 01 - TELECOMMUNICATIONS PLAN
599	OF 693	25TN102	BLDG 25 -LEVEL 02 - TELECOMMUNICATIONS PLAN
600	OF 693	25TN103	BLDG 25 -LEVEL 03 - TELECOMMUNICATIONS PLAN
601	OF 693	25TN104	BLDG 25 -LEVEL 04 - TELECOMMUNICATIONS PLAN
602	OF 693	25TN105	BLDG 25 -LEVEL 05 - TELECOMMUNICATIONS PLAN
603	OF 693	28TN101	BLDG 28 -LEVEL 01 -TELECOMMUNICATIONS PLAN
604	OF 693	34TN100	BLDG 34 -LEVEL 00 -TELECOMMUNICATIONS PLAN
605	OF 693	34TN101	BLDG 34 -LEVEL 01 -TELECOMMUNICATIONS PLAN
606	OF 693	TR1TN101	BLDG TR1 -LEVEL 01 -TELECOMMUNICATION PLAN
607	OF 693	TR2TN101	BLDG TR2 -LEVEL 01 -TELECOMMUNICATIONS PLAN
608	OF 693	TR3TN101	BLDG TR3 -LEVEL 01 -TELECOMMUNICATIONS PLAN
609	OF 693	TR4TN101	BLDG TR4 -LEVEL 01 -TELECOMMUNICATIONS PLAN
610	OF 693	TR5TN101	BLDG TR5 -LEVEL 01 -TELECOMMUNICATIONS PLAN
611	OF 693	01TN400Ga	BLDG 01 -LEVEL 00G -ENLARGED TELECOMMUNICATIONS PLANS
612	OF 693	01TN400Gb	DATA CENTER -DEMOLITION FLOOR PLAN -PHASE 1B
613	OF 693	01TN400Gc	DATA CENTER -DEMOLITION OVERHEAD PLAN -PHASE 1B
614	OF 693	01TN400Gd	DATA CENTER -TELECOMMUNICATIONS PLAN -PHASE 1B
615	OF 693	01TN400Ge	DATA CENTER -OVERHEAD PLAN -PHASE 1B
616	OF 693	01TN400Gf	DATA CENTER -DEMOLITION FLOOR PLAN -PHASE 2A
617	OF 693	01TN400Gg	DATA CENTER -DEMOLITION OVERHEAD PLAN -PHASE 2A
618	OF 693	01TN400Gh	DATA CENTER -TELECOMMUNICATIONS PLAN -PHASE 2A
619	OF 693	01TN400Gi	DATA CENTER -OVERHEAD PLAN -PHASE 2A
620	OF 693	01TN400Gj	DATA CENTER -DEMOLITION FLOOR PLAN -PHASE 2B
621	OF 693	01TN400Gk	DATA CENTER -DEMOLITION OVERHEAD PLAN -PHASE 2B
622	OF 693	01TN400Gl	DATA CENTER -TELECOMMUNICATIONS PLAN -PHASE 2B
623	OF 693	01TN400Gm	DATA CENTER -OVERHEAD PLAN -PHASE 2B
624	OF 693	01TN401	BLDG 01 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
625	OF 693	01TN402	BLDG 01 -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
626	OF 693	01TN403	BLDG 01 -LEVEL 03 -ENLARGED TELECOMMUNICATIONS PLANS
627	OF 693	01ATN400G	BLDG 01A -LEVEL 00G -ENLARGED TELECOMMUNICATIONS PLANS
628	OF 693	01ATN402	BLDG 01A -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
629	OF 693	01ATN403	BLDG 01A -LEVEL 03 -ENLARGED TELECOMMUNICATIONS PLANS
630	OF 693	01STN400Ba	BLDG 01S -LEVEL 00B -ENLARGED TELECOMMUNICATIONS PLANS
631	OF 693	01STN400Bb	BLDG 01S -LEVEL 00B -ENLARGED TELECOMMUNICATIONS PLANS
632	OF 693	01STN400Ga	BLDG 01S -LEVEL 00G -ENLARGED TELECOMMUNICATIONS PLANS
633	OF 693	01STN400Gb	BLDG 01S -LEVEL 00G -ENLARGED TELECOMMUNICATIONS PLANS
634	OF 693	01STN401a	BLDG 01S -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
635	OF 693	01STN401b	BLDG 01S -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
636	OF 693	01STN401c	BLDG 01S -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
637	OF 693	01STN401d	BLDG 01S -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
638	OF 693	01STN402a	BLDG 01S -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
639	OF 693	01STN402b	BLDG 01S -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
640	OF 693	01STN403a	BLDG 01S -LEVEL 03 -ENLARGED TELECOMMUNICATIONS PLANS
641	OF 693	01STN403b	BLDG 01S -LEVEL 03 -ENLARGED TELECOMMUNICATIONS PLANS
642	OF 693	01STN404a	BLDG 01S -LEVEL 04 -ENLARGED TELECOMMUNICATIONS PLANS
643	OF 693	01STN404b	BLDG 01S -LEVEL 04 -ENLARGED TELECOMMUNICATIONS PLANS
644	OF 693	01STN405a	BLDG 01S -LEVEL 05 -ENLARGED TELECOMMUNICATIONS PLANS
645	OF 693	01STN405b	BLDG 01S -LEVEL 05 -ENLARGED TELECOMMUNICATIONS PLANS
646	OF 693	01STN406	BLDG 01S -LEVEL 06 -ENLARGED TELECOMMUNICATIONS PLANS
647	OF 693	01WTN400Ga	BLDG 01W -LEVEL 00G -ENLARGED TELECOMMUNICATIONS PLANS
648	OF 693	01WTN400Gb	BLDG 01W -LEVEL 00G -ENLARGED TELECOMMUNICATIONS PLANS
649	OF 693	01WTN401a	BLDG 01W -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
650	OF 693	01WTN401b	BLDG 01W -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
651	OF 693	01WTN402a	BLDG 01W -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
652	OF 693	01WTN402b	BLDG 01W -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
653	OF 693	01WTN403a	BLDG 01W -LEVEL 03 -ENLARGED TELECOMMUNICATIONS PLANS
654	OF 693	01WTN403b	BLDG 01W -LEVEL 03 -ENLARGED TELECOMMUNICATIONS PLANS
655	OF 693	02TN400B	BLDG 02 -LEVEL 00B -ENLARGED TELECOMMUNICATIONS PLANS
656	OF 693	02TN400G	BLDG 02 -LEVEL 00G -ENLARGED TELECOMMUNICATIONS PLANS
657	OF 693	03TN401	BLDG 03 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
658	OF 693	04TN400a	BLDG 04 -LEVEL 00 -ENLARGED TELECOMMUNICATIONS PLANS
659	OF 693	04TN400b	BLDG 04 -LEVEL 00 -ENLARGED TELECOMMUNICATIONS PLANS

DRAWING INDEX

PAGE #		SHEET #	SHEET NAME
660	OF 693	05TN400	BLDG 05 -LEVEL 00 -ENLARGED TELECOMMUNICATIONS PLANS
661	OF 693	06TN401	BLDG 06 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
662	OF 693	07TN400	BLDG 07 -LEVEL 00 -ENLARGED TELECOMMUNICATIONS PLANS
663	OF 693	08TN400	BLDG 08 -LEVEL 00 -ENLARGED TELECOMMUNICATIONS PLANS
664	OF 693	09TN402	BLDG 09 -LEVEL 02 -ENLARGED TELECOMMUNICATION PLANS
665	OF 693	12TN401	BLDG 12 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
666	OF 693	12TN402	BLDG 12 -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
667	OF 693	20TN401a	BLDG 20 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
668	OF 693	20TN401b	BLDG 20 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
669	OF 693	20TN402a	BLDG 20 -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
670	OF 693	20TN402b	BLDG 20 -LEVEL 02 -ENLARGED TELECOMMUNICATIONS PLANS
671	OF 693	23RTN400B	BLDG 23R -LEVEL 00B -ENLARGED TELECOMMUNICATIONS PLANS
672	OF 693	23RTN401	BLDG 23R -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
673	OF 693	25TN401	BLDG 25 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLAN
674	OF 693	28TN401	BLDG 28 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
675	OF 693	34TN400	BLDG 34 -LEVEL 00 -ENLARGED TELECOMMUNICATIONS PLANS
676	OF 693	TR1TN401a	BLDG TR1 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
677	OF 693	TR1TN401b	BLDG TR1 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
678	OF 693	TR2TN401	BLDG TR2 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
679	OF 693	TR3TN401	BLDG TR3 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
680	OF 693	TR4TN401	BLDG TR4 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
681	OF 693	TR5TN401	BLDG TR5 -LEVEL 01 -ENLARGED TELECOMMUNICATIONS PLANS
682	OF 693	TN501	TELECOMMUNICATIONS DETAILS
683	OF 693	TN502	TELECOMMUNICATIONS DETAILS
684	OF 693	TN503	TELECOMMUNICATIONS DETAILS
685	OF 693	TN504	TELECOMMUNICATIONS DETAILS
686	OF 693	TN505	TELECOMMUNICATIONS DETAILS
687	OF 693	TN506	TELECOMMUNICATIONS DETAILS
688	OF 693	TN507	TELECOMMUNICATIONS DETAILS
689	OF 693	TN508	TELECOMMUNICATIONS DETAILS
690	OF 693	TN509	TELECOMMUNICATIONS DETAILS
691	OF 693	TN510	TELECOMMUNICATIONS DETAILS
692	OF 693	TN601	FIBER RISER DIAGRAM
693	OF 693	TN701	TELECOMMUNICATIONS SCHEDULES

Revisions: Date:

CONSULTANT

ENGINEERING DISCIPLINE:

ARCHITECT/ENGINEER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S. SUITE 300
KENT, WA 98032

SDB SPEESDESIGNBUILD

STAMP

10000 REGISTERED ARCHITECT
JAMES M. KING
STATE OF WASHINGTON
9/3/2025

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
DRAWING INDEX	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700

Building Number: -

Approved:

Location: VA HUNTINGTON
1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn
09/03/2025	JW/MA	RB

Drawing Number: **G-003**

BIM 360://581-22-700 VAHuntington EHRM/GENERAL SHEETS.rvt
27/06/2025 10:20:54 am

VA FORM 08 - 6231

DRAWING NO.	DRAWING TITLE
C-001	CIVIL SHEET INDEX AND GENERAL NOTES
C-002	GENERAL NOTES AND LEGEND
CS100	OVERALL CIVIL SITE PLAN
CG100	OVERALL EROSION CONTROL PLAN
CG101	EROSION CONTROL GENERAL NOTES AND DETAILS
CU250	CIVIL UTILITY CONSTRUCTION DETAILS
CU300	OVERALL FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
CU301	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
CU302	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
CU303	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
CU304	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
CU305	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
CU306	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
CU307	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
CU500	COMMUNICATION DUCTBANK DETAILS
CU501	COMMUNICATION TRENCHING DETAILS
CU502	BUILDING CONNECTION DETAILS

ABBREVIATIONS

AAF	AIR ASSISTED FIBER	GPR	GROUND PENETRATING RADAR	PT	POINT OR POINT OF TANGENCY
ABAN	ABANDONED			PVC	POLYVINYL CHLORIDE PIPE
APROX	APPROXIMATELY	HDPE	HIGH DENSITY POLYETHYLENE PIPE	PVI	POINT OF VERTICAL INTERSECTION
APWA	AMERICAN PUBLIC WORKS ASSOCIATION	HP	HIGH POINT		
ASPH	ASPHALT CONCRETE	HMA	HOT MIX ASPHALT	R	RADIUS
AVE	AVENUE	HORIZ	HORIZONTAL	RJ	RESTRAINED JOINT
AWWA	AMERICAN WATER WORKS ASSOCIATION	HWY	HIGHWAY	RT	RIGHT
BLDG	BUILDING	ID	INSIDE DIAMETER	S	SOUTH
BMP	BEST MANAGEMENT PRACTICES	IE	INVERT ELEVATION	SD	STORM DRAIN
		IN	INCH(ES)	SDCB	STORM DRAIN CATCH BASIN
BOT	BOTTOM	ISP	INTERNET SERVICE PROVIDER	SDCO	STORM DRAIN CLEANOUT
BVC	BEGIN VERTICAL CURVE			SDMH	STORM DRAIN MANHOLE
				SE	SOUTHEAST
CL	CENTERLINE	LBS	POUNDS	SEC	SECTION
CDF	CONTROLLED DENSITY FILL	LF	LINEAR FEET	SF	SQUARE FOOT
CFS	CUBIC FEET PER SECOND	LT	LEFT	SMFO	SINGLE MODE FIBER OPTICS
CLR	CLEAR	LP	LOW POINT	SPEC	SPECIFICATION
CM	CENTIMETER			SS	SANITARY SEWER
CMP	CORRUGATED METAL PIPE	MAX	MAXIMUM	SSFM	SANITARY SEWER FORCE MAIN
COMM	COMMUNICATION(S)	MCR	MAIN COMPUTER ROOM		
CONC	PORTLAND CONCRETE	MH	MANHOLE	SSMH	SANITARY SEWER MANHOLE
COR	CONTRACTING OFFICER'S REPRESENTATIVE	MIN	MINIMUM	ST	STREET
		MISC	MISCELLANEOUS	STA	STATION
CPEP	CORRUGATED POLYETHELENE PIPE (N-12)	MJ	MECHANICAL JOINT	STD	STANDARD
				SW	SOUTHWEST
CSBC	CRUSHED SURFACING BASE COURSE	N	NORTH	SWPPP	STORMWATER POLLUTION PREVENTION PLAN
		NAD	NORTH AMERICAN DATUM		
CSTC	CRUSHED SURFACING TOP COURSE	NAVD	NORTH AMERICAN VERTICAL DATUM	TAN	TANGENT POINT
CTR	CENTER	NE	NORTHEAST	TDR	TELECOMMUNICATIONS DISTRIBUTION ROOM
CY	CUBIC YARDS	NOM	NOMINAL		
		NTS	NOT TO SCALE	TDU	TUBE CABLE DISTRIBUTION UNIT
DDCV	DOUBLE DETECTOR CHECK VALVE	NW	NORTHWEST		
				TESC	TEMPORARY EROSION & SEDIMENT CONTROL
DI	DUCTILE IRON	OC	ON CENTER		
DIA or Ø	DIAMETER	OD	OUTSIDE DIAMETER	TOC	TOP OF CURB
DWG	DRAWING	OSP	OUTSIDE PLANT	TR	TELECOMMUNICATIONS ROOM
		OS1	OPTICAL SINGLEMODE FIBER (LEGACY STANDARD)		
E	EAST				
EA	EACH	OS2	OPTICAL SINGLEMODE FIBER (LATEST STANDARD)	TYP	TYPICAL
EHRM	ELECTRONIC HEALTH RECORDS MODERNIZATION	OVHD	OVERHEAD	UFC	UNIFIED FACILITIES CRITERIA
EG	EXISTING GROUND			UG	UNDERGROUND
ELEC	ELECTRICAL	PC	POINT OF CURVATURE		
ELEV	ELEVATION	PE	PROJECT ENGINEER	VC	VERTICAL CURVE
EP	EDGE OF PAVEMENT	PI	POINT OF HORIZONTAL INTERSECTION	VERT	VERTICAL
ESMT	EASEMENT				
EVC	END VERTICAL CURVE	PHH	PHYSICAL HAND HOLE	W	WEST or WATER
EXIST	EXISTING	POC	POINT ON CURVE	WM	WATER METER
		POB	POINT OF BEGINNING	WSEL	WATER SURFACE ELEVATION
FG	FINISH GRADE	POP	POINT OF PRESENCE	W/	WITH
FL	FLANGE	PPM	PARTS PER MILLION		
FM	FORCE MAIN	PROP	PROPOSED		
FT	FEET				

GENERAL NOTES:

1. CONTRACTOR MUST COMPLY WITH ALL LOCAL, STATE AND FEDERAL LAWS PERTINENT TO THE WORK, AS DESCRIBED IN THE SPECIFICATIONS AND ON THESE DESIGN DRAWINGS. ALL WORKMANSHIP AND MATERIALS MUST BE IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
2. THE CONTRACTOR IS RESPONSIBLE FOR BECOMING FAMILIARIZED WITH THE EXISTING CONDITIONS AND VERIFYING CONSISTENCY WITH DESIGN DRAWINGS AND SPECIFICATIONS. THE CONTRACTOR MUST REPORT ANY DISCREPANCY TO THE CONTRACTING OFFICER IMMEDIATELY AND AWAIT FURTHER INSTRUCTIONS.
3. IT MUST BE THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN ALL APPLICABLE PERMITS, LICENSES AND CERTIFICATES, AND MAKE ALL REQUIRED AGENCY NOTIFICATIONS TO COMPLETE THE PROJECT. COMPLIANCE MUST BE AT ALL LEVELS: FEDERAL, STATE, AND LOCAL RELATING TO THE PERFORMANCE OF THE WORK.
4. PRIOR TO BEGINNING WORK AND PROCURING MATERIALS THAT COULD BE IMPACTED, CONTRACTOR MUST INSPECT AND CONFIRM ALL POINTS OF CONNECTIONS TO EXISTING UTILITIES OR SYSTEMS. POTHOLE WHERE NECESSARY TO VERIFY THE DRAWINGS AGAINST ALL APPLICABLE EXISTING CONDITIONS. NOTIFY THE CONTRACTING OFFICER IMMEDIATELY UPON DISCOVERY OF UNFORESEEN SITE CONDITIONS OR DISCREPANCIES.
5. CALL THE UNDERGROUND LOCATE LINE (811) A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATIONS, AND HIRE PRIVATE UTILITY LOCATE COMPANY TO CONFIRM PRESENCE OF EXISTING BURIED UTILITIES PRIOR TO EXCAVATION. LOCATIONS OF EXISTING UTILITIES SHOWN HEREIN HAVE BEEN ESTABLISHED BY FIELD SURVEY OR OBTAINED FROM AVAILABLE RECORDS AND SHOULD BE CONSIDERED APPROXIMATE ONLY AND NOT NECESSARILY COMPLETE. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO INDEPENDENTLY VERIFY THE ACCURACY OF ALL UTILITY LOCATIONS SHOWN, AND TO FURTHER DISCOVER AND AVOID ANY OTHER UTILITIES NOT SHOWN HEREON WHICH MAY BE AFFECTED BY THE IMPLEMENTATION OF THESE PLANS.
6. UTILITY SYSTEMS MUST BE CONSTRUCTED ACCORDING TO APPROVED PLANS. ANY DEVIATION FROM THE APPROVED PLANS WILL REQUIRE WRITTEN APPROVAL FROM THE CONTRACTING OFFICER.
6. CONTRACTOR MUST PREPARE CONSTRUCTION STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IN ACCORDANCE WITH ALL APPLICABLE FEDERAL AND STATE REQUIREMENTS AND OBTAIN PERMIT FOR PROPOSED WORK. CONTRACTOR MUST MAINTAIN AND UPDATE SWPPP AS REQUIRED THROUGHOUT CONSTRUCTION. A COPY OF THE APPROVED CONSTRUCTION SWPPP MUST BE ON THE JOB SITE WHENEVER CONSTRUCTION IS IN PROGRESS.
7. CONTRACTOR MUST TAKE ALL POSSIBLE CARE TO PROTECT PERSONAL AND ADJACENT PROPERTY AND TO ENSURE THE SAFETY OF THOSE INVOLVED DIRECTLY OR INDIRECTLY WITH THE WORK.
8. THE CONTRACTOR MUST PERFORM ANY AND ALL CUTTING, PATCHING, REPAIRING, RESTORING AND THE LIKE NECESSARY TO RETURN ALL SURFACES AFFECTED BY THE WORK TO THEIR ORIGINAL CONDITION.
9. DEMOLITION MUST BE TO THE LIMITS SHOWN ON THE PLANS. THE DEMOLITION LIMITS DEPICTED IN THE PLANS ARE BASED ON THE AVAILABLE INFORMATION OR SURVEY. DEMOLITION LIMITS MAY VARY DEPENDING ON CHANGED SITE CONDITIONS AT THE TIME OF CONSTRUCTION.
10. EXISTING PAVEMENT, LANDSCAPING, SURFACE OR SUBSURFACE FACILITIES, WITHIN OR ADJACENT TO THE CONTRACTOR'S WORK AREA OR INDICATED ON THE PLANS TO REMAIN MUST BE PROTECTED FROM DAMAGE. ANY FACILITIES DAMAGED BY THE CONTRACTOR'S ACTIVITIES MUST BE IMMEDIATELY REPAIRED TO MATCH ITS ORIGINAL CONDITION AND THE SATISFACTION OF THE CONTRACTING OFFICER AT NO ADDITIONAL COST TO THE GOVERNMENT.
11. ALL MATERIALS MUST BE NEW MATERIALS AND PURCHASED IN ACCORDANCE WITH THE BUY AMERICAN ACT.
12. WRITTEN DIMENSIONS IN SCHEDULES AND DRAWINGS TAKE PRECEDENCE OVER SCALED DRAWINGS. DO NOT SCALE DRAWINGS, AND BRING ALL DISCREPANCIES TO THE ATTENTION OF THE CONTRACTING OFFICER AND AWAIT FURTHER INSTRUCTIONS.
13. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE THE CONSTRUCTION PHASING AND STAGING. NO ADDITIONAL COST TO THE OWNER MUST BE PERMITTED FOR THE RELOCATION OF TRAILERS, STORED MATERIAL, REMOVAL AND REINSTALLATION OF BARRICADES, FENCING, OR ANY OTHER INCIDENTAL ITEMS THAT ARE REQUIRED AND NECESSARY TO ACCOMPLISH THE WORK UNDER THIS CONTRACT. COMPLETE RESTORATION BETWEEN CONSTRUCTION PHASES IS REQUIRED, UNLESS OTHERWISE DIRECTED BY THE CONTRACTING OFFICER.
14. THE CONTRACTOR MUST NOTIFY VA OF ANY WORK TO BE PERFORMED IN CONFINED SPACE. CONTRACTOR MUST CREATE AND SUBMIT INDIVIDUAL CONFINED SPACE WORK PLAN. CONTRACTOR MUST RECEIVE APPROVAL FROM VA PRIOR TO BEGINNING WORK.
15. ANY U.S.G.S. OR CAMPUS SURVEY MONUMENTS WITHIN THE LIMITS OF DEMOLITION OR CONSTRUCTION MUST BE PROTECTED. IF A MONUMENT IS IN DANGER OF BEING DESTROYED AND HAS NOT BEEN PROPERLY REFERENCED IN THE PLANS, THE CONTRACTOR MUST IMMEDIATELY NOTIFY THE CONTRACTING OFFICER. CONTRACTOR MUST REPAIR ANY DAMAGED BENCH MARKS IN ACCORDANCE WITH N.O.A.A. NATIONAL GEODETIC SURVEY GUIDELINES, AND TO THE SATISFACTION OF THE FACILITY'S G.I.S. BENCHMARK REPRESENTATIVE.
16. CONTRACTOR MUST PROVIDE AND MAINTAIN ACCESS, AT ALL TIMES DURING CONSTRUCTION, TO ALL EXISTING FACILITIES AND THOSE THAT MAY BE UNDER CONSTRUCTION IN THE IMMEDIATE VICINITY. FIRE TRUCK AND EMERGENCY VEHICLE ACCESS MUST NOT BE BLOCKED.
17. THE CONTRACTOR MUST BE SOLELY RESPONSIBLE FOR DETERMINING THE ADEQUACY OF EXISTING STRUCTURES AND UTILITIES TO SUPPORT CONSTRUCTION EQUIPMENT AND LOADS.
18. ALL DEVIATIONS FROM THESE PLANS MUST BE RECORDED ON A SET OF "AS-BUILT" OR RECORD REDLINE DRAWINGS. THE CONTRACTOR MUST SUBMIT "AS-BUILT" REDLINE DRAWINGS TO THE CONTRACTING OFFICER.
19. ALL DEMOLITION MATERIAL, INCLUDING PAVEMENT AND EXCESS SOIL, EXCEPT AS NOTED IN THE CONTRACT DRAWINGS / SPECIFICATIONS AND / OR SPECIFIED BY THE CONTRACTING OFFICER, MUST BECOME THE PROPERTY OF THE CONTRACTOR AND BE COMPLETELY REMOVED FROM VA CAMPUS AND DISPOSED OF BY THE CONTRACTOR.
20. THE CONTRACTOR MUST BE SOLELY RESPONSIBLE FOR AND MUST INSTALL AND MAINTAIN SHORING AND BRACING NECESSARY TO PROTECT WORKERS, UTILITIES AND OTHER IMPROVEMENTS AND EXCAVATIONS PER STATE AND FEDERAL REGULATIONS. THE CONTRACTOR MUST ALSO BE RESPONSIBLE FOR REMOVAL OF TEMPORARY SHORING AND BRACING.

EXISTING DATA NOTES:

1. THE EXISTING INFORMATION SHOWN ON THESE DRAWINGS HAVE BEEN PREPARED BASED UPON INFORMATION FURNISHED BY OTHERS. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, GOVERNMENT CANNOT ENSURE ACCURACY AND THUS IS NOT RESPONSIBLE FOR THE ACCURACY OF THAT INFORMATION OR FOR ANY ERRORS OR OMISSIONS WHICH MAY HAVE BEEN INCORPORATED INTO THESE DRAWINGS AS A RESULT.
2. THE ENGINEER ASSUMES NO LIABILITY FOR DAMAGES TO ANY UTILITIES DURING CONSTRUCTION. THE CONTRACTOR MUST BE SOLELY RESPONSIBLE TO REPAIR ANY DAMAGES THAT MAY OCCUR DURING CONSTRUCTION.
3. THE CONTRACTOR MAY CONDUCT TEST PITS (POTHOLE) TO VERIFY EXISTING CONDITIONS. THE CONTRACTOR MUST COORDINATE ALL TEST PITS WITH THE COR.

RESTORATION NOTES:

1. RESTORATION MUST BE IN ACCORDANCE WITH VA AND UFC REQUIREMENTS.
2. RESTORE ALL DISTURBED AREAS AS SHOWN ON PLANS OR AS DIRECTED BY THE CONTRACTING OFFICER.
3. REPAIR ALL UTILITIES DAMAGED BY CONSTRUCTION IN ACCORDANCE WITH CONTRACTING OFFICER'S REQUIREMENTS.
4. CONTRACTOR MUST RESTORE THE SITE AND ALL OTHER PHYSICAL FEATURES TO MATCH EXISTING CONDITIONS WHERE CONSTRUCTION WORK IS PERFORMED.
5. CONTRACTOR TO RETURN DISTURBED SOIL AND LANDSCAPING TO ITS ORIGINAL CONDITION.

DEMOLITION NOTES:

1. PERFORM DEMOLITION IN SUCH MANNER AS TO ELIMINATE HAZARDS TO PERSONS AND PROPERTY; TO MINIMIZE INTERFERENCE WITH USE OF ADJACENT AREAS, UTILITIES AND STRUCTURES OR INTERRUPTION OF USE OF SUCH UTILITIES; AND TO PROVIDE FREE PASSAGE TO AND FROM SUCH ADJACENT AREAS OR STRUCTURES.
2. PROVIDE SAFEGUARDS, INCLUDING WARNING SIGNS, BARRICADES, TEMPORARY FENCES, WARNING LIGHTS, AND OTHER SIMILAR ITEMS THAT ARE REQUIRED FOR PROTECTION OF ALL PERSONNEL DURING DEMOLITION AND REMOVAL OPERATIONS.
3. MAINTAIN FENCES, BARRICADES, LIGHTS AND OTHER SIMILAR ITEMS AROUND EXPOSED EXCAVATIONS UNTIL SUCH EXCAVATIONS HAVE BEEN COMPLETELY FILLED.
4. PREVENT SPREAD OF FLYING PARTICLES AND DUST. SPRINKLE RUBBISH AND DEBRIS WITH WATER TO KEEP DUST TO A MINIMUM. DO NOT USE WATER IF IT RESULTS IN HAZARDOUS OR OBJECTIONABLE CONDITIONS SUCH AS, BUT NOT LIMITED TO; ICE, FLOODING OR POLLUTION. VACUUM, SWEEP, AND DUST THE WORK AREA DAILY.
5. BEFORE BEGINNING ANY DEMOLITION WORK, THE CONTRACTOR MUST SURVEY THE SITE AND EXAMINE THE DRAWINGS AND SPECIFICATIONS TO DETERMINE THE EXTENT OF THE WORK. THE CONTRACTOR MUST TAKE NECESSARY PRECAUTIONS TO AVOID DAMAGES TO EXISTING ITEMS TO REMAIN IN PLACE, TO BE REUSED, OR TO REMAIN THE PROPERTY OF THE MEDICAL CENTER; AND DAMAGED ITEMS MUST BE REPAIRED OR REPLACED AS APPROVED BY THE CONTRACTING OFFICER REPRESENTATIVE (COR). THE CONTRACTOR MUST COORDINATE THE WORK WITH ALL OTHER WORK AND MUST CONSTRUCT AND MAINTAIN SHORING, BRACING, AND SUPPORTS AS REQUIRED. THE CONTRACTOR MUST ENSURE THAT STRUCTURAL ELEMENTS ARE NOT OVERLOADED AND MUST BE RESPONSIBLE FOR INCREASING STRUCTURAL SUPPORTS OR ADDING NEW SUPPORTS AS MAY BE REQUIRED AS A RESULT OF ANY CUTTING, REMOVAL, OR DEMOLITION WORK PERFORMED.
6. DEMOLISH AND REMOVE OUTSIDE UTILITY SERVICE LINES SHOWN TO BE REMOVED.
7. REMOVE ABANDONED OUTSIDE UTILITY LINES THAT WOULD INTERFERE WITH INSTALLATION OF NEW UTILITY LINES AND NEW CONSTRUCTION.
8. COMPLETELY DEMOLISH AND REMOVE BUILDINGS AND STRUCTURES, INCLUDING ALL APPURTENANCES RELATED OR CONNECTED THERETO, AS NOTED BELOW:

8.A. AS REQUIRED FOR INSTALLATION OF NEW UTILITY SERVICE LINES.

8.B. TO FULL DEPTH WITHIN AN AREA DEFINED BY HYPOTHETICAL LINES LOCATED 5 FT (1500 MM) OUTSIDE BUILDING LINES OF NEW STRUCTURES.

9. ALL WASTE DEBRIS, UNSUITABLE, AND EXCESS MATERIAL MUST BE REMOVED FROM THE SITE AND LAWFULLY DISPOSED OF. DEBRIS, INCLUDING BRICK, CONCRETE STONE, METALS AND SIMILAR MATERIALS MUST BECOME PROPERTY OF THE CONTRACTOR AND MUST BE DISPOSED OF BY THE CONTRACTOR DAILY, OFF THE MEDICAL CENTER TO AVOID ACCUMULATION AT THE DEMOLITION SITE. MATERIALS THAT CANNOT BE REMOVED DAILY MUST BE STORED IN AREAS SPECIFIED BY THE CONTRACTING OFFICERS REPRESENTATIVE. CONTRACTOR MUST NOTIFY ENGINEER IMMEDIATELY IF MATERIALS UNCOVERED DURING ANY PART OF THE WORK APPEAR TO BE CONTAMINATED. ALL LOCAL, STATE AND FEDERAL LAWS MUST PREVAIL IN THE EVENT OF CONTAMINATED MATERIALS.
10. BREAK UP CONCRETE SLABS BELOW GRADE THAT DO NOT REQUIRE REMOVAL FROM PRESENT LOCATION INTO PIECES NOT EXCEEDING 24 INCHES (600 MM) SQUARE TO PERMIT DRAINAGE. CONTRACTOR MUST DISPOSE OF DEBRIS IN COMPLIANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL PERMITS, RULES AND/OR REGULATIONS.

TRAFFIC MANAGEMENT NOTES:

1. ALL ROADWAYS MUST REMAIN OPEN DURING CONSTRUCTION, UNLESS OTHERWISE APPROVED BY THE CONTRACTING OFFICER. ROADWAY CLOSURE DURING CONSTRUCTION REQUIRES THE CONTRACTOR SUBMIT A TRAFFIC CONTROL PLAN FOR REVIEW AND APPROVAL IN ADVANCE. IF REQUIRED, ALL TEMPORARY TRAFFIC CONTROL DEVICES MUST BE IN ACCORDANCE WITH THE MOST CURRENT EDITION OF "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS".
2. THE CONTRACTOR MUST MAINTAIN A MINIMUM OF ONE MOVING LANE ALONG ROADWAYS AT ALL TIMES, EXCEPT WHERE GIVEN PERMISSION BY THE VAMC AND CONTRACTING OFFICERS REPRESENTATIVE.
3. THE CONTRACTOR MUST PROVIDE ALL SIGNAGE, BARRICADES, CAUTION TAPE, CONES AND BARRELS REQUIRED TO FACILITATE A SAFE LANE OR SIDEWALK CLOSURE.
4. PEDESTRIAN ACCESS MUST BE MAINTAINED AND MANAGED DURING SIDEWALK AND CROSSWALK CLOSURES.
5. ACCESS TO ALL ROADWAYS, DRIVEWAYS AND LOADING RAMPS MUST BE MAINTAINED DAILY AFTER CONSTRUCTION ACTIVITIES HAVE CONCLUDED.
6. THE CONTRACTOR MUST COORDINATE ANY ROADWAY, DRIVEWAY, LOADING RAMP AND/OR SIDEWALK CLOSURES WITH THE VAMC PRIOR TO PERFORMING WORK.
7. ALL ROAD CLOSURES MUST BE OUTSIDE NORMAL WORKING HOURS OF 8:00 AM TO 5:00 PM MONDAY THROUGH FRIDAY. ROAD CLOSURES AND TRAFFIC CONTROL PLAN MUST BE APPROVED BY COR PRIOR TO CONSTRUCTION. CONTRACTOR TO MAINTAIN ONE ACCESS TO THE EMERGENCY ROOM AMBULANCE BAY AT ALL TIMES.

GENERAL UTILITY NOTES:

1. PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR MUST VERTICALLY AND HORIZONTALLY FIELD LOCATE BY POTHOLING AND SURVEY ALL PROPOSED UTILITY CONFLICTS AND CROSSINGS. IF THE EXISTING UTILITY LOCATION DIFFERS FROM WHAT IS SHOWN ON THE PLANS, THE CONTRACTOR MUST NOTIFY THE CONTRACTING OFFICER AND/OR CONTRACTING OFFICER'S REPRESENTATIVE IMMEDIATELY AND AWAIT FURTHER INSTRUCTIONS.
2. THE CONTRACTOR IS ADVISED THAT ALL EXISTING UNDERGROUND UTILITIES, CABLES, DUCTS, MANHOLES, ETC. (UNDERGROUND FACILITIES) SHOWN ON PLANS WERE LOCATED USING THE BEST INFORMATION AVAILABLE. INFORMATION SHOWN ON THE DRAWING CONCERNING TYPE, SIZE AND LOCATION OF UNDERGROUND UTILITIES IS NOT GUARANTEED TO BE ACCURATE OR ALL-INCLUSIVE, AND IS PROVIDED FOR INFORMATIONAL PURPOSES ONLY. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR LOCATING AND PROTECTING ALL UTILITIES. CONTRACTOR MUST BE RESPONSIBLE FOR CONTACTING GOVERNMENT UTILITY OWNERS TO IDENTIFY UNDERGROUND UTILITIES AND/OR CABLES WITHIN THE PROJECT LIMITS AND STAGING AREAS. THE CONTRACTOR MUST ASSIST UTILITY OWNERS IN EFFORTS TO FIELD VERIFY UNDERGROUND UTILITIES. CONTRACTOR MUST ALSO REVIEW ALL UTILITIES WITH THE CAMPUS MAINTENANCE STAFF PRIOR TO BEGINNING WORK. PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY, THE CONTRACTOR MUST CONDUCT A FIELD UTILITY LOCATION SURVEY USING ELECTRONIC, MAGNETIC OR OTHER UNDERGROUND UTILITY LOCATING PRACTICES. UTILITY OWNERS MUST BE NOTIFIED AND MUST HAVE THE OPTION TO ACCOMPANY THIS FIELD INVESTIGATION. EXPLORATORY EXCAVATIONS IN THE VICINITY OF EXISTING UNDERGROUND UTILITIES, PARTICULARLY THOSE ASSOCIATED WITH OPERATING NAVIGATIONAL AIDS, MUST BE CARRIED OUT WITH HAND TOOLS UNTIL THE EXACT CHARACTER AND LOCATION OF SUCH FACILITIES ARE DETERMINED. ALL INFORMATION SO OBTAINED FROM THIS UTILITY LOCATION SURVEY MUST BE FURNISHED TO THE CONTRACTING OFFICER AND/OR CONTRACTING OFFICER'S REPRESENTATIVE AND THE A/E PRIOR TO CONSTRUCTION.
3. ALL UNDERGROUND CABLE, UTILITIES, AND ASSOCIATED STRUCTURES MUST BE PROTECTED FROM DAMAGE BY THE CONTRACTOR. ANY DAMAGE TO EXISTING UNDERGROUND CABLES AND/OR UTILITIES CAUSED BY THE CONTRACTOR (REGARDLESS OF WHETHER THEY WERE LOCATED OR NOT BY THE CAMPUS, UTILITY COMPANY, ETC.) MUST BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE AND TO THE SATISFACTION OF THE UTILITY OWNER'S AUTHORIZED REPRESENTATIVES. ALL EXISTING UTILITIES, CABLE, DUCTS, EQUIPMENT, DEVICES, ETC. OUTSIDE THE AREA OF DEMOLITION OR CONSTRUCTION LIMITS WHICH ARE DAMAGED OR DISRUPTED AS A RESULT OF THE CONTRACTOR'S OPERATIONS, MUST BE IMMEDIATELY REPAIRED AT THE EXPENSE OF THE CONTRACTOR AND TO THE SATISFACTION OF THE UTILITY OWNER'S AUTHORIZED REPRESENTATIVE.
4. ALL UTILITY OUTAGES MUST BE SCHEDULED AND APPROVED THROUGH THE COR (CONTRACTING OFFICER) PER THE APPLICABLE OUTAGE NOTIFICATION REQUIREMENTS.
5. UNLESS ALREADY SPECIFIED IN THE CONTRACT DRAWINGS, CONTRACTOR MUST RETROFIT ALL EXISTING UTILITY ACCESS POINTS TO BRING FLUSH WITH FINISHED SURFACE WITHIN AREAS OF WORK IN WHICH THE EXISTING GRADE IS MODIFIED BY CONSTRUCTION. THIS WORK IS CONSIDERED PART OF THE CONTRACTED SCOPE, AND APPLIES TO EXISTING UTILITIES THAT ARE NOT TO BE DEMOLISHED OR ABANDONED WITHIN THE PROJECT LIMITS.
6. ALL MATERIALS, WORKMANSHIP, AND TESTING MUST BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CONTRACT SPECIFICATIONS.
7. FIELD VERIFY LOCATION (INCLUDING POT HOLING FOR VERTICAL DEPTH) OF EXISTING UTILITIES AND INVERT ELEVATIONS OF THE POINT OF CONNECTION PRIOR TO CONSTRUCTION.
8. COMPRESSIBLE MATERIALS:
   FOR USE IN AREAS ABOVE BURIED PIPES WHERE OTHER PIPES ARE CROSSING WITH LESS THAN 1'-0" VERTICAL SEPARATION OR WHERE CALLED OUT ON DRAWINGS: POLYETHYLENE PLASTIC FOAM IN ACCORDANCE WITH FEDERAL SPECIFICATION PPP-C-1752C, TYPE 1, CLASS 2, SUCH AS "ETHAFOAM". AT PIPE CROSSINGS, MATERIAL MUST BE A MIN OF 2-INCH THK, 2-FT WIDE, AND 4-FT LONG, BUT MUST BE A MINIMUM OF 6-IN WIDER THAT OUTSIDE DIAMETER OF PIPE ON EACH SIDE.
9. GATE VALVES INSTALLED UNDER PAVEMENT MUST HAVE A 2-INCH OPERATING NUT AND VALVE BOX W/ COVER FLUSH WITH ASPHALT SURFACE. GATE VALVES INSTALLED IN AREAS WHERE THE SURFACE IS OTHER THAN ASPHALT OR CONCRETE, TOP OF VALVE BOX MUST BE EMBEDDED IN A CAST-IN-PLACE COLLAR THAT IS 3'-0" MIN SQUARE BY 8-INCHES THICK PLACED ON 4-INCH THICK (MIN) COMPACTED BASE COURSE WITH SURFACE FLUSH WITH EXISTING GRADE
10. TESTING OF ALL INSTALLED UTILITY LINES AND STRUCTURES MUST BE IN ACCORDANCE WITH CONTRACT SPECIFICATIONS.
11. ANY REVISIONS TO THESE PLANS, ONCE APPROVED BY THE ENGINEER OF RECORD, MUST BE REVIEWED AND RE-APPROVED BY THE CONTRACTING OFFICER.
12. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR UTILITY TRENCH SAFETY INCLUDING SHORING (IF REQUIRED) DESIGNED BY A REGISTERED ENGINEER AND WORKER SAFETY WHILE WORKING WITHIN THE TRENCH.

GRADING & BACKFILL NOTES:

1. BACKFILL MATERIAL MUST NOT CONTAIN PETROLEUM PRODUCTS, OR SUBSTANCES WHICH ARE HAZARDOUS, DANGEROUS, TOXIC, OR WHICH OTHERWISE VIOLATE ANY STATE, FEDERAL. OR LOCAL LAW, ORDINANCE, CODE, REGULATION, RULE, ORDER, OR STANDARD.
2. GENERAL SITE BACKFILL MATERIAL MUST MEET THE VA REQUIREMENTS FOR EARTHWORK AND BE IN ACCORDANCE WITH THE RECOMMENDATIONS IN THE GEOTECHNICAL REPORT FOR THIS PROJECT.
3. SLOPE FINISH GRADE SURFACES UNIFORMLY BETWEEN ELEVATIONS SHOWN ON DRAWINGS UNLESS SPECIFIED OTHERWISE. GRADE AREAS TO ELIMINATE LOW SPOTS AND MAINTAIN POSITIVE DRAINAGE AWAY FROM BUILDING AND STRUCTURES.

SECURITY:

1. THE CONTRACTOR MUST COMPLY WITH ALL REQUIREMENTS OF THE VA SECURITY PROGRAM.
2. THE CONTRACTOR MUST BE RESPONSIBLE FOR BRIEFING ALL CONTRACTOR'S PERSONNEL OF THE VA SECURITY REQUIREMENTS. ALL NEW CONTRACTOR EMPLOYEES MUST BE BRIEFED ON THESE REQUIREMENTS PRIOR TO WORKING IN THE CONSTRUCTION AREA.
3. CONTRACTOR IS SOLELY RESPONSIBLE FOR SECURING JOBSITE AT ALL TIMES THROUGHOUT CONSTRUCTION.

PROJECT PHASING:

1. FOR SPECIFIC TECHNOLOGY SYSTEM PHASING AND CUTOVER PLANS AND SCHEDULES PER BUILDING, SEE SPECIFICATION SECTION 27 06 00.

Revisions:

Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED
PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: CIVIL SHEET INDEX AND GENERAL NOTES	Phase: 100% CONSTRUCTION DOCUMENTS	Project Title: EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	Project Number: 581-22-700
			Building Number:
Approved:		Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Drawing Number: C-001
		Issue Date: 09/03/2025 / Checked: PB / Drawn: RDM	004 OF 693

GENERAL NOTES:

1. THE CONTRACTOR MUST BE RESPONSIBLE FOR SITE SECURITY AND JOB SAFETY. CONSTRUCTION ACTIVITIES MUST BE IN ACCORDANCE WITH OSHA STANDARDS, STATE AND LOCAL REQUIREMENTS. THE CONTRACTOR MUST PROVIDE FENCING OR BARRIERS WHEN CONSTRUCTION IS BEING PERFORMED ADJACENT TO BUILDING ENTRANCES/WALKWAYS.
2. THE CONTRACTOR MUST NOT COMMENCE CONSTRUCTION NOR CLOSE OR OBSTRUCT ROADWAYS, SIDEWALKS AND/OR FIRE HYDRANTS WITHOUT APPROPRIATE PERMITS AND/OR PERMISSIONS.
3. AREAS OUTSIDE THE LIMITS OF PROPOSED WORK THAT BECOME DISTURBED BY THE CONTRACTOR'S OPERATIONS MUST BE RESTORED BY THE CONTRACTOR TO ITS ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
4. VEGETATED AREAS DISTURBED DURING CONSTRUCTION MUST RECEIVE A MINIMUM OF FOUR (4) INCHES OF TOPSOIL. THESE ARES MUST BE IMMEDIATELY SEEDED AND STABILIZED.
5. DAMAGE TO SURFACE FEATURES, SUBSURFACE FEATURES AND SUBSURFACE INFRASTRUCTURE RESULTING FROM CONSTRUCTION LOADS MUST BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
6. THE CONTRACTOR MUST CONTROL STORMWATER RUNOFF DURING CONSTRUCTION TO PREVENT ADVERSE IMPACTS TO OFF-SITE AREAS, AND MUST BE RESPONSIBLE TO REPAIR RESULTING DAMAGES, IF ANY, AT NO COST TO OWNER.
7. THE CONTRACTOR IS REQUIRED TO BACKFILL TRENCHES OR SECURE WITH METAL PLATES OR CONSTRUCTION FENCE DAILY. NO OPEN TRENCHES MUST BE LEFT UNATTENDED.
8. THE CONTRACTOR IS RESPONSIBLE FOR ALL FIELD MEASUREMENTS. THE GOVERNMENT WILL NOT BE HELD RESPONSIBLE FOR BIDDING ERRORS MADE OR FOR THE FAILURE TO ADEQUATELY INSPECT THE JOB SITE FOR EXISTING CONDITIONS, DIMENSIONS, AND GRADES.
9. THE CONTRACTOR MUST VERIFY THE PROPOSED LAYOUT WITH ITS RELATIONSHIP TO THE EXISTING SITE. THE CONTRACTOR MUST ALSO VERIFY ALL DIMENSIONS, SITE CONDITIONS, AND MATERIAL SPECIFICATIONS AND MUST NOTIFY THE OWNER AND ENGINEER OF ANY DISCREPANCIES BEFORE COMMENCING OR PROCEEDING WITH WORK.
10. THE CONTRACTOR MUST NOTIFY OPERATORS WHO MAINTAIN UNDERGROUND UTILITY LINES IN THE AREA OF PROPOSED EXCAVATION AT LEAST TWO WORKING DAYS, BUT NOT MORE THAN TEN WORKING DAYS, PRIOR TO COMMENCEMENT OF EXCAVATION OR DEMOLITION. ALL WATER, GAS, SEWER, ELECTRIC AND OTHER UTILITIES MUST BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION.
11. THE CONTRACTOR MUST BE RESPONSIBLE FOR REPLACING, WITH MATCHING MATERIALS, ANY PAVEMENT, WALKS, CURBS, ETC. THAT MUST BE CUT OR THAT ARE DAMAGED DURING CONSTRUCTION.
12. CONSTRUCTION ACTIVITIES MUST NOT CONFLICT WITH THE VAMC OPERATIONS AND EMPLOYEE/PATIENT PARKING. THE CONTRACTOR MUST COORDINATE ALL WORK WITH THE VAMC POLICE DEPARTMENT AND COR. WORK AFFECTING BUILDING ENTRANCES, WALKWAYS, LOADING AREAS, PARKING, ETC. MUST BE COORDINATED AND SCHEDULED WITH THE VAMC.
13. THE CONTRACTOR MUST MAINTAIN RECORD DOCUMENTS OF CONSTRUCTION CHANGES ("AS-BUILT DRAWINGS") AND MUST PROVIDE SAID DOCUMENTATION TO THE ENGINEER UPON COMPLETION OF CONSTRUCTION IN BOTH DIGITAL AND HARD COPY FORMATS. RECORD DOCUMENTS MUST ARTICULATE WHERE ACTUAL INSTALLATION OF WORK, PRODUCTS AND/OR SYSTEMS VARY FROM THE DESIGN INTENT EXPRESSED/SPECIFIED IN THE CONTRACTOR DOCUMENTS. **NO EXCEPTION ALLOWED**
14. ANY EXISTING PROPERTY LINE MONUMENTATION DISTURBED DURING CONSTRUCTION MUST BE RESET BY A PROFESSIONAL LICENSED SURVEYOR AT THE CONTRACTOR'S EXPENSE.
15. THE CONTRACTOR MUST PROTECT THE VA PROPERTY FROM DUST AND DAMAGE AT ALL TIMES. ANY RESULTING DAMAGE TO THE VA PROPERTY MUST BE IMMEDIATELY CORRECTED BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE.

CONTRACTORS ACCESS & STORAGE AREAS:

1. THE CONTRACTOR MUST COORDINATE WITH CONTRACTING OFFICER FOR EXACT LOCATION OF STAGING AREA(S) TO BE USED DURING CONSTRUCTION FOR STORAGE / STOCKPILING OF MATERIALS. CONTRACTOR MUST NOTIFY THE CONTRACTING OFFICER PRIOR TO OCCUPYING STAGING AREA. THE CONTRACTOR MUST VERIFY WITH THE CONTRACTING OFFICER'S REPRESENTATIVE OF ANY CHANGES IN STAGING / LAYDOWN AREAS THAT MAY HAVE OCCURRED AFTER PLANS WERE ISSUED.
2. UPON COMPLETION OF THE WORK, THE STAGING AREAS MUST BE CLEANED AND RESTORED TO THEIR ORIGINAL CONDITION.
3. CONTRACTOR MUST PROVIDE TEMPORARY SECURITY FENCING AROUND THE CONSTRUCTION STAGING AREAS WHERE REQUIRED BY COR. CONTRACTOR TO COORDINATE PRIVACY FABRIC REQUIREMENTS WITH COR. CONTRACTOR MUST BE AWARE OF THE VERTICAL HEIGHTS OF OBJECTS NEAR FENCE LINES; NO EQUIPMENT OR MATERIAL MUST BE PLACED NEAR FENCE LINES THAT WOULD ALLOW THE FENCE TO BE SCALED. MAINTAIN A 10 FOOT MINIMUM SEPARATION FROM ALL FENCES FROM STOCKPILES, PARKED VEHICLES, OR OTHER MATERIALS WHICH COULD BE CLIMBED. POST A METALLIC SIGN DISPLAYING THE CONTRACTOR'S 24 HOUR EMERGENCY CONTACT NUMBER.
4. ALL CONTRACTOR'S MATERIAL ORDERS FOR DELIVERY TO THE SITE MUST USE THE ACCESS POINT AS DETERMINED BY THE COR. ALL ASSOCIATED FEES AND COST MUST BE PAID BY CONTRACTOR AND ARE CONSIDERED INCIDENTAL TO THE VARIOUS BID ITEMS.
5. CONTRACTOR MUST BE RESPONSIBLE FOR TRAFFIC CONTROL TO AND FROM THE CONSTRUCTION AND STAGING AREAS. THE TRAFFIC CONTROL MEASURES MUST BE DIRECTED AND APPROVED BY THE CONTRACTING OFFICER AND/OR CONTRACTING OFFICER'S REPRESENTATIVE.
6. CONTRACTOR MUST COORDINATE LOCATION(S) OF SOIL STOCKPILE AREAS WITH THE CONTRACTING OFFICER IN ADVANCE OF CONSTRUCTION START. AT A MINIMUM, SOIL STOCKPILES WILL CONSIST OF CLEAN IMPORTED FILL, AND EXCAVATED SOILS WAITING FOR REUSE OR OFF-SITE DISPOSAL, AND STOCKPILES MUST BE ADEQUATELY SEPARATED FROM EACH OTHER WITHIN THE STOCKPILE AREA(S).

CONTRACTOR'S VEHICLES:

1. CONTRACTOR'S VEHICLES MUST BE IN GOOD WORKING ORDER. CONTRACTOR'S PERSONNEL MUST PARK WITHIN THE CONTRACTOR'S STAGING AREA OR AREAS APPROVED BY THE COR.
2. ALL TRUCKS AND/OR ASSOCIATED VEHICLE HAULING TOOLS, LABOR, EQUIPMENT, MATERIAL OR DEBRIS ON THE VA CAMPUS MUST BE EQUIPPED AND PREPARED TO PREVENT SPILLAGE OF DEBRIS DURING TRANSPORTATION. TRUCK BEDS MUST BE SWEPT CLEAN BEFORE LEAVING THE WORK AREA. SIDEBOARDS MUST BE KEPT IN GOOD REPAIR. UNDER NO CIRCUMSTANCES MUST A VEHICLE BE LOADED BEYOND ITS LEGAL LIMITS OR HIGHER THAN THE SIDEBOARDS.

EXISTING LEGEND

- COMMUNICATION LINE
- COMMUNICATION MANHOLE / HANDHOLE
- POWER LINE
- POWER MANHOLE / HANDHOLE
- WATER LINE
- WATER METER / VALVE
- FIRE SUPPRESSION LINE
- FIRE HYDRANT
- SANITARY SEWER LINE
- SANITARY SEWER MANHOLE
- STORM DRAIN LINE
- STORM DRAIN INLET
- STORM DRAIN MANHOLE
- GAS LINE
- GAS METER
- 1280 CONTOUR
- FENCE
- ASPHALT PAVEMENT
- CONCRETE PAVEMENT

PROPOSED LEGEND

- SIDE A FIBER PATHWAY
- SIDE A UNDERGROUND HANDHOLE
- SIDE B FIBER PATHWAY
- SIDE B UNDERGROUND HANDHOLE
- UNDERGROUND POWER PATHWAY
- UNDERGROUND POWER HANDHOLE
- WATER LINE
- WATER LINE BEND
- FIRE DEPARTMENT CONNECTION (FDC)
- POST INDICATOR VALVE (PIV)
- FIRE SUPPRESSION LINE
- CHILLED WATER LINE
- SANITARY SEWER LINE
- SANITARY SEWER CLEANOUT
- STORM DRAIN LINE
- STORM DRAIN BMP
- STORM DRAIN YARD DRAIN
- STORM DRAIN CLEANOUT
- STORM DRAIN SWALE FLOWPATH
- 1280 CONTOUR
- FENCE
- ASPHALT PAVEMENT
- CONCRETE PAVEMENT

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800188\007\CADD\Dwgs\VA Huntington - Civil.dwg

Revisions:	Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

SPEESDESIGNBUILD

STAMP

PETER BAILEY
STATE OF WASHINGTON
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
GENERAL NOTES AND LEGEND	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number
		Issue Date: 09/03/2025; Checked: PB; Drawn: RDM	Drawing Number: C-002

VA FORM 08 - 6231

FIBER DUCT BANK TRENCHING NOTES:

1. THE CONTRACTOR IS ADVISED THAT ALL EXISTING UNDERGROUND UTILITIES, CABLES, DUCTS, MANHOLES, ETC. (UNDERGROUND FACILITIES) SHOWN ON PLANS WERE SHOWN USING THE BEST INFORMATION AVAILABLE. INFORMATION SHOWN ON THE DRAWING CONCERNING TYPE, SIZE AND LOCATION OF UNDERGROUND UTILITIES IS NOT GUARANTEED TO BE ACCURATE OR ALL-INCLUSIVE, AND IS PROVIDED FOR INFORMATIONAL PURPOSES ONLY. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR LOCATING AND PROTECTING ALL UTILITIES. CONTRACTOR MUST ALSO REVIEW ALL UTILITIES WITH THE CAMPUS MAINTENANCE STAFF PRIOR TO BEGINNING WORK.
2. PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY, THE CONTRACTOR MUST HAVE A GROUND PENETRATING RADAR (GPR) SURVEY CAREFULLY PERFORMED BY A CERTIFIED TECHNICIAN TO REVEAL ALL EXISTING UNDERGROUND DUCTS, CONDUITS, CABLES, AND OTHER UTILITY SYSTEMS ALONG THE PROPOSED FIBER DUCT BANK ROUTE.
3. EXPLORATORY EXCAVATIONS IN THE VICINITY OF EXISTING UNDERGROUND UTILITIES MUST BE CARRIED OUT WITH EXTREME CARE USING HAND TOOLS UNTIL THE EXACT CHARACTER AND LOCATION OF SUCH FACILITIES ARE DETERMINED.
4. THE CONTRACTOR MUST SUBMIT ALL INFORMATION OBTAINED FROM THE GPR UTILITY LOCATION SURVEY AND POTHOLING EFFORTS TO THE CONTRACTING OFFICER AND/OR CONTRACTING OFFICER'S REPRESENTATIVE AND THE A/E PRIOR TO STARTING CONSTRUCTION. CONTRACTOR MUST RECEIVE APPROVAL FROM CONTRACTING OFFICE PRIOR TO STARTING ANY TRENCHING.
5. THE CONTRACTOR MUST REFER TO COR AND/OR PREVIOUS GEOTECHNICAL REPORTS FOR THIS SITE FOR ALL DEWATERING AND EXCAVATION REQUIREMENTS.
6. CONTRACTOR MUST PERFORM ALL DUCT BANK TRENCHING IN ACCORDANCE WITH VA STANDARDS. REFER TO STANDARD SPECIFICATION 26 05 41 AND VA DESIGN GUIDE FOR ADDITIONAL INFORMATION.
7. THE CONTRACTOR MUST REFER TO BUILDING TELECOMM SHEETS FOR DETAIL AND LOCATION OF BUILDING CONNECTIONS AND INTERIOR ROUTES.
8. THE CONTRACTOR MUST REMOVE ALL EXISTING WIRE AND FIBER FROM EXISTING DUCTBANKS AFTER THE NEW FIBER SYSTEM IS OPERATIONAL. THE EXISTING STRUCTURES AND PATHWAYS ARE TO BE LEFT IN PLACE FOR FUTURE USE BY THE VA. THE NEW A-SIDE FIBER WILL NOT BE GOING INTO THE EXISTING DUCTBANK.
9. FOR CONTINUATION OF ALL CONDUITS AND FIBER ROUTING WITHIN BUILDINGS, REFER TO TELECOMMUNICATIONS DOCUMENTS, TYPICAL.

BUILDING TYPES

NON-MEDICAL BUILDINGS	MEDICAL BUILDINGS
2 (2 TRs)	1 & 1A (TRs fed from 1S)
3 (1 TR)	1S (12 TRs)
4 (1 TR)	1W (4 TRs)
25 (1 TR)	5 (1 TR)
28 (1 TR)	6 (1 TR)
34 (1 TE)	7 (2 TR)
T-1 (1 TR)	8 (2 TRs)
T-2 (fed from T-2)	9 (1 TR)
T-3 (1 TR)	12 (fed from 1S)
T-4 (1 TR)	20 (2 TRs)
T-5 (1 TR)	23 & 23R (1 TR)

NOTE: 24 STRANDS OS2 PER TR EACH FOR A & B SIDE FIBER

Revisions:	Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

U.S. Department of Veterans Affairs

Drawing Title	OVERALL CIVIL SITE PLAN
Approved:	
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Location	VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date	09/03/2025
Checked	PB
Drawn	RDM
Project Number	581-22-700
Building Number	
Drawing Number	CS100
	006 OF 693





NOTE:

CONTRACTOR MUST INSTALL INLET PROTECTION ON AREA CATCH BASINS IN THE DUCT BANK VICINITY TO PREVENT SEDIMENT LADEN RUNOFF FROM ENTERING DOWNSTREAM STORM DRAIN SYSTEM.

E8 / CG100 **DUCT BANK TRENCH TESC DETAIL (TYP.)**
SCALE: NTS

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800186\007\CADD\Dwgs\VA Huntington - Civil.dwg

Revisions:	Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246
SPEESDESIGNBUILD

STAMP

PETER BAILEY — STATE OF WASHINGTON — 42527 REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
OVERALL EROSION CONTROL PLAN	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number:
		Issue Date: 09/03/2025; Checked: PB; Drawn: RDM	Drawing Number: CG100
			007 OF 693

VA FORM 08 - 6231

TEMPORARY EROSION AND SEDIMENT CONTROL NOTES:

1. THE CONTRACTOR MUST PROVIDE AND MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL (TESC) FACILITIES. REFER TO THE APPLICABLE DRAWINGS AND THE SPECIFICATIONS FOR PLANS AND DETAILS THAT DESCRIBE THE MINIMUM TESC FEATURES REQUIRED. AS CONSTRUCTION PROGRESSES AND SEASONAL CONDITIONS DICTATE, THE CONTRACTOR MUST REVISE TESC FACILITIES AND CONFIGURATIONS AS NECESSARY TO ENSURE COMPLETE SILTATION CONTROL AND THAT NO SEDIMENT LADEN WATER ENTERS THE DOWNSTREAM NATURAL OR PIPED DRAINAGE SYSTEM.
2. DURING THE COURSE OF CONSTRUCTION, IT MUST BE THE OBLIGATION AND RESPONSIBILITY OF THE CONTRACTOR TO ADDRESS ANY NEW CONDITIONS THAT MAY BE CREATED BY ITS ACTIVITIES AND TO PROVIDE ADDITIONAL TESC FACILITIES THAT MAY BE NEEDED TO PROTECT THE SITE, ADJACENT LAND AND EXISTING DRAINAGE FEATURES.
3. TEMPORARY EROSION/WATER POLLUTION PREVENTION MEASURES MUST BE REQUIRED IN ACCORDANCE WITH THE CURRENT ENVIRONMENTAL PROTECTION AGENCY'S (EPA) CONSTRUCTION STORMWATER GENERAL PERMIT AND THE APPLICABLE STATE STANDARDS OR MANUAL. DURING THE COURSE OF CONSTRUCTION, IT MUST BE THE OBLIGATION AND RESPONSIBILITY OF THE CONTRACTOR TO ADDRESS ANY NEW CONDITIONS THAT MAY BE CREATED BY ITS ACTIVITIES AND TO PROVIDE ADDITIONAL TESC FACILITIES THAT MAY BE NEEDED TO PROTECT THE SITE, ADJACENT LAND, AND EXISTING DRAINAGE FEATURES.
4. THE CONTRACTOR MUST ENSURE THE TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES AS SHOWN ON THESE DRAWINGS PROVIDE ADEQUATE CONTROL SO THAT NO SEDIMENT LADEN WATER LEAVES THE SITE. THE CONTRACTOR MUST INSTALL ADDITIONAL FACILITIES AS NECESSARY TO PROTECT ADJACENT PROPERTIES, SENSITIVE AREAS, NATURAL WATER COURSES, AND/OR STORM DRAINAGE SYSTEMS TO ENSURE COMPLETE SILTATION CONTROL.
5. PRIOR TO STARTING ANY WORK ON THE SITE, THE CONTRACTOR MUST NOTIFY THE OWNER AND MUST INSTALL ALL EROSION AND SEDIMENT CONTROL MEASURES AS SHOWN ON THE APPROVED PLANS. ALL TEMPORARY EROSION CONTROL MEASURES MUST BE MAINTAINED FOR THE DURATION OF PROJECT CONSTRUCTION.
6. THE BMP FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT ENTER THE DRAINAGE SYSTEM, ROADWAYS, OR VIOLATE APPLICABLE WATER STANDARDS.
7. PROVIDE STRAW WATTLE AND COMPOST FILTER SOCK SEDIMENT CONTROL MEASURES OR OTHER APPROVED PERIMETER PROTECTION SEDIMENT CONTROL MEASURES FOR EXISTING DRAINAGE CHANNELS NEARBY OR ADJACENT TO THE PROJECT SITE.
8. PROVIDE INLET PROTECTION AT ALL AREA STORM DRAIN STRUCTURES IN THE AREA OF CONSTRUCTION.
9. THE BMP FACILITIES MUST BE INSPECTED DAILY AND AFTER STORM EVENTS BY THE APPLICANT/CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING. WRITTEN RECORDS MUST BE KEPT OF MONTHLY REVIEWS.
10. THE CONTRACTOR MUST BE RESPONSIBLE FOR CLEANING DIRT, MUD, AND OTHER CONSTRUCTION DEBRIS, WHICH MAY ACCUMULATE ON PAVED STREETS ADJACENT TO THE SITE AS A RESULT OF THE CONSTRUCTION ACTIVITY. AS A MINIMUM, DIRT, MUD AND OTHER DEBRIS MUST BE REMOVED FROM PAVEMENT AT THE CLOSE OF EACH CONSTRUCTION DAY.
11. EXPOSED SLOPES AND SURFACES MUST BE STABILIZED FROM SEDIMENT TRANSPORT USING APPROVED BMPS UNTIL THE SITE HAS BEEN STABILIZED AND THE CONTRACTING OFFICER APPROVES THE REMOVAL OF SLOPE STABILIZATION MEASURES.
12. THE CONTRACTOR MUST BE RESPONSIBLE TO ENSURE THAT NO SEDIMENT LADEN RUNOFF LEAVES THE CONSTRUCTION SITE, WORK AREA, OR HAUL ROUTES. THE CONTRACTOR MUST SUBMIT A SEDIMENT AND WATER POLLUTION PREVENTION PLAN TO THE CONTRACTING OFFICER FOR APPROVAL PRIOR TO BEGINNING ANY WORK.
13. THE CONTRACTOR MUST BE RESPONSIBLE FOR DEWATERING OF ANY EXCAVATION DURING INCLEMENT WEATHER. DEWATERING WATER MUST BE TESTED AND DISPOSED OF IN ACCORDANCE WITH STATE ENVIRONMENTAL REQUIREMENTS ACCORDING TO THE APPROVED SWPPP PLAN.
14. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES ONCE THE SITE IS STABILIZED AFTER CONSTRUCTION COMPLETION.



C5 / CG101 TEMPORARY SEDIMENT FENCE
SCALE: NTS



C9 / CG101 TEMPORARY FIBER ROLL
SCALE: NTS



F5 / CG101 TEMPORARY GRAVEL BAG INSTALLATION
SCALE: NTS



STORM DRAIN INLET PROTECTION NOTES:

1. ACCUMULATED SEDIMENT ON OR AROUND A PROTECTED INLET MUST BE REMOVED IMMEDIATELY. SEDIMENT MUST NOT BE REMOVED BY FLUSHING.
2. REPLACE CATCH BASIN INSERT WHEN THE SEDIMENT HAS FILLED ONE-THIRD OF THE AVAILABLE STORAGE. THE INSERT MUST BE INSPECTED FREQUENTLY AND REPLACED AS NEEDED, OR AS DIRECTED BY THE CONTRACTING OFFICER.

F8 / CG101 TEMPORARY INLET PROTECTION
SCALE: NTS

Revisions: | Date:

CONSULTANT
CIVIL ENGINEER:
WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD
A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246
SPEESDESIGNBUILD

STAMP
PETER BAILEY — STATE OF WASHINGTON — 42527 — REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
EROSION CONTROL GENERAL NOTES AND DETAILS	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700

Approved:

Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn
09/03/2025	PB	RDM

Building Number:

Drawing Number: CG101

008 OF 693

VA FORM 08 - 6231

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800186\007\CADD\Dwgs\VA Huntington - Civil.dwg



B1 / CU250 UTILITY GUARD POST (TYP)

SCALE: NTS

Revisions:	Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
CIVIL UTILITY CONSTRUCTION DETAILS	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number:
		Issue Date: 09/03/2025 / Checked: PB / Drawn: RDM	Drawing Number: CU250

009 OF 693

VA FORM 08 - 6231

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800186\007\CADD\Dwgs\VA Huntington - Civil.dwg



1" = 150'
150 0 150 300
scale feet

Revisions: | Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED
PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

U.S. Department of Veterans Affairs

Drawing Title	OVERALL FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
Approved:	
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Location	VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date	09/03/2025
Checked	PB
Drawn	RDM
Project Number	581-22-700
Building Number	
Drawing Number	CU300

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800188\007\CADD\Dwgs\VA Huntington - Civil.dwg

VA FORM 08 - 6231

LEGEND

C(A)	PROPOSED SIDE A FIBER PATHWAY
	PROPOSED SIDE A UNDERGROUND HANDHOLE
C(B)	PROPOSED SIDE B FIBER PATHWAY
	PROPOSED SIDE B UNDERGROUND HANDHOLE

SITE KEYNOTES

#	SITE KEYNOTES
1	TYPE 1 DUCT BANK PER DETAIL F3 ON SHEET CU500
2	TYPE 2 DUCT BANK PER DETAIL F6 ON SHEET CU500



KEYMAP
NOT TO SCALE

1" = 20'
20 0 20 40
scale feet

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800188\007\CADD\Dwgs\VA Huntington - Civil.dwg

Revisions: Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
FIBER OPTIC OUTSIDE PLANT UTILITY PLAN	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700

Building Number:

Approved:

Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn
09/03/2025	PB	RDM

Drawing Number: CU301

VA FORM 08 - 6231



MATCHLINE SEE SHEET CU303

LEGEND

- PROPOSED SIDE A FIBER PATHWAY
- PROPOSED SIDE A UNDERGROUND HANDHOLE
- PROPOSED SIDE B FIBER PATHWAY
- PROPOSED SIDE B UNDERGROUND HANDHOLE

#	SITE KEYNOTES
1	TYPE 1 DUCT BANK PER DETAIL F3 ON SHEET CU500
2	TYPE 2 DUCT BANK PER DETAIL F6 ON SHEET CU500



KEYMAP
NOT TO SCALE

1" = 20'
20 0 20 40
scale feet

Revisions: Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
FIBER OPTIC OUTSIDE PLANT UTILITY PLAN	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700

Building Number:

Approved:

Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn	Drawing Number
09/03/2025	PB	RDM	CU302

012 OF 693

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800188\007\CADD\Dwgs\VA Huntington - Civil.dwg

MATCHLINE SEE SHEET CU302

LEGEND

- PROPOSED SIDE A FIBER PATHWAY
- PROPOSED SIDE A UNDERGROUND HANDHOLE
- PROPOSED SIDE B FIBER PATHWAY
- PROPOSED SIDE B UNDERGROUND HANDHOLE

#	SITE KEYNOTES
1	TYPE 1 DUCT BANK PER DETAIL F3 ON SHEET CU500
2	TYPE 2 DUCT BANK PER DETAIL F6 ON SHEET CU500



KEYMAP
NOT TO SCALE

1" = 20'
20 0 20 40
scale feet

Revisions:	Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

U.S. Department of Veterans Affairs

Drawing Title	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
Approved:	
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Location	VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date	09/03/2025
Checked	PB
Drawn	RDM
Project Number	581-22-700
Building Number	
Drawing Number	CU303



MATCHLINE SEE SHEET CU305

LEGEND

C(A)	PROPOSED SIDE A FIBER PATHWAY
☐	PROPOSED SIDE A UNDERGROUND HANDHOLE
C(B)	PROPOSED SIDE B FIBER PATHWAY
☐	PROPOSED SIDE B UNDERGROUND HANDHOLE

#	SITE KEYNOTES
1	TYPE 1 DUCT BANK PER DETAIL F3 ON SHEET CU500
2	TYPE 2 DUCT BANK PER DETAIL F6 ON SHEET CU500



KEYMAP
NOT TO SCALE

1" = 20'
20 0 20 40
scale feet

Revisions:	Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

SPEESDESIGNBUILD

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title
FIBER OPTIC OUTSIDE PLANT UTILITY PLAN

Approved:

Phase
100% CONSTRUCTION DOCUMENTS

Project Title
EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON

Location
VA HUNTINGTON
1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn
09/03/2025	PB	RDM

Project Number
581-22-700

Building Number

Drawing Number
CU304

014 OF 693

VA FORM 08 - 6231

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800188\007\CADD\Dwgs\VA Huntington - Civil.dwg

MATCHLINE SEE SHEET CU304



MATCHLINE SEE SHEET CU302

MATCHLINE SEE SHEET CU303

MATCHLINE SEE SHEET CU307

LEGEND

- PROPOSED SIDE A FIBER PATHWAY
- PROPOSED SIDE A UNDERGROUND HANDHOLE
- PROPOSED SIDE B FIBER PATHWAY
- PROPOSED SIDE B UNDERGROUND HANDHOLE

#	SITE KEYNOTES
1	TYPE 1 DUCT BANK PER DETAIL F3 ON SHEET CU500
2	TYPE 2 DUCT BANK PER DETAIL F6 ON SHEET CU500



KEYMAP
NOT TO SCALE

1" = 20'
20 0 20 40
scale feet

Revisions: Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
FIBER OPTIC OUTSIDE PLANT UTILITY PLAN	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number
		Issue Date: 09/03/2025 · Checked: PB · Drawn: RDM	Drawing Number: CU305
			015 OF 693

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800188\007\CADD\Dwgs\VA Huntington - Civil.dwg

VA FORM 08 - 6231

MATCHLINE SEE SHEET CU304



MATCHLINE SEE SHEET CU307

LEGEND

- PROPOSED SIDE A FIBER PATHWAY
- PROPOSED SIDE A UNDERGROUND HANDHOLE
- PROPOSED SIDE B FIBER PATHWAY
- PROPOSED SIDE B UNDERGROUND HANDHOLE

#	SITE KEYNOTES
1	TYPE 1 DUCT BANK PER DETAIL F3 ON SHEET CU500
2	TYPE 2 DUCT BANK PER DETAIL F6 ON SHEET CU500

KEYMAP
NOT TO SCALE

1" = 20'
20 0 20 40
scale feet

Revisions: Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

SPEESDESIGNBUILD

STAMP

PETER BAILEY
STATE OF WASHINGTON
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
FIBER OPTIC OUTSIDE PLANT UTILITY PLAN	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700

Building Number:

Approved:

Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn	Drawing Number
09/03/2025	PB	RDM	CU306

016 OF 693



LEGEND

- PROPOSED SIDE A FIBER PATHWAY
- PROPOSED SIDE A UNDERGROUND HANDHOLE
- PROPOSED SIDE B FIBER PATHWAY
- PROPOSED SIDE B UNDERGROUND HANDHOLE

#	SITE KEYNOTES
1	TYPE 1 DUCT BANK PER DETAIL F3 ON SHEET CU500
2	TYPE 2 DUCT BANK PER DETAIL F6 ON SHEET CU500



KEYMAP
NOT TO SCALE

1" = 20'
20 0 20 40
scale feet

Revisions: Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED
PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

U.S. Department of Veterans Affairs

Drawing Title	FIBER OPTIC OUTSIDE PLANT UTILITY PLAN
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Project Number	581-22-700
Building Number	
Approved:	
Location	VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date	09/03/2025
Checked	PB
Drawn	RDM
Drawing Number	CU307

017 OF 693

Last Saved by: USRM675467 on: Aug 27, 2025 3:54 PM File: C:\Users\USRM675467\WSP O365\Federal Group - Jobs\31800186\007\CADD\Dwgs\VA Huntington - Civil.dwg

VA FORM 08 - 6231



NOTE:

ALL EXTERIOR ENCLOSURE LIDS TO BE MARKED AS "COMMUNICATIONS." VERIFY AND COORDINATE EXACT PLACEMENT BEFORE INSTALLATION.

D3 CU500 **MEDIUM HANDHOLE DETAIL (TYP)**
SCALE: NTS



F3 CU500 **TYPE 1 DUCTBANK (TYP)**
SCALE: NTS



F6 CU500 **TYPE 2 DUCTBANK (TYP)**
SCALE: NTS

Revisions:	Date:

CONSULTANT

CIVIL ENGINEER:

WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD

A/E:

SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246

SPEESDESIGNBUILD

STAMP

PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED
PROFESSIONAL ENGINEER

Office of Construction and Facilities Management

U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
COMMUNICATION DUCTBANK DETAILS	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number
		Issue Date: 09/03/2025; Checked: PB; Drawn: RDM	Drawing Number: CU500
			018 OF 693

VA FORM 08 - 6231



B1 / CU501 **CONCRETE PAVEMENT SECTION**
SCALE: NTS



C1 / CU501 **ASPHALT PAVEMENT SECTION**
SCALE: NTS



C4 / CU501 **TRENCH IN PAVED AREAS (TYP.)**
SCALE: NTS



C7 / CU501 **TRENCH IN NON-PAVED AREAS (TYP.)**
SCALE: NTS

FIBER OPTIC DUCTBANK SURFACE RESTORATION NOTES:

1. ALL DUCTBANK TRENCHING TO FOLLOW VA STANDARD SPECIFICATIONS.
2. SURFACE RESTORATION IN EXISTING AREAS MUST MATCH EXISTING SURFACE. IN ASPHALT PAVING AREAS, HMA TO MATCH THICKNESS OF EXISTING PAVEMENT, BUT MUST NOT BE LESS THAN 4", PLACED OVER 8" OF BASE COURSE.
3. FOR TRENCH IN NON-PAVED AREAS, PLACE 4" OF TOP SOIL SUCH THAT TOP IS FLUSH WITH EXISTING GRADE ON EACH SIDE AND SLIGHTLY MOUNDED BETWEEN. STABILIZE TOP OF TRENCH WITH GRASS SEED MIX AND MULCH, GRAVEL, BARK, OR WHATEVER MATERIAL MATCHES EXIST SURROUNDING CONDITIONS.
4. UTILITY IDENTIFICATION TAPE MUST BE BURIED 12" BELOW FINISHED GRADE OR 6" BELOW TOP OF SUBGRADE IF UNDERNEATH PAVEMENT. DETECTION WIRE MUST BE BURIED DIRECTLY ABOVE NON-METALLIC PIPING AND 12" MAX. ABOVE TOP OF PIPE.
5. TRENCH SAFETY SYSTEMS (SHORING) INCLUDING TRENCH BOXES MUST BE USED AS APPLICABLE AND AS DESCRIBED BY OSHA TO MAINTAIN VERTICAL SIDES FOR TRENCH AND MINIMIZE AMOUNT OF EXCAVATION, BACKFILL, AND SURFACE REPAIR. LAYING BACK TRENCH EXCAVATION (FLATTER SIDE SLOPES) IN LIEU OF SHORING MUST ONLY BE DONE IF APPROVED BY CONTRACTING OFFICER.
6. DEWATER TRENCH AS NECESSARY FOR DEEPER EXCAVATIONS. DEWATERING AND THAWING AT CONTRACTORS SOLE EXPENSE IN BOTH TIME AND DOLLARS.
7. TOP OF CONCRETE-ENCASED DUCTS MUST BE: 24" MIN. BELOW FINISHED GRADE IN NON-PAVED AREAS OR 30" MIN. BELOW PAVEMENT IN PAVED AREAS, AS WELL AS 6" MIN. BELOW FROST DEPTH.



PIPE DIA.	W (MAX)
< 4"	12"+ PIPE O.D.
4" < 24"	24"+ PIPE O.D.
> 24"	36"+ PIPE O.D.

NOTES:

1. MATERIAL MUST BE AS FOLLOWS:
   1.1. RIGID PIPE: HAND-PLACED, COMPACTED INITIAL BACKFILL MATERIAL.
   1.2. FLEXIBLE PIPE: HAND-PLACED, COMPACTED BEDDING MATERIAL. 4 INCHES FOR PIPE 18 INCH DIA. AND LESS.
2. CONTRACTOR TO MAINTAIN 48 INCHES MIN DEPTH OF COVER OVER WATER LINES PER NFPA 24 FIGURE A.10.4.1, AND 30 INCHES MIN COVER OVER OTHER UTILITIES UNLESS OTHERWISE NOTED ON PLANS.

F1 / CU501 **UTILITY TRENCH SECTION**
SCALE: NTS



F4 / CU501 **JOINT COMMUNICATIONS DUCT BANK (TYP.)**
SCALE: NTS

Revisions:	Date:

CONSULTANT
CIVIL ENGINEER:
WSP
WSP USA Solutions Inc.
1201 Pacific Avenue
Suite 550
Tacoma, WA 98402
TEL: (206) 431-2300
FAX: (206) 431-2250

DESIGNER OF RECORD
A/E:
SPEES DESIGN BUILD
23830 PACIFIC HIGHWAY S, STE 300
KENT, WA 98032
(206) 209-2246
SPEESDESIGNBUILD

STAMP
PETER BAILEY
STATE OF WASHINGTON
42527
REGISTERED PROFESSIONAL ENGINEER

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
COMMUNICATION TRENCHING DETAILS	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number
		Issue Date: 09/03/2025 / Checked: PB / Drawn: RDM	Drawing Number: CU501
			019 OF 693

VA FORM 08 - 6231

Last Saved by: USPB675341 on: Sep 3, 2025 1:48 PM File: C:\Users\uscb096136\WSP O365\Federal Group - Jobs\31800188\007CADD\Dwgs\VA Huntington - Civil.dwg



C7 / CU502 PIPE PENETRATION THROUGH WALLS BELOW GRADE (TYP.)

SCALE: NTS



1. CONCRETE ENCASED 4" CONDUITS
2. BUILDING FEEDING HAND HOLE
3. SECURE HAND HOLE COVER MARKED "COMMUNICATIONS"
4. GALVANIZED 4" CONDUIT
5. WALL PENETRATION, SEE DETAIL C7 THIS SHEET
6. INSIDE CONDUITS TO TR (SEE TELECOMM DRAWINGS)

NOTE:
FIBER DUCTBANK CONDUITS MUST BE SLOPED DOWN AND AWAY FROM BUILDING 20' (TYP.) OR TO MAXIMUM EXTENT FEASIBLE TO AVOID POTENTIAL WATER INTRUSION FROM NEW DUCTBANKS INTO BUILDING.

F2 / CU502 UNDERGROUND CRAWL SPACE BUILDING ENTRY

SCALE: NTS



1. CONCRETE ENCASED 4" CONDUITS
2. BUILDING FEEDING HAND HOLE
3. SECURE HAND HOLE COVER MARKED "COMMUNICATIONS"
4. GALVANIZED 4" CONDUIT
5. WALL PENETRATION, SEE DETAIL C7 THIS SHEET
6. INSIDE CONDUITS TO TR (SEE TELECOMM DRAWINGS)

NOTE:
FIBER DUCTBANK CONDUITS MUST BE SLOPED DOWN AND AWAY FROM BUILDING 20' (TYP.) OR TO MAXIMUM EXTENT FEASIBLE TO AVOID POTENTIAL WATER INTRUSION FROM NEW DUCTBANKS INTO BUILDING.

F7 / CU502 UNDERGROUND BASEMENT ENTRY

SCALE: NTS

CODES AND STANDARDS

MATERIAL SPECIFIC STANDARDS ARE LISTED IN THE RESPECTIVE MATERIAL SECTION.

1. VA SEISMIC DESIGN REQUIREMENTS, H-18-8, JULY 1ST 2023
2. 2021 INTERNATIONAL BUILDING CODE (IBC) WITH STATE AND LOCAL AMENDMENTS

DESIGN LOADS

REFERENCES:

ASCE 7-16 MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES
VA STRUCTURAL DESIGN MANUAL PG-18-10 OCTOBER 1ST 2022, REVISED JULY 1, 2023

DEAD LOADS

WEIGHT OF STRUCTURAL ELEMENTS AND PERMANENT FIXED EQUIPMENT.

SUPERIMPOSED DEAD LOADS

LOCATION	CATEGORY	UNIFORM LOAD (PSF)
ROOF	ROOFING MATERIALS	18
WALLS	EXTERIOR WALL SKIN	15
WALLS	PARTITIONS	20 (10 LATERAL)

LIVE AND ROOF LIVE LOADS

OCCUPANCY OR USE		UNIFORM LOAD (PSF)	CONCENTRATED LOAD (LBS)
CORRIDORS	FIRST FLOOR	100	
DATA CENTER MECHANICAL ROOM TOWER FLOORS		250 150 125	3500 (16 sq ft) 2000 (2.5 sq ft) 2000 (2.5 sq ft) 2300 (16 sq ft)
OFFICE	OFFICES FILE AND COMPUTER ROOMS	80 125	2000 (2.5 sq ft) 2000 (2.5 sq ft)
STAIRS & EXITS		100	300
ROOF ROOF STAIRS AND PLATFORM		20 40	300 300

SNOW LOAD

DESIGN PARAMETER	VALUE
SNOW LOAD IMPORTANCE FACTOR, Is	1.2
GROUND SNOW LOAD, Pg	20 PSF
SNOW LOAD ON FLAT ROOFS, Pf	24 PSF
EXPOSURE CATEGORY	C
SNOW LOAD EXPOSURE FACTOR, Ce	1.1
THERMAL FACTOR, Ct	1.0

WIND LOAD

REFER TO THE COMPONENTS AND CLADDING DIAGRAMS AT THE END OF THE GENERAL NOTES SECTION.

DESIGN PARAMETER	VALUE
BASIC WIND SPEED (3-SEC GUST), V	119 MPH
WIND EXPOSURE CATEGORY	C
KZT	1.62
ENCLOSURE CLASSIFICATION	ENCLOSED
INTERNAL PRESSURE COEFFICIENT	±0.18

DEFERRED SUBMITTALS

1. DEFERRED COMPONENT SUBMITTALS ARE INTENDED TO BE VENDOR DESIGNED AND HAVE NOT BEEN DESIGNED BY THE ARCHITECT/ENGINEER OF RECORD. THE COMPONENT DESIGNER IS RESPONSIBLE FOR CODE CONFORMANCE AND NECESSARY CONNECTIONS NOT CALLED OUT ON ARCHITECTURAL OR STRUCTURAL DRAWINGS.
2. DEFERRED SUBMITTALS INCLUDING CALCULATIONS MUST BE STAMPED AND SIGNED BY A REGISTERED PROFESSIONAL ENGINEER. DEFERRED SUBMITTALS MUST FIRST BE SUBMITTED TO THE ENGINEER OF RECORD FOR A CURSORY REVIEW FOR LOADS IMPOSED ON THE BASIC STRUCTURE.
3. A SUBMITTAL MAY THEN BE MADE BY THE CONTRACTOR TO THE CONTRACTING OFFICER'S REPRESENTATIVE TO SUBMIT TO THE AUTHORITY HAVING JURISDICTION FOR REVIEW AND APPROVAL.
4. THE LIST OF ITEMS FOR DEFERRED SUBMITTALS INCLUDES THE FOLLOWING ITEMS:
   A. MICROPILES.
   B. MCR ROOF STAIRS AND PLATFORM.
   C. SEISMIC RESTRAINT FOR NON-STRUCTURAL COMPONENTS.
   D. TEMPORARY ROOF OVER DATA CENTER.
5. SUBMITTAL MUST INCLUDE:
   A. CALCULATIONS.
   B. A DIAGRAM SHOWING LOAD MAGNITUDES AND LOCATIONS, SEPARATED INTO DEAD, LIVE, WIND AND/OR SEISMIC COMPONENTS - THAT ARE APPLIED TO THE PRIMARY STRUCTURE.

SEISMIC LOAD

DESIGN PARAMETER		VALUE
SEISMIC IMPORTANCE FACTOR, Ie		1.5
SITE LOCATION	LATITUDE LONGITUDE	38.3841745° N -82.5165789° E
SOIL SITE CLASS		C
MAPPED SPECTRAL ACCELERATION	SHORT PERIOD, Ss 1-SECOND PERIOD, S1	0.155 0.069
DESIGN SPECTRAL ACCELERATION	SHORT PERIOD, Sds 1-SECOND PERIOD, Sd1	0.134 0.069
SEISMIC DESIGN CATEGORY		C



PRINCIPLE BUILDING AXES (NTS)

SEISMIC SYSTEM DESIGN	BOTH DIRECTION TOWER 3	BOTH DIRECTION MCR
SEISMIC FORCE RESISTING SYSTEM	STEEL ORDINARY MOMENT FRAME	LIGHT-FRAME (COLD-FORMED STEEL) WALLS SHEATHED WITH WOOD STRUCTURAL PANELS RATED FOR SHEAR RESISTANCE OR STEEL SHEETS
RESPONSE MODIFICATION FACTOR, R OVERSTRENGTH FACTOR, Ω0 DEFLECTION AMPLIFICATION FACTOR, Cd	3.5 3 3	6.5 2.5 4
SEISMIC WEIGHT, W SEISMIC RESPONSE COEFF., Cs DESIGN BASE SHEAR, V	66 KIPS 0.062 4.1 KIPS	36 KIPS 0.038 1.37 KIPS
ANALYSIS PROCEDURE	EQUIVALENT LATERAL FORCE ANALYSIS	EQUIVALENT LATERAL FORCE ANALYSIS

DEFLECTION LIMITS

1. DEFLECTION LIMITS OF MATERIAL STANDARDS ALSO APPLY.
2. SPAN LENGTH (L) AND WALL HEIGHT (H) ARE MEASURED IN INCHES FROM THE CENTERLINES OF SUPPORTS. THE LENGTH OF CANTILEVERED ELEMENTS MUST BE FACTORED BY 2.

ELEMENT		DEFLECTION LIMITS FOR LOAD CASE	
		LL OR SL OR WL	TOTAL: DL + LL
VERTICAL	VENEER LINTELS	L/600	L/600
	ROOFS (NOT SUPPORTING PLASTER OR STUCCO CEILINGS)	L/240	L/180
LATERAL	WALLS WITH BRITTLE FINISHES (EXCL. VENEER)	H/600	
	WALLS WITH FLEXIBLE FINISHES	H/180	
STORY DRIFT	WIND	H/500 (ELASTIC)	
	SEISMIC	0.010 H (INELASTIC)	

GENERAL CONDITIONS

1. CONFLICTS BETWEEN THE DRAWINGS AND SPECIFICATIONS MUST BE BROUGHT TO THE ATTENTION OF THE CONTRACTING OFFICER AND STRUCTURAL ENGINEER OF RECORD (SER) IN WRITTEN FORM AND RESOLVED BEFORE PROCEEDING WITH AFFECTED WORK.
2. STRUCTURAL DRAWINGS REPRESENT THE COMPLETED STRUCTURE. THE CONTRACTOR IS RESPONSIBLE FOR THE MEANS AND METHODS NECESSARY TO COMPLETE THE WORK, FOR JOB SITE SAFETY AND FOR COORDINATING WITH OTHER DISCIPLINES AS REQUIRED.
3. THE CONTRACTOR IS RESPONSIBLE FOR THE ERECTION PROCEDURE AND SEQUENCING TO ENSURE STABILITY OF THE STRUCTURE DURING CONSTRUCTION. PROVIDE SHORING, BRACING, AND FALSEWORK AS NEEDED TO PROTECT THE STRUCTURE THROUGHOUT CONSTRUCTION.
4. ERECTION AIDS FOR FACILITATING CONSTRUCTION NOT SHOWN IN THESE DRAWINGS MUST BE REMOVED AND ELEMENTS RESTORED TO ITS ORIGINAL DESIGN INTENT SHOWN PER THESE DRAWINGS.
5. STRUCTURAL DRAWINGS SHOW GENERAL AND TYPICAL DETAILS OF CONSTRUCTION. WHERE SPECIFIC CONDITIONS ARE NOT SHOWN, DETAILS OF SIMILAR TYPE AND CHARACTER MAY BE USED BUT REQUIRE APPROVAL FROM THE SER.
6. TYPICAL DETAILS MAY NOT BE REFERENCED FROM THE PLANS BUT APPLY FOR THE CONDITIONS AS DESCRIBED BY THE DETAIL.
7. CONTRACTOR-INITIATED CHANGES REQUIRE APPROVAL FROM THE SER.
8. FOR A CONTRACTOR REQUESTED DESIGN REVISION, THE PROPOSED ALTERNATIVE MUST BE SUBMITTED TO THE CONTRACTING OFFICER FOR REVIEW AND APPROVAL BY THE SER. THE SUBMITTAL MUST INCLUDE DRAWINGS, STRUCTURAL DETAILS AND RELATED CALCULATIONS, STAMPED AND SIGNED BY A PROFESSIONAL ENGINEER LICENSED TO PRACTICE IN THE JURISDICTION OF THE PROJECT LOCATION. CALCULATIONS MUST DEMONSTRATE COMPLIANCE WITH THE CODES AND DESIGN REQUIREMENTS LISTED PER THESE DRAWINGS; AND THAT THE ALTERNATIVE DESIGN DOES NOT ADVERSELY AFFECT THE STRUCTURE SHOWN IN THESE DRAWINGS.
9. CONTRACTOR MUST COORDINATE THESE DRAWINGS WITH THE DRAWINGS OF THE OTHER DISCIPLINES AND SPECIFICATIONS FOR ADDITIONAL INFORMATION NOT SHOWN ON THE STRUCTURAL DRAWINGS. EXAMPLES INCLUDE EMBEDDED ANCHORS, SLEEVES AND INSERTS, MISCELLANEOUS ATTACHMENT DETAILS, FLOOR FINISHES, DOOR THRESHOLDS, SLOPES TO DRAINS, OPENINGS IN STRUCTURAL ELEMENTS, ETC.
10. VERIFY DIMENSIONS AND DETAILS PRIOR TO FABRICATION AND CONSTRUCTION. THIS INCLUDES COORDINATING THE SIZE AND LOCATION OF OPENINGS THROUGH STRUCTURAL ELEMENTS WITH THE RESPECTIVE SUBCONTRACTOR, AS WELL AS COORDINATING INSERTS AND ATTACHMENTS FOR USE BY OTHER TRADES.
11. NO PIPES OR DUCTS MAY BE PLACED IN STRUCTURAL MEMBERS UNLESS DETAILED BY THE STRUCTURAL PLANS OR APPROVED BY THE SER.
12. DIMENSIONS MUST NOT BE SCALED FROM THE DRAWINGS.
13. PROVIDE SUBMITTALS AND (FABRICATION, AND ERECTION, ETC.) SHOP DRAWINGS FOR THE WORK SHOWN IN THESE DRAWINGS TO THE CONTRACTING OFFICE FOR APPROVAL FROM THE SER. WORK MUST NOT PROCEED WITHOUT REVIEW AND APPROVAL BY THE SER.
14. SUBMIT A DETAILED PLAN OF THE CONSTRUCTION INCLUDING A DESCRIPTION OF DEMOLITION, CONSTRUCTION METHODS, ERECTION SEQUENCING, METHODS OF STABILIZING THE STRUCTURE, SHORING LAYOUT, ELEMENT SIZES, CONNECTIONS AND ACCESSORIES WITH SUPPORTING CALCULATIONS STAMPED AND SIGNED BY A REGISTERED PROFESSIONAL ENGINEER, TO THE CONTRACTING OFFICER FOR REVIEW AND APPROVAL PRIOR TO BEGINNING WORK.
15. SHOP DRAWINGS MUST BE SUBMITTED TO THE CONTRACTING OFFICER FOR REVIEW AND APPROVAL PRIOR TO FABRICATION. UNLESS NOTED OTHERWISE, PROVIDE SHOP DRAWINGS FOR:
    A. DEFORMED BAR REINFORCING LAYOUT FOR CONCRETE AND MASONRY.
    B. STRUCTURAL AND MISCELLANEOUS STEEL.
    C. COLD-FORMED STEEL FRAMING.
    D. ROOF METAL.
    E. MICROPILES.
16. BY SUBMITTING FOR ENGINEER'S REVIEW, THE CONTRACTOR CONFIRMS THE ACCURACY OF THE SUBMITTALS FOR DIMENSIONS, QUANTITIES, ELEMENT SIZES, CONSTRUCTION MATERIALS, FIELD MEASUREMENTS AND THAT THE CONTENTS HAVE BEEN REVIEWED FOR MEANS, METHODS, AND OPERATIONS OF CONSTRUCTION, AND FOR ITS ADHERENCE TO SAFETY PROTOCOLS AT THE SITE.
17. SHOP DRAWING REVIEW DOES NOT RELIEVE THE CONTRACTOR FROM HAVING SOLE RESPONSIBILITY FOR THE ACCURACY OF ELEMENT SIZES, DIMENSIONS AND DETAILS. SUCH REVIEW DOES NOT CONSTITUTE ACCEPTANCE BY THE ENGINEER OF THE CORRECTNESS OR ADEQUACY OF SUCH SUBMITTALS, NOR IS A WARRANTY THAT THE SUBMITTALS SATISFY THE REQUIREMENTS OF THE CONTRACT.

FOUNDATIONS

1. GROUND PREPARATION FOR THE SITE MUST BE IN ACCORDANCE WITH THE FINAL GEOTECHNICAL REPORT LISTED.

GEOTECHNICAL REPORT	
REPORT TITLE PREPARED BY PROJECT NUMBER DATED	HUNTINGTON VA FIBER DUCTBANK NGE W24044 APRIL 2024

2. THE CONTRACTOR MUST BE FAMILIAR WITH SUBSURFACE CONDITIONS AND RELEVANT ASPECTS OF THIS REPORT BEFORE COMMENCING EXCAVATION. THE CONTRACTOR MUST RETAIN A GEOTECHNICAL ENGINEER FOR INSPECTIONS, TO VERIFY CONDITIONS, OR TO PERFORM ADDITIONAL EXPLORATION, AS NECESSARY.
3. LOCATIONS OF SUBSURFACE SITE CONDITIONS, INCLUDING BURIED UTILITIES OR OBSTRUCTIONS AND OTHER FEATURES KNOWN TO THE DESIGN TEAM ARE IDENTIFIED IN DRAWINGS. VERIFY THE EXTENT AND LOCATIONS OF SITE UTILITIES AND OBSTRUCTIONS. REPORT ANY DISCREPANCY ENCOUNTERED AS SOON AS THEY ARE KNOWN TO THE CONTRACTING OFFICER.
4. FOOTING DESIGN IS BASED ON THE FOLLOWING ALLOWABLE SOIL PROPERTIES:

SOIL PROPERTY	LOAD CASE	VALUE
BEARING CAPACITY SHALLOW FOUNDATION: TOWER 3	SUSTAINED TRANSIENT (INCL. W ,E,OR BLAST)	5,000 PSF 6650 PSF
MCR	SUSTAINED TRANSIENT (INCL. W ,E,OR BLAST)	3000 PSF 3900 PSF
MODULUS OF SUBGRADE REACTION		100 PCI
COEFFICIENT OF FRICTION AT STRENGTH		0.40
FROST DEPTH		30"
MICROPILE GROUT IN BEDROCK SKIN FRICTION		5 KSF (ULTIMATE) DOWN 2.5 KSF (ULTIMATE) UPLIFT

5. EXTERIOR FOOTINGS MUST BEAR AT OR BELOW MINIMUM FROST DEPTH, UNLESS NOTED OTHERWISE.
6. MCR FOUNDATIONS TO BEAR ON BEDROCK OR OVER-EXCAVATE TO BEDROCK AND BACK FILL WITH 2000 PSI SLURRY BACKFILL. SEE GEOTECHNICAL REPORT FOR MORE INFORMATION.
7. SLAB ON GRADE TO BEAR ON EXISTING SOIL OR RECOMPENSED SOIL. SEE GEOTECHNICAL REPORT FOR MORE INFORMATION
8. SPECIAL INSPECTION MUST BE PERFORMED DURING SITE EXCAVATION TO CONFIRM THAT EXISTING CONDITIONS COMPLY WITH CONDITIONS IN THE GEOTECHNICAL REPORT.
9. EXCAVATIONS MUST BE DEWATERED TO ALLOW FOR CASTING FOUNDATION CONCRETE IN DRY CONDITIONS.
10. USE FORMWORK TO CAST CONCRETE, SOIL FORMING CONCRETE WORK IS PROHIBITED.
11. USE A 15 MIL MIN VAPOR RETARDER AND A 4 INCH COMPACTED DRAINAGE LAYER BELOW SLABS-ON-GRADE, UNLESS NOTED OTHERWISE OR PER SPECIFIC REQUIREMENTS OF THE GEOTECHNICAL REPORT.

CAST IN PLACE CONCRETE

1. REFERENCES:
   A. ACI 301-20 SPECIFICATIONS FOR CONCRETE CONSTRUCTION
   B. ACI 315R-18 DETAILS AND DETAILING CONCRETE CONSTRUCTION
   C. ACI 318-19 BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE
   D. ACI 347-14 GUIDE TO FORMWORK FOR CONCRETE

1. CONCRETE WORK MUST CONFORM TO ACI 301. FORMWORK MUST CONFORM TO ACI 347.
2. MINIMUM CONCRETE PROPERTIES AT 28-DAYS PER THE FOLLOWING TABLE.

LOCATION	MIN 28-DAY COMPRESSIVE STRENGTH (PSI)	ACI 318, CH. 19 EXPOSURE CATEGORIES						
		FREEZING & THAWING	SULFATE	WATER CONTACT	CORROSION PROTECTION	MAX WATER/CEMENT RATIO	CEMENT TYPE	NOMINAL MAX AGGREGATE SIZE
FOUNDATIONS	5,000	F2	S1	W1	C1	0.45	II	1"
CONC OVER METAL DECK (LT.WT 115PCF MAX)	4,000	F0	S0	W0	C0	0.50	I OR II	3/4"
SLAB-ON-GROUND (INTERIOR)	4,000	F0	S0	W0	C0	0.50	I OR II	1 1/2"

3. CONCRETE EXPOSED TO THE ENVIRONMENT MUST HAVE 6% +/- 1% AIR ENTRAINMENT BY VOLUME PER ASTM C260.
4. PROVIDE A MUD SLAB (MINIMUM 2 INCHES OF CONCRETE, LEVELED AT THE TOP SURFACE) UNDER SLABS AND FOOTINGS AT WET OR MUDDY GROUND SURFACES WHICH ARE UNSUITABLE FOR SUPPORTING REBAR CHAIRS, CONSTRUCTION WORKERS AND EQUIPMENT. PROVIDE WATERPROOF MEMBRANE TO TOP OF MUD SLAB AS REQUIRED.
5. HORIZONTAL CONSTRUCTION JOINTS IN SPREAD FOOTINGS, STRIP FOOTINGS, PILE CAPS, BEAMS AND SLABS ARE PROHIBITED UNLESS SHOWN ON THE DRAWINGS OR APPROVED BY THE SER.
6. THE EXTENT OF CONCRETE PLACEMENTS MUST BE LIMITED AS FOLLOWS, UNLESS NOTED OTHERWISE:
   A. STRIP FOOTINGS AND WALLS: 60 FT (UNLESS INTERMEDIATE CONTROL JOINTS ARE PROVIDED).
   B. SLABS-ON GROUND: 30 FT MAXIMUM LENGTH AND 900 SQ FT MAXIMUM AREA (UNLESS INTERMEDIATE CONTROL JOINTS ARE PROVIDED).
7. BEFORE CASTING THE SECOND SIDE OF A CONSTRUCTION JOINT, ROUGHEN SURFACE OF CONCRETE ELEMENTS AT CONSTRUCTION JOINTS TO A MINIMUM AMPLITUDE OF 1/4 INCH, UNLESS NOTED OTHERWISE. CLEAN AND APPLY BONDING AGENT TO THE HARDENED CONCRETE SURFACE RECEIVING FRESH CONCRETE.
8. SECTIONS AND DETAILS MAY NOT SHOW ALL REQUIRED DEFORMED BAR REINFORCEMENT FOR CLARITY. ADDITIONAL REINFORCEMENT MAY BE DESCRIBED IN PLANS, SCHEDULES, NOTES, OR OTHER DETAILS, AS APPLICABLE.
9. COORDINATE FLOOR FINISHES, SLAB SLOPES & DEPRESSIONS, FLOOR DRAINS, CURBS, CONCRETE PADS, AND OTHER CONCRETE FEATURES IDENTIFIED IN THE CONTRACT DOCUMENTS.
10. THE STRUCTURAL DRAWINGS DO NOT NECESSARILY SHOW ALL ITEMS EMBEDDED IN THE CONCRETE. COORDINATE AND PROVIDED EMBEDDED ITEMS AS SHOWN IN THE CONTRACT DOCUMENTS AND AS REQUIRED BY THE EQUIPMENT MANUFACTURERS, AS NEEDED.
11. NON-STRUCTURAL STEEL MEMBERS EMBEDDED IN CONCRETE MUST BE HOT-DIP GALVANIZED OR PAINTED. DAMAGED COATINGS OF EMBEDDED ITEMS MUST BE REPAIRED PRIOR TO CASTING CONCRETE.
12. PENETRATIONS THROUGH CONCRETE WALLS OR SLABS MUST CONFORM TO STANDARD DETAIL DRAWINGS.
13. PROVIDE 3/4" CHAMFER ON EXPOSED CONCRETE EDGES UNLESS NOTED OTHERWISE.

REINFORCING STEEL

1. REFERENCES:
   A. ACI 301-20 SPECIFICATIONS FOR CONCRETE CONSTRUCTION.
   B. ACI SP-66-04 ACI DETAILING MANUAL.
   C. ACI 315R-18 DETAILS AND DETAILING CONCRETE CONSTRUCTION.
   D. AWS D1.4 2018 STRUCTURAL WELDING CODE – REINFORCING STEEL.
2. STEEL REINFORCEMENT MUST CONFORM TO:

CONDITION	STANDARD AND GRADE	MIN YIELD (KSI)
TYPICAL DEFORMED BAR	ASTM A615 GR 60 OR ASTM A706	60

3. PROVIDE BAR SUPPORTS AND SPACERS PER ACI 315 UNLESS NOTED OTHERWISE. DEFORMED BAR REINFORCEMENT AND INSERTS MUST BE SECURED IN-PLACE PRIOR TO PLACING CONCRETE. DO NOT PLACE REBAR MATS DIRECTLY AGAINST SOIL; REBAR MATS ADJACENT TO SOIL OR OVER MUD SLABS MUST BE SUPPORTED BY CHAIRS, DO NOT LIFT INTO PLACE DURING POURING.
4. UNLESS INDICATED OTHERWISE, REINFORCEMENT BARS ARE CONTINUOUS AND MUST BE LAP SPLICED OR COUPLED WITH MECHANICAL CONNECTORS. LAP LENGTH NOTES:
   A. SEE DEVELOPMENT AND LAP SPLICE LENGTH SCHEDULES FOR REINFORCEMENT DETAILS.
   B. LAP SPLICE LENGTH MUST BE USED FOR THE LARGER BAR SIZE WHEN BAR SIZE TRANSITIONS AT LAP.
   C. OVERLAP WELDED WIRE LAYER REINFORCEMENT A LENGTH OF 1.5X WIRE DEVELOPMENT LENGTH OR ONE CROSSWIRE SPACING PLUS 2 INCHES, WHICHEVER IS LARGER.
   D. MECHANICAL CONNECTORS MUST HAVE A MINIMUM CAPACITY OF 1.25 X YIELD STRENGTH OF THE BAR.
   E. MECHANICAL CONNECTORS IN MEMBERS DESIGNATED AS PART OF THE SEISMIC-FORCE-RESISTING SYSTEM MUST HAVE A MINIMUM CAPACITY EQUAL TO THE TENSILE STRENGTH OF THE BAR.
5. TYPE 1 MECHANICAL CONNECTORS MUST DEVELOP 125% OF THE YIELD STRENGTH (Fy) OF THE STRONGER OF THE TWO BAR BEING SPLICED. TYPE 2 MECHANICAL CONNECTORS MUST DEVELOP THE FULL TENSILE STRENGTH OF THE STRONGER OF THE TWO BARS BEING SPLICED. WHERE MECHANICAL CONNECTORS ARE USED IN LIEU OF LAP SPLICES, PROVIDE TYPE 2 MECHANICAL CONNECTORS EXCEPT WHERE TYPE 1 ARE PERMITTED AS INDICATED.
6. HEADED DEFORMED BARS (TERMINATORS) MUST BE INTEGRALLY FORMED OR THREADED DEVICES MEETING THE REQUIREMENTS OF ACI 318, SECTION 25.4.4.1.
7. UNLESS NOTED OTHERWISE ON THE DRAWINGS:
   A. DEFORMED BAR COVER MUST CONFORM TO SPECIFIED CONCRETE COVER REQUIREMENTS OF ACI 318.
   B. REINFORCEMENT MUST BE CONTINUOUS THROUGH CONSTRUCTION JOINTS.
   C. APPROVAL FROM SER REQUIRED BEFORE WELDING NON-ASTM A706 Gr. 60 REINFORCEMENT .
   D. APPROVAL FROM SER REQUIRED BEFORE FIELD BENDING REINFORCEMENT PARTIALLY EMBEDDED CONCRETE.
   E. MATCH DOWELS TO THE LARGER OF MULTIPLE BAR SIZES.
8. DOWELS MUST BE SECURED WITH A RIGID TEMPLATE TO ENSURE SPLICE IS LOCATED INSIDE THE CONFINED REGION (REGION ENCLOSED BY SHEAR OR HORIZONTAL REINFORCEMENT) OF CROSS-SECTION.

Revisions:	Date:

CONSULTANT
ENGINEERING DISCIPLINE:
WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD
A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES
SPEESDESIGNBUILD

STAMP
REGISTERED PROFESSIONAL ENGINEER DANTE VALDEZ No. 5752 EXP. 6/30/27 STRUCTURAL STATE OF CALIFORNIA

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
STRUCTURAL GENERAL NOTES	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700

Approved:

Building Number:

Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn	Drawing Number
09/03/2025	CH	JKM	S-001

STRUCTURAL STEEL

1. REFERENCES:
   - A. AISC 303-22 CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES.
   - B. AISC 360-16 SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS.
   - C. AISC 341-16 SEISMIC PROVISIONS FOR STEEL BUILDINGS.
   - D. AISC RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS (RCSC) SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS 2014.
2. STRUCTURAL STEEL WORK MUST BE PERFORMED BY AISC CERTIFIED FABRICATORS & ERECTORS.
3. STEEL CONSTRUCTION AND DESIGN AS PART A DEFERRED DESIGN SUBMITTAL MUST CONFORM TO AISC 360 AND AISC 303.
4. USE STRUCTURAL STEEL SHAPES (AS APPLICABLE PER THE DRAWINGS), WITH CROSS-SECTIONS PER ASTM A6, PER THE FOLLOWING TABLE.

SHAPE	STANDARD & GRADE (UNO)	MIN YIELD (KSI)
WIDE FLANGES (W) AND TEES (WT)	ASTM A992	50
CHANNELS (C & MC) AND ANGLES (L)	ASTM A36	36
PLATE AND FLAT BAR STOCK (PL)	ASTM A36 GR 36	36
HSS RECTANGULAR OR SQUARE	ASTM A500 GR C	50
HSS ROUND	ASTM A500 GR C	46
PIPE	ASTM A53 GR B	35
OTHER STEEL	ASTM A572	50

5. PROVIDE PROTECTIVE COATING AT STEEL EXPOSED TO THE ENVIRONMENT AND WEATHER PER ARCHITECTURAL REQUIREMENTS.
6. MACHINE COLUMN ENDS AT SPLICES TO PROVIDE A FLUSH BEARING CONTACT SURFACE, UNLESS NOTED OTHERWISE.
7. EQUALLY SPACE STEEL BEAMS, NOT SPECIFICALLY DIMENSIONED ON PLAN, BETWEEN COLUMN GRID LINES OR THE INDICATED DIMENSIONED POINTS.
8. CAMBER BEAMS AS INDICATED. WHERE CAMBER IS NOT SHOWN, FABRICATE BEAMS WITH INCIDENTAL CAMBER SO THE HIGH SIDE IS PLACED UPWARD, OR OUTWARD AT WIND GIRTS.
9. CAMBER MUST BE COLD FORMED PER AISC SPECIFICATIONS AND TOLERANCES.
10. USE HIGH STRENGTH (HS) BOLTS PER ASTM F3125, GRADES AS INDICATED IN THE FOLLOWING TABLE, UNLESS NOTED OTHERWISE.

TYPICAL HIGH STRENGTH BOLTS	STANDARD, GRADE, AND NOTES
BOLT DIAMETER	7/8 INCH DIAMETER, UNO
BOLT ASTM F3125 GRADE	A325, TYPE 1 UNO
BOLT FINISH/COATING	ASTM F2329 HDG
HEAVY HEX NUT	ASTM A563 TYPE DH
HARDENED WASHER (CIRCULAR, BEVELED OR CLIPPED, AS REQ'D)	ASTM F436 TYPE 1
DIRECT TENSION INDICATING WASHERS	
BOLT DIAM. 1-1/2 IN AND SMALLER	ASTM F959
BOLT DIAM. UP TO 2-1/2 INCHES	ASTM F2437
TENSION CONTROLLED BOLTS (USE MANUFACTURER SUPPLIED NUTS AND WASHERS)	F1852 , TYPE 1

11. SLIP-CRITICAL (SC) BOLTS MUST BE PER THE RCSC SPECIFICATION AND INSPECTED IN ACCORDANCE WITH THE IBC.
12. USE SNUG-TIGHT (ST) BOLTS PER THE RCSC WHEN SLIP-CRITICAL IS NOT IDENTIFIED IN THE DRAWINGS.
13. USE ASTM A449 BOLTS WITH ASTM F563 NUTS AND ASTM F436 HARDENED WASHERS FOR THROUGH BOLTING HSS SHAPES. BOLTS MUST BE SNUG TIGHT ONLY. PROVIDE JAMB NUT TIGHTENED AGAINST STANDARD NUT TO FASTEN CONNECTOR.
14. DIRECT TENSION INDICATING (DTI) WASHERS, IF USED FOR HIGH STRENGTH BOLTS, MUST NOT BE TIGHTENED TO A FULLY CRUSHED CONDITION. DTI MUST HAVE THE MINIMUM ACCEPTABLE NUMBER OF TAPERED GAGE REJECTIONS BETWEEN LUGS. REJECTION OF GAGE AT EACH LUG LOCATION IS CAUSE FOR REJECTION OF BOLT INSTALLATION.
15. CONTRACTOR MUST SUBMIT A BOLTING PROCEDURE PLAN TO THE CONTRACTING OFFICER FOR REVIEW AND APPROVAL BY THE SER BEFORE BEGINNING WORK.
16. BOLT HOLES CUT IN THE FIELD MUST BE DRILLED, NOT BURNED. BOLT HOLES CUT IN THE SHOP MAY BE DRILLED, WATER-JET OR LASER CUT; PLASMA CUTTING HOLES NOT PERMITTED.
17. LOCATION OF EMBEDDED ELEMENTS MUST BE COORDINATED WITH CONTRACT DOCUMENTS.
18. STEEL COMPONENTS EMBEDDED IN CONCRETE OR MASONRY AT EXTERIOR LOCATIONS, EXPOSED TO EARTH, OR LOCATED IN UNCONDITIONED SPACE, MUST BE HOT-DIPPED GALVANIZED PER ASTM A123.
19. AT INTERIOR CONDITIONS (NOT EXPOSED TO WEATHER) AND COMPONENTS EMBEDDED IN CONCRETE OR MASONRY MUST BE LEFT UNPAINTED.
20. ERECTION AIDS, WHICH ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR, MUST BE REMOVED AND THE AFFECTED ELEMENTS RESTORED TO ORIGINAL DESIGN INTENT. ERECTION AIDS AND OTHER ATTACHMENTS ARE NOT PERMITTED IN PROTECTED SEISMIC ZONES OF ELEMENTS WITHOUT PRIOR APPROVAL FROM THE SER.
21. NOTIFY CONTRACTING OFFICER OF ANY FABRICATION OR ERECTION ERRORS, OR DEVIATIONS. WRITTEN APPROVAL IS REQUIRED BEFORE FIELD CORRECTIONS ARE MADE.

ANCHOR RODS

1. ANCHOR RODS MUST BE ASTM F1554 GRADE 55 WITH S-1 (WELDABLE) SUPPLEMENT, UNLESS NOTED OTHERWISE.
2. PROVIDE SMOOTH ANCHOR RODS THREADED ONLY AT EACH END OF THE ANCHOR ROD. BEFORE CASTING CONCRETE, GREASE THE UPPER 2/3 LENGTH OF EACH ANCHOR ROD. IN LIEU OF GREASE, PROVIDE TWO, INDEPENDENT LAYERS OF VISQUEEN OVER UPPER 2/3 THE LENGTH OF THE ANCHOR.
3. USE TWO HEAVY HEX NUTS ON EACH END OF ANCHOR ROD. AT TOP, USE DOUBLE NUTS FOR SECURING A WASHER AND WASHER PLATE TO THE TOP SURFACE
4. WHERE AISC OVERSIZED HOLES ARE USED AT BASE PLATES PROVIDE SINGLE-PLY MINIMUM 3/8 INCH ASTM A572 GR 50 PLATE WASHERS WELDED ALL AROUND TO THE BASE PLATE.
5. USE A RIGID STEEL TEMPLATE TO LOCATE AND SECURE ANCHOR RODS BEFORE PLACING CONCRETE. TEMPLATES MUST BE REMOVED AFTER THE CONCRETE HAS HARDENED WITHOUT DAMAGING THE STRUCTURE.
6. AFTER BASE PLATE INSTALLATION, FULLY TIGHTEN ANCHOR ROD NUTS UNLESS NOTED OTHERWISE.
7. HEATING OR BENDING ANCHOR RODS IS PROHIBITED AND GROUNDS FOR REJECTION.

COLD-FORMED STEEL

1. REFERENCES:
   - A. AISI S100-16 (2020) WITH S2-20 NORTH AMERICAN SPECIFICATION FOR THE DESIGN OF COLD-FORMED STEEL STRUCTURAL MEMBERS.
   - B. AISI S202-20 CODE OF STANDARD PRACTICE FOR COLD-FORMED STEEL STRUCTURAL FRAMING.
   - C. AISI S240-20 NORTH AMERICAN STANDARD FOR COLD-FORMED STEEL STRUCTURAL FRAMING.
   - D. AISI S400-20 NORTH AMERICAN STANDARD FOR SEISMIC DESIGN OF COLD-FORMED STEEL STRUCTURAL SYSTEM.
   - E. AWS D1.3-18 STRUCTURAL WELDING CODE – SHEET STEEL.
2. CFS STRUCTURAL MEMBERS MUST MEET THE FOLLOWING MATERIAL REQUIREMENTS. PROVIDE MINIMUM PROTECTION COATING EQUAL TO G60 GALVANIZED FINISHED. (THIS TABLE DOES NOT APPLY TO METAL DECK)

MEMBER THICKNESS	STANDARD AND GRADE	MIN YIELD (KSI)
54 MIL AND THICKER	ASTM A1003 GR 50	50
43 MIL AND THINNER	ASTM A1003 GR 33	33

3. CFS FRAMING MEMBERS MUST MEET THE TYPE, SIZE AND THICKNESS AS INDICATED ON THE STRUCTURAL PLANS AND SPECIFICATIONS, AND MUST BE MANUFACTURED BY A MEMBER OF THE STEEL STUD MANUFACTURER'S ASSOCIATION (SSMA), OR PRE-APPROVED EQUAL, IN ACCORDANCE WITH SSMA ICC EVALUATION REPORT ESR-3064P.
4. FASTENING OF COMPONENTS MUST BE WITH SCREWS OR WELDS AS NOTED ON THE DRAWINGS. WELDERS MUST BE CERTIFIED FOR WELDING OF SHEET STEEL PER AWS AND WELDING MUST CONFORM TO AWS D1.3.
5. POWDER ACTUATED FASTENERS (PAF) MUST HAVE A MINIMUM SHANK DIAMETER OF 0.145 INCHES WITH A MINIMUM WASHER BEARING AREA OF 0.321 SQUARE INCHES. THE PAF MUST COMPLY WITH THE IBC AND MUST BE PROVIDED IN ACCORDANCE WITH THE MANUFACTURER'S PUBLISHED INSTRUCTIONS AND APPROVED ICC-ES REPORT OR IAPMO-ES REPORT. INSPECTION AND TESTING MUST BE PROVIDED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, GENERAL STRUCTURAL NOTES AND APPROVED ICC-ES REPORT OR IAPMO-ES REPORT.
6. FRAMING COMPONENTS MUST BE CUT TO FIT SQUARELY AGAINST ABUTTING MEMBERS. MEMBERS MUST BE HELD FIRMLY IN POSITION UNTIL PROPERLY FASTENED. SPLICES IN STUDS AND BRACES ARE NOT PERMITTED.
7. PROVIDE ACCESSORIES INCLUDING CLIPS, STRUTS, BRACES, FASTENING DEVICES, AND OTHER ACCESSORIES REQUIRED FOR A COMPLETE AND PROPER INSTALLATION. BRIDGING PER MANUFACTURER'S REQUIREMENTS AND AS SHOWN IN THE STRUCTURAL DRAWINGS MUST BE IN PLACE PRIOR TO PLACING OF CONSTRUCTION LOADS. RUNS MUST BE RIGIDLY ANCHORED TO END WALLS.
8. CONTRACTOR MUST SUBMIT SHOP DRAWINGS AND CALCULATIONS STAMPED AND SIGNED BY AN SSE AND ALL SUPPORTING DESIGN DOCUMENTATION TO THE CONTRACTING OFFICER FOR REVIEW AND APPROVAL BY THE SER BEFORE CONSTRUCTION BEGINS.
9. CALCULATIONS MUST DEMONSTRATE THE ADEQUACY OF THE PROPOSED MEMBERS AND CONNECTIONS FOR STRUCTURAL DESIGN CRITERIA SHOWN IN DOCUMENTS. DRAWINGS MUST SHOW CFS SIZE, THICKNESS, LAYOUT, CONNECTIONS, MATERIAL DESIGNATION, METHOD OF INSTALLATION AND ACCESSORIES. DESIGN MUST BE IN ACCORDANCE WITH AISI STANDARDS.
10. MANUFACTURED PRODUCTS DEMONSTRATING ADEQUATE CAPACITY MAY BE USED IN LIEU OF THE CONNECTORS AND MEMBERS SPECIFIED. A COPY OF THE ICC EVALUATION REPORTS OF THE PRODUCTS SELECTED MUST BE INCLUDED IN THE SUBMITTAL.
13. WHERE NOTE SPECIFICALLY CALLED OUT ONT HE DRAWINGS, CONTRACTOR MAY USE STANDARD WALL CONNECTIONS TO THE ROOF MEMBERS.

STRUCTURAL WELDING

1. REFERENCES:
   - A. AWS D1.1-18 STRUCTURAL WELDING CODE – STEEL.
2. WELDING MUST BE DONE BY AWS CERTIFIED WELDERS AND PER AWS D1.1.
3. USE LOW HYDROGEN E70XX ELECTRODE WITH TENSILE STRENGTH PER AWS D1.1, UNLESS NOTED OTHERWISE.
4. WELDS THAT ARE PART OF THE SEISMIC FORCE-RESISTING SYSTEM MUST HAVE A MINIMUM CHARPY V-NOTCH TOUGHNESS OF 20 FOOT-POUNDS AT 0° F.
5. FIELD WELDING SYMBOLS HAVE NOT NECESSARILY BEEN USED IN THE DRAWINGS. CONTRACTOR MUST COORDINATE THE USE OF SHOP AND FIELD WELDS AS NECESSARY.
6. FILLET WELD SIZES SHOWN ON DRAWINGS INDICATE THE MINIMUM LEG SIZE REQUIRED AT THE JOINT. INCREASE WELD SIZE BY ROOT GAP DIMENSION IF A GAP EXISTS AT THE JOINT. IF THE INCLUDED ANGLE OF THE TWO CONNECTED PLATES EXCEEDS 90°, THE WELD MUST BE CONTOURED TO PROVIDE AN EFFECTIVE THROAT DIMENSION NO LESS THAN 72% OF WELD SIZE INDICATED. IF NOT SHOWN THE MINIMUM FILLET WELD SIZE AT INTERIOR LOCATIONS MUST BE NO LESS THAN 3/16 INCHES, AND NO LESS THAN 1/4 INCHES AT EXTERIOR LOCATIONS.
7. PARTIAL JOINT PENETRATION (PJP) GROOVE WELDS SHOWN ON THE DRAWINGS REFER TO EFFECTIVE THROAT THICKNESS AND MUST BE SIZED ACCORDINGLY FOR THE WELD PROCESS USED.
8. COMPLETE JOINT PENETRATION (CJP) MUST HAVE A BACKUP BAR WITH RUNOFF TABS TO ACHIEVE FULL DEPTH OVER FULL LENGTH OF WELD. BACKGOUGING THE ROOT IS REQUIRED. BACKUP BAR MUST BE REMOVED AND GROUND SMOOTH, UNLESS NOTED OTHERWISE.
9. ULTRASONICALLY TEST (UT) CJP WELDS UPON COMPLETION OF THE WELDED JOINT. PLATE THICKNESS OF 5/16-INCH OR LESS MAY USE MAGNETIC PARTICLE INSPECTION (MPI) OR EDDIE CURRENT ARRAY (ECA) TESTING.
10. QUALIFICATIONS AND WELDING PROCEDURE SPECIFICATION (WPS) PER AWS D1.1 AND D1.8 MUST BE SUBMITTED TO THE ENGINEER FOR REVIEW BEFORE STARTING FABRICATION OR ERECTION. COPIES OF THE WPS MUST BE ON SITE AND AVAILABLE TO WELDERS AND THE SPECIAL INSPECTOR.

STEEL FLOOR AND ROOF DECK

1. REFERENCES:
   - A. AISI SDI SD-22 STANDARD FOR STEEL DECK.
   - B. AISI S100-16 (2020) WITH S2-20 NORTH AMERICAN SPECIFICATION FOR THE DESIGN OF COLD-FORMED STEEL STRUCTURAL MEMBERS.
   - C. AWS D1.3-18 STRUCTURAL WELDING CODE – SHEET STEEL.
2. METAL FLOOR AND ROOF DECK MUST CONFORM TO THE STEEL DECK INSTITUTE (SDI) STANDARD FOR STEEL DECK.
3. METAL DECK AND ACCESSORIES MUST BE FORMED FROM STEEL SHEET CONFORMING TO ASTM A653, SS GR. 50, WITH A ZINC COATING FINISH CONFORMING TO ASTM A 525, CLASS G-60 (OR G-90 WHERE SPECIFIED). METAL DECK SURFACE USED FOR COMPOSITE CONSTRUCTION IN CONTACT WITH CONCRETE MUST BE PHOSPHATIZED OR GALVANIZED.
4. METAL DECK EXPOSED TO THE WEATHER MUST BE HOT-DIPPED GALVANIZED AFTER FABRICATION.
5. ALL DECK MUST BE INSTALLED USING 3 OR MORE SPANS. WHERE ONLY 1 OR 2 SPAN CONDITIONS ARE POSSIBLE, PROVIDE A DECK WITH SUFFICIENT SECTION PROPERTIES TO EQUAL BOTH LOAD AND DEFLECTION CONDITIONS OF THE 3 SPAN CONDITION. DECK LAPS MUST OCCUR OVER SUPPORT.
6. FLOOR DECK MUST HAVE A 3-INCH MINIMUM BEARING AND ROOF DECKING MUST HAVE A 2-INCH MINIMUM BEARING.
7. FURNISH ALL ACCESSORIES, INCLUDING REINFORCING ANGLES, CLOSURE STRIPS, POUR STOPS, AND OTHER ELEMENTS TO ADEQUATELY SUPPORT DECK GRAVITY LOADS AROUND OPENINGS TO COMPLETE INSTALLATION.

ANCHORED MASONRY VENEER

1. ANCHORED MASONRY VENEER AND ATTACHMENTS MUST CONFORM TO THE REQUIREMENTS OF IBC CHAPTER 14 AND THE PROJECT SPECIFICATIONS.
2. ANCHOR TIES AND JOINT REINFORCEMENT MUST BE HOT-DIPPED GALVANIZED PER ASTM A153, CLASS B-2 AND MUST BE MANUFACTURED BY DUR-O-WAL OR APPROVED EQUAL.
3. PROVIDE #9 GAUGE HORIZONTAL JOINT REINFORCEMENT WIRE. JOINT REINFORCEMENT MUST BE CONTINUOUS WITH BUTT SPLICES BETWEEN TIES PERMITTED.
4. ANCHOR TIES MUST BE SPACED 16" O.C. EACH WAY MAXIMUM AND MUST HAVE A LIP OR HOOK ON THE EXTENDED LEG THAT WILL ENGAGE OR ENCLOSE HORIZONTAL JOINT REINFORCEMENT WIRE. ATTACH TO BACKING PER THE FOLLOWING TABLE.

BACKING CONDITION	DUR-O-WALL VENEER TIE	ATTACHMENT TO BACKING
METAL STUDS	DA 213S	DA 807 VENEER SCREW
STRUCTURAL STEEL	DA 700	WELD DA 709 TO STEEL
CONCRETE WALL	DA 904 WITH DA 931	1/4 IN DIAM EXP ANCHOR

POST INSTALLED ANCHOR IN CONCRETE AND MASONRY

1. EXCEPT WHERE INDICATED ON THE DRAWINGS, POST-INSTALLED ANCHORS CONSIST OF THE FOLLOWING ANCHOR TYPES OR APPROVED EQUAL:

CONDITION	TYPE	ACCEPTABLE ANCHORS
CONCRETE	SCREW	HILTI KWIK HUS-EZ SCREW ANCHORS PER ICC ESR-3027 SIMPSON TITEN HD SCREW ANCHOR PER ICC ESR-2713 DEWALT WEDGE-BOLT+ PER ICC ESR-2526
	EXPANSION	HILTI KWIK-BOLT TZ2 ANCHOR PER ICC ESR-4266 SIMPSON STRONG BOLT 2 ANCHOR PER ICC ESR-3037 DEWALT POWER-STUD+ SD1 ANCHOR PER ICC ESR-2818
	ADHESIVE	HILTI HIT-HY 200 ADHESIVE ANCHOR SYSTEM PER ICC ESR-3187 SIMPSON SET-XP ADHESIVE ANCHOR SYSTEM PER ICC ESR-2508 DEWALT PE1000+ ADHESIVE ANCHOR SYSTEM PER ICC ESR-2583
	UNDERCUT	HILTI HDA-P UNDERCUT ANCHOR PER ICC ESR-1546 SIMPSON TORQ-CUT SELF UNDERCUTTING ANCHOR PER ICC ESR-2705 DEWALT CCU+ UNDERCUT ANCHOR CARBON STEEL PER ICC ESR-4810
SOLID-GROUTED MASONRY	SCREWS	HILTI KWIK HUS-EZ SCREW ANCHORS PER ICC ESR-3056 SIMPSON TITEN HD SCREW ANCHOR PER ICC ESR-2713 DEWALT SCREW-BOLT+ PER ICC ESR-4042
	EXPANSION	HILTI KWIK-BOLT 3 ANCHOR PER ICC ESR-1385 SIMPSON STRONG BOLT 2 ANCHOR PER UES ER-240 DEWALT POWER-STUD+ SD1 ANCHOR PER ICC ESR-2966
	ADHESIVE	HILTI HIT-HY 270 ADHESIVE SYSTEM PER ICC ESR-4143 SIMPSON SET-XP ADHESIVE SYSTEM PER IAPMO UES ER-265 DEWALT AC100+GOLD ADHESIVE SYSTEM PER ICC ESR-3200 (STEEL ANCHOR MUST BE ASTM F1554 GRADE 55 CONTINUOUSLY THREADED ROD PER DRAWINGS)

2. ANCHOR CAPACITY USED IN DESIGN MUST BE BASED ON THE TECHNICAL DATA PUBLISHED IN THE ICC APPROVAL REPORT. SUBSTITUTION REQUESTS MUST INCLUDE ICC ESR REPORT SHOWING COMPLIANCE WITH RELEVANT BUILDING CODE AND INSTALLATION CATEGORY AND BE APPROVED IN WRITING BY THE CONTRACTING OFFICER FOR REVIEW AND APPROVAL BY THE SER PRIOR TO USE.
3. INSTALL ANCHORS PER THE MANUFACTURER INSTRUCTIONS, AS INCLUDED IN THE ANCHOR PACKAGING.
4. INSTALL ANCHORS IN ACCORDANCE WITH SPACING AND EDGE CLEARANCES INDICATED ON THE DRAWINGS.
5. EXISTING DEFORMED BAR REINFORCEMENT IN THE STRUCTURE MAY CONFLICT WITH SPECIFIC ANCHOR LOCATIONS. UNLESS NOTED OTHERWISE, THE CONTRACTOR MUST LOCATE THE POSITION OF THE EXISTING REINFORCING BARS AND AVOID CUTTING.
6. DRILLING, CORING, SAW-CUTTING, ETC. INTO CONCRETE SHALL MEET THE LATEST OSHA REGULATIONS FOR SILICA DUST EXPOSURE.

SPECIAL INSPECTION AND TESTING

1. SPECIAL INSPECTION AND TESTING MUST CONFORM TO SECTION 1704 OF THE INTERNATIONAL BUILDING CODE (IBC) AS AMENDED BY H-18-8.
2. ONE OR MORE QUALIFIED SPECIAL INSPECTION & TESTING AGENCIES MUST BE EMPLOYED TO PERFORM THE NECESSARY INSPECTION OF IBC SECTION 1705, AS APPLICABLE. QUALIFICATIONS FOR SPECIAL INSPECTION AND TESTING AGENCIES AND INSPECTORS MUST BE SUBMITTED TO THE CONTRACTING OFFICER FOR REVIEW AND APPROVAL.
3. SPECIAL INSPECTOR QUALIFICATIONS MUST MEET THE REQUIREMENTS OF SPECIFICATION SECTION 01 45 35.
   - FOR STATEMENT OF SPECIAL INSPECTION SEE PROJECT SPECIFICATIONS.
5. REPORTING ON SPECIAL INSPECTION AND TESTING MUST CONFORM TO IBC SECTION 1704.5 AND BE SUBMITTED TO THE CONTRACTING OFFICER WEEKLY , OR AS REQUIRED BY THE SPECIFICATIONS.

STRUCTURAL OBSERVATIONS

1. STRUCTURAL OBSERVATIONS MUST BE PERFORMED BY THE DESIGNATED REPRESENTATIVE BY THE GOVERNMENT, FOR THE FOLLOWING:
   - A. FOUNDATION: PLACEMENT OF DEFORMED BAR REINFORCEMENT, BEFORE CONCRETE.
   - B. CONCRETE WALLS: FINAL PLACEMENT OF DEFORMED BARS REINFORCEMENT AND ANCHORS PRIOR TO POUR.
   - C. STRUCTURAL STEEL: BEAMS AND METAL DECK.
   - D. ANCHORAGE: ANCHORAGE OF TOWERS TO EXISTING BUILDINGS.
2. CONTRACTOR MUST NOTIFY CONTRACTING OFFICER 14 DAYS IN ADVANCE OF WHEN WORK IS EXPECTED TO COORDINATE THE DATE OF OBSERVATION.
3. STRUCTURAL OBSERVATION DOES NOT WAIVE THE RESPONSIBILITY OF SPECIAL INSPECTION REQUIREMENTS.

Revisions:	Date:

CONSULTANT
ENGINEERING DISCIPLINE:
WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD
A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

STAMP
REGISTERED PROFESSIONAL ENGINEER
DANTE VALDEZ
No. 5752
STRUCTURAL
STATE OF CALIFORNIA

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
STRUCTURAL GENERAL NOTES	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number:
		Issue Date: 09/03/2025 · Checked: CH · Drawn: JKM	Drawing Number: S-002

VA FORM 08 - 6231

&	AND
@	AT
ADDL	ADDITIONAL
ADJ	ADJACENT
AFF	ABOVE FINISHED FLOOR
ALT	ALTERNATE
ALUM	ALUMINUM
APPROX	APPROXIMATE
AR	ANCHOR RODS
ARCH	ARCHITECT
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS
ATFP	ANTI-TERRORISM FORCE PROTECTION
BAL	BALANCE
BD	BOARD
BLDG	BUILDING
BLKG	BLOCKING
BLW	BELOW
BM	BEAM
BOT	BOTTOM
BRG	BEARING
BTB	BACK TO BACK
BTWN	BETWEEN
CFS	COLD-FORMED STEEL
CG	CENTER OF GRAVITY
CIP	CAST IN PLACE
CJ	CONTROL JOINT
CJ	CONSTRUCTION JOINT
CL	CENTERLINE
CLR	CLEAR
CMU	CONCRETE MASONRY UNIT
COL	COLUMN
CONC	CONCRETE
CONN	CONNECTION
CONSTR	CONSTRUCTION
CONT	CONTINUOUS
CONTR	CONTRACTOR
COORD	COORDINATE
CTR	CENTER
DBL	DOUBLE
DEMO	DEMOLISH
DET	DETAIL
DIA OR Ø	DIAMETER
DIAG	DIAGONAL
DIM	DIMENSION
DIST	DISTANCE
DL	DEAD LOAD
DWG	DRAWING
E	EAST
EA	EACH
EF	EACH FACE
EL	ELEVATION
ELEC	ELECTRIC
EMBED	EMBEDMENT
ENGR	ENGINEER
EQ	EQUAL
EQUIV	EQUIVALENT
EW	EACH WAY
EXIST	EXISTING
EXP	EXPANSION
EXT	EXTERIOR
FD	FLOOR DRAIN
FDTN	FOUNDATION
FIN	FINISH(ED)
FIN FLR	FINISHED FLOOR
FLG	FLANGE
FLR	FLOOR
FOC	FACE OF CONCRETE
FOM	FACE OF MASONRY
FOS	FACE OF STUD, FACE OF STEEL
FRMG	FRAMING
FS	FAR SIDE
FT	FOOT, FEET
FTG	FOOTING
FV	FIELD VERIFY
GA	GAGE
GALV	GALVANIZED
HDG	HOT-DIP GALVANIZED
HORIZ	HORIZONTAL
HS	HIGH STRENGTH
HSA	HEADED STUD ANCHOR
HT	HEIGHT
ID	INSIDE DIAMETER
IJ	ISOLATION JOINT
IN	INCH
INFO	INFORMATION
INT	INTERIOR
JBE	JOIST BEARING ELEVATION
JT	JOINT
KSI	KIPS PER SQUARE INCH
LBS	POUNDS
LF	LINEAR FEET
LL	LIVE LOAD
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
LONG	LONGINTUDINAL
LSL	LONG SLOTTED HOLE
LSLP	LONG SLOTTED HOLE PARALLEL
LSLT	LONG SLOTTED HOLE TRANSVERSE
LT GA	LIGHT GAGE
MAX	MAXIMUM
MECH	MECHANICAL
MFR	MANUFACTURER
MIN	MINIMUM
MISC	MISCELLANEOUS
MTL	METAL
#	NUMBER
N	NORTH
NA	NOT APPLICABLE
NIC	NOT IN CONTRACT
NOM	NOMINAL
NS	NEAR SIDE
NTS	NOT TO SCALE
OA	OVERALL
OC	ON CENTER
OD	OUTSIDE DIAMETER
OF	OUTSIDE FACE
OPNG	OPENING
OPP	OPPOSITE
OWJ	OPEN WEB JOIST
PAF	POWDER ACTUATED FASTENERS
PCF	POUNDS PER CUBIC FOOT
PEMB	PRE-ENGINEERED METAL BUILDING
PERP	PERPENDICULAR
PH	PHASE
PL	PLATE
PLWD	PLYWOOD
PNL	PANEL
PREFAB	PREFABRICATED
PROJ	PROJECT
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	POST TENSIONED
QTY	QUANTITY
R	RADIUS
REF	REFERENCE
REINF	REINFORCE, REINFORCEMENT
REQD	REQUIRED
REV	REVISION
RO	ROUGH OPENING
S	SOUTH
SC	SLIP-CRITICAL
SCHED	SCHEDULE
SECT	SECTION
SF	SQUARE FOOT
SHT	SHEET
SIM	SIMILAR
SOG	SLAB ON GRADE
SPA	SPACE, SPACING
SPEC	SPECIFICATION
SQ	SQUARE
SSL	SHORT SLOTTED HOLE
SSLP	SHORT SLOTTED HOLE PARALLEL
SSLT	SHORT SLOTTED HOLE TRANSVERSE
SST	STAINLESS STEEL
STD	STANDARD
STL	STEEL
STRUCT	STRUCTURAL
SUSP	SUSPENDED
SW	SHEAR WALL
SYMM	SYMMETRICAL
T&B	TOP AND BOTTOM
TEMP	TEMPORARY
THK	THICK
THRU	THROUGH
TOB	TOP OF BEAM
TOC	TOP OF CONCRETE
TOF	TOP OF FOOTING
TOM	TOP OF MASONRY
TOS	TOP OF STEEL
TOW	TOP OF WALL
TRANSV	TRANSVERSE
TYP	TYPICAL
UL	UNDERWRITERS LABORATORIES
UNO	UNLESS NOTED OTHERWISE
VERT	VERTICAL
VOL	VOLUME
W	WEST
W/	WITH
W/O	WITHOUT
WD	WOOD
WP	WORKING POINT
WT	WEIGHT
WTS	WELDED THREADED STUDS
WWR	WELDED WIRE REINFORCEMENT

STRUCTURAL DRAWING SYMBOLS



SLOPE
SECTION OR ELEVATION CUT
SECTION, DETAIL, OR ELEVATION CALLOUT
DRAWING WHERE SECTION, DETAIL OR ELEVATION IS SHOWN OR CALLED FROM
PLAN
SECTION, DETAIL, OR ELEVATION
COORDINATES
GRID NO.
WORK POINT
PLAN REVISION
ELEVATION OF COMPONENTS
INDICATES STEP FOOTING PER DETAIL
INDICATES STEP IN SLAB / DECK
INDICATES SLOPE IN SLAB / DECK
INDICATES APPROXIMATE SPOT ELEVATION
CENTERLINE

STRUCTURAL DRAWING LEGEND

C-1	INDICATES STEEL COLUMN PER SCHEDULE
C-24-1	INDICATES CONCRETE COLUMN PER SCHEDULE
MC-1	INDICATES MOMENT FRAME COLUMN PER SCHEDULE
GB-1	INDICATES GRADE BEAM PER SCHEDULE
G-1	INDICATES GIRDERS PER DETAILS
B-1	INDICATES BEAMS PER DETAILS
MB-1	INDICATES MOMENT FRAME BEAM PER SCHEDULE
S-1	INDICATES SLAB PER SCHEDULE
BF-1	INDICATES BRACED FRAME
SMF-1	INDICATES SPECIAL MOMENT FRAME
CJ	INDICATED PROPOSED LOCATION FOR SLAB-ON-GRADE CONTROL JOINT

Revisions: Date:

CONSULTANT
ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

STAMP
REGISTERED PROFESSIONAL ENGINEER DANTE VALDEZ No. 5752 STRUCTURAL STATE OF CALIFORNIA

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title: ABRREVIATIONS AND SYMBOLS
Approved:
Phase: 100% CONSTRUCTION DOCUMENTS
Project Title: EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date: 09/03/2025 | Checked: CH | Drawn: JKM
Project Number: 581-22-700
Building Number:
Drawing Number: S-003

VA FORM 08 - 6231



C1 FOUNDATION PLAN T1

1/4" = 1'-0"



C5 FRAMING PLAN - LEVELS 01 THROUGH 05 T1

1/4" = 1'-0"



F1 ROOF FRAMING PLAN T1

1/4" = 1'-0"

PLAN NOTES:

1. REFER TO SHEETS S-001 THRU S-003 FOR GENERAL NOTES. THESE NOTES & DETAILS ON SHEET S-511, S-512, AND S-515 SHALL BE USED WHERE APPLICABLE, WHETHER SPECIFICALLY REFERENCED OR NOT.
2. REFER TO FOUNDATION AND SLAB-ON-GRADE NOTES ON SHEET S-001 & SPECIFICATIONS FOR GEOTECHNICAL RECOMMENDATIONS AND PAD PREPARATION.
3. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR ANY DIMENSIONS, OPENINGS, AND ELEVATIONS NOT SHOWN.
4. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR THE FOLLOWING:
   A. DIMENSIONS NOT SHOWN.
   B. OPENINGS NOT SHOWN.
   C. FLOOR ELEVATIONS.
5. FOR TYPICAL OPENINGS EXACT LOCATION AND SIZE, SEE ARCHITECTURAL AND MECHANICAL DRAWINGS.
6. DIMENSIONS AND ELEVATIONS SHALL BE VERIFIED PRIOR TO STEEL FABRICATION AND ERECTION.
7. FOR TYPICAL CONCRETE DETAILS, REFER TO SHEET S-501.
8. FOR FOUNDATION DETAILS, REFER TO SHEET S-502.
9. FOR TYPICAL STRUCTURAL STEEL DETAILS, REFER TO SHEET S-511, S-512, AND S-515.
10. BEAM-TO-BEAM CONNECTION PER B1/S-511 UNO.

LEGEND:

W14x22( )	INDICATES BEAM AND BEAM SIZE (#OF STUDS)
	GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
	LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH	INDICATES COLD FORMED HEADER PER **C3 / S-525**
	INDICATES DIRECTION OF DECK SPAN.
SW1	INDICATES METAL STUD SHEAR WALL PER **3 / S-527**
X'-XX"	INDICATES APPROXIMATE LENGTH OF SHEAR WALL
	INDICATES LOCATION OF SHEAR WALL SHEATHING
S/HDU4	INDICATES SIMPSON HOLDOWN TYPE AND SIZE PER
D1	COMPOSITE DECK PER **B1 / S-512**
	DECK OPENING
	MICROPILE
TB	TIE BEAM PER **D1 / S-503**

KEY PLAN



SHOWN AREA

Revisions:	Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

SPEESDESIGNBUILD

STAMP

REGISTERED PROFESSIONAL ENGINEER
DANTE VALDEZ
No. 5752
STRUCTURAL
STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	STRUCTURAL PLANS - TOWER T1	Phase	100% CONSTRUCTION DOCUMENTS
Approved:			
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	Project Number	581-22-700
		Building Number	01S
Location	VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Drawing Number	S-101
Issue Date: 09/03/2025	Checked: CH	Drawn: JKM	024 OF 693



C1 FOUNDATION PLAN T2
1/4" = 1'-0"



C5 FRAMING PLAN - LEVELS 00G THROUGH 03 T2
1/4" = 1'-0"



F1 ROOF FRAMING PLAN
1/4" = 1'-0"

PLAN NOTES:

1. REFER TO SHEETS S-001 THRU S-003 FOR GENERAL NOTES. THESE NOTES & DETAILS ON SHEET S-511, S-512, AND S-515 SHALL BE USED WHERE APPLICABLE, WHETHER SPECIFICALLY REFERENCED OR NOT.
2. REFER TO FOUNDATION AND SLAB-ON-GRADE NOTES ON SHEET S-001 & SPECIFICATIONS FOR GEOTECHNICAL RECOMMENDATIONS AND PAD PREPARATION.
3. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR ANY DIMENSIONS, OPENINGS, AND ELEVATIONS NOT SHOWN.
4. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR THE FOLLOWING:
   A. DIMENSIONS NOT SHOWN.
   B. OPENINGS NOT SHOWN.
   C. FLOOR ELEVATIONS.
5. FOR TYPICAL OPENINGS EXACT LOCATION AND SIZE, SEE ARCHITECTURAL AND MECHANICAL DRAWINGS.
6. DIMENSIONS AND ELEVATIONS SHALL BE VERIFIED PRIOR TO STEEL FABRICATION AND ERECTION.
7. FOR TYPICAL CONCRETE DETAILS, REFER TO SHEET S-501.
8. FOR FOUNDATION DETAILS, REFER TO SHEET S-502.
9. FOR TYPICAL STRUCTURAL STEEL DETAILS, REFER TO SHEET S-511, S-512, AND S-515.
10. BEAM-TO-BEAM CONNECTION PER B1/S-511 UNO.

LEGEND:

W14x22( )	INDICATES BEAM AND BEAM SIZE (#OF STUDS)
	GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
	LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH	INDICATES COLD FORMED HEADER PER **C3 / S-525**
	INDICATES DIRECTION OF DECK SPAN.
SW1	INDICATES METAL STUD SHEAR WALL PER **3 / S-527**
X'-XX"	INDICATES APPROXIMATE LENGTH OF SHEAR WALL
	INDICATES LOCATION OF SHEAR WALL SHEATHING
S/HDU4	INDICATES SIMPSON HOLDOWN TYPE AND SIZE PER
D1	COMPOSITE DECK PER **B1 / S-512**
	DECK OPENING
	MICROPILE
TB	TIE BEAM PER **D1 / S-503**

KEY PLAN



SHOWN AREA

PROJECT NORTH

Revisions: | Date:

CONSULTANT
ENGINEERING DISCIPLINE:
WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD
A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES
SPEESDESIGNBUILD

STAMP

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title: STRUCTURAL PLANS - TOWER T2
Approved:
Phase: 100% CONSTRUCTION DOCUMENTS
Project Title: EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Project Number: 581-22-700
Building Number: 01W
Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Drawing Number: S-102
Issue Date: 09/03/2025
Checked: CH
Drawn: JKM
025 OF 693

VA FORM 08 - 6231



NOTE:

DO NOT DAMAGE EXISTING BUILDING FOOTING.
INSTALL WITHIN 6" OF EXISTING FOOTING FOOTING.

C1 FOUNDATION PLAN T3

1/4" = 1'-0"



C6 FRAMING PLAN - LEVELS 00B AND 00G T3

1/4" = 1'-0"



F1 ROOF FRAMING PLAN T3

1/4" = 1'-0"



F6 OPENING AT EXIST CONC WALL

1/2" = 1'-0"

PLAN NOTES:

1. REFER TO SHEETS S-001 THRU S-003 FOR GENERAL NOTES. THESE NOTES & DETAILS ON SHEET S-511, S-512, AND S-515 SHALL BE USED WHERE APPLICABLE, WHETHER SPECIFICALLY REFERENCED OR NOT.
2. REFER TO FOUNDATION AND SLAB-ON-GRADE NOTES ON SHEET S-001 & SPECIFICATIONS FOR GEOTECHNICAL RECOMMENDATIONS AND PAD PREPARATION.
3. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR ANY DIMENSIONS, OPENINGS, AND ELEVATIONS NOT SHOWN.
4. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR THE FOLLOWING:
   A. DIMENSIONS NOT SHOWN.
   B. OPENINGS NOT SHOWN.
   C. FLOOR ELEVATIONS.
5. FOR TYPICAL OPENINGS EXACT LOCATION AND SIZE, SEE ARCHITECTURAL AND MECHANICAL DRAWINGS.
6. DIMENSIONS AND ELEVATIONS SHALL BE VERIFIED PRIOR TO STEEL FABRICATION AND ERECTION.
7. FOR TYPICAL CONCRETE DETAILS, REFER TO SHEET S-501.
8. FOR FOUNDATION DETAILS, REFER TO SHEET S-502.
9. FOR TYPICAL STRUCTURAL STEEL DETAILS, REFER TO SHEET S-511, S-512, AND S-515.
10. BEAM-TO-BEAM CONNECTION PER B1/S-511 UNO.

LEGEND:

W14x22( )	INDICATES BEAM AND BEAM SIZE (#OF STUDS)
	GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
	LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH	INDICATES COLD FORMED HEADER PER **C3 / S-525**
	INDICATES DIRECTION OF DECK SPAN.
SW1	INDICATES METAL STUD SHEAR WALL PER **3 / S-527**
X'-XX"	INDICATES APPROXIMATE LENGTH OF SHEAR WALL
	INDICATES LOCATION OF SHEAR WALL SHEATHING
S/HDU4	INDICATES SIMPSON HOLDOWN TYPE AND SIZE PER
D1	COMPOSITE DECK PER **B1 / S-512**
	DECK OPENING
	MICROPILE
TB	TIE BEAM PER **D1 / S-503**

KEY PLAN



SHOWN AREA

Revisions:	Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:

SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

STAMP

REGISTERED PROFESSIONAL ENGINEER DANTE VALDEZ No. 5752 STRUCTURAL STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
STRUCTURAL PLANS - TOWER T3	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
			Building Number: 02
Approved:		Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Drawing Number: S-103
		Issue Date: 09/03/2025 · Checked: CH · Drawn: JKM	026 OF 693



NOTE:

CENTER COLUMN ON EXISTING WALL BELOW.

C1 GROUND LEVEL PLAN T4

1/4" = 1'-0"



C5 FRAMING PLAN - LEVELS 01THROUGH 05 T4

1/4" = 1'-0"



F1 ROOF FRAMING PLAN T4

1/4" = 1'-0"

PLAN NOTES:

1. REFER TO SHEETS S-001 THRU S-003 FOR GENERAL NOTES. THESE NOTES & DETAILS ON SHEET S-511, S-512, AND S-515 SHALL BE USED WHERE APPLICABLE, WHETHER SPECIFICALLY REFERENCED OR NOT.
2. REFER TO FOUNDATION AND SLAB-ON-GRADE NOTES ON SHEET S-001 & SPECIFICATIONS FOR GEOTECHNICAL RECOMMENDATIONS AND PAD PREPARATION.
3. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR ANY DIMENSIONS, OPENINGS, AND ELEVATIONS NOT SHOWN.
4. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR THE FOLLOWING:
   A. DIMENSIONS NOT SHOWN.
   B. OPENINGS NOT SHOWN.
   C. FLOOR ELEVATIONS.
5. FOR TYPICAL OPENINGS EXACT LOCATION AND SIZE, SEE ARCHITECTURAL AND MECHANICAL DRAWINGS.
6. DIMENSIONS AND ELEVATIONS SHALL BE VERIFIED PRIOR TO STEEL FABRICATION AND ERECTION.
7. FOR TYPICAL CONCRETE DETAILS, REFER TO SHEET S-501.
8. FOR FOUNDATION DETAILS, REFER TO SHEET S-502.
9. FOR TYPICAL STRUCTURAL STEEL DETAILS, REFER TO SHEET S-511, S-512, AND S-515.
10. BEAM-TO-BEAM CONNECTION PER B1/S-511 UNO.

LEGEND:

W14x22( )	INDICATES BEAM AND BEAM SIZE (#OF STUDS)
	GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
	LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH	INDICATES COLD FORMED HEADER PER **C3 / S-525**
	INDICATES DIRECTION OF DECK SPAN.
SW1	INDICATES METAL STUD SHEAR WALL PER **3 / S-527**
X'-XX"	INDICATES APPROXIMATE LENGTH OF SHEAR WALL
	INDICATES LOCATION OF SHEAR WALL SHEATHING
S/HDU4	INDICATES SIMPSON HOLDOWN TYPE AND SIZE PER
D1	COMPOSITE DECK PER **B1 / S-512**
	DECK OPENING
	MICROPILE
TB	TIE BEAM PER **D1 / S-503**

KEY PLAN



SHOWN AREA

Revisions: | Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

STAMP

REGISTERED PROFESSIONAL ENGINEER
DANTE VALDEZ
No. 5752
STRUCTURAL
STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	STRUCTURAL PLANS - TOWER T4
Approved:	
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Project Number	581-22-700
Building Number	01S
Location	VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date	09/03/2025
Checked	CH
Drawn	JKM
Drawing Number	S-104

VA FORM 08 - 6231

PLAN NOTES:

1. REFER TO SHEETS S-001 THRU S-003 FOR GENERAL NOTES AND SHEET S-502 FOR TYPICAL DETAILS. THESE NOTES & DETAILS SHALL BE USED WHERE APPLICABLE, WHETHER SPECIFICALLY REFERENCED OR NOT.
2. REFER TO FOUNDATION AND SLAB-ON-GRADE NOTES ON SHEET S-001 & SPECIFICATIONS FOR GEOTECHNICAL RECOMMENDATIONS AND PAD PREPARATION.
3. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR ANY DIMENSIONS, OPENINGS, AND ELEVATIONS NOT SHOWN.
4. SEE DETAILS REFERENCED ON PLANS FOR TOP AND BOTTOM FOOTING ELEVATIONS.
5. ATTACH CFS STUDS TO HSS COLUMN IN WALL PER D9/S-526

LEGEND:

W14x22( )	INDICATES BEAM AND BEAM SIZE (#OF STUDS)
	GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
	LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH	INDICATES COLD FORMED HEADER PER **C3 / S-525**
	INDICATES DIRECTION OF DECK SPAN.
SW1	INDICATES METAL STUD SHEAR WALL PER **3 / S-527**
X'-XX"	INDICATES APPROXIMATE LENGTH OF SHEAR WALL
	INDICATES LOCATION OF SHEAR WALL SHEATHING
S/HDU4	INDICATES SIMPSON HOLDOWN TYPE AND SIZE PER
D1	COMPOSITE DECK PER **B1 / S-512**
	DECK OPENING
	MICROPILE
TB	TIE BEAM PER **D1 / S-503**



F1 FOUNDATION PLAN - DATA CENTER - PHASE 1B

1/4" = 1'-0"

KEY PLAN



SHOWN AREA

Revisions:	Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

SPEESDESIGNBUILD

STAMP

REGISTERED PROFESSIONAL ENGINEER
DANTE VALDEZ
No. 5752
EXP. 6/30/27
STRUCTURAL
STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	FOUNDATION PLAN - DATA CENTER - PHASE 1
Approved:	
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Project Number	581-22-700
Building Number	GC115-1
Location	VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Drawing Number	S-105-1B
Issue Date	09/03/2025
Checked	CH
Drawn	JKM
	028 OF 693

VA FORM 08 - 6231



F1 FOUNDATION PLAN - DATA CENTER - PHASE 2B

1/4" = 1'-0"

PLAN NOTES:

1. REFER TO SHEETS S-001 THRU S-003 FOR GENERAL NOTES AND SHEET S-502 FOR TYPICAL DETAILS. THESE NOTES & DETAILS SHALL BE USED WHERE APPLICABLE, WHETHER SPECIFICALLY REFERENCED OR NOT.
2. REFER TO FOUNDATION AND SLAB-ON-GRADE NOTES ON SHEET S-001 & SPECIFICATIONS FOR GEOTECHNICAL RECOMMENDATIONS AND PAD PREPARATION.
3. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR ANY DIMENSIONS, OPENINGS, AND ELEVATIONS NOT SHOWN.
4. SEE DETAILS REFERENCED ON PLANS FOR TOP AND BOTTOM FOOTING ELEVATIONS.

LEGEND:

W14x22( )	INDICATES BEAM AND BEAM SIZE (#OF STUDS)
	GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
	LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH	INDICATES COLD FORMED HEADER PER **C3 / S-525**
	INDICATES DIRECTION OF DECK SPAN.
SW1	INDICATES METAL STUD SHEAR WALL PER **3 / S-527**
X'-XX"	INDICATES APPROXIMATE LENGTH OF SHEAR WALL
	INDICATES LOCATION OF SHEAR WALL SHEATHING
S/HDU4	INDICATES SIMPSON HOLDOWN TYPE AND SIZE PER
D1	COMPOSITE DECK PER **B1 / S-512**
	DECK OPENING
	MICROPILE
TB	TIE BEAM PER **D1 / S-503**

KEY PLAN



SHOWN AREA

Revisions: | Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

SDB SPEESDESIGNBUILD

STAMP

REGISTERED PROFESSIONAL ENGINEER DANTE VALDEZ No. 5752 STRUCTURAL STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
FOUNDATION PLAN - DATA CENTER - PHASE 2	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number: GC115-1
		Issue Date: 09/03/2025 · Checked: CH · Drawn: AAC	Drawing Number: S-106-2B



C1 DEMOLITION PLAN TR1
1/4" = 1'-0"



F1 FOUNDATION PLAN TR1
1/4" = 1'-0"



F6 ROOF FRAMING PLAN TR1
1/4" = 1'-0"

NOTES:

1. OPENING FRAMING :
   - A. IF EXISTING WALL IS WOOD FRAMED, REFER TO **D6 / S-515** FOR FRAMING AT NEW OPENING
   - B. IF EXISTING WALL IS CFS FRAMED, REFER TO **F3 / S-525** FOR FRAMING AT NEW OPENING

LEGEND:

	EXISTING WALL TO BE DEMOLISHED
W14x22( )	INDICATES BEAM AND BEAM SIZE (#OF STUDS)
	GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
	LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH	INDICATES COLD FORMED HEADER PER **C3 / S-525**
	INDICATES DIRECTION OF DECK SPAN.
SW1	INDICATES METAL STUD SHEAR WALL PER **3 / S-527**
X'-XX"	INDICATES APPROXIMATE LENGTH OF SHEAR WALL
	INDICATES LOCATION OF SHEAR WALL SHEATHING
S/HDU4	INDICATES SIMPSON HOLDOWN TYPE AND SIZE PER
D1	COMPOSITE DECK PER **B1 / S-512**
	DECK OPENING
	MICROPILE
TB	TIE BEAM PER **D1 / S-503**

KEY PLAN



Revisions:	Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

SPEESDESIGNBUILD

STAMP

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	STRUCTURAL PLANS - BUILDING TR1
Approved:	
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Project Number	581-22-700
Building Number	TRAILER 1
Location	VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date	09/03/2025
Checked	CH
Drawn	Author
Drawing Number	S-107

PLAN NOTES:

1. REFER TO SHEET S-001 THROUGH S-004 FOR GENERAL NOTES, AND SHEETS S-501 THROUGH S-540 FOR TYPICAL DETAILS. THESE NOTES AND DETAILS SHALL BE USED WHERE APPLICABLE, WHETHER SPECIFICALLY REFERENCED OR NOT.
2. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR THE FOLLOWING:
   A. DIMENSIONS NOT SHOWN.
   B. OPENINGS NOT SHOWN.
   C. FLOOR ELEVATIONS.
3. FOR TYPICAL OPENINGS EXACT LOCATION AND SIZE, SEE ARCHITECTURAL AND MECHANICAL DRAWINGS. FOR JOIST AND BEAM REINFORCING USE DETAILS.
4. ROOF JOISTS ARE SPACED AT 16" OC MAX TYPICAL UNO.
5. DIMENSIONS AND ELEVATIONS SHALL BE VERIFIED PRIOR TO STEEL FABRICATION AND ERECTION.
6. TYPICAL STEEL BEAM CONNECTIONS PER S-511.
7. TYPICAL OPENINGS IN ROOF JOISTS PER **B6 / S-528**
8. TYPICAL BB JOIST CONNECTION PER **D4 / S-528**
9. COORDINATE CONNECTION OF MECHANICAL UNIT CURB TO ROOF DECK WITH MECHANICAL DRAWINGS. MAXIMUM WEIGHT OF MECHANICAL UNITS NOTED UNCLUDES THE COMBINED WEIGHT OF THE UNIT, CURB, AND APPENDAGES.

LEGEND:

W14x22	INDICATES BEAM AND BEAM SIZE
	GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
	LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH	INDICATES COLD FORMED HEADER PER **C3 / S-525**
CFH-SIM	INDICATES ALTERNATE COLD FORMED HEADER PER **C3 / S-525**
	INDICATES DIRECTION OF DECK SPAN. FOR ROOF DECK SEE **B1 / S-511**



F1 ROOF FRAMING PLAN - DATA CENTER - PHASE 1B

1/4" = 1'-0"

KEY PLAN



SHOWN AREA

Revisions:	Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

SPEESDESIGNBUILD

STAMP

REGISTERED PROFESSIONAL ENGINEER DANTE VALDEZ No. 5752 STRUCTURAL STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
ROOF FRAMING PLAN - DATA CENTER - PHASE 1	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
			Building Number: GC115-1
Approved:		Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Drawing Number: S-115-1B
		Issue Date: 09/03/2025 · Checked: CH · Drawn: JKM	031 OF 693

VA FORM 08 - 6231

LEGEND:

EXISTING WALL TO BE DEMOLISHED



F1 DEMOLITION PLAN - DATA CENTER - PHASE 2B

1/4" = 1'-0"

KEY PLAN



SHOWN AREA

Revisions: | Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:

SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

SPEESDESIGNBUILD

STAMP

REGISTERED PROFESSIONAL ENGINEER
DANTE VALDEZ
No. 5752
EXP. 6/30/27
STRUCTURAL
STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: DEMOLITION PLAN - DTATA CENTER

Approved:

Phase: 100% CONSTRUCTION DOCUMENTS

Project Title: EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON

Project Number: 581-22-700

Building Number: GC115-1

Location: VA HUNTINGTON
1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Drawing Number: SD105

Issue Date	Checked	Drawn
09/03/2025	CH	Author

VA FORM 08 - 6231



PLAN NOTES:

1. REFER TO SHEET S-001 THROUGH S-004 FOR GENERAL NOTES, AND SHEETS S-501 THROUGH S-540 FOR TYPICAL DETAILS. THESE NOTES AND DETAILS SHALL BE USED WHERE APPLICABLE, WHETHER SPECIFICALLY REFERENCED OR NOT.
2. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR THE FOLLOWING:
   A. DIMENSIONS NOT SHOWN.
   B. OPENINGS NOT SHOWN.
   C. FLOOR ELEVATIONS.
3. FOR TYPICAL OPENINGS EXACT LOCATION AND SIZE, SEE ARCHITECTURAL AND MECHANICAL DRAWINGS. FOR JOIST AND BEAM REINFORCING USE DETAILS.
4. ROOF JOISTS ARE SPACED AT 16" OC MAX TYPICAL UNO.
5. DIMENSIONS AND ELEVATIONS SHALL BE VERIFIED PRIOR TO STEEL FABRICATION AND ERECTION.
6. TYPICAL STEEL BEAM CONNECTIONS PER S-511.
7. TYPICAL OPENINGS IN ROOF JOISTS PER **B6 / S-528**
8. TYPICAL BB JOIST CONNECTION PER **D4 / S-528**
9. COORDINATE CONNECTION OF MECHANICAL UNIT CURB TO ROOF DECK WITH MECHANICAL DRAWINGS. MAXIMUM WEIGHT OF MECHANICAL UNITS NOTED UNCLUDES THE COMBINED WEIGHT OF THE UNIT, CURB, AND APPENDAGES.

LEGEND:

W14x22 INDICATES BEAM AND BEAM SIZE
GRAVITY MOMENT FRAME CONNECTION PER **D7 / S-511**
LATERAL MOMENT FRAME CONNECTION PER **D7 / S-511**
CFH INDICATES COLD FORMED HEADER PER **C3 / S-525**
CFH-SIM INDICATES ALTERNATE COLD FORMED HEADER PER **C3 / S-525**
INDICATES DIRECTION OF DECK SPAN. FOR ROOF DECK SEE **B1 / S-511**

KEY PLAN



F1 ROOF FRAMING PLAN - DATA CENTER - PHASE 2B

1/4" = 1'-0"

Revisions:	Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

STAMP

REGISTERED PROFESSIONAL ENGINEER
DANTE VALDEZ
No. 5752
EXP. 6/30/27
STRUCTURAL
STATE OF CALIFORNIA

Office of Construction and Facilities Management

U.S. Department of Veterans Affairs

Drawing Title	ROOF FRAMING PLAN - DATA CENTER - PHASE 2
Approved:	
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Project Number	581-22-700
Building Number	GC115-1
Location	VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date	09/03/2025
Checked	CH
Drawn	Author
Drawing Number	S-116-2B

VA FORM 08 - 6231



A4 CONC CURB DETAIL

1" = 1'-0"



F1 TYPICAL SECTION

3/4" = 1'-0"

Revisions:	Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

STAMP

REGISTERED PROFESSIONAL ENGINEER DANTE VALDEZ No. 5752 EXP. 6/30/27 STRUCTURAL STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: BUILDING SECTIONS - DATA CENTER

Approved:

Phase: 100% CONSTRUCTION DOCUMENTS

Project Title: EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON

Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn
09/03/2025	CH	JKM

Project Number: 581-22-700

Building Number: GC115-1

Drawing Number: S-301

VA FORM 08 - 6231



NOTES:
1. SEE GEOTECHNICAL REPORT FOR ADDITIONAL REQUIREMENTS.
2. SEE PLANS FOR LOCATION OF COLUMN BLOCKOUTS, JOINTS AND SLAB DEPRESSIONS.
3. 4" MIN SAND AND GRAVEL BASE COURSE UNO IN GEOTECHNICAL REPORT. COMPACT SUBGRADE PER GEOTECHNICAL REPORT.

B1 TYP SLAB-ON-GRADE DETAIL
1" = 1'-0"



NOTES:
1. LOCATE CONTROL JOINTS PER PLAN.
2. SAWCUT JOINTS AFTER PEAK HEAT OF HYDRATION BUT NO LATER THAN 12 HOURS AFTER CONCRETE HAS BEEN MIXED.
3. FOR SLAB SUBGRADE SEE TYPICAL SLAB-ON-GRADE DETAIL.

B3 SLAB CONTROL JOINT
1" = 1'-0"



NOTES:
1. LOCATE CONSTRUCTION JOINTS PER PLAN.
2. OPTION: PLASTIC SLEEVES MAY BE CAST IN POUR 1 (SPEED DOWEL OR SIMILAR) SO DOWELS MAY BE INSTALLED AFTER EDGE FORM REMOVAL.
3. DELAY POUR 2 MINIMUM 24 HOURS AFTER POUR 1.
4. FOR SLAB SUBGRADE SEE TYPICAL SLAB-ON-GRADE DETAIL.

B5 SLAB CONSTRUCTION JOINT
1" = 1'-0"



NOTES:
1. SEE ARCHITECTURAL/MECHANICAL DRAWINGS FOR PAD SIZE AND LOCATION.
2. PROVIDE INSERT AS REQUIRED BY ARCHITECTURAL AND MECHANICAL DRAWINGS.
3. 4"≤H≤12"

B7 HOUSEKEEPING PAD DETAIL
1" = 1'-0"



B9 TYP SLAB ISOLATION JOINT
1 1/2" = 1'-0"



NOTE:
OBTAIN APPROVAL OF ENGINEER FOR LOCATION OF CONSTRUCTION JOINTS.

C1 WALL CONSTRUCTION JOINTS
1" = 1'-0"



C3 TYP SOG SLAB AT CONDUIT
1" = 1'-0"



C5 PIPING & CONDUIT AT SLAB OR WALL
1" = 1'-0"



NOTE:
FOR INFORMATION NOT SHOWN REFER TO **D4 / S-503** .

C7 HSS COLUMN BASE
1" = 1'-0"



C9 FDTN JOINT NEW TO EXISTING
1" = 1'-0"



NOTES:
1. SEE GENERAL NOTES FOR CONCRETE COVER REQUIREMENTS & BAR CLEARANCES.
2. CORNER BARS ARE THE SAME SIZE AND SPACING AS HORIZONTAL REINFORCEMENT.
3. REINFORCEMENT AT ALL CONCRETE WALL CORNERS, INTERSECTIONS AND ENDS TO BE FABRICATED AND PLACED IN ACCORDANCE WITH APPROPRIATE DETAIL SHOWN.
4. DETAIL ALSO APPLIES TO ALL CONTINUOUS WALL FOOTINGS.
5. SINGLE CURTAIN REINFORCEMENT SHALL BE PLACED AT WALL CENTERLINE UNLESS NOTED OTHERWISE.
6. VERTICAL REINFORCEMENT SHOWN IS ADDITIONAL IF TYPICAL VERTICAL REINFORCEMENT IS NOT IN PROPER LOCATION.
7. 90° STANDARD HOOK MAY BE SUBSTITUTED FOR CORNER BARS. USE 90° STANDARD HOOK FOR EMBEDMENT LESS THAN 24" PAST FACE OF WALL.

F1 TYP HORIZ REINF PLACING DETAIL FOR CONCRETE WALLS AND STEM WALLS
3/4" = 1'-0"

f'c = 4,000 psi
fy = 60,000 psi

SIZE	Ld	Ldt	Lb	Lbt	Ldh
#4	19	25	25	32	9
#5	24	31	31	40	12
#6	28 (43)	37 (55)	37 (55)	48 (72)	14
#7	42 (62)	54 (81)	54 (81)	70 (105)	17
#8	47 (71)	62 (92)	62 (92)	80 (120)	19
#9	54 (80)	70 (104)	70 (104)	90 (136)	21
#10	60 (90)	78 (117)	78 (117)	102 (153)	24
#11	67 (100)	87 (130)	87 (130)	113 (170)	27

f'c = 5,000 psi
fy = 75,000 psi

SIZE	Ld	Ldt	Lb	Lbt	Ldh
#4	21	28	28	36	11
#5	27	34	34	45	13
#6	32 (48)	41 (62)	41 (62)	54 (81)	16
#7	46 (70)	60 (90)	60 (90)	78 (118)	19
#8	53 (80)	69 (103)	69 (103)	90 (134)	21
#9	60 (90)	78 (117)	78 (117)	101 (152)	24
#10	67 (101)	88 (131)	88 (131)	114 (171)	27
#11	75 (112)	97 (146)	97 (146)	126 (190)	30

NOTES:
1. USE THE LENGTH IN THESE SCHEDULES, UNLESS NOTED OTHERWISE.
2. USE LENGTH IN (" ") WHEN BAR COVER IS db OR LESS OR BAR CLEAR SPACING IS 2db OR LESS.
3. TOP BAR IS HORIZONTAL BAR WITH MORE THAN 12" OF FRESH CONCRETE CAST BELOW IT.

ABBREVIATIONS

db = BAR DIAMETER
Ld = TENSION DEVELOPMENT LENGTH
Ldt = TENSION DEVELOPMENT LENGTH FOR A TOP BAR
Lb = CLASS B LAP SPLICE LENGTH, 1.3Ld
Lbt = CLASS B LAP SPLICE LENGTH FOR A TOP BAR, 1.3 Ldt
Ldh = TENSION DEVELOPMENT LENGTH FOR A STANDARD HOOK
f'c = CONCRETE COMPRESSIBLE STRENGTH AT 28 DAYS
fy = BAR YIELD STRENGTH

F5 DEVELOPMENT & LAP SPLICE LENGTH SCHED - CONCRETE
1/2" = 1'-0"



F7 TYP ISOLATION JOINT AT COLUMN
1" = 1'-0"

Revisions: | Date:

CONSULTANT
ENGINEERING DISCIPLINE:
WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD
A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

STAMP

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title	TYPICAL CONCRETE DETAILS
Approved:	
Phase	100% CONSTRUCTION DOCUMENTS
Project Title	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Location	VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date	09/03/2025
Checked	CH
Drawn	JKM
Project Number	581-22-700
Building Number	
Drawing Number	S-501



NOTES:

1. EACH MICRO PILE TO BE DESIGNED FOR MAXIMUM REACTION OF 150 KIPS (LRFD).
2. ALL MICRO PILES TO BE PROOF LOAD TESTED IN 25% INCREMENTS TO 150% OF THE SPECIFIED DESIGN LOAD ABOVE. RECORD ELONGATION AT EACH INCREMENT. HOLD THE 150% LOAD FOR TEN (10) MINUTES.
3. THE CRITERIA FOR A SUCCESSFUL PROOF TEST IS A CREEP RATE AT THE MAXIMUM LOAD OF LESS THAN 0.04 INCHES BETWEEN 1 MINUTE AND 10 MINUTES AND THE SAME TOTAL MOVEMENT CRITERIA AS THE PERFORMANCE TESTS.
4. IF THE MICRO PILE DISPLACEMENT BETWEEN 1 AND 10 MINUTES EXCEEDS 0.04 INCHES, THE PROOF LOAD SHALL BE MAINTAINED FOR AN ADDITIONAL 50 MINUTES AND THE DISPLACEMENT RECORDED AT 20, 30, 40, 50, AND 60 MINUTES. THE MICRO PILE IS THEN CONSIDERED ACCEPTABLE IF THE ADDITIONAL MEASURED DISPLACEMENT DOES NOT EXCEED 0.04 INCHES BETWEEN THE PROOF TESTS. IF THE DISPLACEMENT LIMIT IS EXCEEDED THE MICRO PILE SHALL BE DEEPENED AND RETESTED, OR ABANDONED AND A NEW, REDESIGNED REPLACEMENT MICRO PILE INSTALLED. AT THE END OF THE SUCCESSFUL TEST, RELEASE AND LOCK OFF THE MICRO PILE TO 100% THE SPECIFIED DESIGN LOAD.
5. AS PER GEOTECHNICAL REPORT, THE MICRO PILE CASING MUST BE SEATED INTO COMPETENT BEDROCK A MINIMUM OF 1.0 FT THE BOND LENGTH SHOULD BE 10.0 FT MINIMUM INTO BEDROCK BELOW THE 1.0 FT CASING EMBEDMENT.
6. SEE SOILS REPORT FOR MINIMUM BOND ZONE DEPTHS (BELOW THE EXISTING GROUND SURFACE) FOR EACH TOWER AND ADDITIONAL REQUIREMENTS.

C1 MAT FOOTING AT TOWER 1
1" = 1'-0"



B4 COLUMN BASE PLATE AT TOWER 1
1 1/2" = 1'-0"



C4 TYPICAL TOWER COLUMN BASE PLATE
1 1/2" = 1'-0"



NOTES:

1. EACH MICRO PILE TO BE DESIGNED FOR MAXIMUM REACTION OF 70 IPS (LRFD).
2. SEE DETAIL C1/S-502 FOR PROOF LOAD TESTING CRITERIA.

C6 PILE CAP PC2
1" = 1'-0"



NOTES:

1. EACH MICRO PILE TO BE DESIGNED FOR MAXIMUM REACTION OF 50 KIPS (LRFD).
2. SEE DETAIL C1/S-502 FOR PROOF LOAD TESTING CRITERIA.

C8 PILE CAP PC3
1" = 1'-0"



E1 MAT FOOTING AT TOWER 1
1" = 1'-0"



NOTES:

1. ADDITIONAL INFORMATION NOT SHOWN PER C1 / S-502

E4 MAT FOOTING AT TOWER 1
1" = 1'-0"



E6 PILE CAP SECTION-PC2
1" = 1'-0"



E8 PILE CAP SECTION-PC3
1" = 1'-0"



F1 COLUMN BASE CONNECTION
1 1/2" = 1'-0"



F4 SECTION - GRADE BEAM GB2
1" = 1'-0"



F6 INTERIOR BEARING/SHEAR WALL FOUNDATION DETAIL
1" = 1'-0"



F8 COLUMN TO EXIST CONC WALL CONN
1" = 1'-0"



F9 CONC PEDESTAL
1" = 1'-0"

Revisions: | Date:

CONSULTANT
ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

SPEESDESIGNBUILD

STAMP



Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: FOUNDATION DETAILS	Phase: 100% CONSTRUCTION DOCUMENTS	Project Title: EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	Project Number: 581-22-700
			Building Number:
Approved:		Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Drawing Number: S-502
		Issue Date: 09/03/2025 · Checked: CH · Drawn: JKM	036 OF 693



C1 WALL FOUNDATION DETAIL
1" = 1'-0"



B4 CURB DETAIL
1" = 1'-0"



B6 TYPICAL EXTERIOR FRAMED WALL CONNECTION
1" = 1'-0"



D1 TIE BEAM
1" = 1'-0"



D4 WALL FOUNDATION DETAIL
1" = 1'-0"



F1 SECTION - GRADE BEAM GB1
1" = 1'-0"



F4 WALL FOUNDATION DETAIL
1" = 1'-0"

Revisions: | Date:

CONSULTANT
ENGINEERING DISCIPLINE:
WSP
WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD
A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES
SDB SPEESDESIGNBUILD

STAMP
REGISTERED PROFESSIONAL ENGINEER DANTE VALDEZ No. 5752 STRUCTURAL STATE OF CALIFORNIA

Office of Construction and Facilities Management
VA U.S. Department of Veterans Affairs

Drawing Title: FOUNDATION DETAILS
Approved:
Phase: 100% CONSTRUCTION DOCUMENTS
Project Title: EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON
Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300
Issue Date: 09/03/2025
Checked: CH
Drawn: Author
Project Number: 581-22-700
Building Number:
Drawing Number: S-503
037 OF 693

VA FORM 08 - 6231



NOTES:

1. DO NOT CORE IN THE SHADED AREAS.
2. SEE **B6 / S-504** FOR MORE INFORMATION.

C1 PENETRATIONS IN EXISTING CONCRETE OR CMU WALL

3/4" = 1'-0"



NOTES:

1. LOCATE EXISTING REINFOIRCEMENT PRIOR TO DRILLING AND DO NOT CUT OR DAMAGE EXISTING REINFORCEMENT.
2. DO NOT DRILL MORE THAN 2 HOLES WITHIN 3'-0" UNLESS APPROVED BY COR AND CUBMITTED TO SEOR.
3. DO NOIT DRILL THROUGH BEAMS.

B6 PIPING & CONDUIT AT EXISTING SLAB OR WALL

1" = 1'-0"



NOTES:

1. LOCATE ALL EXISTING REINFORCEMENT, TENDONS, AND PT ANCHOR HEADS PRIOR TO DRILLING SUCH THAT CORING AND CUTTING DO NOT DAMAGE ANY EXISTING ANCHOR HEADS, PT TENDONS OR REINFORCEMENT.
4. NEW PENETRATIONS @ 8'-0" OC MIN.
5. NEW ROUND OPENINGS TO BE 6" MAX. NEW SQUARE OR RECTANGULAR OPENING LENGTH/ WIDTH TO BE 1'-0" MAX.
6. **BEFORE ANY WORK STARTS:** LOCATE AND DOCUMENT EXISTING REINFORCING THAT HAS THE POTENTIAL TO INTERFERE W/ CONSTRUCTION. IDENTIFY AND DOCUMENT ALL THIS REINFORCEMENT IN A SHOP DRAWING SUBMITTAL AND SUBMIT TO ARCHITECT FOR STANDARD SHOP DRAWING REVIEW AND APPROVAL TIME DURATION.

C6 PENETRATIONS AT EXIST POST TENSION SLABS

1" = 1'-0"





E5 OPENINGS IN EXIST RIBBED SLABS

1" = 1'-0"





NOTE:

THE OPENING NOTED REQUIRES A CLEAR SPACING FROM ADJACENT OPENINGS OF THREE TIMES THE MAXIMUM OPENING DIMENSION. IF THE REQUIRED LAYOUT CANNOT CONFORM TO THESE REQUIREMENTS, REINFORCE THE GROUP AS A SINGLE COMBINED PENETRATION.

F1 PENETRATIONS IN EXISTING CONCRETE SLABS WITH COLUMNS AND NO BEAMS

3/4" = 1'-0"

F5 COMPOSITE DECK OPENINGS

1" = 1'-0"

F7 ROOF DECK OPNG LESS THAN 5'-6"

1" = 1'-0"

Revisions: | Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

STAMP

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
TYPICAL PENETRATIONS IN EXISTING STRUCTURE	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700
Approved:		Location: VA HUNTINGTON 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300	Building Number
		Issue Date: 09/03/2025 / Checked: CH / Drawn: Author	Drawing Number: S-504

VA FORM 08 - 6231

1	2	3	4	5	6	7	8	9	10



TYPICAL BEAM TO BEAM

ALL BEAM TO BEAMS WITH SAME DEPTH OR W12 BEAMS AND LARGER BEAMS

NOTES:
1. SEE BOLT **B3 / S-511** FOR BOLTS, PLATES, COPES, AND WELD A. REFER TO AISC FOR k DISTANCE.
2. BOLTS IN CONNECTIONS OF BEAM TO BEAM/GIRDER MAY BE SNUG TIGHT UNLESS SPECIFICALLY CALLED OUT AS SLIP CRITICAL (SC).

B1 TYPICAL SHEAR TAB CONNECTION
1" = 1'-0"

TABLE A

BEAM SECTION	MAXIMUM REACTION: MIN NUMBER OF BOLTS REQUIRED 7/8"Ø A325(F1852) UNLESS NOTED OTHERWISE	MAX ASD REACTION Rn/Ω (KIPS)	MAX LRFD REACTION φRn (KIPS)	A36 PLATE THICKNESS (INCH)	WELD SIZE A (INCH)	TOP COPE ONLY Fy (BEAM) = 50 KSI: MIN WEB THICKNESS (INCH)	MAX COPE LENGTH (INCH)	TOP & BOTTOM COPE Fy (BEAM) = 50 KSI: MIN WEB THICKNESS (INCH)	MAX COPE LENGTH (INCH)
C8,MC8,W8,W10	2	22	33	3/8	1/4	0.25	4	0.25	-
C12,MC12,W12,W14	3	39	58			0.25	4	0.25	2 1/2
W16	4	52	78			0.25	5	0.26	3
W18	5	65	97			0.25	9	0.27	5
W21	6	78	117			0.25	11	0.30	6
W24	7	91	137			0.25	14	0.29	11
W27,W30	8	104	156			0.25	16	0.28	14
W33, W36	9	116	174			0.25	16	0.27	14

NOTES:
1. BEAMS SHALL HAVE STANDARD ROUND HOLES (STD) AND SHEAR TAB PLATES MAY HAVE HORIZONTAL SHORT SLOTTED HOLES (HSSH) IF NOT SLIP CRITICAL.
2. PROVIDE THE MINIMUM QUANTITY OF BOLTS SHOWN IN TABLE A.
3. MAXIMUM COPE DEPTH SHALL BE 2" FOR DEPTHS UP TO W18 AND 3" FOR BEAMS W21 OR GREATER. CHANNELS (C AND MC) BE COPED WITHOUT PRIOR APPROVAL FROM THE STRUCTURAL ENGINEER.
4. COPED BEAMS SHALL BE CHECKED FOR MINIMUM WEB THICKNESS AND MAXIMUM COPE LENGTH PER TABLE A.

B3 TYPICAL BOLT SCHEDULE
1" = 1'-0"



FULL DEPTH STIFFENER

NOTES:
1. REFER TO TYPICAL BOLT SCHEDULE **B3 / S-511** FOR WELD SIZE A
2. STIFFENERS SHALL BE FULL DEPTH, UNLESS NOTED OTHERWISE REFERENCING DETAILS. PARTIAL DEPTH STIFFENERS ARE NOT PERMITTED WITHOUT APPROVAL OF THE STRUCTURAL ENGINEER.

B7 TYPICAL STIFFENER PLATES
1" = 1'-0"



NOTES:
1. BOLTS SHALL BE SPACED AT BEAM GAGE.
2. SIZE CAP PLATE ACCORDINGLY.

B9 TYPICAL BEAM TO HSS COLUMN
1" = 1'-0"



NOTES:
1. CONTRACTOR SHALL COORDINATE SIZES AND LOCATIONS OF ALL BEAM PENETRATIONS WITH MECHANICAL, ELECTRICAL AND FIRE PROTECTION DRAWINGS. ALL PENETRATIONS LARGER THAN 2"Ø SHALL BE SHOWN ON SHOP DRAWINGS OR SKETCHES AND SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL. FIELD CUTTING NOT PERMITTED WITHOUT APPROVAL.
2. OPENINGS MAY OCCUR IN HALF OF BEAM LENGTH ONLY.
3. NO CUTTING SHALL OCCUR IN TOP OR BOTTOM QUARTER OF BEAM DEPTH.
4. ADJACENT OPENINGS SHALL BE SPACED AT THE LESSER OF 12" OR 2.5 x LARGER OPENING SIZE, EDGE TO EDGE.
5. MAXIMUM SIZES OF OPENINGS SHALL BE D/3 DIA OR 2/3D WIDE x D/3 HIGH.
6. NO OPENINGS SHALL OCCUR WITHIN 12" OF AN INCOMING BEAM CONNECTION OR POINT LOAD ON BEAM.
7. REQUIRED OPENINGS NOT MEETING ABOVE CRITERIA SHALL BE SUBMITTED TO ENGINEER FOR REINFORCING DESIGN.

D1 BLOCKOUTS IN BEAM WEB
1" = 1'-0"



BEAM TO COLUMN FLANGE

NOTES:
1. SEE BOLT SCHEDULE FOR BOLTS, PLATES, COPES, AND WELD A. REFER TO AISC FOR k DISTANCE.

D3 TYPICAL SHEAR TAB CONNECTION
1" = 1'-0"



BEAM TO COLUMN WEB CONNECTION

BEAM TO COLUMN FLANGE MOMENT CONNECTION

D7 GRAVITY BEAM TO COLUMN MOMENT CONNECTION
1" = 1'-0"





TYPICAL STITCH PLATE

NOTES:
1. STL DECK PERPENDICULAR TO BEAMS SHOWN, DECK PARALLEL TO BEAMS - SIMILAR.
2. DOUBLE ANGLE SHALL RUN FROM THE TOP FLANGE OF THE SMALLER BEAM & BRACE THE BOTTOM FLANGE OF THE DEEPER BEAM AS SHOWN
3. AS AN ALTERNATIVE, BOLT DOUBLE ANGLE TO STEEL BEAM USING (1) HIGH STRENGTH BOLT EACH END. PROVIDE SLIP CRITICAL FAYING SURFACES PER RCSC.

E1 TYPICAL BEAM BOTTOM FLANGE BRACING
1" = 1'-0"



NOTE:

LOCATE EXISTING BEAM REINFORCEMENT WITH XRAY PRIOR TO DRILLING. MARK EXISTING REINFORCING BARS AND PROTECT FROM DAMAGE.

E5 DECK TO EXIST STRUCURE CONN
1" = 1'-0"



NOTE:

LOCATE EXISTING COLUMN REINFORCEMENT WITH XRAYS PRIOR TO DRILLING. MARK EXISTING REINFORCING BARS AND PROTECT FROM DAMAGE.

E7 CONN TO EXIST SHEAR WALL
1" = 1'-0"



NOTE:

LOCATE EXISTING COLUMN REINFORCEMENT WITH XRAYS PRIOR TO DRILLING. MARK EXISTING REINFORCING BARS AND PROTECT FROM DAMAGE.

E9 BEAM CONN TO EXIST SHEAR WALL
1" = 1'-0"



BEAM TO COLUMN WEB CONNECTION

BEAM TO COLUMN FLANGE MOMENT CONNECTION

F5 LATERAL BEAM TO COLUMN MOMENT CONNECTIONS
1" = 1'-0"



NOTE:

LOCATE EXISTING COLUMN REINFORCEMENT WITH XRAYS PRIOR TO DRILLING. MARK EXISTING REINFORCING BARS AND PROTECT FROM DAMAGE.

F9 BEAM CONN TO EXIST BEAM
1" = 1'-0"

Revisions:	Date:

CONSULTANT

ENGINEERING DISCIPLINE:

WSP USA Inc.
33301 9th Avenue South
Suite 300
Federal Way, WA 98003-2600
TEL: (206) 431-2300
FAX: (206) 431-2250

ARCHITECT/ENGINEER OF RECORD

A/E:
SPEES DESIGN BUILD
625 1ST AVE, STE 301
SEATTLE, WA 98104
(206) 590-2118
RAY SPEES

SPEESDESIGNBUILD

STAMP

REGISTERED PROFESSIONAL ENGINEER DANTE VALDEZ No. 5752 EXP. 6/30/27 STRUCTURAL STATE OF CALIFORNIA

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Phase	Project Title	Project Number
TYPICAL STRUCTURAL STEEL DETAILS	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES - HUNTINGTON	581-22-700

Building Number:

Approved:

Location: VA HUNTINGTON, 1540 SPRING VALLEY DRIVE, HUNTINGTON, WV 25704-9300

Issue Date	Checked	Drawn	Drawing Number
09/03/2025	CH	JKM	S-511

039 OF 693

VA FORM 08 - 6231

1	2	3	4	5	6	7	8	9	10