

Statement of Work: Graded Crushed Aggregate Base Course

Dated 5 May, 2026

Definitions

- GCA: Graded Crushed Aggregate Base Course
- UFGS: Uniform Guide Specifications
- UFC: Unified Facilities Criteria
- AVPAFR: Avon Park Air Force Range
- CO: Contracting Officer
- COR: Contracting Officer's Representative
- ASTM: American Society for Testing and Materials

Referenced Documents

- This section lists all documents referenced within this SOW. The contractor is responsible for obtaining and adhering to the latest versions of these documents.
 - UFGS 32.11.23 - Graded Crushed Aggregate Base Course
 - UFC 3-206-02 - Pavement Design for Airfields
 - Avon Park Air Force Range (AVPAFR) Design Standards
 - ASTM C131/C121M - Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
 - ASTM C117 - Standard Test Method for Materials Finer than 75- μ m (No. 200) Sieve in Mineral Aggregates by Washing
 - ASTM D1557 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort
 - ASTM D4318 - Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
 - ASTM C142 - Standard Test Method for Clay Lumps and Friable Particles in Aggregates
 - ASTM D4791 - Standard Test Method for Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate

One (1) Design:

The Contractor shall provide all, plant, labor, material, design, and supervision to provide and deliver a base quantity of 16,410 tons of Graded Crushed Aggregate Base Course (GCA), with an optional quantity for up to 1,000 additional tons. The GCA will be used for taxiway Hotel and the C-17 Assault strip at Avon Park Florida Air Force Range, Avon Park, Florida. The Taxiway is Type A traffic area and will be required to support C-17 Operations. The C-17 Assault strip must support a Modified Heavy Aircraft as per UFC

3-206-02. The Contractor shall not commence work without prior coordination with the Contracting Officer, Project Inspector and Using Agency.

GCA will conform to the Uniform Guide Specifications (UGFS) 32.11.23

General Design Notes:

o Design shall be in strict accordance with Unified Facilities Criteria (UFC) and the Avon Park Air Force Range Design Standards. The information provided in this SOW, the specifications provided and the requirements of the AVPAFR Design Standards shall be determined to be the minimum standards required in this project. Where the information provided and/or AVPAFR Design Standards conflict, then the most stringent shall be used. This includes all standards, codes, regulations and requirements provided by reference. The Contractor shall notify the Contracting Officer in writing of any identified conflicts between design standards for resolution.

o If any submittal doesn't, in the opinion of the Contracting Officer, meet or exceed the requirements contained within this SOW, in the AVPAFR Design Standards or in any referenced design guidance or nationally recognized code, then it shall be unacceptable and returned to the Contractor for correction and resubmission. The Contracting Officer has the option, in lieu of disapproval, to provide acceptance of a submittal with required corrections identified if it is determined the submittal is substantially complete.

Two (2) Submittals:

Contractor shall submit the following information to the Contracting Officer, for approval. All required submittals for the GCA design mix must be provided to the Contracting Officer for approval no later than 15 days after date of contract award. If the contractor cannot provide such tests, they can provide equivalent engineering tests that display similar geotechnical properties of the GCA stock. All proposed alternative tests, along with technical justification for their equivalency, must be submitted for Contracting Officer approval prior to use.

- o L.A Abrasion Test: ASTM C131/C121M (Toughness and Hardness of Rock)
- o Gradation Analysis: ASTM C117 (Size of aggregates by weight)
- o Degree of Compaction: ASTM D1557 (Optimum Moisture Content, Method C)
- o Liquid Limit and Plasticity Index: ASTM D4318 (Soil Classification)
- o Clay Lumps and Friable Particles: ASTM C142 (Cleanliness)
- o Flat and Elongated Particles: ASTM D4791 (remove undesirable rocks)

Three (3) Work Requirements:

The Contractor shall provide all plant, labor, material, design and supervision to provide and deliver GCA. Contractors shall also provide field and laboratory quality control testing, as required by the Government. Work will consist of the following:

3.1 Base Requirement (CLIN 0001)

The contractor shall provide a firm-fixed quantity of 16,410 Tons of GCA conforming to UFGS 32.11.23. This quantity is required and will be ordered upon award of the contract.

3.2 Optional Requirement (CLIN 0002)

The Government holds the option to purchase additional GCA up to a maximum of 1,000 additional tons. The exact amount needed by the Government, if any, will be specified via written notice from the Contracting Officer at a later date. The exercise of this option is governed by FAR 52.217-7, "Option for Increased Quantity—Separately Priced Line Item."

3.3 Delivery

The Contractor shall deliver all GCA specified under CLIN 0001 in pre-coordinated intervals agreed upon by the customer on or before the delivery date specified in the contract and any quantities ordered under CLIN 0002 in pre-coordinated intervals agreed upon by the customer on or before the delivery date specified in the contract. Deliveries shall be made to the vicinity of APR, FL 33825, 45 South BLVD, Avon Park, FL 33825. The Contractor shall coordinate specific delivery dates and times with the Project Inspector at least 72 hours in advance. The project plans will dictate the location of the stockpile area on the jobsite. The Contractor is responsible for maintaining the stockpile in a manner that prevents segregation of materials and contamination from foreign debris.

3.4 Quality Control & Testing

Test every 2,500 tons of GCA delivered, provide a Quality Assurance test consisting of a Gradation Analysis, Liquid Limit and Plasticity Index, Moisture Density Relationship, Wear, Flat and Elongated Pieces. As stated in section two (2) submittals, if the contractor cannot provide this information, they will provide the corresponding engineering tests describing similar geotechnical properties of the GCA stock. The Government reserves the right to test material upon delivery. Any material found to be non-compliant with the approved submittals shall be rejected and removed from the site at the Contractor's expense.

3.5 Pricing Instructions for Solicitation

In response to the solicitation, offerors shall provide pricing on a per-unit (i.e., per ton) basis for both the Base Requirement (CLIN 0001) and the Optional Requirement (CLIN 0002).

Four (4) Performance:

Before Final payment is allowed, all waybills and certified delivery tickets must be complied by the customer and contractor. Final payment will be processed upon Government acceptance of all 16,410 tons of GCA, reconciliation of all delivery tickets, and satisfactory completion of all work described herein. Contractors will provide waybills and receipts for every vehicle moving GCA to the jobsite.

Contractor shall be able to produce a minimum sub-lot of 500 tons in an eight-hour period.

Contractors are responsible for the safety and wellbeing of their employees. Prior to the commencement of work, the Contractor shall submit a comprehensive Safety Plan for review and approval. The plan must comply with all applicable federal, state, and local regulations, as well as any specific requirements of the Avon Park Air Force Range.

- o Drivers must be properly licensed, capable of operating heavy machinery, and capable of communicating in English.
- o Drivers must be legally allowed to enter and operate a motor vehicle on a military installation and must always carry proper identification.
- o Drivers must be able to contact business leadership during all hours of operation via cell phone.

All mud, dirt, debris, foreign objects, trash, or spills caused by the contractor (including Sub-Contractors) on a street or parking lot, used as access to the work site or staging area shall be cleaned off the same day or as soon as practicable or requested by the CO. Failure to comply with the requirements of this SOW may result in actions including, but not limited to, stop-work orders until deficiencies are corrected.