

PERFORMANCE WORK STATEMENT

Hopper Scaffold, Surface Preparation, Coating, and Guillotine Replacement

NAB Coronado, San Diego, CA

In Support of

Amphibious Construction Battalion ONE (PHIBCB ONE)

1. SCOPE OF WORK

The Contractor shall provide all labor, supervision, materials, equipment, tools, transportation, and incidentals necessary to safely erect scaffolding, perform surface preparation via abrasive blasting, apply protective coatings to the hopper, remove and replace the existing guillotine, and properly dispose of all hazardous and non-hazardous waste generated during performance. All work shall be performed in accordance with applicable Navy safety requirements, OSHA standards, and environmental regulations.

2. PLACE OF PERFORMANCE

Work shall be performed at ACB-1 on Naval Amphibious Base Coronado, or as otherwise directed by the Government.

3. PERIOD OF PERFORMANCE

The period of performance shall be as soon as possible and determined upon contract award. Total estimated labor effort is 181 man-hours.

4. TASKS AND REQUIREMENTS

1. Mobilization and setup of trucks, scaffolding, and equipment.
2. Erection and dismantling of scaffolding to provide fall protection and safe access.
3. Daily QA/Safety inspections including red/green tagging of scaffolding.
4. Surface preparation of hopper via abrasive blasting using approved media.
5. Operation of blasting and painting equipment by certified personnel (C-7 Blaster and C-14 Sprayer).
6. Application of high-solids epoxy coating system in accordance with manufacturer specifications.
7. Touch-up painting as required to ensure complete coverage.
8. Removal of existing guillotine, cutting as necessary, and installation of new guillotine.
9. Welding operations performed by qualified personnel.
10. Breakdown and demobilization of all equipment.
11. Collection, handling, and disposal of grit, solvents, and hazardous waste in accordance with regulations.

5. GOVERNMENT-FURNISHED PROPERTY (GFP)

No Government-Furnished Property or Equipment will be provided unless otherwise specified by the Government.

6. CONTRACTOR-FURNISHED ITEMS

The Contractor shall furnish all materials, equipment, and supplies required to complete the work, including but not limited to scaffolding, blast grit, coatings, dust collectors, protective materials, and a new guillotine assembly.

7. SAFETY AND QUALITY ASSURANCE

The Contractor shall comply with all applicable safety regulations, including OSHA and Navy safety requirements. Daily safety inspections shall be conducted. All coating applications shall meet manufacturer specifications and industry standards.

8. ENVIRONMENTAL COMPLIANCE

All hazardous materials, blast media, and solvent waste shall be handled, transported, and disposed of in accordance with federal, state, and local environmental regulations.

9. ACCEPTANCE CRITERIA

Work shall be considered complete upon successful inspection by the Government representative, confirmation that coatings are properly applied, scaffolding removed, the new guillotine installed and operational, and all waste properly disposed.