

Questions	Answers
Received 04/21/2026	
1. Duration of the 5 years maintenance is there any water source close by?	Water sources be determined by contractor.
2. Watering irrigation system will be design and built?	Contractor to provide means and method for watering plants.
3. On state park side grading and dirt work where will be stored or hauled be all excess dirt?	Soil disposal area shown on Plan Sheet D1.
4. When would be starting time because of the all the plants will be contract grown? Is it acceptable to get plan from local nurseries without collecting and propagating them ?	The Notice to Proceed (NTP) will be issued after bond approval. Provide seeds in compliance with specification Section 625.03 and plants in compliance with specification Section 626.03.
5. Surveying will be done by owner or contractor.	Contractor to provide surveying per specification Section 152
6. If need biological monitoring will be done by owner or contractor?	Contractor to provide biological services per specification Section 107.10(e)(1), 107.13, and 623.03(c). Paid for under item 62303-1010 SPECIAL LABOR, HIRED TECHNICAL SERVICES, BIOLOGICAL SERVICES, (BIOLOGICAL MONITOR).
7. POC's for Bureau of Land Management if you would like to view the project sites?	Zachary Ormsby Field Manager Central Coast Field Office Bureau of Land Management 831-601-6242 zormsby@blm.gov Ben Hoke Assistant Field Manager - Multi-Resource Group Bureau of Land Management Central Coast Field Office Marina, CA Cell: (831) 737-0374 Desk: (831) 285-2235 bhoke@blm.gov
Received 04/23/2026	

8. On the grading plan, Detail A & B show 18"-30" depth of cut for the grading work. The total grading area on the bid schedule is 5,860 SQYD (52,740 SF). With a total square footage of 52,740, each foot of depth we excavate equates to 1,953 cubic yards (CY) of grading work. If the excavation is 18" deep (1.5' deep), the grading equates to 2,930 CY total If the excavation is 30" deep (2.5' deep), the grading equates to 4,883 CY total A 2,000 CY delta is a good amount of dirt. This is about 200 10-wheeler truckloads. Since we don't know the exact required excavation depth, is it possible to change the grading pay item from SQYD to Cubic Yards on the bid schedule? I think you will get better grading numbers this way.	Bid As Shown
--	---------------------