

STATEMENT OF NEED
460 CES
1 Megawatt (MW) Generator Rental
Current as of 4 May 2026

1. SCOPE:

460 CES requires an additional backup power source for infrastructure support. The contractor shall provide a 1000 kW (1MW) mobile diesel generator rental for 30 days and all necessary additional equipment for operation. The generator rental shall include two (2) options to extend for an additional 30-days each based on the needs for the government.

2. REQUIREMENT:

Product	Quantity
1000 kW (1MW) Mobile Generator	1
300ft 20-0000 AWG cables with Camlock Connection	1

3. SPECIFICATIONS:

1000 kW (1MW) Mobile Generator

- Shall be a diesel fueled power generator system.
- Shall be 480-volt (V) 3-phase power at 60 hertz (Hz) with telemetry.
- Shall be 1600 amperes (A).
- Shall not include WiFi, Bluetooth or GPS capabilities.
- Shall include necessary Cable Tail, Female, Single Conductors.
- Shall include necessary Cable Tail, Male, Single Conductors.

300ft 20-0000 AWG cables with Camlock Connection

- Shall be seven (7) per phase, plus three (3) grounds.
- Shall be rated to 600V.

3a. ENVIRONMENTAL AND PERMITTING REQUIREMENTS:

- The prospective contractor shall be responsible for ensuring full compliance with all applicable local and state regulations regarding air quality and emissions. This includes, but is not limited to, all requirements set forth by the Colorado Department of Public Health and Environment (CDPHE), Air Pollution Control Division. The contractor is required to secure any and all necessary air quality permits for the operation of the generator at Buckley Space Force Base. This may include the filing of an Air Pollutant Emission Notice (APEN) and obtaining any necessary general or site-specific operating permits prior to the commencement of operations.

4. DELIVERY:

Generator and components shall be delivered to Buckley Space Force Base. The Contractor's technician must place, install and service the unit. The Contractor must decommission and retrieve the generator at contract completion. The Contractor must be able to enter all areas of the installation by adhering to all 460th Security Forces Squadron (SFS) protocols and standards.

Items, when delivered, will be accepted and inspected by the government officials responsible for receiving the products and performing any required inspections.

Delivery and installation of the required generator and cables to be fully functional shall be completed within 7 calendar days after receipt of award.

Upon delivery and at fully operational status, the contractor shall perform a walkthrough and provide a demonstration of generator operations with CES personnel to ensure Buckley personnel can operate equipment unassisted.

END OF STATEMENT OF NEED

