

Price Schedule
FY26 Spillway Drainage Inspection
Garrison Dam, ND

Item No.	Required Services	Description	QTY	UNIT	UNIT PRICE	TOTAL
001	Task #1 Flush, measure sediment, camera and report for Rows 2-9 spillway subdrain	The work for this item shall include all equipment, materials, and labor necessary for the flushing, measuring the sediment volume, camera-inspecting and reporting for all spillway slab subdrains accessed from Rows 2 through 9 manholes in the spillway chute slab.	14,060	Linear Foot (LF)		
002	Task #2 Flush, measure sediment, camera and report for Row 1 spillway subdrain	The work for this item shall include all equipment, materials, and labor necessary for the flushing, measuring the sediment volume, camera-inspecting and reporting for all spillway slab subdrains accessed from Row 1 manholes in the spillway chute slab.	2,120	Linear Foot (LF)		
003	Task #3 Flush, measure sediment, camera and report for spillway box drains	The work for this item shall include all equipment, materials, and labor necessary for the flushing, measuring the sediment volume, camera-inspecting and reporting for all box drains located along the outer base of the spillway chute walls.	4,800	Linear Foot (LF)		
004	Task #4 Sound and inspect crest relief wells	The work for this item shall include all equipment, materials, and labor necessary for the depth-sounding, camera-inspecting and reporting of the 14 spillway crest relief wells.	550	Linear Foot (LF)		
005	Task #5 Temporary Chute Access Staircase	The work for this item shall include all equipment, materials, and labor necessary for the construction of a chute access staircase to be maintained for the duration of activities within the spillway chute.	1	Job		
006	Task #6 All Other Work	This work shall include costs associated with mobilization and de-mobilization of personnel and equipment, pre-fieldwork submittals and meetings, and fulfillment of any requirements not associated with other specific tasks.	1	Job		
007	Task #7 (OPTION 1) Flush, measure sediment, camera and report for power plant drainage	The work for this item shall include all equipment, materials, and labor necessary for the flushing, measuring the sediment volume, camera-inspecting and reporting for the power plant seepage drain network	5,295	Linear Foot (LF)		

Notes:

The quantities for unit priced items are estimated only and the respective unit price will prevail in the event of an overrun or underrun subject to Contract Clauses "Variation in Estimated Quantity."

2. Prices must be entered for all items of the schedule. Total amount of line items submitted without unit prices being entered on individual items will be rejected. In case of variation between the unit prices and the total price per line item, the unit prices will be considered the quoted price. No more than two decimal places are allowed for the unit and total prices.

3. A modification to the award which provides for a single adjustment to the total amount of the award should state the application of the adjustment to each respective unit price and total price affected. If the modification is not so apportioned, the single adjustment will be applied to Item No. 006.