



DEPARTMENT OF HOMELAND SECURITY
UNITED STATES COAST GUARD

Station San Francisco

Scope of Work
for

Barracks Bathroom Renovations

at

**1 Yerba Buena Island,
Yerba Buena Island Northgate Rd
San Francisco, CA. 94130**

Sector San Francisco	Initial	Date
Contracting Officer (KO)		
CWO Victor M. Regalado Sector Engineer Officer	VMR	

A. GENERAL INFORMATION

1. Scope of Work: This document outlines the scope of work for the comprehensive renovation and restoration of the male and female restroom facilities. The primary objectives are to enhance hygiene, improve functionality, upgrade fixtures for longevity and efficiency, and create a clean, modern, and safe environment for all users. This project involves a combination of deep cleaning, repair, and complete replacement of various components as detailed below.

The specific areas of performance identified are:

Male Head / Showers: Building 3 Room B03.320 (246 sq. ft.)

Female Head / Showers: Building 3 Room B03.330 (158 sq. ft.)

2. General Site Requirements (Applicable to both Bathrooms)

- 2.1 Site Preparation & Protection:

- 2.1.1 The Contractor shall protect all non-work areas from dust, debris, and damage. This includes laying down protective coverings for floors and corridors leading to the work site.

- 2.1.2 The Contractor shall isolate the work area to prevent unauthorized access and contain construction materials.

- 2.2 Debris Removal & Disposal:

- 2.2.1 All demolition debris, old fixtures, packaging, and construction waste shall be legally and properly disposed of off-site by the Contractor on a daily basis. The work site is to be kept clean and orderly.

- 2.3 Submittals:

- 2.3.1 The Contractor shall submit product data sheets for all specified materials for approval prior to procurement, including composite partitions, shower stalls, fixtures, ventilation fans, paint, caulk, and sealant within 10 days of award.

3. General Scope of Work (Applicable to both Bathrooms)

- 3.1 Industrial Tile & Grout Restoration:

-
-
- 3.1.1 Cleaning: Mechanically scrub all floor and wall tile and grout lines using a high-alkaline, degreasing cleaning solution to remove all dirt, soap scum, and organic buildup.
 - 3.1.2 Steam Treatment: Utilize high-temperature, low-pressure steam cleaning to sanitize and brighten grout lines after initial scrubbing.
 - 3.1.3 Resealing: Apply two coats of a commercial-grade, impregnating grout sealer to all grout lines to ensure water repellency and stain resistance.
 - 3.2 Ventilation System Upgrade:
 - 3.2.1 Removal: Decommission and remove the existing ventilation fans.
 - 3.2.2 Installation: Install one (1) new Energy Star rated, quiet-operation ventilation fan (rated at 1.0 sones or less) with the CFM required by building codes in each bathroom. Ensure proper venting to the exterior and secure, airtight connection and it has its own on/off switch.
 - 3.3 Ceiling System Replacement:
 - 3.3.1 Removal: Carefully remove and dispose of all existing ceiling grid tiles.
 - 3.3.2 Grid Inspection: Inspect the existing ceiling grid for integrity and level. Report any damage or deficiencies.
 - 3.3.3 Installation: Install new, mold and sag-resistant acoustic ceiling tiles into the existing grid.
 - 3.4 Wall Finishing:
 - 3.4.1 Surface Preparation: Inspect all drywall surfaces. Patch any holes, cracks, or imperfections using professional-grade joint compound, followed by sanding to a smooth, level finish (Level 4 finish).
 - 3.4.2 Painting: Apply one coat of primer and two topcoats of high-quality, semi-gloss, mold and mildew-resistant acrylic-latex paint to all previously painted wall surfaces. Color to be selected by the client.
-
-

4. Male Bathroom: Full Renovation Details

4.1 Toilet Partition Replacement:

4.1.1 Demolition: Carefully dismantle and remove all existing toilet partitions, hardware, and anchoring components.

4.2.2 Installation: Furnish and install new, floor-mounted, overhead-braced solid composite partitions. Ensure all panels are plumb, level, and securely anchored to the floor and walls per manufacturer's installation guidelines.

4.2 Complete Shower Overhaul (All 3 Stalls):

4.2.1 Demolition: Demolish all three shower stalls to the wall studs. Remove existing shower pans, wall surrounds, moisture barriers, fixtures, valves, and lighting.

4.2.2 Framing & Substrate Inspection: Inspect wood/metal studs for water damage or rot and report any findings.

4.2.3 Moisture Barrier Installation: Install new, code-compliant moisture-resistant gypsum board or cement board on all shower walls. Seal all joints and fastener penetrations with waterproofing membrane.

4.2.4 Stall & Fixture Installation:

4.2.4.1 Install three (3) new prefabricated shower stalls/bases.

4.2.4.2 Install new plumbing, including hot/cold mixing valves.

4.2.4.3 Install new shower fixtures in each stall, including a fixed shower head and single-lever handle.

4.2.4.4 Install new vapor-proof (wet-location rated) lighting fixtures in each shower stall, controlled by a separate switch.

5. Female Bathroom: Restoration & Upgrade Details

5.1 Shower Stall Maintenance & Repair:

5.1.1 Deep Cleaning: Perform an industrial-grade cleaning of the interior and exterior of all existing shower stalls to remove residue and discoloration.

5.1.2 Structural Re-adhesion: For the right-side shower stall, remove any loose material, prepare the wall and stall surfaces, and reattach the shower stall panel to the wall using a high-strength, waterproof construction adhesive and concealed mechanical fasteners as required.

5.1.3 Caulking Replacement: Remove 100% of the old caulk from all interior seams, corners, and fixture perimeters within all shower stalls. Clean the surfaces and apply a new bead of 100% silicone, mildew-resistant caulk.

5.2 Shower Fixture & Lighting Replacement:

5.2.1 Fixture Replacement: In each shower stall, remove the existing shower heads and handles. Install new, water-efficient shower fixtures to match the style of the new fixtures in the male bathroom.

5.2.2 Lighting Replacement: In each shower stall, replace the existing light fixture with a new, vapor-proof (wet-location rated) lighting fixture.

6. Project Completion & Acceptance

6.1 Walk-through: Upon substantial completion, the Contractor shall schedule a final walk-through with the Government point of contact to review the work performed and create a punch list of any deficient items.

6.2 Acceptance Criteria: Final acceptance will be granted when all items in this SOW are completed to professional standards, the punch list is fully addressed, all systems are operational, and the site is left in a clean, "broom-swept" condition.

B. CONTRACTOR REQUIREMENTS

1. During the execution of this contract, the Contractor shall conform to the rules and regulations as set forth by EPA and OSHA Safety and Health Standards, 29 CFR Part 1926 - Safety and Health Regulations for Construction and California Code of Regulations, Title 8, Div. 1, Ch. 4, Subchapter 4 Construction Safety Orders, and EM

385-1. When the standards differ, the more restrictive standard shall apply. The Contractor shall provide barriers, temporary fencing, trench covers, etc. wherever work could cause injury to workers, visitors, Coast Guard personnel, or dependents. An Accident Prevention Plan shall be submitted by the Contractor prior to any commencement of work.

2. Contractor employees shall refrain from smoking while inside any federal buildings, within 50 feet of any entrance to the buildings, and within 50 feet of any flammables. A designated smoking area is available on-site.
3. The Contractor shall provide all labor, materials, and equipment (except as otherwise noted herein) to complete the tasks in this Statement of Work.
4. Refuse, excess or waste materials resulting from construction operations shall become the property of the Contractor and shall be recycled or disposed of off Government property. All disposals shall be done in accordance with federal, state, and local laws and regulations.
5. The Contractor shall be responsible for protecting stockpiled materials against weather, damage, theft, and other risks of loss. The Coast Guard assumes no responsibility for material or equipment left in the lay down area.
6. Contractor employees using extension cords shall employ portable ground fault circuit interrupters (GFCIs), even if connecting to building electricity. Use of portable generators is authorized at Contractor expense to power portable equipment.
7. The Contractor shall investigate the site per FAR 52.236-3 to ascertain the general and local conditions which can affect the work or its cost. The Contractor is highly encouraged to field verify all factors or interferences concerning the job

C. GOVERNMENT RESPONSIBILITIES

1. The government will provide Contractor personnel with access to all spaces necessary for any component associated with this project during normal business hours. Office building hours are as follows: Monday through Friday 0700 through 1700 (7am – 5 pm). Any scheduled working times outside normal business hours by Contractor personnel shall be coordinated with the Engineer Officer or Engineer Petty Officer prior to the commencement of said work. At any time, scheduled work needs to go beyond normal business hours, the Contractor shall immediately notify the aforementioned points of contact.

-
-
2. The government shall provide limited water and standard 110v electricity where available.
 3. The government shall provide a lay down area for materials and equipment. The location of the lay down area for materials will be available on base with location to be determined by COR and Facilities Engineer.
 4. The government shall provide restroom facilities. Contractor employees are authorized to utilize government building restroom facilities
 5. No work shall be scheduled during Federal Holidays or Weekends, unless prior approval has been coordinated with the Engineer Officer or Engineer Petty Officer.
 6. All Contractor access to designated restricted or controlled access spaces will be coordinated with the Command Security Officer prior to accessing these spaces. Once in these spaces, Contractor personnel will be monitored by Coast Guard personnel with appropriate access and clearance to be inside these designated restricted or controlled access spaces throughout the performance of work in these spaces. ***At no time shall the entry points of these spaces remain unlocked to facilitate ease of access.***

D. REPORTING REQUIREMENTS

1. The Contractor shall provide ***verbal progress reports daily*** for the duration of the project. The progress report shall cover all work completed during the day; present the work to be accomplished during the subsequent period; identify any problems that arose during the day; and explain how problems were resolved. The report shall also identify any problems encountered but not completely resolved and provide an explanation.
2. All verbal progress reports shall be provided to the Engineer Officer or Engineer Petty Officer prior to Contractor departing the premises where the work is being performed.

E. CONTRACTOR EXPERIENCE

1. The Contractor shall provide a Certificate of Insurance to indicate the liability, property, and accident coverage held by the Contractor, as well as any optional insurance recommended by the Contractor.

-
2. The Contractor shall maintain high standards of behavior during performance of this project. All individuals associated with this project shall be properly trained and qualified for the work to which they are assigned.

F. SECURITY REQUIREMENTS

1. The Contractor performing work under this project shall be escorted whenever work is to be performed in designated restricted or controlled access spaces. At no time shall the Contractor be left unattended while working in designated restricted or controlled access spaces. Escorts shall be Coast Guard members currently assigned to the designated facility with appropriate clearance levels and authority to be in the specific designated restricted or controlled access space at the time work is to be performed.
2. The Contractor shall provide employee information for all foreign nationals (defined as those employees not currently designated a U.S. Citizen as determined by applicable U.S. law, regulation, or policy) prior to the commencement of any on-site work related to this project and entry onto the premises of the U.S. Coast Guard owned facilities. Individuals determined to meet the criteria to be considered a foreign national will be allowed access to U.S. Coast Guard owned facilities; however, these individuals will be prohibited from accessing the designated restricted or controlled access spaces, even when under escort, unless otherwise approved by the Command Security Officer.
3. The Contractor shall provide a personnel roster of all individuals assigned to perform work under this project, listing the dates work is to be performed by the individual. Daily rosters shall be provided to the Engineer Petty Officer no later than 3:00 PM the day before work is to be performed.
4. The Contractor shall provide a valid non-expired state or federal issued photo identification card or credential upon accessing U.S. Coast Guard owned property. Identification cards or credentials shall be handed to the sentry and front desk watchstander for visual inspection and validation. Failure to provide a valid non-expired state or federal issued photo identification card or credential will prevent access, even if under escort.
5. Any U.S. Coast Guard facilities credentials issued to the Contractor shall clearly indicate an expiration date no later than the completion date of this project. Each credential issued will be tracked and surrendered upon request by the Coast Guard or upon completion of this project, whichever occurs first. Issued credentials shall be always worn and visible. Whenever actively working, the credential may be removed as a safety precaution but shall be immediately returned to a visible location on person when safe to do so.
6. The Contractor shall provide the Engineer Petty Officer with 24 hours of advance notice of every delivery to the site and provide the company name, delivery person, and phone number of the firm making deliveries. All vehicle access to government property requires

vehicle registration and proof of liability insurance. Access to the Coast Guard facility may be denied otherwise.

G. PLACE AND PERIOD OF PERFORMANCE

1. Place of Performance: All work related to the components of this project shall be performed at

Yerba Buena Island
Northgate Rd
San Francisco, CA. 94130

2. Period of Performance:

2.1 A Notice to Proceed shall be issued once all submittals are received and approved.

2.2 The performance start date shall be the day the Notice to Proceed is issued. This project shall be completed within sixty (60) calendar days after the award date.

2.3 The Contractor shall complete all work in one bathroom before initiating work in the other to maintain continuous resident access to at least one operational bathroom.