

STATEMENT OF WORK
CONSTRUCTION SERVICES
BUILDING 31B
May 04, 2026

PROJECT TITLE: C116635.ORF.31B NEW ROOFING AND WP OF STRUCTURE BELOW GRADE
LOCATION OF WORK: Building 31B Below Grade Structure

1. **BACKGROUND:** There have been occasional incidences of water infiltration from the roof and walls of the Fitness Center area at the B4 level of Building 31-B Wing, mostly towards the south exterior wall. This extended portion of the building 31B roof over the Fitness Center area is approximately 6 feet below grade. The portion of the building that is affected by water leak has 60 years-old below grade original roofing and waterproofing. There are signs of water infiltration from the roof and down the south exterior wall of the Fitness Center in B4 level. This project is to implement a long-term measure to stop water infiltration to the interior by removing the existing roofing and waterproofing and install new roofing, and waterproofing on the below grade roof, walls, and foundation with new foundation/subsurface drainage and surface drainage.
2. **SCOPE OF CONSTRUCTION SERVICES**
The General Contractor is referred to as the contractor.
 - 2.1. **Construction Documents:** The stamped and signed permit drawings and specifications, herein referred to as 'construction documents', are provided as an Enclosure. This project involves demolition, modification, new construction work as required by the construction documents to accomplish the work for removal of the existing waterproofing/dampproofing from the below grade construction (roof, wall, foundation) extended between the loading dock and building 31C and replace with new waterproofing and exterior envelope treatment for example insulation and air-water barrier, and other related work. The project also include work related to existing and new drainage utility systems, tree removal, exterior stair and masonry work at retaining wall reconstruction as indicated on the construction documents. Construction work shall be in full conformance with the construction documents and any deviation deemed necessary must be brought to the attention of the CO/PO (Contracting Officer/Project Officer) immediately for prior approval.
 - 2.2. **Period of Performance:** This project is to be completed within three hundred (300) **workdays** from the Notice to Proceed date issued by the CO. If there is a project schedule delay, that is not the fault of the Government, the Contractor shall provide a **schedule recovery plan** to maintain the original project schedule or amendments approved by the CO at no cost to the government.
3. **CONSTRUCTION SERVICES** - The contractor shall provide all material, labor, equipment, and supervision as necessary to complete the construction of this project. The project scope as defined above must be accomplished in the following tasks:
 - 3.1. **Construction:** Perform all work as indicated in the approved construction documents. The contractor shall engage and provide technical manpower, expertise, and other resources necessary for a sustained and steady work progress, to meet major milestones and interim deadlines.

The contractor shall provide safe access to construction site and collaborate with all stakeholders including the Construction Administration team, CQM team, SMEs for Quality Control inspections, FAR/Labor compliance inspection and interview, other Government inspections, for the duration of the project.

The contractor shall inform the PO/CO immediately of any hazard, accident, or unusual circumstances onsite. If the PO/CO cannot be reached then inform the NIH Police.

3.2. General Requirements:

- 3.2.1. The contractor shall have daily sign-in/sign-out sheet available for inspection onsite.
- 3.2.2. The contractor shall be responsive to and shall take necessary measures for potential risks and mitigation, hazards, fall protection, extreme weather conditions and safety of staff and others.
- 3.2.3. The contractor shall comply with Division 01 Specification requirements including specification section 015950 for Severe Storm Plan requirements.
- 3.2.4. The contractor shall secure and protect all items in place to ensure they are not air-borne in high wind and protect the site from environmental damage.
- 3.2.5. The contractor shall install onsite temporary signage including for Life Safety, egress, and emergency information.
- 3.2.6. The contractor shall ensure proper PPE for staff and hold daily safety tool talks prior to work onsite and remind the staff to maintain proper conduct and not use foul language or not play very loud music onsite.
- 3.2.7. The contractor shall comply with OSHA requirements to provide adequate lighting at work areas, provide toilet facilities and drinking water onsite.
- 3.2.8. The contractor shall stack materials onsite per manufacturer's recommendations. Damaged and discarded items shall be promptly removed from site.
- 3.2.9. The contractor shall keep the construction site safe, clean and tidy at all times. No food or drink (except water) allowed on site. Lunch break at appropriate locations. Trash placed in approved receptacles.

3.3. Safety: The contractor shall comply with all applicable safety requirements listed on the Division of Occupational Health and Safety (DOHS) website. Construction work shall not begin until the Accident Prevention Plan has been approved by the Government. The DOHS website for safety information is <https://www.ors.od.nih.gov/sr/dohs/YourRole/Pages/Contractor-Safety-Materials.aspx#deliver>

3.4. NIH Security Requirements: Coordinate with the NIH Division of Police (DP), Division of Physical Security Management (DPSM), and Division of Personnel Security and Access Control (DPSAC) as needed to clarify and implement NIH security requirements, which include but are not limited to those listed below:

- 3.4.1. Badging requirements: The contractor shall coordinate with the PO for campus access and staff badging, and comply with all requirements.
- 3.4.2. NIH Policy Manual 1381 Physical Security Project Requirements for NIH Owned and Leased Facilities are found here: <https://policymanual.nih.gov/1381>.
- 3.4.3. After Hours access requirements: The contractor shall coordinate with the COR and NIH Police to obtain a stamped/signed "Police Permit" for work required outside of NIH Staff General Working Hours of 6 a.m. to 6 p.m. See the Division 1 Specifications Work Restrictions section for more information on work hours. The contractor shall secure access to the project site during after-hours.

3.4.4. Contractor shall comply with DPSM Physical Security Policy and Design Requirements:

- PDR Appendix B, Electronic Locking Devices (*Card Readers*)
- PDR Appendix C, *Security Wiring*
- PDR Appendix J, *Use of Powder Actuated Tools*
- PDR Appendix G, *Photographing Filming and Video Recording* at NIH.

3.4.5. Contractor shall coordinate with the PO to obtain the NIH hardware specifications and standards (DRM Section 4.2: Doors) for additional requirements issued by the NIH Locksmith Department for door lock core replacement requirement. Locksmith Shop is located in Building 13, Room 1405 or contact by email at locksmith@mail.nih.gov.

3.5. Noisy Work Hours: Typical noisy work hours are prior to 7:00am and after 6:00pm, but may vary. Coordinate actual noisy work hours with the Project Officer to obtain prior authorization. The Contractor may have to schedule noisy work for during the early morning hours, evening hours or weekend hours.

3.6. Project Management: The contractor shall appoint a qualified and experienced Project Manager (PM) to manage this project and be the Government's single point of contact for the duration of the project. The PM shall be responsible for quality management and ensuring conformance with the division 01 specification for all work performed in the project. The PM shall coordinate with the government's construction administration team for their post design services.

3.7. Construction Schedule:

3.7.1. The schedule type for this project will be (Gantt Chart, MS Project, Primavera, etc.) or as agreed to by the Contractor and the CO. Schedule type shall be appropriate to the size, type and complexity of the project.

3.7.2. The schedule shall contain, as a minimum, the major milestones as agreed by the CO, significant features of work, start date, finish date, activities with durations (not to exceed 20 calendar days except for procurement), cost, percent complete, and predecessors.

3.7.3. Contractor shall submit a cost-loaded schedule with separate line item for each significant activities within Ten (10) workdays from date of award for review and approval of the CO.

3.7.4. The contractor shall coordinate with the PO for delivery of Government Furnished Contractor Installed (GFCI) items to incorporate into the updated schedule as agreed by the CO.

3.7.5. The Contractor shall review the schedule at bi-weekly meetings identifying actual completed work and discuss potential delays with revised forecast dates as agreed by the CO and submit a schedule recovery plan for work items that may not finish on the last approved scheduled date.

3.7.6. Changes to the approved schedule or changes to the Period of Performance (PoP) must be approved by the CO.

3.7.7. Contractor shall provide the CO with an updated schedule within five (5) workdays after the CO has agreed to the changes.

3.8. Meetings: The contractor shall provide for and conduct meetings to be held on campus or web conference. Prepare and submit meeting minutes in accordance with construction specifications.

3.8.1. Pre-Construction Kickoff Meeting: Attend an onsite One (1) hour pre-construction kickoff meeting within two (2) weeks after award hosted by the PO. The purpose of this meeting is to discuss and develop a mutual understanding concerning the schedule and administrative work.

3.8.2. Progress Meetings: The contractor shall host and conduct a One (1) hour bi-weekly progress meetings alternating between onsite and in-person virtual web-conference using TEAMS, send out meeting invites, prepare and distribute meeting agenda and minutes.. The contractor shall provide for each meeting an agenda to include a 2 or 3 weeks look ahead schedule, a list of

outstanding and upcoming RFIs and submittals, outstanding items from previous meeting minutes and new issues to discuss.

- 3.9. Photographic Documentation:** The contractor shall document Before and After condition photos, and weekly progress photos to send to the PO.
- 3.10. Utility Shutdowns:** The Contractor shall endeavor to provide a list of necessary utility outages needed at the beginning of the construction project in order to tie in new utilities during the project. This will provide the Division of Facilities Operation and Maintenance (DFOM) sufficient time to assess the impact of the outages, locate and test shutoff valves and other fixtures, and allow affected building occupants to plan their research around the shutdown schedule. The further advance the shutdown request the better, but **shall be no less than four (4) weeks from the desired shutdown date**. There is no guarantee that the requested date will be approved, and the Contractor shall work with the Project Officer (PO) and DFOM to negotiate another date.
- 3.11. Flood Mitigation:** Flooding of workspaces is of critical concern particularly in clinical and laboratory areas. Contractor is to maintain Shop Vacuums at work areas in the event of a flood, other water leaks or spillage to prevent further water damage. Contractors shall have a Fire Sprinkler Shut off tool readily available on hand in the event work involves live sprinkler heads or the sprinkler is accidentally activated. Fire sprinkler leakage and other sources of flooding shall be discussed at the Pre-Construction meeting and water shutoff valves will be identified on individual floors. Contractors will train workers at their Safety Meetings on the location of these valves. Contractors should post valve location drawings and or label such valves. Any significant water leakage shall be reported to the Project Officer immediately upon discovery.
- 3.12. Request for Information (RFI):** Unless an existing RFI form is already part of a Government or Contractor provided construction management software, use the RFI form provided as an Enclosure when formally seeking information or clarification after award. The contractor shall submit RFIs to the PO for any field conditions that may require additional work, to initiate a change order process.
- 3.13. Construction Administration (CA):** The Contractor shall collaborate and coordinate with the Government's construction administration (CA) services team for the duration of the project to address and resolve all issues notified by the CA team. The contractor shall assist and cooperate with the CA team as necessary.
- 3.14. Construction Quality Management (CQM):** The Contractor shall collaborate and coordinate with the Government's CQM contractor for the duration of this project and resolve any conflicts as applicable. The contractor shall review the CQM Plan and provide review comments to the PO within 5 calendar days. The contractor shall coordinate with the CQM contractor to integrate key CQM activities into their construction schedule. The contractor shall coordinate with the CQM Plan to align their construction schedule. The contractor shall collaborate with the CQM for QC requirements and Testing procedures. The contractor shall coordinate their test schedule with the CQM contractor. The contractor shall provide access and assist the CQM contractor in their work onsite. The contractor shall coordinate with the CQM contractor for Record Documents review and address any issues.
- 3.15. Construction and Demolition Waste Contract Requirements:** The Contractor shall comply with the NIH Division of Environmental Protection's requirements pertaining to dumpsters, recycling, chemical and hazardous waste, and universal waste as described in the following link:
https://orf.od.nih.gov/EnvironmentalProtection/WasteDisposal/Documents/Construction%20and%20Demolition%20Waste%20Contract%20Requirements_508.pdf

3.16. BIM and CADD: Using Building Information Modeling (BIM) is not required but if the contractor chooses to use BIM process instead of Computer Aided Design and Drawings (CADD) in this project then it shall be in accordance with the US National BIM Standard version 3 (NBIM-US V3) which can be downloaded at <https://www.nationalbimstandard.org/>.

- 3.16.1. BIM Project Execution Plan (PxP) – If BIM is used in this project then the contractor shall submit a BIM Project Execution Plan for Revit to the PO as part of the submittals package. The NIH is embracing Building Information Modeling (BIM) as a pillar of its built environment. To that effect the NIH is adopting and implementing the consensus of standards presented and referenced in the National BIM Standard – United States (NBIMS-US) by the National Institute of Building Sciences building SMART alliance to guide the NIH’s BIM implementation and execution. To successfully implement BIM on this project, the NIH has developed a detailed BIM Project Execution Plan (PxP) provided as an Enclosure. This living document shall not supersede contractual requirements, but rather enhance the existing requirements and promote collaboration, communication and understanding between all BIM stakeholders. The PxP is a template for the contractor to populate and submit as a formal submittal for review/ feedback.
- 3.16.2. The contractor shall use a live modeling, cloud-based, BIM coordination tool (e.g., ACC/Autodesk Construction Cloud, Procore, or similar). Live BIM coordination will reduce the time for overall coordination and risk of schedule delays.
- 3.16.3. The contractor shall submit Clash Detection Report to the PO for review, prior to starting the activity.
- 3.16.4. During the construction period the Contractor shall record all BIM meetings including those with subcontractors. NIH will be notified of all BIM meetings.
- 3.16.5. Models shall be delivered in Revit (.rvt) and Industry Foundation Classes (.ifc) format. The Contractor shall also convert the BIM models to a 3D PDF for required deliverables.
- 3.16.6. CADD documents shall be delivered in AutoCAD (.dwg). CAD drawings are acceptable for civil information models for site work. New or demolished elements must be modeled from the utility connection point to the user’s space as specified and/or as agreed by the CO/PO. When CAD files are used, the references must be fully bound to the sheets during final turnover. Files containing special fonts must be included with the bound file transfer. Any image files used should be embedded directly into the drawings rather than referenced externally. This includes company logos, details, maps, legends, etc. Any CAD file with multiple sheets in them must be exported and saved as separate bound files/sheets. CAD) Deliverables shall be in conformance with US National CAD standards of the version current at the time of project contract.

3.17. Construction Submittals:

- 3.17.1. The contractor shall host and manage at no cost to the government a web-based project management system, acceptable to the CO/PO, to track project documentation for record keeping, process submittals and shop drawings with particular emphasis on tracking due dates.
- 3.17.2. Submittal Schedule: Unless an existing Submittal Schedule form is already part of a Government or Contractor provided construction management software, use the Government provided template listed in Enclosure 4 to create and develop the submittal schedule.
- 3.17.3. Submittal Approval: No payment will be made for any billable construction until the associated submittals have been provided, reviewed and approved by the Government.
- 3.17.4. Transmittal Form: Unless an existing Transmittal Form is already part of a Government or Contractor provided construction management software, use the Government provided transmittal form listed in Enclosure 5 to transmit submittals.

- 3.17.5. Warranty Form: If applicable, use the Government provide warranty form listed in Enclosure 6 to create and develop the warranty schedule.
- 3.17.6. Asset Turnover Form: If applicable, update the reminder of “Asset Turnover Form” provided by the IWMS Team (iwms@nih.gov) Enclosure 7.

3.18. Asset Tagging & Labeling - Asset Information: The contractor shall complete the Asset Turnover Form data fields. The Turnover Form will be pre-filled by the IWMS Team. The Turnover Form will only contain data of assets that are tracked and maintained under the NIH IWMS inventory.

- 3.18.1. Existing assets: For existing assets being demolished, modified, or relocated, the project drawings and equipment schedules must accurately record the asset identifier (i.e., asset type abbreviation, number, and 5-digit Facility number (FAC#) if available) as seen on the equipment in the field or as identified in the Turnover Form. For existing assets where the equipment identifier is illegible, not available in the field, and not available in the Turnover Form, then a typical equipment identifier may be used per NIH drawing standards. For newly installed assets, the project drawings and equipment schedules must depict unique asset identifiers per NIH drawing standards as identified in the Turnover Form.
- 3.18.2. Physical Asset Tags: All new or replacement assets shall have a physical tag containing the unique asset identifier. Each physical tag shall be affixed to the equipment, have black or red background (red for Emergency equipment), white engraved letters at least 0.75 inches high, and be made of material suitable to sustain the environmental conditions of the equipment.
- 3.18.3. FPAA Projects: For new construction and other large projects that surpass the Federal Project Authorization and Agreement (FPAA) threshold, the Constructor may be required to apply a second physical tag in addition to the tag described above. The secondary tag is yellow and will contain additional information used by DFOM to accurately identify the assets (e.g., barcode linked to IWMS, FAC#, Service of asset, Location of asset). IWMS will provide all the necessary details for the secondary tag and have the AE/Contractor prepare and affix the secondary tags in addition to the Physical Asset Tag. The second tag will be in accordance with the ORF Asset Tag standard and include a barcode number provided by the IWMS Team.
- 3.18.4. Asset Tag and Documentation: Asset documentation including, but not limited to, equipment Operations and Maintenance (O&M) manuals and warranty information. Based on documentation size and quantity, said documents may be transferred to the PO and the IWMS Team via NIH approved digital file transfer means (e.g., Box).
- 3.18.5. POC: The IWMS Team may be contacted via email (iwms@nih.gov) through the Project Officer for any additional information needed regarding the turnover of asset data or documentation of the project.

4. PROJECT CLOSE-OUT

- 4.1 Punch List:** The final punch list will be developed at a date to be determined by the Project Officer, after the Contractor submits a written notice of substantial completion, indicating all major work has been completed. The Project Officer may accept this notice, or reject it, pending further work to be completed.

4.2 Redline Drawings: Provide redline mark-up drawings indicating actual install conditions that deviate from construction drawings.

4.3 Operation and Maintenance Manuals: Operation and Maintenance Manuals, including Preventive Maintenance, Special Tools, Repair Requirements, Parts List, Spare Parts List, and Operating Instructions shall be delivered to the Project Officer in PDF format as a submittal.

4.4 Video Training: The tracker shall submit video training for major assets in MP4 format. Coordinate with the project officer to identify which assets require video training.

4.5 Attic Stock: Provide attic stock as required and store as directed by the COR.

4.6 Warranties: Complete the Warranty Form included with this Scope of Work and transmit as a submittal to the Project Officer.

4.7 Approved Submittals: Provide the approved submittals. Operators and Maintenance personnel will use them to perform their duties.

4.8 Potable Water System Testing: All new water systems shall be flushed out and tested (includes all sinks such as for potable use and laboratory) prior to placing the system in operational use. All system flushing and testing shall be the responsibility of the contractor. Test results shall be provided to the NIH Division of Occupational Health and Safety (DOHS) Community Health Branch (CHB) for review and acceptance. Consult NIH Facilities Development Manual SECTION 3-15: POTABLE WATER POLICY for further details.

5. GENERAL REQUIREMENTS - Comply with the following requirements, as applicable:

5.1. Fire Safety: The NIH Division of the Fire Marshal, the fire safety "authority having jurisdiction" (AHJ), as well as the Project Officer will monitor renovation and construction areas for compliance. The NIH AHJ shall inspect all completed work for compliance with provisions of the National Fire Codes prior to acceptance and approval of substantial completion.

- Non-compliance with compliance checklist is sufficient cause for a "Stop Work Order".
- Refer to the NIH Policy Manual 1370 - *Fire Protection and Life Safety Building Permit Process* (<https://policymanual.nih.gov/1370>).
- Refer to the Facility Development Manual (FDM) online at: <https://www.orf.od.nih.gov/Pages/default.aspx>.

5.2. Construction and Demolition Waste Contract Requirement - The Contractor shall comply with the NIH Division of Environmental Protection's requirements pertaining to dumpsters, recycling, chemical and hazardous waste, and universal waste as described in the following link:

https://orf.od.nih.gov/EnvironmentalProtection/WasteDisposal/Documents/Construction%20and%20Demolition%20Waste%20Contract%20Requirements_508.pdf

5.3. Directional Signage - As part of the project scope of work, room and affected directional signage will be replaced, updated, or added as necessary to ensure that it is clear and easy to understand for all users. Signage shall comply with DRM Appendix M and any specific design guidelines required by the building institute where the project is taking place. These site-specific signage standards, if applicable, will be provided by the PO following the award of project task order.

5.4. Site Impact Review and Coordination System - Submit the appropriate form with all requested information through the COR, who will utilize the web-based Site Impact Review and Coordination (SIRC) system to forward to the NIH DFS Site Coordination Team no less than twenty one (21) calendar days before the need date. The COR can provide a copy of the request forms listed below:

- NIH Site Selection Request Form is required for activities such as placement of a construction trailer, storage container, dumpster, fence, staging area, temporary signage, construction signage, etc. Refer to the NIH FDM Section 2-6 *Site Selection*.
- NIH Road Closure Request Form is required for any disruption to campus vehicular or pedestrian traffic. Refer to the FDM Section 6-11-10 F *Temporary Use of NIH Road, Sidewalks, or Parking Lots*.

5.5. Building Codes - This project shall be constructed to meet or exceed the applicable building code(s) for the location of the facility, such as: the Life Safety Code (NFPA 101), ABA Accessibility Standards, Standard for the Installation of Sprinkler Systems (NFPA 13), The American Institute of Architects Academy of Architecture for Health with the assistance from the U.S. Department of Health and Human Services (Note: The Department of Health and Human Services (DHHS) as an agency of the Government of the United States of America, derives its authority from the Congress of the United States, and is not subject to laws, ordinances, regulations established by state and local governments or authorities of a lesser jurisdiction).

5.6. Federal Regulations - This project shall be constructed in compliance with all applicable Federal Regulations including but not necessarily limited to the following: Uniformed Federal Accessibility Standards, OSHA 29CFR 1910; The National Environmental Policy Act of 1969 (NEPA); The Endangered Species Act; The National Historic Preservation Act of 1966; The Archeological and Historic Preservation Act; The Wild and Scenic Rivers Act; 40CFR Environmental which includes: Safe Drinking Water Act, Clean Air Act, Clean Water Act, Toxic Substance Control Act, Solid Waste Disposal Act, and RCRA; Executive Order 11990 (Wetlands); Executive Order 11988 (Floodplains); Executive Order 12088 (Compliance with State environmental laws); National Capital Planning Commission (NCPC) "Master Planning Regulations"; Energy Policy Act of 1992; Executive Order 13423 (Strengthening Federal Environmental, Energy, and Transportation Management), etc.

6. GOVERNMENT FURNISHED INFORMATION (GFI)

Government furnished items shall be provided to the contractor as an enclosure to the SOW.

7. ENCLOSURES:

- 7.1.** Construction Drawings and Specifications for project C116635 produced by LSY Architects.
- 7.2.** Request for Information (RFI) Form
- 7.3.** DOHS Forms
- 7.4.** Transmittal Form
- 7.5.** Warranty Form
- 7.6.** Asset Turnover Form
- 7.7.** Site Selection Request Form
- 7.8.** Road Closure Request Form

8. NIH Bethesda Campus Access and Parking:

Mass Transit is available near the NIH Visitor Center. Access to NIH Campus is secured.

Access information weblink <https://security.nih.gov/visitors/Pages/visitor-campus-access.aspx>

Parking permit is not issued for contractors but limited visitor paid parking is available on campus.

Parking information weblink <https://ors.od.nih.gov/pes/dats/parking/pages/generalinfo.aspx>

9. PROJECT CONTACTS:

Contact the PO immediately for any safety issues or urgent matters onsite.

CONTRACTING OFFICER (Government's overall authority in all matters of this project)

Brian Baek
NIH/OD/ORF/
Building 13 South Dr, 9000 Rockville Pike, Bethesda, MD 20892
Phone: (301)-435-1604; Email: brian.baek@nih.gov

PO/COR (Project Officer/Contracting Officer's Representative) As the Government's point of contact (POC) all correspondence shall be sent to the PO/COR and the CO shall be copied (cc'd).

Mohammed Biswas
NIH/ORF/DDCM-Office & Leased Branch
Building 13, Suite 2S75, 9000 Rockville Pike, Bethesda, MD 20982
Mobile: (202) 934-2138; Email: mohammed.biswas@nih.gov