

UNCLASSIFIED

ATTACHMENT 1: STATEMENT OF WORK

Building Automation System Preventative Maintenance Service Contract
Revision 0



Project Title: Post HYDERABAD BAS PMSC

Organization: The US Department of State, Bureau of Overseas Building Operations,
OPS/FAC/PS BAS Support

Preparation Date: May 6, 2026

Prepared By: Burke Gower

BAS PMSC Statement of Work

Version 1.12

ATTACHMENT 1: STATEMENT OF WORK

Table of Contents

Contents

Table of Contents	I
Acronyms and Abbreviations	1
1. General.....	3
2. Period of Performance.....	4
3. Building Automation Systems to be Serviced.....	5
3.1 Building Automation Systems (BAS) installed at Post	5
3.2 Equipment Controlled and/or Monitored.....	7
3.3 Buildings where BAS are Installed.....	8
4. BAS Preventative Maintenance (PM) Services	8
4.1 General.....	8
4.2 Scheduling.....	8
4.3 Checklist Development	9
4.4 Implementation	9
4.5 Periodic PM Activities	9

BAS PMSC Statement of Work

Version 1.12

ATTACHMENT 1: STATEMENT OF WORK

4.6	Annual PM Activities (these are the total activities to be covered in two semi-annual visits).....	13
4.7	Planned Out Five (5) Year PM Activities (these are the additional check points/activities to be covered during entire five-year visits (i.e. 10 visits) without any additional costs)	18
4.8	Manufacturers' Recommended PM	19
4.9	Deficiency Reporting	19
4.10	Remote Support	19
4.11	Allocation for Repairs	19
4.12	Post FM Sign-Off	20
5.	Exclusions, Purchase Orders and Modifications	20
5.1	Exclusions	20
5.2	Purchase Orders and Modifications.....	20
6.	General Deliverable Requirements	22
6.1	General.....	22
6.2	Document Creation, Classification and Handling Requirements.....	23
7.	Execution Schedules.....	26
7.1	General.....	26
7.2	Tasks, Milestones and Scaling	26
7.3	Updates	27
8.	Pre-Travel Deliverables.....	27
8.1	PM Service Activity Schedule	27

BAS PMSC Statement of Work

Version 1.12

ATTACHMENT 1: STATEMENT OF WORK

8.2	PM Service Activity Description List	27
9.	Post-Travel Deliverables	28
9.2	PM Service Activity Schedule and PM Activity Description List.....	28
9.3	Preventative Maintenance Site Visit Report	28
9.4	Appendices.....	37
10.	Deliverable Submission Schedule	38
10.1	Execution Schedules	38
10.2	Pre-Travel Deliverables.....	39
10.3	Post-Travel Deliverables	39
11.	Retention of Deliverables and Other Data by the Contractor	39
11.1	General.....	39
12.	Contractor's Responsibility	40
12.1	General.....	40
12.2	Codes and Regulations	41
12.3	Authorization to Visit Site (applicable if works at CAA space).....	41
12.4	Contractor and Personnel Qualifications	42
12.4.1	The Contractor shall employ a competent On-Site Supervisor, satisfactory to the Government, to work at all times with the authority to act for the Contractor.....	42
12.5	Materials and Equipment	43
12.6	Contractor Use of Premises.....	45
13.	Delivery, Mail and Courier Addresses.....	46

BAS PMSC Statement of Work

Version 1.12

UNCLASSIFIED

ATTACHMENT 1: STATEMENT OF WORK

13.1	Classified Packages & Mail.....	46
13.2	Unclassified Packages & Mail.....	48
14.	Government's Responsibility	49
14.1	General.....	49
Attachment A: Additional Security Requirements for BAS PMSC in Secure Areas		50
1.	General.....	50
1.2.	Public Release of Information.....	50
2.	Personnel Requirements.....	50
2.1.	Personnel Clearances.....	50
2.2.	Visit Authorization Requests	50
2.3.	Country Clearance for Travel to Post/Site	50
2.4.	Standards of Conduct.....	51
2.5.	Removal of Individual Contractor Employees for Cause	51
3.	Briefing and Reporting Requirements.....	52
3.1.	Security Briefings.....	52
3.2.	Personal (Unofficial) Travel Outside of the Project Country	52
3.3.	Suspicious Contact Reports (SCRs)	53
3.4.	Reporting of Suspicious Incidents Occurring at Off-site Locations or During Travel to/from the Project Site	53
3.5.	Foreign Contact Reporting	53

BAS PMSC Statement of Work

Version 1.12

IV

UNCLASSIFIED

UNCLASSIFIED

ATTACHMENT 1: STATEMENT OF WORK

3.6.	Reporting Marriage, Intent to Marry, Cohabitation or Other Continuing Bonds of Affection with Foreign Nationals.....	54
3.7.	Reporting Adverse Financial Situation and Certain Arrests.....	54
3.8.	Dual Citizenship.....	54
4.	Subcontracting Requirements	54
4.1.	DD Forms 254 for Subcontractors	54
5.	Handling/Marking Requirements - Classified & Sensitive But Unclassified (SBU).....	55
5.1.	Security Classification Guide.....	55
5.2.	Protection of Classified and SBU Information.....	55
5.3.	Disposition and Retention of Task/Project Information	55
5.4.	Project Generated Information at Contractor's Facility – Disposal/Destruction Plan	56
5.5.	Project Related Classified Working Papers, As-Built and other Classified Generated at Post.....	56
5.6.	Photographs.....	57
6.	Transmission Requirements for SBU.....	57
6.1.	Transmission of Sensitive But Unclassified (SBU).....	57

BAS PMSC Statement of Work

Version 1.12

ATTACHMENT 1: STATEMENT OF WORK

Acronyms and Abbreviations

The following are commonly used acronyms and abbreviations in this document.

- | | |
|---|--|
| 1. AHU = Air Handling Unit | 19. FAC = Facilities or OBO/CFSM Facilities |
| 2. ASHRAE = American Society of Heating, Refrigerating and Air-Conditioning Engineers | 20. FCU = Fan Coil Unit |
| 3. BAS = Building Automation System | 21. FM = Facility Manager |
| 4. CAA = Cleared Access Area (Secure Area) | 22. FMS = Facility Maintenance Staff |
| 5. CCR = Country Clearance Request | 23. GSO = General Services Officer |
| 6. CFSM = OBO Construction, Facilities, and Security Management | 24. GWA = General Work Area (Unsecured Area) |
| 7. CLIN = Contract Line Item | 25. HAZMAT = Hazardous Material |
| 8. CMR = Chief of Mission Residence | 26. HVAC = Heating, Ventilation, and Air Conditioning |
| 9. CO = Contracting Officer | 27. I/O = Input/Output |
| 10. COR = Contracting Officer's Representative | 28. IBC = International Building Code |
| 11. CRP = Consolidated Receiving Point | 29. LAA = Limited Access Area (Unsecure) |
| 12. DBA = Defense Base Act | 30. MSDS = Material Safety Data Sheet |
| 13. DCSA = Defense Counterintelligence and Security Agency | 31. MSGQ = Marine Security Guard Quarters |
| 14. DOS = Department of State | 32. NEC = National Electrical Code |
| 15. DS = Diplomatic Security | 33. NFPA = National Fire Protection Association |
| 16. DS/IS/IND = Bureau of Diplomatic Security, Industrial Security Division | 34. OBO = Bureau of Overseas Building Operations |
| 17. eCC = Electronic Country Clearance | 35. O&M = Operations and Maintenance |
| 18. ES = Execution Schedule | 36. OSHA = Occupational Safety and Health Administration |

ATTACHMENT 1: STATEMENT OF WORK

- 37. OWS = Operator Workstation
- 38. PAA = Public Access Area (Unsecured Area)
- 39. PM = Preventative Maintenance
- 40. Post = Department of State Overseas Embassy, Consulate, or Mission
- 41. POWS = Portable Operator Workstation (Laptop)
- 42. PS = Program Support
- 43. RFP = Request for Proposal
- 44. RSO = Regional Security Officer
- 45. SBU = Sensitive but Unclassified
- 46. SC = Supervisory Controller
- 47. SCG = Security Classification Guide
- 48. SME = Subject Matter Expert
- 49. TDY = Temporary Duty (Work Travel OCONUS)
- 50. UPS = Uninterruptible Power Supply
- 51. VAR = Visit Authorization Request
- 52. VAV = Variable Air Volume

1. General

- 1.1. The U.S. Consulate General located in Hyderabad, India requires Building Automation System (BAS) Preventative Maintenance (PM) services. The Contractor shall perform BAS PM Services as described in this Statement of Work. The Contractor shall also provide further evaluation of the overall functionality of the BAS based on concerns and input provided to the Contractor by the Facility Manager (FM) and Facility Maintenance Staff (FMS).
- 1.2 The Contractor shall provide BAS PM Services for the upkeep of the BAS indicated below in *Section 3. "Building Automation Systems to be Serviced"*.
 - 1.2.1 The objective of scheduled preventive maintenance is to eliminate system malfunction, breakdown and deterioration. The BAS PM work required shall include, but is not limited to: Preventative Maintenance; Investigation & troubleshooting; Adjustments; Trend & Alarm configuration; etc.
 - 1.2.2 BAS PM Services shall result in all systems serviced under this agreement being in good operational condition when the work is completed.
 - 1.2.3 The Contractor shall provide all necessary managerial, administrative and direct labor personnel as well as all transportation, tools, instrumentation, equipment and supplies required to perform the BAS PM Services defined in this Statement of Work. The Contractor shall provide the services of qualified, trained, manufacturer certified technicians to perform the required BAS PM Services.
 - 1.2.4 BAS PM Services shall be performed on BAS installed in and/or serving the General Work Areas (GWA) & Public Access Areas (PAA) at Post.
 - 1.2.5 BAS PM Services shall be performed on BAS installed in the Controlled Access Areas (CAA) Restricted spaces at Post.
 - 1.2.5.1 Additional clearance and security provisions are required to access and work in these spaces.
 - 1.2.5.2 Additional document security classification provisions are required. See Sections 6.2.8-13 for additional details.
 - 1.2.6 BAS PM Services shall be performed on BAS installed in and/or serving the CAA Core spaces at Post.

- 1.2.6.1 Additional clearance and security provisions are required to access and work in these spaces.
- 1.2.6.2 Additional document security classification provisions are required. See Sections 6.2.8-13 for additional details.
- 1.3 All work shall be accomplished in a manner which conforms to the intent of all applicable IBC, ASHRAE, NFPA/NEC, U.S. EPA, and DOS policy, procedures, and directives; causes no damage to buildings or property; endangers none of the building occupants or workers during these tasks; and leaves the areas safe for occupancy.
- 1.4 This contract includes security provisions which require a DD Form 254, Contract Security Classification Specification, issued by the Bureau of Diplomatic Security, Industrial Security Division (DS/IS/IND). Issuance of the DD Form 254 is contingent on the Contractor's possessing and maintaining a Defense Counterintelligence and Security Agency (DCSA) TOP SECRET facility clearance. Loss or Invalidation of the prime contractor's facility clearance may result in termination of the contract for default. Personnel requiring access to Controlled Access Areas (CAAs), CORE/PCC or classified information must possess a TOP SECRET security clearance. See *Attachment A: Additional Security Requirements for BAS PMSC in Secure Areas*.

2. Period of Performance

- 2.1 The period of performance shall be one (1) year as of the date of the Notice to Proceed for the base contract year, with **four (4)** additional one (1) year option periods, to be exercised at the sole discretion of the Government.
- 2.2 This contract shall provide for **two (2) BAS PM Site Visits (Semi-Annual) per year for each year of the contract.**
- 2.3 BAS PM Site Visits shall be equally spread out over the course of the contracted year.
 - 2.3.1 All BAS PM Site Visits shall occur within the 365-day window.
 - 2.3.2 Combining multiple site visits into a single site visit is not allowed.
 - 2.3.3 The first BAS PM Site Visit must occur within 60 days of contract award / renewal.
 - 2.3.4 The work shall be considered deficient if the Contractor fails to provide the required number of BAS PM Site Visits within the 365 days after contract award / renewal or fails to space out the BAS PM Site Visits in the manner described above.

3. Building Automation Systems to be Serviced

3.1 Building Automation Systems (BAS) installed at Post

3.1.1 The Contractor shall maintain the Building Automation System(s) in a safe, reliable, and efficient operating condition. The following information provides a rough summary of each BAS that is to be serviced. NOTE: Quantities listed below are estimates and the Contractor must verify quantities during the initial Site Visit.

3.1.1.1 BAS #1

- a. Manufacturer of the BAS: **DELTA Controls**
- b. Name of BAS Product Line: ORCAview
- c. BAS Software Name and Version Number: ORCAview, V3.40 Build (10051)
- d. Operator Workstations (OWS): Navigator and ORCAview V3.40 Build (10051)
- e. Portable Operator Workstations (POWS): HP Workstation and HP Laptop
- f. Supervisory Controllers (SC):
 - 1) DSC-1212E
 - 2) DSC-1616E
 - 3) DAC-600
 - 4) DAC-1600
 - 5) eBM-440-M
 - 6) eBM-800
 - 7) eBM-D400R4
 - 8) eBM-D400R4-H
 - 9) eBMGR
 - 10) eBMGR-TCH

g. I/O Modules Installed:

- 1) DZNR-768
- 2) eBX-04
- 3) eBX-08

h. Sub-Controllers Installed:

- 1) DFC-322R3-240
- 2) DVC-V322A-B
- 3) DFM-400
- 4) DFM-400-P
- 5) DNS-24L
- 6) DNS-24L-FAN
- 7) RTS-20
- 8)

3.1.1.2 BAS # 2

- a) Manufacturer of the BAS: **DELTA Controls**
- b) Name of BAS Product Line: ORCAview
- c) BAS Software Name and Version Number: ORCAview, V3.40 Build (10051)
- d) Operator Workstations (OWS): Navigator and ORCAview V3.40 Build (10051)
- e) Portable Operator Workstations (POWS): HP Laptop
- f) Supervisory Controllers (SC):

1. eBMGR-TCH
2. eBM-440-M
3. eBM-800
4. eBM-D400R4
5. eBM-D400R4-H
6. eBus Address
7. DSC-1616E

3.2 Equipment Controlled and/or Monitored

3.2.1 The following is a rough summary of the types and quantities of equipment controlled and/or monitored at Post by BAS. NOTE: Quantities listed below are estimates and the Contractor must verify quantities during initial Site visit.

3.2.1.1 Chilled Water System (Primary/Secondary Variable Flow):

- a. Air-Cooled Chillers: Controlled, Quantity : 02
- b. Variable Flow Secondary Chilled Water Pumps: Controlled, Quantity : 03

3.2.1.2 Backup Chilled Water System (Primary Constant Flow):

- a. Air Cooled Chillers: Monitoring, Quantity : 01
- b. Constant Flow Chilled Water Pumps: Monitoring, Quantity : 01
- c. Heat Exchangers: Controlled, Quantity : 01

3.2.1.3 Heating Hot Water System (Primary/Secondary Variable Flow):

- a. Boilers: Controlled, Quantity : 02
- b. Variable Flow Secondary Hot Water Pumps: Controlled, Quantity : 03
- c. Variable Flow Heat Recovery Pumps: Controlled, Quantity : 04
- d. Constant Flow Boiler Water Pumps: Controlled, Quantity : 02

3.2.1.4 Air Handling Units: Recirculation Type: Controlled - 16 no's

3.2.1.5 Air Handling Units: Outside Air Type: Controlled - 02 no's

3.2.1.6 Fan Coil Units: Controlled, Quantity 24

3.2.1.7 DX Units: Monitoring, Quantity 04

3.2.1.8 Supply/Exhaust Fans: Controlled, Quantity 28

3.2.1.9 Relief Exhaust Fans: Controlled, Quantity 06

3.2.1.10 Smoke Exhaust Fans: Controlled, Quantity 05

3.2.10.11 VRV/VRF Units: Monitoring, Quantity 40

3.2.1.12 Water Meters: Monitoring, Quantity 16

3.2.1.13 Domestic Water Filtration System (Monitoring Only): Quantity 1

3.2.1.14 Toilet Flush Water Filtration System (Monitoring Only): Quantity 1

- 3.2.1.15 Fuel System (Monitoring Only): Quantity 1
- 3.2.1.16 Fire Alarm System (Interlocks & Monitoring Only): 1 in every AHU

3.3 Buildings where BAS are Installed

- 3.3.1 The Post is composed of multiple buildings. The following buildings at Post utilize BAS:
 - a. New Office Building (NOB): DELTA Controls, ORCAView
 - b. Support Annex Building (SPX): DELTA Controls, ORCAView
 - c. Warehouse Building: DELTA Controls, ORCAView
 - d. Utility Building: DELTA Controls, ORCAView
 - e. MSGR: DELTA Controls, ORCAView
 - f. MCAP: DELTA Controls, ORCAView
 - g. CCAP: DELTA Controls, ORCAView
 - h. SCAP: DELTA Controls, ORCAView

3.4 Some of the BAS and Mechanical equipment described in this section will require the Contractor to possess clearance and to utilize cleared personnel in order to perform the work required by this Contract. This equipment will be identified for the Contractor by Facility Maintenance Staff when the Contractor is at Post providing BAS PM Services.

4. BAS Preventative Maintenance (PM) Services

4.1 General

- 4.1.1 The Contractor shall perform BAS Preventative Maintenance services for the Building Automation Systems indicated. Provide the necessary investigative services to ensure BAS controls are working as designed and in accordance with documented operating sequences. BAS PM Services shall include, but are not limited to, the following tasks.

4.2 Scheduling

- 4.2.1 The Contractor shall indicate which PM Activities will be performed at each site visit
(This schedule has to be provided by vendor before executing the services).
- 4.2.2 The schedule shall cover a five (5) year time period so that the schedule can properly address tasks that are to be spread out over this time frame.

- 4.2.3 As a supplement to the schedule, the Contractor shall include a PM Service Activity Description List which will provide a detailed description of each PM activity, including the means and methods by which the Contractor intends to perform each PM activity.
- 4.2.4 See *Section 8. "Pre-Travel Deliverables"* for further requirements.

4.3 Checklist Development

- 4.3.1 For the first BAS PM Site Visit to Post the Contractor shall utilize generic PM Checklists that the Contractor has previously utilized in the performance of their trade.
- 4.3.2 During the site visit the Contractor shall collect data on the existing BAS(s) at Post and the associated equipment being controlled. This data shall be used to create site specific PM checklists for use in future BAS PM Site Visits.
- 4.3.3 After the completion of the Contractor's first BAS PM Site Visit, the Contractor shall create site specific Checklists for each BAS and the equipment controlled and/or monitored by each BAS. These Checklists shall be developed from existing As-Built Data; Operation & Maintenance Data; Set Point Data; Time Schedule Data; and any other data relevant to the PM effort found at Post. This data shall be reviewed by the Contractor to determine the operational baseline requirements that will be used in the Checklists.
- 4.3.4 All future BAS PM Site Visits shall utilize the site-specific Checklists. These Checklists will be used by the Contractor when Preventative Maintenance is performed to verify the Building Automation Systems are functioning as originally intended.
- 4.3.5 There shall be one Checklist provided for each system controlled and/or monitored by a BAS.
- 4.3.6 See *Section 8. "Pre-Travel Deliverables"* for further requirements.

4.4 Implementation

- 4.4.1 The Contractor shall perform BAS PM Services at the frequencies indicated in the PM Service Activity Schedule using the site-specific Checklists developed for the equipment and systems called out in the Contract. The Contractor's technician shall sign off on every item of each checklist when the associated PM is performed.

4.5 Periodic PM Activities

- 4.5.1 At a minimum, the following PM Service activities are required to occur during each site visit.

- 4.5.2 Check BAS Communication Network: Validate the network connectivity of all BAS controllers, Operator Workstations (OWS/POWS; desktop and laptop computers), Servers, and Network components (repeaters, switches, hubs, etc.). Investigate and remediate any issues found.
- 4.5.3 Confirm Time Schedules: Review existing time schedules and validate correct operation based on actual time of day and facility occupancy. Adjust time schedules as needed to reflect the actual occupancy patterns of the buildings at Post.
- 4.5.4 BAS Investigation and Troubleshooting: The Contractor shall provide investigation and troubleshooting services for issues related to the BAS as required in this Statement of Work or as requested by the Facility Manager at Post during a PM Services site visit.
- 4.5.4.1 The Contractor shall review Facility Maintenance logs since the last visit to Post and determine if there are any operational issues which need to be checked.
- 4.5.4.2 The Contractor shall determine the cause(s) of any problems found with the BAS and determine the repairs and/or modifications to the BAS that will be needed to correct these problems.
- 4.5.5 BAS Trend and Alarm Configuration: The Contractor shall review the BAS Alarm History and Trend log files. Any problems noted from this review shall be investigated.
- 4.5.5.1 The Contractor shall validate the correct reporting of alarms and verify that the correct codes and messages are being reported.
- 4.5.5.2 If no trends or alarms are configured in the BAS, the Contractor shall coordinate with the Facility Manager and configure the trends and alarms desired by the Post.
- 4.5.5.3 Archive data as necessary to free up hard drive space on the BAS OWS / Server for future trend and data storage.
- 4.5.6 BAS OWS Graphics: The Contractor shall confer with the Facility Manager after reviewing the BAS OWS graphics and trend logs to determine if any modifications are desired to the presentation of information. Minor changes to improve graphics and reports shall be implemented as needed.
- 4.5.7 Review of Post's Spare Part Inventory: The contractor shall review the Post's spare part inventory during each PM Site Visit and determine what parts need to be procured by Post

and update the Spare Part Schedule. See *Section 9. "Post-Travel Deliverables"* in this statement of work for additional requirements.

4.5.8 BAS Backup Retention: The Contractor shall, at the end of each site visit, create a current backup of the data, programming, graphics, settings, license files, and any other files necessary to restore a controller, Operator Workstation (OWS, POWS; Desktop or laptop computer) or Server for each BAS installed at Post.

4.5.8.1 Each backup shall be configured to allow Facility Maintenance staff to recover the associated BAS in the event there is a BAS failure.

4.5.8.2 Step by step instructions on how to recover a controller, OWS/POWS or Server shall be included with each BAS backup.

4.5.8.3 The Contractor shall include screenshots of each BAS OWS Graphics screen. Graphics screens for identical components with the same I/O configuration, such as VAVs or FCUs, can be represented by a single screenshot.

4.5.9 User Account Retention: For each BAS OWS/POWS/Server at Post the Contractor shall:

4.5.9.1 Create an Administrator level user account called "BAS Support" in the Operating System, the BAS software and the encryption software. The account shall be configured in such a manner that it cannot be deleted by an account that does not have administrator rights. The Contractor will utilize a random password generator to create a password for this account. This step can be skipped if the "BAS Support" user account already exists.

4.5.9.2 Create a listing of the user accounts that exist within each BAS. The Contractor shall create tables listing the Operating System user accounts, BAS user accounts and encryption software user accounts that exist within each BAS OWS and/or Server that are used to access each BAS at Post.

4.5.9.3 If there are user accounts that are generic in nature, the Contractor shall also gather the passwords associated with these generic accounts. The Contractor will not attempt to gather password information for user accounts that are set up for specific individuals.

4.5.9.4 Separate tables shall be created for each BAS OWS/POWS/Server. The associated BAS OWS/POWS/Server shall be identified, and the designation included with the following information:

a. The Operating System User Account tables shall contain the following information. These tables shall include the following four (4) columns.

- 1) User Account Name
- 2) Name of Person Associated` with the User Account
- 3) User Account Password (if applicable)
- 4) Type of User Account (Administrator, Standard User, etc.)

b. The BAS User Account tables shall contain the following information. These tables shall include the following four (4) columns.

- 1) User Account Name
- 2) Name of Person Associated with the User Account
- 3) User Account Password (if applicable)
- 4) Type of User Account (Administrator, Standard User, etc.)

c. The Encryption Software User Account tables shall contain the following information. These tables shall include the following three (3) columns.

- 1) User Account Name
- 2) Name of Person Associated with the User Account
- 3) User Account Password (if applicable)

4.5.10 Retaining and Updating BAS As-Built and BAS Operation & Maintenance Manual Documents (Appendix E): The Contractor shall coordinate with the Facility Maintenance Staff at Post to find the existing BAS As-Built and O&M Manual documentation for each BAS installed at Post. When work is performed which modifies the existing BAS hardware/software configuration and/or programming, the Contractor will be responsible for providing updated As-Built and O&M Manual documentation to accurately reflect the new state of each BAS at Post.

- 4.5.10.1 If electronic media versions of these documents exist at Post, the electronic media versions of the documentation shall be copied. If no electronic media versions of this documentation are available at Post, the Contractor shall scan hard copies of this documentation to create electronic media for submission.
- 4.5.10.2 Modifications shall be made to reflect any changes made to the Sequences of Operation by the Contractor and any permanent changes to the Sequences of Operation discovered by the Contractor but not previously documented.
- 4.5.10.3 Modifications shall be made to reflect any physical changes made to the BAS, to include, but not be limited to, wiring changes, changes to controller configurations, the addition or removal of points, etc.
- 4.5.10.4 Any new BAS Software and/or Hardware Licenses associated with the work performed shall be provided. Licenses shall be fully documented, and information provided in a manner that allows Post to work directly with the BAS manufacturer.
- 4.5.10.5 In cases where BAS CAD As-Built Drawings are not available, the Contractor shall produce BAS CAD Drawings for only the drawings that are affected by the work performed. PDFs of these modified drawings shall be inserted into the existing BAS As-Built drawings to replace the outdated drawing pages.
- 4.5.10.6 O&M Manual data shall be provided for any BAS equipment installed as part of this work. A PDF of the Original O&M Manual shall be altered to remove components that are no longer used. O&M information for components added shall be appended to the O&M Manual.
- 4.5.11 UPS Battery Rotation: The batteries of all Uninterruptible Power Supplies that Post has in their Spare Stock shall be rotated with installed UPS batteries during each PM visit. This action will reduce the battery degradation that occurs in long-dormant batteries. An acceptable, alternative action is to fully charge Spare Stock UPS batteries during each PM visit.

4.6 Annual PM Activities (these are the total activities to be covered in two semi-annual visits)

- 4.6.1 At a minimum, the following PM Service activities are required to occur at least once a year. It is the intention of this statement of work that tasks noted here which cannot be

realistically completed during a single site visit, shall be broken up to occur over multiple site visits.

4.6.2 Panel, Controller and Wiring Inspection:

- 4.6.2.1 Physically inspect all field panels and controllers for damage, excessive dirt or moisture and clean/vacuum as necessary.
- 4.6.2.2 Verify proper voltage at all control transformers.
- 4.6.2.3 Inspect all connections, wire raceways in panels and wire arrangements. Remove any abandoned devices and wiring and update panel diagrams as may be necessary to reflect current arrangements and configurations.
- 4.6.2.4 Verify condition of local battery / UPS that may be connected to the panel power source.
- 4.6.2.5 Take photographs, where permissible, of each Supervisory Controller Enclosure installed at Post. Photographs should include interior and exterior shots, including nearby wall space, and shall be labeled with the Controller name. All photos must be cleared by the RSO prior to removing from Post and/or sharing electronically.

4.6.3 Confirmation of Sequences: The Contractor shall review the operation of BAS controlled equipment / systems and confirm that the functionality corresponds with the As-Built Sequences of Operation. When equipment / systems do not operate as described in the sequences the Contractor shall review the associated programming, sensors, wiring, etc. and determine the cause.

- 4.6.3.1 The Contractor shall consult with Facility Maintenance personnel and the Facility Manager to determine if functionality that does not correspond with the sequences is legitimate or if it is a deficiency that needs to be corrected.
- 4.6.3.2 If it is determined that the functionality discovered is not correct, the Contractor shall make adjustments and modify programming as needed to reinstate the functionality described in the As-Built Sequences of Operation.

4.6.4 Review of Post's Expendable Sensors / Equipment: Parts for which product data indicates there is a defined operating life expectancy shall be tracked and scheduled for replacement at the time intervals recommended by the manufacturer. For HVAC applications these will typically include Humidity Sensors, Carbon Monoxide Sensors, Carbon Dioxide Sensors,

UPS Batteries, etc. There are other specialty parts that can fall under this category. See "I. POST-TRAVEL DELIVERABLES" in this statement of work for additional requirements.

4.6.5 BAS Evaluation: For each BAS at Post, review the system and provide an assessment of and recommendations with regard to the condition, level of functionality, age, possible obsolescence, possible need for upgrades or replacement, etc. of all or any portion of the system.

4.6.5.1 BAS Software Assessment: The Contractor shall review the BAS software installed on the BAS OWS and/or Servers to determine if the software needs to be upgraded.

- a. If the software needs to be upgraded, it shall be ascertained if upgrading the software is possible with the current operating system / computer combination.
- b. BAS Software that is not of the most current version is not considered in and of itself a justification for upgrading the software. Other factors justifying the need for an upgrade must be presented. Supporting information justifying the recommendation shall be provided.
- c. A description of the effort involved, and a cost estimate shall be provided if the software needs to be upgraded.

4.6.5.2 BAS OWS / Server Assessment: The Contractor shall review the condition of the BAS OWSs and/or Servers to determine if the hardware is in need of being upgraded or replaced. A description of the effort involved, and a cost estimate shall be provided if the hardware needs to be upgraded or replaced.

4.6.5.3 Missing BAS OWS: Under circumstances where a BAS OWS is found to be missing (typically a laptop computer) the Contractor shall determine what hardware / software is needed. A description of the effort involved in providing the missing BAS OWS and a cost estimate, shall be provided if a BAS OWS is needed at Post.

4.6.5.4 BAS Controller Assessment: The Contractor shall review the various models of BAS controllers installed and determine if any of the controllers are obsolete, are no longer available from the manufacturer and/or are no longer supported by the manufacturer.

- a. Documentation from the manufacturer that clearly indicates one of these conditions exists shall also be provided.
- b. A description of the effort that would be involved and a cost estimate for this effort shall be provided if the controller(s) needs to be updated or replaced.
- c. Work of this nature will not be considered by the COR if supporting documentation from the manufacturer is not provided.

4.6.5.5 Additional BAS Assessments: The Contractor shall also report on the following:

- a. Condition of Network Devices and Quality of Communications
- b. Condition of Controller Enclosures and Power Supplies
- c. Condition of End-Devices (Sensors, Actuators, VFDs, etc.)
- d. Hot/Cold Zones
- e. Humidity Concerns
- f. Pressurization Concerns

4.6.6 BAS Inventory Retention: While at Post performing PM services, the Contractor shall take inventory of each existing BAS. BAS Inventory data collection shall be performed once, during the initial site visit. The BAS Inventory shall be updated during subsequent PM site visits and resubmitted if it is found that changes have been made that affect the inventory data. The intent of this requirement is to take a full inventory of each installed BAS and to document all of the programming and physical hardware points in each BAS.

4.6.6.1 Inventory data collection for each BAS shall include the following information. Separate inventory data collection documents shall be provided for each BAS:

- a. The quantity and locations of BAS OWS / Servers and the software installed on each of these OWS / Servers. (Operating System, BAS software, production software, encryption software, etc.)
- b. The locations of each OWS, Server, Hub, Router, Switch, Repeater, Supervisory Controller, and any other Ethernet-level controller that communicates directly to the Server, shall be shown on sanitized floor plans. If CAD drawn floor plans are not available, it is acceptable to show this information on a scanned copy of the floor plan drawings.
- c. A table providing the following details about the BAS Supervisory Controllers, which communicate directly to the Server. This table shall include the following five (5) columns:

- 1) Manufacturer of the controller
 - 2) Product Line of the controller
 - 3) Name of the controller, as defined in the BAS
 - 4) Model of the controller
 - 5) Part Number of the controller
- d. A table providing the following details about the BAS Sub-Controllers, which communicate to a Supervisory Controller, sub-totaled by Supervisory Controller. This table shall include the following six (5) columns:

- 1) Name of the Supervisory Controller
- 2) Manufacturer of each type of sub-controller
- 3) Model of each type of sub-controller
- 4) Part Number of each type of sub-controller
- 5) Quantity of each type of sub-controller

- e. A table providing the following details about the Equipment and Systems monitored and/or controlled by the BAS. This table shall include the following two (2) columns:

- 1) Type of Equipment / System controlled /monitored
- 2) The quantity of each type of Equipment / System installed

4.6.6.2 The Contractor shall generate a document containing a database printout of the BAS programming, points and other settings for each controller. This will be done using the built-in functionality of the associated OWS / Server. An individual printout shall be provided for each controller.

4.7 Planned Out Five (5) Year PM Activities (these are the additional check points/activities to be covered during entire five-year visits (i.e. 10 visits) without any additional costs)

4.7.1 At a minimum, the following PM Service activities are required to occur at least once over the five (5) year span of the BAS PM Service Activity Schedule. It is the intention of this statement of work that tasks noted here shall be broken up evenly to occur over multiple site visits, over the duration of five (5) years.

4.7.2 Sensor, Operator and End Device Point-to-Point Checkout: Hardware points in the BAS shall be verified against actual field conditions once every five (5) years of service life.

4.7.2.1 This checkout shall verify that each hardware point indicated in the BAS is the actual physical point connected to the controller, that the point is functioning properly and that the point is shown / labeled correctly on the appropriate graphic screens.

4.7.2.2 Any discrepancies shall be investigated, and adjustments made as necessary so that all sensors monitored, and devices controlled by the BAS match the associated hardware points indicated in the BAS and provide the desired functionality.

4.7.3 Sensor, Operator and End Device Calibration: The calibration of hardware points in the BAS shall be verified against actual field conditions once every five (5) years of service life.

4.7.3.1 Where sensors, operators and other end devices are capable of being adjusted, the Contractor shall perform the calibration.

4.7.3.2 Sensors shall be calibrated to within the accuracy range stated in the associated manufacturer's literature.

4.7.3.3 Operators and other end devices shall be adjusted so that the BAS output signal corresponds to operator's or end device's full control range.

4.7.3.4 Where sensors, operators and other end devices are not capable of being adjusted, the Contractor shall note the deviation between actual and measured value for sensors and between actual output function and commanded signal.

- a. The Contractor shall use calibrated instrumentation with a higher accuracy than the sensor, end device or operator being calibrated.
- b. Calibrated instrumentation used shall have been certified by an independent calibration agency within one (1) year of the dates used.

4.8 Manufacturers' Recommended PM

- 4.8.1 It is the responsibility of the Contractor to perform all BAS Manufacturers' recommended PM. This shall be completed in addition to the tasks listed above if there are any discrepancies between what is required by this statement of work and the Manufacturers' recommended PM.

4.9 Deficiency Reporting

- 4.9.1 Any and all problems, issues, failures, etc. related to the BAS and/or the equipment / systems controlled and/or monitored by the BAS, discovered by the Contractor while performing any of the PM Services described within *Section 4. "BAS Preventative Maintenance (PM) Services"* of this Statement of Work shall be considered Deficiencies. All Deficiencies (open or closed) shall be documented in the PM Report, following the criteria described in *Section 9. "Post-Travel Deliverables"*.

4.10 Remote Support

- 4.10.1 The Contractor shall provide up to 20 hours of Remote Support to Post per year, either by phone or by email. The Contractor shall respond to all non-emergency requests within 24 hours, or on the next business day. If Post requires Emergency Support, the Contractor shall respond to Post within 4 hours. All correspondence with Post shall be shared with BAS Support via email. If the Contractor reaches 15 hours of support in a given year and anticipates that more than 20 hours will be required, the Contractor shall notify BAS Support and request a Change Order for the additional hours.

Note: If the contractor anticipates more than 20 hours of remote support services, kindly provide us the price for additional anticipation of hours from 21st hour along with the original proposal.

4.11 Allocation for Repairs

- 4.11.1 Prior to each successive PM Site Visit, the Contractor shall evaluate all Open Deficiencies and needed Spare Parts captured during the previous PM Site Visit and submit a Proposal

to Post and BAS Support to correct the most critical of these shortcomings, up to a maximum proposal amount of \$10,000 per visit.

4.12 Post FM Sign-Off

- 4.12.1 Each Visit to Post shall conclude with the delivery of a BAS PM Site Visit Summary to the Facility Manager, or a staff member designated by the FM, who will sign and date the document. The BAS PM Site Visit Summary shall outline all activities that were performed during the visit, based on the planned PM Service Activity Schedule activities, along with all investigations and repairs, and shall be included in the Post-Travel Deliverables (Appendix G).

5. Exclusions, Purchase Orders and Modifications

5.1 Exclusions

- 5.1.1 This Statement of Work does NOT include the repair of equipment, the replacement or procurement of parts, controllers or computers, the replacement of BAS systems, software upgrades or re-commissioning of the BAS. This exclusion does not apply if the work (parts and/or services) is to correct damage caused by Contractor negligence.

5.2 Purchase Orders and Modifications

- 5.2.1 Work outside the scope of PM Services must be approved by the COR prior to performance of the work. The Contractor shall prepare a proposal, including pricing and scope of work, for Non-PM Service work and submit it to the Government for approval and acceptance as a separate Purchase Order or as a Modification to the Contract.
- 5.2.2 The Government shall accept, reject, or defer action on the Contractor's proposal for work outside the PM Services statement of work and reserves the right to obtain similar work from other competitive sources.
- 5.2.3 When a proposal from the Contractor to perform work outside the scope of PM Services is approved by the Contracting Officer (CO), the Government will issue a Purchase Order or a Modification to the Contract for the additional work. Work is not authorized to proceed until the date so indicated in the Purchase Order or the Modification to the Contract.
- 5.2.4 The Contractor shall coordinate this additional work with the PM Service work to achieve logistic efficiencies. In addition to the requirements described elsewhere in this statement of work, the following requirements will also apply:

- 5.2.4.1 The Contractor shall be required to provide a Submittal for review to the COR. The submittal shall clearly describe in detail repairs and/or modifications being made and shall include control drawings, product data and Sequences of Operation as applicable to the work being done. Work will not proceed without approval of the Submittal by the COR.
- 5.2.4.2 The Contractor shall procure parts (including controllers and computers) and/or software required to perform the additional services defined in the approved proposal and arrange for shipping that will allow for the arrival of parts at Post prior to the dates scheduled for the associated PM Service site visit. These additional works / services will be provided as part of an upcoming, regularly scheduled PM Service site visit.
- 5.2.4.3 Non-PM Service work being provided as part of a Purchase Order or a Contract Modification shall be thoroughly tested by the Contractor and functionality demonstrated to a Government designated representative (COR or Facility Manager as project conditions require.) Depending on the scale and scope of the work, Commissioning may also be required by the Purchase Order / Contract Modification.
- 5.2.4.4 The Contractor shall warrant all parts, labor, installation, modification and other services provided by a Purchase Order or a Contract Modification for a period of one (1) year from the date of acceptance by the COR.
- a. The warranty shall guarantee that the work performed, and any parts provided, function as intended.
- b. The warranty shall guarantee that the portions of the BAS that were worked on function after the work is completed.
- c. The warranty shall guarantee that the work is complete and that the intent of the Purchase Order or Contract Modification was achieved.
- d. The Contractor shall provide technical support by telephone throughout the warranty period.
- e. The Government reserves the right to make changes to the BAS during the Warranty Period. Such changes do not constitute a waiver of warranty. The Contractor shall warrant

parts and installation work regardless of any such changes made by the Government, unless the Contractor provides clear and convincing evidence that a specific problem is the result of such changes to the BAS.

- 5.2.5 If the Contractor proceeds to perform any work without Government approval, the Contractor will be performing this work “At-Risk” and the Government will not be obligated to pay for this work. Furthermore, the Contractor shall fix, repair or replace, at the Government’s sole discretion, any systems adversely impacted by unauthorized work.

6. General Deliverable Requirements

6.1 General

- 6.1.1 The Contractor shall be responsible for producing schedules and documenting work and activities performed while on site. The deliverables required by this statement of work shall be submitted to the Post Facility Manager / COR at Post and also to OBO/CFSM/FAC/PS - “BAS Support” for review and approval as well as record keeping purposes. Failure by the Contractor to provide submissions to either party will result in a delay of payment. This information will also be used by OBO to assist in making decisions concerning the funding of other work, as recommended by the Contractor.
- 6.1.2 All deliverables, unless otherwise noted, shall be uploaded to FAN.gov in accordance with the COR’s instructions. Exceptions include software installation files and mirrored or cloned disks, which are to be left with Post. FAN.gov deliverables will be uploaded to a Post folder structure as instructed by BAS Support. Files within each sub-folder shall be combined and compressed in “zip” files before uploading to reduce the file count on FAN.gov. The Contractor is responsible for obtaining and maintaining a FAN.gov account. Guidance on FAN.gov accounts can be obtained from BAS Support.
- 6.1.3 Deliverables to the Post FM shall be submitted as follows:
- 6.1.3.1 One (1) set of Deliverable disk(s) shall be submitted by the Contractor to the Post Facility Manager.
- 6.1.3.2 The Contractor shall supply proof of turnover of this disk set, signed by the Post FM, to BAS Support.

6.2 Document Creation, Classification and Handling Requirements

- 6.2.1 Each submission shall consist of the appropriate documentation as required herein.
- 6.2.2 Drawings and other documents prepared for or used for this work shall become the property of the Government. The Government reserves the right to reproduce, in part or whole, the deliverables for internal Government purposes.
- 6.2.3 Deliverables shall be prepared after each PM site visit has been completed. It is not acceptable for the Contractor to spend time at Post preparing reports and other deliverables. Information required to create deliverables shall be generated / gathered while at Post and utilized by the Contractor to create the required deliverables after the trip has been completed.
- 6.2.4 All Contractor deliverables shall be provided as electronic media. No paper deliverables are required.

6.2.4.1 Multiple deliverable items shall be provided on individual CD or DVD disks, when possible, to reduce the number of disks required to create the deliverable.

6.2.4.2 USB thumb drives or other forms of removable, re-writeable media are not allowed.

6.2.4.3 Each individual deliverable shall include a Transmittal Number for tracking purposes. The Transmittal Numbers shall be formatted **XXXXXXXXXXXX-YYY (Rev Z)**:

- a. **XXXXXXXXXXXX** represents the Contract Number which the deliverable is associated with.
- b. **YYY** represents the deliverable number. This number increases for each new deliverable provided for review and approval.
- c. **Z** is the revision number for the deliverable in question. This number will increase when a deliverable has been resubmitted, provided for review and approval more than one (1) time.
- d. Example: SAQMMA18D2948-003 (Rev 1). This would be a deliverable associated with Contract SAQMMA18D2948; 003 indicates that this is the third unique deliverable provided for review and approval; (Rev 1)

Indicates that this is the second time this deliverable has been provided for review and approval.

6.2.5 The CDs and/or DVDs on which deliverables are provided shall be labeled with computer generated labels as indicated below. CDs or DVDs which are submitted without a proper label, that have no label, or are labeled by hand will be rejected without review.

6.2.5.1 The Post location

6.2.5.2 The Contract number

6.2.5.3 The Contractor's name

6.2.5.4 The Transmittal Number associated with the deliverable

6.2.5.5 The date when the deliverable was created

6.2.5.6 The classification marking.

6.2.5.7 The name(s) of the deliverable(s) that has (have) been burned onto the disk.

6.2.5.8 When multiple deliverables are provided on a single disk, the deliverables shall be included in dedicated directories which have been named appropriately for each deliverable being submitted. A document shall be included in the root directory which provides a list of the deliverables included in each directory.

6.2.6 Electronic media documentation shall be submitted in the form of searchable PDF files. These documents shall also be submitted in their native file formats (AutoCAD, Word, Excel, Power Point, Project, etc.).

6.2.6.1 Any new documents generated using Microsoft Office products shall be submitted utilizing Microsoft Office file formats that are backwards compatible with Office 2010.

6.2.6.2 Any new drawings included in the documentation provided shall be submitted utilizing the AutoCAD file format (*.dwg files) and shall be backwards compatible with AutoCAD 2013.

6.2.6.3 Execution Schedules provided shall be submitted utilizing the Microsoft Project file format (*.mpp files) and shall be backwards compatible with Project 2010.

6.2.6.4 The quality of electronic media prints and plots will, at a minimum, be 600 dpi.

- 6.2.6.5 All new documentation shall be provided in the English language.
- 6.2.5.6 All new documents shall include a Table of Contents. The Table of Contents shall include all sections of the document and any addendums included with the document.
- 6.2.5.7 The pages in all new documents shall be numbered. The numbering in the associated Table of Contents shall be coordinated to ensure the correct page numbers are used.
- 6.2.5.8 Numeric values shall be provided in both Imperial and Metric units of measurement.
- 6.2.5.9 The files associated with each BAS Backup created shall be compressed into the standard ZIP file format. Each ZIP file will contain all of the files and directories associated with the BAS Backup created.

- 6.2.7 New drawings, if required, will be set up in accordance with OBO A&E Design Guidelines and Criteria. Drawings will be set up to plot on 11" x 17" media.
- 6.2.8 The Contractor shall be responsible for reviewing all documentation generated under the contract against the "Security Classification Guide for Design and Construction of Overseas Facilities" (SCG) to ensure appropriate classification, marking and handling. This shall include but not be limited to reports, submittals, manuals, drawings, etc.
- 6.2.9 "Classified" documents shall be generated on a "Classified" computer approved by Defense Security Service.
- 6.2.10 Documentation established to be "Classified" or "Sensitive but Unclassified" (SBU) will need to follow specific classification, storage, and delivery guidelines.
- 6.2.11 Any deliverables deemed to be "Classified" shall be provided to the Government separately from other deliverables, in a manner that meets SCG requirements.
- 6.2.12 Please note that all BAS at Post are "Unclassified" systems. The Contractor will make every effort to avoid over-classifying documents used and created for this Contract.
- 6.2.13 To avoid unintentionally creating a "Classified" document, the Contractor is instructed to avoid associating BAS and controlled / monitored equipment with CAA Restricted or CAA Core spaces at Post. Associating BAS information with these areas will create a "Classified" document in accordance with the requirements of the "Security Classification Guide for Design and Construction of Overseas Facilities" (SCG).

7. Execution Schedules

7.1 General

- 7.1.1 The Contractor shall submit to the COR and the Post Facility Manager an Execution Schedule (ES) for review. The ES will provide a reference plan of execution for the contract, forecast final PM completion, and assure coordination of the work between Post, the Contractor's staff / personnel and all other parties associated with the work.

7.2 Tasks, Milestones and Scaling

- 7.2.1 The ES shall include the following tasks and milestones:
- 7.2.1.1 Contract Award
 - 7.2.1.2 Creation and Update of Execution Schedule
 - 7.2.1.3 Submission, Review and Approval of New / Updated Execution Schedule
 - 7.2.1.4 Creation of Pre-Travel Deliverables
 - 7.2.1.5 Submission, Review and Approval of Pre-Travel Deliverables
 - 7.2.1.6 Start of each Site Visit
 - 7.2.1.7 End of each Site Visit
 - 7.2.1.8 Creation of Post-Travel Deliverables for each Site Visit
 - 7.2.1.9 Submission, Review and Approval of Post-Travel Deliverables for each Site Visit.
 - 7.2.1.10 Annual Contract Renewal
 - 7.2.1.11 Contract Completion
- 7.2.2 The schedule shall include each task, specifically linked together in a logical manner, which clearly identifies the critical path of the work.
- 7.2.3 The schedule shall be broken down to the task and activity level for all activities required by the contract. The schedule shall include all milestone activities (i.e., scheduling of Site Visits, submittal preparation start and completion, etc.).
- 7.2.4 The schedule shall include the following information for each broken out activity:
- 7.2.4.1 Activity description
 - 7.2.4.2 Activity duration in hours
 - 7.2.4.3 Early start and finish dates

- 7.2.4.4 Late start and finish dates
- 7.2.4.5 Activity duration
- 7.2.4.6 A unique activity identifier for each activity.

7.2.5 The schedule shall be scaled by weeks or as requested by the COR and shall fully disclose all activities (i.e., no roll-ups or summations).

7.3 Updates

7.3.1 The Contractor shall update the ES on a yearly basis. The updated ES shall incorporate updated schedule changes and actual progress of the work.

8. Pre-Travel Deliverables

8.1 PM Service Activity Schedule

8.1.1 A schedule that indicates which PM Service Activities will be performed at each site visit. The Contractor shall submit the PM Service Activity Schedule for approval prior to commencement of any work at Post. ~~The schedule shall cover a span of five (5) years to account for PM Service Activities that occur only once over this time frame.~~

8.1.2 Each PM Service activity described within this statement of work shall be broken into separate line items for each individual BAS installed at Post. (i.e., there will be three separate line items for activity “Check BAS Communication Network” if there are three separate standalone BAS installed at Post.)

8.1.3 For activities that are spread out over multiple site visits, each line item will indicate the equipment that will be worked on during each specific site visit.

8.1.4 For all activities, each line item will note what equipment shall be serviced during the PM site visit, the dates when all equipment were last serviced, the recommended dates for the next servicing for all equipment.

8.1.5 For each site visit during the schedule’s five (5) year timeline, the schedule shall indicate the equipment for which “Sensor, Operator and End Device Point-to-Point Checkout” and “Sensor, Operator and End Device Calibration” will be performed.

8.2 PM Service Activity Description List

8.2.1 The activity description list shall provide detailed descriptions for each of the PM Service Activities listed in the PM Service Activity Schedule. The Contractor shall submit the PM

Service Activity Description List for approval prior to commencement of any work at Post. Each description will be presented in narrative form and broken down into the three (3) parts described below:

8.2.1.1 Name of PM Service activity that is being described.

8.2.1.2 A detailed description of the PM Service activity which clearly describes the Contractor's understanding of what the PM Service activity is intended to accomplish.

8.2.1.3 A detailed description of the means and methods the Contractor will be using in order to provide the PM Services required by the activity.

9. Post-Travel Deliverables

9.1 Site-Specific PM Checklists

9.1.1 PM Checklists, modified to reflect actual field conditions, shall be submitted for approval. There shall be one Checklist for each system controlled and/or monitored by a BAS. This shall be done after the completion of the initial site visit.

9.2 PM Service Activity Schedule and PM Activity Description List

9.2.1 A revised PM Service Activity Schedule and PM Activity Description List, updated based on actual field conditions, shall be submitted for approval. This shall be done after the completion of the initial PM site visit.

9.3 Preventative Maintenance Site Visit Report

9.3.1 The Contractor shall be responsible for providing a detailed PM Report after each site visit. Each PM Report shall include, at a minimum, the following:

9.3.1.1 Executive Summary: A narrative of the PM Services performed, up to two pages long, shall provide background on the PM Services Provided, how the work went, and a brief description of major issues encountered.

9.3.1.2 PM Activities Performed: A table listing all PM Activities Performed while at Post. The table shall include the following four (4) columns:

- a. Date PM Activity was performed
- b. PM Activity that was performed
- c. Detailed description of Adjustments made, if any
- d. Date Adjustments were made

9.3.1.3 Deficiencies: A table listing all Deficiencies found while at Post. The table shall include the following six (6) columns:

- a. Date Deficiency was discovered
- b. A brief description of the Deficiency
- c. Status of Deficiency – “Open” or “Closed”
- d. This column shall include references to the unique designators associated with the Corrective Action descriptions for Deficiencies that have a status of “Closed”. A description of the Corrective Action taken shall be provided in the body text of the “Corrective Action” section in the PM Report. The unique designator shall point to where in the PM Report the description of the Corrective Action is located.
- e. Date Corrective Action was taken
- f. This column shall include references to the unique designators associated with the Proposed Solution descriptions for Deficiencies that have a status of “Open”. A description of the Proposed Solution shall be provided in the body text of the “Proposed Solution” section in the PM Report. The unique designator shall point to where in the PM Report the description of the Proposed Solution is located.

9.3.1.4 Corrective Actions: A section describing the Corrective Actions taken to resolve “Closed” issues listed in the Deficiency List. The beginning of each description shall include a unique designation which can be used as a reference designator in the Deficiency List. Use of paragraph numbers / letters is acceptable for this purpose. Corrective Action descriptions will be presented in narrative form and broken down into the three (3) parts described below.

- a. A clear and detailed description of the deficiency and the cause of the deficiency (if known).
- b. A clear and detailed description of the Corrective Action Taken.
 - 1) Indicate if the Deficiency was resolved as part of the PM effort or if a separate Purchase Order or Contract Modification was required to implement the Corrective Action. Append any Purchase Orders and/or Contract Modifications to the end of the PM Report along with the associated proposal.
 - 2) If the Corrective Action involved revisions to the associated Sequence of Operation, include the revised Sequences.
 - 3) If the programming was changed to correctly implement the existing Sequence of Operation, describe the changes that were made to the programming.
 - 4) If point or system override(s) were removed or added to the system in order to allow for proper system operation, identify the point or system override(s) that were modified and describe the reason for removing or adding the override(s).
 - 5) If the Sequences of Operation were modified in order to meet new conditions at Post, describe the changes that were made to the Sequences.
 - 6) If the BAS hardware installation was modified, clearly indicate what was changed (wiring, sensors, end devices, operators, the network, controllers, etc.)
- c. A table listing any parts that were utilized to implement the Corrective Action Taken. (If Applicable) The table shall include the following four (4) columns:

- 1) Complete part numbers specific to each part. Part numbers shall include all selection specific information required to order the desired part.
- 2) Quantity Required
- 3) Part description
- 4) Manufacturer

9.3.1.5 Proposed Solutions: A section describing the Proposed Solutions proffered to resolve “Open” issues listed in the Deficiency List. The beginning of each description shall include a unique designation which can be used as a reference designator in the Deficiency List. Use of paragraph numbers / letters is acceptable for this purpose. Proposed Solution descriptions will be presented in narrative form and broken down into the seven (7) parts described below.

- a. A clear and detailed description of the deficiency and the cause of the deficiency (if known).
- b. A clear and detailed description of the Proposed Solution.
- c. A description of any impact the work will have on Post. (If Applicable)
- d. A description of any assistance the Contractor would require from Post to implement the Proposed Solution. (If Applicable)
- e. A table listing any parts that would be needed to implement the Proposed Solution. (If Applicable) The table shall include the following five (5) columns:

- 1) Complete part numbers specific to each part. Part numbers shall include all selection specific information required to order the desired part.
- 2) Quantity Required
- 3) Part description
- 4) Manufacturer
- 5) Unit Cost

- f. A manpower estimate for how much effort would be required to implement the Proposed Solution during a future PM visit.
 - g. A Cost Estimate for the Contractor to implement the Proposed Solution during a future PM Site Visit.
-
- 1) If parts that failed or are needed to implement the Proposed Solution are available in the Post's Spare Part Inventory and the Facility Manager permits the Contractor to use the available spare parts, the Contractor shall modify the cost estimate to utilize the spare parts now and procure replacement parts to replenish the Spare Part Inventory later.
 - 2) If a Post's Spare Part Inventory does not include the appropriate parts or the Facility Manager will not allow the use of the Post's spare parts, the Contractor's cost estimate shall include procurement and shipping of the parts needed.
 - 3) If the Post chooses to procure the parts on their own, the Contractor's proposal shall include only the cost to remove parts / install new parts.

9.3.1.6 Completed Checklists: This section shall compile all of the signed PM Checklists that were filled out during the PM site visit. All checklists provided shall be complete and clearly legible. Handwritten or document scans that cannot be easily read will be rejected.

9.3.1.7 Updated PM Service Activity Schedule: A revised PM Service Activity Schedule, annotated to note what equipment was serviced during the PM site visit, the dates when all equipment were last serviced, the recommended dates for the next servicing for all equipment and any other alterations that the Contractor may make to the schedule.

9.3.1.8 Spare Part Schedule: The Contractor shall create a Spare Part Schedule listing the spare parts the Contractor recommends Post keep on site, after the initial PM Site Visit has been completed. The schedule shall list the spare parts the Contractor recommends Post keep on site. The Spare Part Schedule shall be updated during

each subsequent PM Site Visit. Separate tables shall be provided for each standalone BAS at Post. If more than one BAS product line is installed at Post, a separate Spare Parts Schedule shall be provided for each system. Each table shall include the following seven (7) columns:

- a. Complete part numbers specific to each part. Part numbers shall include all selection specific information required to order the desired part.
- b. Recommended quantity to keep in stock
- c. Actual quantity in stock at Post
- d. Part description
- e. Manufacturer
- f. Supplier, including contact information for ordering parts
- g. Part Availability: Locally Available, Commercially Available, Authorized Reseller Only, etc.

9.3.1.9 Expendable Part Replacement Schedule: The Contractor shall create an Expendable Part Replacement Schedule listing all Expendable BAS Parts installed, after the initial PM Site Visit has been completed. The Expendable Part Replacement Schedule shall be updated during each subsequent PM Site Visit. Separate tables shall be provided for each standalone BAS at Post. Each table shall include the following eight (8) columns:

- a. Complete part numbers specific to each part. Part numbers shall include all selection specific information required to order the desired part.
- b. Quantity installed
- c. Part description
- d. Manufacturer
- e. Supplier, including contact information for ordering parts
- f. Manufacturer's recommended replacement period
- g. Recommended date on which the expendable part should be replaced
- h. Part Availability: Locally Available, Commercially Available, Authorized Reseller Only, etc.

9.3.1.10 Contractor's PM Staff: A section that identifies the Contractor's staff that was involved in the preparation of deliverables and in providing BAS PM Services at Post. This shall include the following information:

- a. Full Name
- b. Company Name
- c. Job Title
- d. Role in providing BAS PM Services
- e. Work Phone Number
- f. Work Email address
- g. Work Mailing address

1.3.1.11.1 Post Key Staff: A section that identifies the Post Facility Manager and the Facility Maintenance Staff BAS Technician. This shall include the following information:

- a. Full Name
- b. Company Name (if not an employee of the Department of State)
- c. Job Title
- d. Office Symbol
- e. Work Phone Number
- f. Work Email address
- g. Work Mailing address

9.3.1.12 FM Staff PM Assistance: A section that identifies any Facility Maintenance Staff at Post that assisted the Contractor in providing PM Services. This shall include the following information:

- a. Full Name
- b. Company Name (if not an employee of the Department of State)

- c. Job Title
- d. Office Symbol
- e. Work Phone Number
- f. Work Email address
- g. Work Mailing address

9.3.1.13 Test Equipment Calibration Certificates: A section that contains Calibration Certificates for all testing instrumentation used.

9.3.1.14 Sensor, Operator and End Device Point-to-Point Checkout Schedule: A multi-year Point-to-Point checkout schedule, spanning five (5) years, shall be created after the initial site visit has been completed. This schedule shall be updated after each subsequent site visit as work is completed. A separate table shall be provided for each system monitored and/or controlled by a BAS. Records of Point-to-Point Checkouts shall be kept in such a manner that a change in BAS technicians or Contractors will not adversely impact the overall multi-year Point-to-Point Checkout Schedule. These tables shall include the following thirteen (13) columns:

- a. Point Name
- b. Point Address
- c. Part Description
- d. Part Number
- e. Name / Designation of the Associated Controller
- f. Network Address and/or IP Address of the Associated Controller
- g. Terminal Wire Connection Information (Terminal Block Designation and Terminal Numbers) at Associated Controller
- h. Terminal Wire Connection Information (Terminal Block Designation and Terminal Numbers) at Sensor, Operator or End Device
- i. Method which the Contractor used to perform the Point-to-Point Checkout
- j. Status after Point-to-Point Checkout: "Good", "Bad", "Corrected", etc.
- k. Date Last Point-to-Point Checkout was performed (Leave blank if Point-to-Point Checkout has not occurred yet.)

- l. Date of Next Scheduled Point-to-Point Checkout (This date will most likely fall outside the multi-year window of the contract.)
- m. Checkbox for each line item to indicate if Point-to-Point Checkout was or was not performed during the site visit. (A check in the checkbox will indicate that the Point-to-Point Checkout for that point occurred during the site visit.).

9.3.1.15 Sensor, Operator and End Device Calibration Schedule: A multi-year calibration schedule, spanning five (5) years, shall be created after the initial site visit has been completed. This schedule shall be updated after each subsequent site visit as work is completed. A separate table shall be provided for each system monitored and/or controlled by a BAS. Records of Sensor, Operator and End Device Calibration shall be kept in such a manner that a change in BAS technicians or Contractors will not adversely impact the overall multi-year calibration schedule. These tables shall include the following sixteen (16) columns:

- a. Point Name
- b. Point Address
- c. Part Description
- d. Part Number
- e. Checkbox to indicate if Part can or cannot be calibrated (A check in the checkbox will indicate that the Part can be calibrated.)
- f. Value before calibration
- g. Deviation from measured/known value before calibration
- h. Value after calibration
- i. Deviation from measured/known value after calibration
- j. Acceptable Deviation Range in accordance with Manufacturer's literature
- k. The procedure used by the Contractor to perform the calibration
- l. A description of how the actual part was calibrated (Span and zero screws, built in calibration button, etc.)
- m. Status after calibration: "Good", "Questionable", "Failed"
- n. Date the part was last calibrated. (Leave blank if calibration has not occurred yet.)

- o. Date of Next Scheduled Calibration (This date will most likely fall outside the multi-year window of the contract.)
- p. Checkbox for each line item to indicate if calibration was or was not performed during the site visit. (A check in the checkbox will indicate that the point was calibrated during the site visit.).

9.3.1.16 Consolidated Proposed Solutions Cost Estimate: A section that provides an overall combined cost estimate for the Contractor to provide repairs described in the Proposed Solutions for all of the “Open” Deficiencies described within the PM Report. This cost estimate shall be broken down into Parts, Shipping to Post, Labor and Travel. This Proposed Solutions Cost Estimate shall also be presented to BAS Support as a separate, formal Proposal document, that can then be used by BAS Support to request funding for these solutions.

9.3.1.17 Spare Part Procurement Cost Estimate: A section that provides an overall cost estimate to provide the Spare Parts required by Post. This estimate shall include shipping costs to Post.

9.3.1.18 Expendable Part Procurement / Installation Cost Estimate: A section that provides an overall cost estimate to provide and replace the scheduled Expendable Parts required by Post. This estimate shall include shipping costs to Post.

- a. When the Expendable Part Replacement Schedule indicates that there are expendable parts due for replacement, the contractor shall provide a proposal to the Facility Manager which lists the expiring parts along with the associated costs to remove the expired parts and to procure and install the new parts. If the proposal is accepted, the expired parts shall be replaced at the next PM visit to Post.
- b. If the Post chooses to procure the parts on their own, the contractor’s proposal shall include only the costs to remove the expired parts and install the new parts.

9.4 Appendices

9.4.1 Appendix A - BAS Backup Retention: An appendix to the report which contains the BAS backups collected for each BAS installed at Post. The BAS Backups shall contain all files necessary to recreate the database and graphics upon the event of a controller or

workstation failure. It shall NOT contain any software installation files that are readily available on installation disks. This appendix shall also include the screenshots collected of each BAS OWS Graphics screen.

- 9.4.2 Appendix B – User Account Retention: An appendix to the report which documents the user account information collected for each BAS installed at Post. NOTE: The Report shall contain confirmation that this appendix was created and left with Post. Due to security policies, it shall NOT be transmitted electronically to BAS Support. Policy is still being developed around the transmittal and storage of this information, and any updates will be communicated to the Contractor upon their release.
- 9.4.3 Appendix C – Updated BAS As-Built and BAS Operation & Maintenance Manual Documents: An appendix to the report which contains the updated BAS As-Built and Operation & Maintenance documents created by, or collected at Post and updated by, the Contractor, for each control system installed at Post.
- 9.4.4 Appendix D – BAS Evaluation: An appendix to the report that documents the condition of, and makes recommendations with respect to, each BAS installed at Post.
- 9.4.5 Appendix E – BAS Inventory Retention: An appendix to the report that documents the inventory information collected for each BAS installed at Post.
- 9.4.6 Appendix F – Supervisory Controller Photos: An appendix to the report that contains photographs, where permissible, of each Supervisory Controller Enclosure installed at Post. Photographs should include interior and exterior shots, including nearby wall space, and shall be labeled with the Controller name.
- 9.4.7 Appendix G – Facility Manager Sign-Off: An appendix to the report that contains a scan of the BAS PM Site Visit Summary document, signed and dated by the Post Facility Manager, or a staff member designated by the FM.

10. Deliverable Submission Schedule

10.1 Execution Schedules

- 10.1.1 Initial Execution Schedule (ES) must be submitted within fifteen (15) business days of the Notice to Proceed. Subsequently, the ES shall be submitted annually throughout the duration of the contract. The Contracting Officer's Representative will respond within fifteen (15) business days of receipt of each ES regarding further action or revisions, if any are required.

10.2 Pre-Travel Deliverables

10.2.1 The items described under *Section 8. "Pre-Travel Deliverables"* must be submitted within twenty (20) business days of the Notice to Proceed. Subsequently, the Pre-Travel Deliverables shall be submitted a minimum of 40 days before each PM Site Visit. For each of these submissions, the COR will respond within fifteen (15) business days of receipt regarding additional actions or revisions, if any are required.

10.3 Post-Travel Deliverables

10.3.1 The items described under *Section 9. "Post-Travel Deliverables"* must be submitted within twenty (20) business days following completion of each PM Site Visit. The COR will respond within fifteen (15) business days of receipt regarding additional actions or revisions, if any are required.

11. Retention of Deliverables and Other Data by the Contractor

11.1 General

- 11.1.1 All documentation, deliverables, backups, user account information and other data gathered and/or created by the Contractor as part of this contract shall be retained by the Contractor for a period of fifteen (15) years after the completion of the Contract. This data shall be stored as electronic media.
- 11.1.2 This information shall be securely stored by the Contractor at a facility that maintains an appropriate Facility Level Clearance for the type and classification of the information being stored.
- 11.1.3 The retention of this data by the Contractor shall act as an external backup for OBO and Post to reference back to when this information cannot be located within the Department of State.
- 11.1.4 The Contractor shall make this data available to OBO and/or Post upon request of the Government.

12. Contractor's Responsibility

12.1 General

- 12.1.1 Performance will be accomplished in strict conformance with the contract clauses, provisions, and conditions contained herein.
- 12.1.2 The Contractor shall be responsible for all methods, techniques, and procedures used and for coordinating the work following the proposed schedule. Portions of the facility not directly affected by work activities shall remain functional.
- 12.1.3 The Contractor shall be responsible to the Government for acts and omissions of the Contractor's employees, subcontractors and their employees, and other persons performing any of the work under contract with the Contractor.
- 12.1.4 If the Contractor performs any work contrary to U.S. laws, ordinances, or regulations, the Contractor shall assume full responsibility and shall bear all costs attributable thereto.
- 12.1.5 The Contractor shall save, defend, keep harmless and indemnify the U.S. Department of State, officers, departments, agencies, agents, and employees from and against any and all claims, losses, damages, injuries, fines, penalties, costs (e.g., court costs and attorney's fees), charges, liability of exposure, however caused, on account of any copyright, patented or un-patented invention, process or article manufactured or used in the performance of this Contract, including its use by the Department of State. If the Contractor uses a design, device, or materials covered by license, patent, or copyright, it is mutually agreed and understood that the Contract price, without exception, includes all royalties or costs arising from the use of such design, device, or materials in any way involved with the work.
- 12.1.6 The Contractor's work schedule shall be as directed by the Post Facility Manager. When not indicated otherwise work shall occur during one 8-hour shift per day, 5 days per week. Weekends and holidays shall be considered workdays provided access to the worksite is available, these specific workdays are needed to complete the work, and approval to work these specific days has been granted by the Post's Facility Manager. The proposed work schedule is subject to Post's Facility Manager (FM), General Services Officer (GSO) and/or the Management Officer's approval. The work schedule shall be determined prior to the scheduling of site visit activities at Post.

12.2 Codes and Regulations

- 12.2.1 U.S. Government codes and regulations, the applicable laws, codes, and standards of foreign countries, and industry standards apply and are incorporated herein by reference and made part of the contract.
- 12.2.2 Contractor shall adhere to work practices and procedures set forth in applicable codes, regulations, and standards, including obtaining permits, licenses, inspections, releases and similar documentation, as well as payments, statements and similar requirements associated with codes, regulations, and standards.
- 12.2.3 Except to the extent that more explicit or more stringent requirements are written directly into the contract, all applicable U.S. EPA and U.S. OSHA codes, regulations, and standards have the same force and effect (and are made a part of the contract by reference) as if copied directly into the contract, or as if published copies are bound herewith.
- 12.2.4 The Contractor shall assume full responsibility and liability for compliance with all applicable U.S. EPA and U.S. OSHA regulations and shall hold the U.S. Government and its representatives harmless for failure to comply with any applicable work, hauling, disposal, safety, health or other regulations on the part of the Contractor, their employees, or subcontractors.

12.3 Authorization to Visit Site (applicable if works at CAA space)

- 12.3.1 The Contractor is responsible for obtaining proper passports, visas, emergency medical evacuation insurance, Defense Base Act insurance and immunizations.
- 12.3.2 A "Notice to Proceed" cannot be issued for a site visit until the Contracting Officer has received verification / proof that the Contractor is covered by Defense Base Act (DBA) insurance for the site visit. No authorization to travel will be given if this information is not provided.
- 12.3.3 The following describes the minimum clearance requirements that must be met for BAS work performed at Post as part of this contract.

- 12.3.3.1 Contractor personnel performing Contract requirements in General Work Areas (GWA) and Public Access Areas (PAA) do not require a clearance.

- 12.3.3.2 information for Un-cleared personnel must be submitted to the Post Resident Security Officer (RSO) for screening and approval prior to being granted access to Post.
- 12.3.3.3 Contractor personnel performing Contract requirements in CAA Restricted spaces shall be U.S. Citizens and have a minimum-security clearance at the SECRET level, verified by DS, to allow for unescorted access. (Required by 12 FAH-6 H-631.5-2) An Interim SECRET clearance will not be accepted for CAA Restricted unescorted access.
- 12.3.3.4 Contractor personnel performing Contract requirements in CAA Core spaces shall be U.S. Citizens and have a minimum-security clearance at the TOP SECRET level, verified by DS, to allow for limited escorted access. (Required by 12 FAH-6 H-631.5-2) An Interim TOP SECRET clearance will not be accepted for CAA Core access.
- 12.3.3.5 Clearances shall be certified to DS/IS/IND via Visit Authorization Requests (VAR).

12.4 Contractor and Personnel Qualifications

- 12.4.1 The Contractor shall employ a competent On-Site Supervisor, satisfactory to the Government, to work at all times with the authority to act for the Contractor.
- 12.4.2 The Contractor shall utilize competent BAS engineers, technicians, programmers, etc., satisfactory to the Government, to perform the work and services required by the contract. BAS Engineers, technicians, programmers, etc. shall have a minimum of five (5) years of experience performing the type of work described within the Statement of Work.
 - 12.4.2.1 The personnel engaged in providing PM Services for the DOS shall be trained and certified by the BAS Manufacturer on the Manufacturer's Product Line(s) being serviced by that employee. Certifications shall be current and maintained throughout the life of the contract.
 - 12.4.2.2 Biographical data (a resume), a list of recently completed projects demonstrating five (5) years of BAS experience and proof of training and certification from the BAS hardware and software manufacturer shall be submitted for personnel providing BAS PM Services under this statement of work.

The manufacturer shall certify that installer has been trained on the proper installation of the manufacturer's BAS and is an approved installer.

12.4.2.3 Personnel not trained and certified by the manufacturer of a BAS will not be permitted to work on that BAS. Exceptions to this requirement will be made on a case-by-case basis for older BAS that are no longer produced or supported by the Manufacturer or for which the Manufacturer no longer exists.

12.4.2.4 The personnel who are proposed by the Contractor to perform BAS work on site in the CAA Restricted spaces at Post shall have appropriate security clearances as required by *Section 12.3*, and the associated sub-sections, in this Statement of work.

12.4.2.5 The personnel who are proposed by the Contractor to perform BAS work on site in the CAA Core spaces at Post shall have appropriate security clearances as required by *Section 12.3*, and the associated sub-sections, in this Statement of work.

12.4.3 The Contractor shall not change the proposed personnel without permission from the COR. The Contractor shall submit such a request in writing with justification for change to the COR.

12.4.4 The Contractor shall provide a means of transportation to bring personnel, supplies, tools and equipment to and from Post. The Contractor shall be responsible for providing this service. The costs shall be included in the Contractor's proposal.

12.4.5 The Contractor shall be responsible for providing all tools required to perform the work at Post. If the Contractor requires Post to provide tools or equipment, written permission shall be required in advance of the trip.

12.4.6 The Contractor shall at all times enforce strict discipline and good order among all persons utilized to work and shall not utilize any unfit persons not skilled in the tasks assigned to them.

12.5 Materials and Equipment

12.5.1 The Contractor shall obtain the approval of a Procurement Plan and/or a Shipping Plan from the Post Facility Manager prior to undertaking either activity.

12.5.2 All parts, materials, components, equipment, systems, and products furnished by the Contractor shall be new, unused and shall not be remanufactured in any manner. Used or remanufactured parts or components are not allowed nor are they acceptable for use. All

replacement or warranty parts shall be new and equal to or better than manufacturer recommended replacements. Exception: BAS Controllers may be provided that are refurbished or repaired if they are no longer produced by the BAS Manufacturer and the BAS Manufacturer no longer has any new stock for sale.

12.5.3 The Contractor shall ship all materials and equipment in accordance with current Government regulations governing carrier usage (contact Post General Service Officer (GSO) for specific entry guidance).

12.5.4 The Contractor shall deliver all materials and supplies to the site in the original packaging bearing the name of the manufacturer and details for proper storage and usage. The Contractor shall pack all project materials and equipment to protect them from damage that can be caused by shipment, transit and rough handling. Damaged or deteriorated materials and supplies must be promptly removed from the premises and new materials and supplies sent to Post to replace the damaged or deteriorated materials and supplies.

12.5.5 The Contractor shall complete a line-item inventory for materials received and validate that received materials are correct.

12.5.5.1 The Contractor shall furnish to the Post Facility Manager a line-item list of material ordered (to include quantities and cost) and a line item receiving report of material received by the Contractor (to include quantities and cost) prior to shipment of any material to Post.

12.5.5.2 The Contractor shall furnish to the Post Facility Manager a line-by-line packing list (to include quantities and cost) of materials being shipped to Post by the Contractor.

12.5.6 The Contractor shall submit to the Post Facility Manager MSDS sheets for all HAZMAT. The Contractor shall pack HAZMAT per DOT requirements and provide line-item inventory and packing list(s) for all packages containing HAZMAT.

12.5.7 Upon arrival at Post, storage of all materials will be subject to security restrictions and inspections in accordance with Diplomatic Security (DS) mandated requirements.

12.5.8 The Contractor shall securely procure all materials destined for use in the CAA Restricted and CAA Core Spaces. Personnel involved in the procurement process of CAA Restricted and CAA Core materials, specifically all coordination with potential vendors, choice of vendor, issuance of orders and coordination of deliveries to the Contractor's Consolidated

Receiving Point (CRP), if applicable, must possess SECRET clearances. Secure procurement may not be accomplished by un-cleared individuals. Secure procurement shall be accomplished by not disclosing the Post name, location or project for which the items are ordered to any un-cleared vendor. Vendors will not be informed of the ultimate destination or that the materials are destined for installation in CAA Restricted or CAA Core spaces.

12.5.8.1 All materials and equipment destined for CAA Restricted and CAA Core spaces shall be shipped using secure transport modes.

12.5.8.2 The Contractor shall establish a Consolidated Receiving Point (CRP), or utilize an existing DS approved CRP, to receive, stage, store and ship all secure materials.

12.5.8.3 Shipping plans for secure materials, those which will be installed in CAA Restricted and CAA Core spaces, shall identify the Consolidated Receiving Point (CRP) to be utilized by the Contractor.

12.6 Contractor Use of Premises

12.6.1 The Contractor shall confine operations to the areas permitted under the Contract. Portions of the site beyond areas in which work is indicated are not to be disturbed. All persons shall report directly to the Facility Manager (FM) or General Services Officer (GSO) upon arrival and participate in a security briefing provided by the Regional Security Officer (RSO). The Contractor's personnel shall conform to Post's security rules and regulations affecting the work while engaged in the effort and regarding personal behavior. No cameras, computers, phones or other electronic equipment will be permitted at Post without prior approval by the Regional Security Officer (RSO). The RSO will identify any other site restrictions to the Contractor.

12.6.2 The Contractor shall at all times keep the site free from accumulation of waste materials or rubbish generated by the work. At the completion of the work, the Contractor shall remove all such waste materials and rubbish as well as tools, equipment, and surplus materials.

12.6.3 The Contractor must adequately protect and work around equipment or other fixed items that cannot be moved out of the work area.

12.6.4 The Contractor shall keep existing driveways and entrances serving the premises clear and available to Post personnel and the public at all times, and not unreasonably encumber the

site with materials or equipment. Stockpiling of equipment and materials shall be confined in a construction trailer or other area approved by the Post Facility Manager. All public areas such as hallways, stairs, elevator lobbies, and toilets are to be kept free from accumulation of waste, rubbish and debris.

- 12.6.5 The Contractor shall take all precautions necessary to protect the building and its occupants during work at Post, and repair damages caused during execution of the work.

13. Delivery, Mail and Courier Addresses

13.1 Classified Packages & Mail

- 13.1.1 Classified packages / mail shall NOT be sent via the U.S. Postal Service.

13.1.2 Delivery by Courier: Contractors and subcontractors authorized to send Classified packages to the Department shall provide delivery of packages, by appropriately Cleared Contractor, via approved hand-carry methods in accordance with NISPOM 5-410 and 5-411.

- 13.1.2.1 All Classified hand-carry deliveries from the Contractor to DOS shall be made between the hours 8:00 AM and 3:00 PM during business days. The contractor shall advise the intended recipient of the materials and estimated time of arrival a minimum of 72 hours prior to dispatching the package by courier.

- 13.1.2.2 Address for Classified Packages / Mail to be sent by Courier to Post:

FACILITY MANAGER
6230 HYDERABAD PL
WASHINGTON DC 20521-6230

- 13.1.2.3 .Address for Classified Packages / Mail sent by Courier to OBO/CFSM/FAC/PS "BAS Support":

OBO/CFSM/FAC/PS BAS Support
1701 NORTH FORT MYER DRIVE
SA-6, FLOOR 8
ARLINGTON, VA 22209

ALTERNATE POINTS OF CONTACT:
CHRIS TJIATTAS (571-345-0301)
ASENATH HILL (703-812-2223)

13.1.3 Delivery by Commercial Carrier: Alternatively, GSA Schedule 48, Commercial Delivery Carriers, may be used in accordance with NISPOM 5-403-e, and ISL 2006-02, para 18.

13.1.3.1 Currently, the carriers on that list include:

- a. DHL (Astar Air Cargo) - Same Day Service
- b. FedEx – Same Day Service, First Overnight, Priority Overnight or Standard Overnight
- c. Airnet Systems – Mission Critical or Same Day Service
- d. United Parcel Service – UPS Next Day Air Early, Next Day Air, or Next Day Air Saver
- e. UPS Supply Chain Solutions – Constant Surveillance Service

13.1.3.2 Classified Packages / Mail to be delivered via authorized Commercial Delivery Carrier listed above should be addressed as follows:

a. Address for Classified Packages / Mail sent by Commercial Carrier to Post:

FACILITY MANAGER
6230 HYDERABAD PL
WASHINGTON DC 20521-6230

b. Address for Classified Packages / Mail sent by Commercial Carrier to OBO/CFSM/FAC/PS “BAS Support”:

OBO/CFSM/FAC/PS BAS Support
1701 NORTH FORT MYER DRIVE
SA-6, FLOOR 8
ARLINGTON, VA 22209

ALTERNATE POINTS OF CONTACT:
CHRIS TJIATTAS (571-345-0301)
ASENATH HILL (703-812-2223)

13.2 Unclassified Packages & Mail

13.2.1 Unclassified packages / mail sent via U.S. Mail, Registered or Certified Mail, Courier Service and U.S. Postal Service Overnight Express shall be addressed as follows.

13.2.1.1 NOTE: Classified information cannot be sent via the methods described above.

13.2.1.2 Address for Unclassified Packages sent to Post:

FACILITY MANAGER
6230 HYDERABAD PL
WASHINGTON DC 20521-6230

13.2.1.3 Address for Unclassified Mail sent to Post:

FACILITY MANAGER
6230 HYDERABAD PL
WASHINGTON DC 20521-6230

13.2.1.4 Address for Unclassified Packages sent to OBO/CFSM/FAC/PS "BAS Support":

OBO/CSFM/FAC/PS - BAS SUPPORT
U.S. DEPARTMENT OF STATE
1701 NORTH FORT MYER DRIVE
SA-6, FLOOR 8

ARLINGTON, VA 22209

ALTERNATE POINTS OF CONTACT:

CHRIS TJIATTAS (571-345-0301)

ASENATH HILL (703-812-2223)

13.2.1.5 Address for Unclassified Mail sent to OBO/CSFM/FAC/PS "BAS Support":

OBO/CSFM/FAC/PS - BAS SUPPORT

U.S. DEPARTMENT OF STATE

SA-6, FLOOR 8

WASHINGTON, DC 20522-0608

14. Government's Responsibility

14.1 General

14.1.1 The Government will provide access to all identified areas for work.

14.1.2 The Government will provide to the Contractor the name and phone number of at least one person at Post with authority who can be contacted 24 hours a day.

14.1.3 Any escort responsibilities shall be arranged and provided by the Post Facility Manager at no expense to the Contractor.

Attachment A: Additional Security Requirements for BAS PMSC in Secure Areas

1. General

1.1. This Purchase Order includes security provisions that are contained in the attached DD Form 254, Contract Security Classification Specification, issued by the Bureau of Diplomatic Security, DS/IS/IND. Contractor must maintain a TOP SECRET Facility Clearance issued by Defense Counterintelligence and Security Agency (DCSA) for period of performance.

1.2. Public Release of Information

There shall be no press release of information or photographs, to include on company websites, concerning any aspect of the design, construction, or other services relating to this contract, or other documents resulting there from, without the written prior approval of the Contracting Officer. The contractor shall include the substance of this provision in all subcontracts hereunder.

2. Personnel Requirements

2.1. Personnel Clearances

Contractor personnel requiring unescorted access to CAA spaces at overseas posts, or access to classified information domestically or overseas, shall possess SECRET personnel security clearances issued by DCSA prior to contract performance.

2.2. Visit Authorization Requests

Visit Authorization Requests (VARs) for all cleared personnel performing on this task at DOS locations, domestically and overseas, are to be sent via e-mail to DSINDOBOVARs@state.gov (with the DS/IS/IND POC copied). A VAR is valid for 12 months; an updated VAR is required 30 days prior to the current VAR expiring.

2.3. Country Clearance for Travel to Post/Site

The Contractor must submit to the COR a Country Clearance Request (CCR) for all Contractor and all subcontractor employees visiting the site short term (less than one month) or deploying to the site long-term (in excess of one month). CCRs shall be submitted for both cleared and uncleared personnel. The Contractor shall submit

CCRs in the format required by the COR. Submission of specified form will result in official notification to the Regional Security Officer (RSO) of contractor personnel arriving at Post, dates of visit or duration of stay, purpose of visit or employee's position with Contractor, security clearance level, and passport or other identifying information. CCRs shall be submitted to COR and the VARs to DS/IS/IND at least 14 business days prior to site arrival date. **Admission to Post by the RSO and appropriate badging for access are dependent upon receipt of Country Clearance Requests and VARs prior to arrival.**

2.4. Standards of Conduct

Contractor personnel assigned to the contract shall observe appropriate standards of conduct and other appropriate Departmental regulations, as well as any special standards of conduct promulgated by the local embassy/post to govern U.S. Government personnel. Non-adherence to the provisions of the above may subject Contractor personnel to removal at the Contractor's expense.

2.5. Removal of Individual Contractor Employees for Cause

A determination to remove a Contractor employee from Post, or from contract performance at a domestic facility, due to misconduct or unsuitability may involve, but is not limited to, the following types of misconduct or delinquency that may be documented by the Regional Security Officer or DS/IS/IND:

- a. Notoriously disgraceful conduct, to include the frequenting of prostitutes, engaging in public or promiscuous sexual relations, spousal abuse, neglect or abuse of children, manufacturing or distributing pornography, entering into debts the employee could not pay, or making use of one's position or immunity to profit or to provide favor to another or to create the impression of gaining or giving an improper favor.
- b. Failure to report notoriously disgraceful conduct and/or non-compliance of other employees (DoS, Contractor or foreign national) in accordance with existing Post and Department of State policies and regulations.
- c. Neglect of duty, unsatisfactory performance, unreasonable delays or failure to carry out assigned tasks, conducting personal affairs during official time, refusing to render assistance/cooperate in upholding the integrity of the objectives of this contract.

- d. Falsification or unlawful concealment, removal, mutilation or destruction of any document or record, or concealment of material facts by willful omissions from documents or records. Improper use of credentials, badges or official papers.
- e. Disorderly conduct, use of abusive or offensive language, quarreling, intimidation by words or actions, or fighting. Participation in disruptive activities that interfere with the normal efficient operations of the worksite.
- f. Theft, vandalism, immoral conduct, or any other criminal action under U.S. or host country law.
- g. Selling, consuming or being under the influence of drugs, or other illegal substances that produce similar effects.
- h. Abuse of alcohol.
- i. Any evidence that would indicate that the individual is guilty of security violations including black market dealings, currency manipulation, violations of the post contact policy regarding criteria country nationals, espionage or treason.
- j. Noncompliance with post security and reporting policies.

3. Briefing and Reporting Requirements

3.1. Security Briefings

All U.S. citizens will be required to attend Contractor-provided initial, pre-deployment, and continuing security awareness briefings regarding policies and procedures for the protection of classified, SBU and unclassified information, and the contractual security requirements contained in this Attachment to the DD Form 254. Contractor shall maintain a copy of signed briefing acknowledgements for each employee performing on the contract

Upon arrival at an overseas Post/Site, all American personnel will be required to attend initial and subsequent periodic security briefings by the RSO, or designee. All personnel must attend a debriefing by the RSO, or designee. Additional debriefing may be requested by Diplomatic Security, either at post/site prior to departure and/or at the Contractor's location.

3.2. Personal (Unofficial) Travel Outside of the Project Country

Cleared contractor personnel must report all unofficial travel to the RSO one week prior to departure. RSO will arrange appropriate travel briefing/debriefing through

the RSO when the itinerary includes transit through or visit to a Prohibited Countries List country. Domestically, contractors should report unofficial travel which includes transit through or visit to a Prohibited Countries List country to DS/IS/IND.

3.3. Suspicious Contact Reports (SCRs)

Any contact with host or third country nationals that seems suspicious (such as undue curiosity as to the purpose of presence in country, requests for information regarding the project or project personnel), or attempts to establish suspicious recurring contact beyond routine professional or personal services, shall be reported immediately to the RSO. Reporting of suspicious contacts requires filing a DS-1887 form, which can be obtained from the RSO. When completed, the form should be returned to the RSO for any necessary investigative action and for submission to Diplomatic Security's Counterintelligence Division (DS/CI). Additionally, the company FSO shall submit a Suspicious Contact Report to the DCSA Industrial Security Representative (in accordance with the NIPSOM) and DS/IS/IND.

3.4. Reporting of Suspicious Incidents Occurring at Off-site Locations or During Travel to/from the Project Site

Avoid discussing project and post activities while not on the site, to include in hotel rooms, restaurants and all other public places. Report any suspicious or actual incidents, any contact with the local authorities, or undue attention or surveillance of project personnel or the project site.

3.5. Foreign Contact Reporting

All contractors at the project site must adhere to the foreign contact reporting requirements specific to each project site, as briefed by the RSO, which may include all unofficial contact with nationals from specific HUMINT threat countries, the reporting of close and continuing social contact with foreign nationals, cohabitation with foreign nationals, and non-project related personal business and/or financial relationships with any foreign nationals. Reporting of foreign contacts requires filing a DS-1887 form, which can be obtained from the RSO. When completed, the form should be returned to the RSO for any necessary investigative action and for submission to Diplomatic Security's Counterintelligence Division (DS/CI). If investigative action results in information of which the contractor should be aware, the reporting contractor will be briefed by the RSO.

3.6. Reporting Marriage, Intent to Marry, Cohabitation or Other Continuing Bonds of Affection with Foreign Nationals

Cleared contractor personnel working at DoS locations must report marriage, impending marriage, cohabitation and other continuing bonds of affection with foreign nationals to the RSO and DS/IS/IND, in accordance with 12 FAM 270.

3.7. Reporting Adverse Financial Situation and Certain Arrests

Cleared contractor personnel working on DoS contracts must report to DS/IS/IND, through their Facility Security Officer, wage garnishments, credit judgments, repossessions, tax liens, bankruptcies, and/or intentions to file for bankruptcy. Cleared contractors must also report adverse involvement with law enforcement agencies to include: Arrests, other than minor traffic violations, for which a fine or forfeiture of \$150 or more was imposed; or arrests for “driving under the influence” or “driving while intoxicated.” Arrests must be reported in a timely fashion (i.e., within 72 hours). Reporting must not be delayed pending the conclusion of any judicial action. Contractors arrested or detained overseas for reasons listed above, or for any reason, must report to RSO and DS/IS/IND.

3.8. Dual Citizenship

Cleared contractors contemplating applying for citizenship with a foreign country must report this fact to their Contracting Officer’s Representative (COR) and DS/IS/IND when any act is initiated in furtherance of obtaining foreign citizenship.

4. Subcontracting Requirements

4.1. DD Forms 254 for Subcontractors

The prime Contractor must request a DD Form 254 for all cleared subcontractors performing on this contract. Requests for DD Forms 254 must be forwarded via e-mail to DS_IND_OBOTeam@state.gov, prior to Subcontractor (or prospective subcontractor) access to any classified information or deployment to the site. DD Forms 254 issued by DS/IS/IND will be forwarded to the prime contractor for distribution to subcontractors. Contractors are not authorized to issue their own subcontractor DD Forms 254.

5. Handling/Marking Requirements - Classified & Sensitive But Unclassified (SBU)

5.1. Security Classification Guide

All documents, such as blueprints, drawings, sketches, notes, surveys, reports, photographs, exposed film, negatives, specifications, scopes of work, lists of Government Furnished Equipment and any other material received or generated in conjunction with this task, shall be classified, marked and handled in accordance with the Security Classification Guide (SCG) for Design and Construction of Overseas Facilities dated July 2018, which identifies the specific types of information associated with diplomatic construction projects, and the level of classification for such information.

5.2. Protection of Classified and SBU Information

The Contractor and all Subcontractors must comply with all Department of State (DOS) and Department of Defense (DOD) requirements relating to the protection of classified and Sensitive But Unclassified (SBU) information and cooperate fully in all security matters that may arise relating to this contract.

The loss, compromise, or suspected compromise or loss of any classified information (documents, notes, drawings, sketches, surveys, reports, exposed film, negatives, or photographs) or ANY information which may adversely affect the security interests of the United States, must be immediately brought to the attention of the Contracting Officer, the DoS COR listed on the reciprocal DD 254 and DS/IS/IND, point of contact listed at the bottom of Item 13 of the reciprocal DD Form 254.

5.3. Disposition and Retention of Task/Project Information

All classified and SBU material, including copies and reproductions and classified information stored on approved IS (Information Systems) and classified or SBU electronic media, received or generated in the performance of this task, shall be returned to the CO upon completion of the project unless the material has been destroyed or retention of the material is authorized in accordance with the National Industrial Security Program Operating Manual (NISPOM). Retention authority for classified material can be requested from DS/IS/IND, which shall coordinate an approval letter with the CO. Classified and SBU material shall be returned or

destroyed within 120 days after final delivery of project drawings and specifications and any other services; or 120 days after completion or termination of the project.

5.4. Project Generated Information at Contractor's Facility – Disposal/Destruction Plan

The Contractor FSO shall develop a waste paper disposal/destruction plan for all task related paper documents and drawings generated at their facility. Waste paper includes any DoS, OBO, contract or project documentation related to contract personnel matters, working papers, contract deliverables, submittals, correspondence, schedules, warranty and equipment manuals, any drawings regardless of sensitivity and all other task related paper. All paper produced in Contractor and subcontractors' offices relating to this contract shall be collected separately from refuse, garbage and material, and disposed of in accordance with the plan. Contractor shall provide appropriate means of disposal for both Sensitive But Unclassified and classified information. Sensitive But Unclassified information must be destroyed by crosscut shredder (residue must be 1/32 inch width by ½ inch length or smaller), burned beyond reconstruction, or disintegrated, just as classified information is required to be destroyed. Task related waste paper may not be put into commercial trash containers for removal.

5.5. Project Related Classified Working Papers, As-Builts and other Classified Generated at Post

Contractors are not authorized to hand-carry classified material overseas. Classified information required for use at Post will be provided by the OBO COR. Any classified information to be generated electronically at Post must be generated in DoS secure spaces on secure computers, coordinated with RSO. Project related classified material generated while at the Post must be delivered to the RSO for transmission to OBO by classified Diplomatic Pouch or authorized DoS courier. Secure fax or DoS Classified LAN (CLAN) can be utilized when coordinated with the COR. All classified materials given to the RSO for transmission must be appropriately marked with appropriate classification markings (unclassified, SBU, SBU/NOFORN, Confidential or Secret), government warnings against reproduction and distribution and bear the proper name of the site/project. Unmarked submittals shall be returned to the prime for classification and marking prior to transmission. Upon delivery of the classified material to OBO, the OBO COR will arrange for the return of the classified material to the contractor's cleared facility via appropriate means.

All project related working papers and drawings to be removed from the Post shall be reviewed by RSO or designated Contractor document security manager one (1) day prior to departure, to ensure that classified material has not been generated and is not hand-carried back to Contractor facility.

Only SBU and unclassified project documentation may be hand-carried back to contractor facility for storage/disposal. Contractor shall maintain positive, personal control over documentation at all times.

5.6. Photographs

Photographs of any diplomatic overseas building or facility must be authorized in advance by the DoS Regional Security Officer (RSO), or DoS COR, who will establish any controls, limits, and/or restrictions as necessary. Exposed film depicting any Controlled Access Area and/or sensitive equipment must be developed in a U.S.-controlled environment. The contractor shall submit all CAA photographs taken by digital cameras and stored on electronic media to the RSO or COR for review. Written approval for removal from the site must be obtained by the Government reviewer. Any photographs or storage media (memory cards) determined to be classified shall be turned over to the RSO to forward via classified Diplomatic Pouch. No further dissemination, publication, duplication, or other use beyond that which was requested and approved is authorized without specific, advance approval from DS. DS reserves the right to demand retention of all copies of said photographs and/or negatives, following fulfillment of the previously authorized usage.

6. Transmission Requirements for SBU

6.1. Transmission of Sensitive But Unclassified (SBU)

SBU information via the Internet is prohibited, in accordance with the Security Classification Guide (SCG) for Design and Construction of Facilities Overseas, dated July 2018. SBU information can be transmitted via ProjNet, mail, GSA Schedule 48 commercial carriers or fax, as outlined in the SCG, or hand-carried by authorized contractor personnel. When it is deemed necessary to take personal or contractor-owned laptops, Personal Digital Assistants (PDAs), smart phones (such as BlackBerrys), cell phones, digital cameras or any other electronic processing media outside a cleared facility, or overseas, to process or store any DoS project information (on or off the site), the following guidelines must be adhered to:

- a. The device must have its hard drive encrypted using any product on the IT CCB list, or any NIST approved product. (NIST approved products can be found at <http://csrc.nist.gov/groups/STM/cmvp/validation.html>)
- b. An overwrite utility software must be used to remove all previous data in the following manner: A first overwrite pass using the number '1'; A second overwrite pass using the number '0'; and a third overwrite pass using ANY character.
- c. Transmission/storage of classified information on laptops, PDAs, smart phones or digital cameras is not authorized.
- d. Electronic media which contains DoS project information MUST be hand-carried at all times, both domestically and overseas. This equipment shall NOT be checked with luggage. It must remain in the carrier's possession at all times. Any loss or compromise of electronic media containing project information must be reported to DS/IS/IND immediately.

6.2. Separate Packaging of Electronic Media and Hardcopy Material

The Contractor and any associated subcontractors will package all paper documents and drawings separately from electronic media, regardless of its classification. Specifically, electronic media (such as CDs) will be transported in electronic media packages that contain no other hard copies of any kind, beyond that of transfer/receipt documentation. Paper drawings and documents will be packaged separately.

6.3. Double-Wrapping and Addressing of Packages

For all shipping methods, the prime contractor and any associated subcontractors will ensure that all project documentation, regardless of classification, is double-wrapped with both layers addressed properly and labeled with the sender's address. Document tracking receipts should be packaged inside the inner wrapping with the materials the receipt describes. No indication of the classification or sensitivity should appear on the outer wrapper. Unclassified and SBU packages addressed to

overseas facilities or sites may not have the words “blueprints” or “drawings” displayed on the outer wrapper.

6.4. Packaging Heavy Materials in Appropriate Containers

In applying the above double-wrapping and addressing procedures, items sent via US mail or commercial carrier weighing more than one (1) pound shall be double wrapped and then the package shall be enclosed within an appropriately sized double-walled box or, for rolled drawings, a manufactured mailing tube. Unclassified and SBU packages addressed to overseas facilities or sites may not have the words “blueprints” or “drawings” displayed on the outer wrapper.