

US Army Corps
of Engineers ®
New Orleans District

IFB NO. W912P825BA007

Mississippi River, Baton Rouge to the Gulf, Saltwater Barrier Sill, Cutterhead Dredge Contract No. 2-2025

(OM25136)

New Orleans, Louisiana



DEPARTMENT OF THE ARMY
CORPS OF ENGINEERS, NEW ORLEANS DISTRICT
7400 LEAKE AVENUE
NEW ORLEANS, LOUISIANA 70118-3651

REPLY TO
ATTENTION OF

SOLICITATION: W912P825BA007

FOR: Mississippi River, Baton Rouge to the Gulf, Saltwater Barrier Sill, Cutterhead Dredge Contract No. 2-2025. Specification Nos. OM25136

TO OPEN: The Bid Opening is to be opened by a future Amendment.

- I. NOTE THE AFFIRMATIVE ACTION PROGRAM REQUIREMENT OF THE EQUAL OPPORTUNITY CLAUSE WHICH MAY APPLY TO THE CONTRACT RESULTING FROM THIS SOLICITATION.
- II. NOTE THE CERTIFICATION OF NONSEGREGATED FACILITIES IN THIS SOLICITATION.
Bidders, offerors and applicants are cautioned to note the "Certification of Non-segregated Facilities" in the solicitation. Failure of a bidder or offeror to agree to the certification will render his bid or offer non-responsive to the terms of solicitations involving awards of contracts exceeding \$10,000 which are not exempt from the provisions of the Equal Opportunity clause.
- III. Prospective contractors must register in the System for Award Management (SAM). See FAR Clause 52.204-7 for required information. The website for SAM is <https://www.sam.gov>. You will be required to provide your company's Dun and Bradstreet number along with an original, signed notarized letter identifying the authorized Entity Administrator before the registration will be activated. If you do not already have a D&B number, one can be requested from Dun and Bradstreet at (800) 333-0505 or <http://fedgov.dnb.com/webform>. Contractors must complete, and submit with their bid, the provisions located in section 00600. A bidder may also submit, in lieu of the completed section 00600, a complete hard copy of their Online Representations and Certifications which is located within the System for Award Management (SAM). Prospective contractors with expired or inactive Representations and Certifications in SAM at time of award will be deemed unresponsive.

Bidders must provide full, accurate, and complete information as required by this solicitation and its attachments. The penalty for making false statements in bids is prescribed in 18 U.S.C. 1001. (FAR 52.214-4 APR 1984).

DESCRIPTION AND MAGNITUDE OF WORK: The Contractor's dredge and attendant plant will primarily be used in connection with the construction and possible maintenance of a saltwater barrier sill located between Mile 63.0 and Mile 64.0 Above Head of Passes (AHP) on the Mississippi. The work will consist of satisfactorily placing hydraulically dredged material which shall be taken from a borrow area located on the river bottom. The contract plates show the approximate location of the sill and configuration of the sill (should the sill need to be built to -30' LWRP with a 620' notch to -55' LWRP) and borrow areas. Further details of the location, size, and configuration of the sill and borrow area required will be given in the dredging assignments.

NOTE: ALL WORK UNDER THIS CONTRACT SHALL BE PERFORMED IN ACCORDANCE WITH THE PROVISIONS OF EM 385-1-1 "SAFETY AND OCCUPATIONAL HEALTH REQUIREMENTS."

ALL INQUIRIES REGARDING THIS SOLICITATION

SHOULD BE MADE TO THE FOLLOWING:

Cori A. Caimi

AND/OR

Bambi Raja

CONTRACT SPECIALISTS

U.S. ARMY CORPS OF ENGINEERS, NEW ORLEANS DISTRICT

E-MAILS: Cori.A.Caimi@USACE.ARMY.MIL

PHONE: (504) 862-1352

AND/OR

Bambi.L.Raja@usace.army.mil

PHONE: (504) 862-1499

COLLECT CALLS NOT ACCEPTED

NOTE: FOR THE MOST PROMPT RESPONSE, PLEASE SEND ALL QUESTIONS VIA

E-MAIL

PROJECT TABLE OF CONTENTS**DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS**

00010	BID SCHEDULE
00100	INSTRUCTIONS TO BIDDERS
00600	REPRESENTATIONS AND CERTIFICATIONS
00700	CONTRACT CLAUSES INSERTS
00800	SUPPLEMENTARY CONDITIONS

DIVISION 01 - GENERAL REQUIREMENTS

01 30 00	ADMINISTRATIVE REQUIREMENTS
01 33 00	SUBMITTAL PROCEDURES
01 35 26	GOVERNMENTAL SAFETY REQUIREMENTS
01 45 00.15 10	RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM)
01 57 20.00 10	ENVIRONMENTAL PROTECTION

DIVISION 35 - WATERWAY AND MARINE CONSTRUCTION

35 01 50.73	SURVEYS
35 20 23.23	HYDRAULIC DREDGING
35 20 23.23 16	HYDRAULIC DREDGING - MISSISSIPPI RIVER SALTWATER BARRIER SILL DREDGING REGION
35 20 23.23 33	NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM PIPELINE HYDRAULIC DREDGE

-- End of Project Table of Contents --

SOLICITATION, OFFER, AND AWARD <i>(Construction, Alteration, or Repair)</i>	1. SOLICITATION NUMBER W912P825BA007	2. TYPE OF SOLICITATION ☒ SEALED BID (IFB) INVITATION FOR BID ☐ NEGOTIATED (RFP) REQUEST FOR PROPOSAL	3. DATE ISSUED	PAGE OF PAGES 1 37
---	---	--	----------------	---------------------------

IMPORTANT - The "offer" section on the reverse must be fully completed by offeror.

4. CONTRACT NUMBER	5. REQUISITION/PURCHASE REQUEST NUMBER W912P8	6. PROJECT NUMBER OM25136
7. ISSUED BY W07V ENDIST N ORLEANS KO CONTRACTING DIVISION, 7400 LEAKE AVE NEW ORLEANS, LA 70118-3651 UNITED STATES CORI CAIMI, EMAIL: CORI.A.CAIMI@USACE.ARMY.MIL TELEPHONE: 504-862-1352	CODE	8. ADDRESS OFFER TO W07V ENDIST N ORLEANS KO CONTRACTING DIVISION, 7400 LEAKE AVE NEW ORLEANS, LA 70118-3651 UNITED STATES
9. FOR INFORMATION CALL:	a. NAME CORI CAIMI	b. TELEPHONE NUMBER <i>(Include area code) (NO COLLECT CALLS)</i> 504-862-1352

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS *(Title, identifying number, date)*

PROJECT TITLE: MISSISSIPPI RIVER SALTWATER BARRIER SILL CUTTERHEAD DREDGE NO. 2-2025
PROJECT LOCATION: NEW ORLEANS, LA

MISSISSIPPI RIVER SALTWATER BARRIER SILL CUTTERHEAD DREDGE NO. 2-2025 (OM25136)

THIS IS AN UNRESTRICTED PROCUREMENT

MAGNITUDE OF CONSTRUCTION: BETWEEN \$10,000,000 AND \$25,000,000.

SUBJECT TO THE AVAILABILITY OF FUNDS FAR 52.232-18 FUNDS ARE NOT PRESENTLY AVAILABLE FOR THIS ACQUISITION. NO CONTRACT AWARD WILL BE MADE UNTIL APPROPRIATE FUNDS ARE MADE AVAILABLE.

** BID OPENING TO BE ESTABLISHED BY AMENDMENT

*** SEE PARAGRAPH 00010-1.5"

11. The contractor shall begin performance within 15 calendar days and complete it within 53 calendar days after receiving ☐ award, ☒ notice to proceed. This performance period is ☒ mandatory ☐ negotiable. <i>(See FAR 52.211-10)</i> .	12a. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS? <i>(If "YES", indicate within how many calendar days after award in Item 12b.)</i> ☒ YES ☐ NO	12b. CALENDAR DAYS 1
13. ADDITIONAL SOLICITATION REQUIREMENTS:		
a. Sealed offers in original and _____ copies to perform the work required are due at the place specified in Item 8 by 11:00 AM <i>(hour)</i> local time 01 MAY 2027 <i>(date)</i> . If this is a sealed bid solicitation, offers will be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.		
b. An offer guarantee ☒ is, ☐ is not required.		
c. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.		
d. Offers providing less than 53 calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.		

OFFER (Must be fully completed by offeror)

14. NAME AND ADDRESS OF OFFEROR (Include ZIP Code)		15. TELEPHONE NUMBER (Include area code)	
		16. REMITTANCE ADDRESS (Include only if different than Item 14.)	
CODE	FACILITY CODE		

17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within _____ calendar days after the date offers are due. (Insert any number equal to or greater than the minimum requirement stated in Item 13d. Failure to insert any number means the offeror accepts the minimum in Item 13d.)

AMOUNTS



18. The offeror agrees to furnish any required performance and payment bonds.

19. ACKNOWLEDGMENT OF AMENDMENTS

(The offeror acknowledges receipt of amendments to the solicitation -- give number and date of each)

AMENDMENT NUMBER										
DATE										

20a. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER (Type or print)

20b. SIGNATURE

20c. OFFER DATE

AWARD (To be completed by Government)

21. ITEMS ACCEPTED:

22. AMOUNT

23. ACCOUNTING AND APPROPRIATION DATA

24. SUBMIT INVOICES TO ADDRESS SHOWN IN
(4 copies unless otherwise specified)



ITEM

25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO THE UNITED STATES
CODE AT

☐ 10 U.S.C. 3204(a) () ☐ 41 U.S.C. 3304(a) ()

26. ADMINISTERED BY

27. PAYMENT WILL BE MADE BY

CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE

☐ 28. NEGOTIATED AGREEMENT (Contractor is required to sign this document and return _____ copies to issuing office.) Contractor agrees to furnish and deliver all items or perform all work requirements identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications incorporated by reference in or attached to this contract.

☐ 29. AWARD (Contractor is not required to sign this document.) Your offer on this solicitation is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.

30a. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN
(Type or print)

31a. NAME OF CONTRACTING OFFICER (Type or print)

30b. SIGNATURE

30c. DATE

31b. UNITED STATES OF AMERICA

31c. DATE

BY

SECTION TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

SECTION 00010

BID SCHEDULE

PART 1 GENERAL

1.1 BIDDING SCHEDULE

1.1.1 Bid Form Notes

1.2 BIDDING

1.3 EVALUATION OF BIDS

1.4 CONDITIONS OF CONTRACT AWARD

1.5 BIDDER QUALIFICATIONS

1.6 PRE-AWARD INSPECTION OF PLANT

1.7 OPTION ITEMS

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

-- End of Section Table of Contents --

SECTION 00010

BID SCHEDULE

PART 1 GENERAL

1.1 BIDDING SCHEDULE

SECTION 00010 - BIDDING SCHEDULE

MISSISSIPPI RIVER, BATON ROUGE TO THE GULF,
SALTWATER BARRIER SILL
CUTTERHEAD DREDGE CONTRACT NO. 2-2025
PLAQUEMINES PARISH, LOUISIANA
SOLICITATION NO. W912P825A007

30 INCHES OR GREATER INSIDE DIAMETER (ID) PUMP DISCHARGE WITH SUBMERGED PUMP

Bid Item	DESCRIPTION	Estimated Quantity	Unit	Unit Price	Total Price
0001	MOBILIZATION AND DEMOBILIZATION	1	Job		
0002	DREDGING	350	Hour		
Option 0003	OPTION DREDGING I	400	Hour	XXXXXX	
Option 0004	OPTION DREDGING II	400	Hour	XXXXXX	
Option 0005	OPTION DREDGING III	400	Hour	XXXXXX	
Option 0006	ADDITIONAL PUMPING CAPABILITY FOR DREDGING PAYMENT ITEMS 0002, 0003, 0004, AND 0005	500	Hour		
Option 0007	MOBILIZATION AND DEMOBILIZATION OF ADDITIONAL PUMPING CAPABILITY EQUIPMENT FOR PAYMENT ITEM 0006	1	Job		
Option 0008	INTERIM DEMOBILIZATION AND INTERIM MOBILIZATION OF CUTTERHEAD DREDGE	200	Mile		
Option 0009	STANDBY OF ATTENDANT PLANT	90	Day		

Bid Item	DESCRIPTION	Estimated Quantity	Unit	Unit Price	Total Price
Option 0010	STANDBY OF ADDITIONAL PUMPING CAPABILITY FOR DREDGING PAYMENT ITEMS 0002, 0003, 0004, AND 0005	90	Day		
Option 0011	DREDGE TOWING SERVICE	20	Mile		
TOTAL:					

*SEE BID FORM NOTES

1.1.1.1 Bid Form Notes

- a. Bidders shall bid on all items including optional items (see "Evaluation of Options" FAR 52.217-5). Failure to bid on all items will result in a non-responsive bid.
- b. Bidders shall use the Item No. 0002 unit price to compute Option Item No. 0003 total price, Option Item No. 0004 total price, and Option Item No. 0005 total price.
- c. Any bid may be rejected if the Contracting Officer determines in writing that it is unreasonable as to price. Unreasonableness of price includes not only the total price of the bid, but the prices for individual line items as well. Any bid may be rejected if the prices for any line items or subline items are materially unbalanced (see "Rejection of Individual Bids" FAR 14.404-2).
- d. THE NOTICE TO PROCEED (NTP): The successful bidder is advised that performance and payment bonds shall be submitted in accordance with the time frame in block 12B of SF 1442 after Notice of Award. The NTP will be issued after verification of acceptable performance and payment bonds. Within 24 hours after issuance of the NTP, the Contractor shall initiate a meeting to discuss the submittal process with the Administrative Contracting Officer or his/her authorized representative. Physical work cannot start until the Quality Control System is set-up, the Accident Prevention Program and other required submittals have been submitted and approved, and all preliminary meetings called for under the contract have been conducted.
- e. RAPID VENDOR PAYMENT: See the following web based instructions for the submission of invoices:
<http://www.mvn.usace.army.mil/BusinessWithUs/Contracting/RapidVendorPayment.aspx>.
- f. The unit "job" is synonymous with the previously used term "lump sum".
- g. Bidders shall select the bid lot determined by the dredge discharge size. The dredge discharge size is considered to be the least inside diameter of the following: the main pump discharge, the submerged pump discharge, the booster pump discharge, or the discharge pipeline.
- h. As per FAR 9.104-1 (b) and (f) General Standards and FAR 9.104-2, special standards of responsibility have been established for this acquisition. A pre-award survey will be required. Before award, the apparent low bidder shall provide documentation to satisfy the following definitive responsibility criteria. An apparent low bidder who is not able to meet the following definitive responsibility criteria will be deemed to lack responsibility and will be ineligible for award:
- 1) Acceptable Performance and Payment Bonds shall be received by the Contracting Officer no more than twenty-four (24) hours after award of the contract.
 - 2) Due to the urgency of commencement and timely performance of this contract, the Contractor shall be required to certify in writing that (a) dredging shall commence under this contract within 120 hours after issuance of the Notice to Proceed, (b) shall prosecute the work diligently and meet the minimum

production rate specified in Section 35 20 23.23 16, paragraph entitled "Minimum Production Rate Requirements", and (c) shall be able to concurrently remove any shoal material accumulating in the one-way navigation channel section and dredge the borrow area to restore the saltwater barrier sill's elevation and grade. This period of performance is mandatory and the Contractor shall have equipment designated for use on this contract readily available and in good operating condition and ready for immediate use. Certification shall be included with the bid at the given date and time of the bid opening.

3) Bidders shall furnish in their bid package a completed "Cutterhead Dredge and Attendant Plant Data Sheet" (see Section 35 20 23.23 entitled "Hydraulic Dredging"). If the apparent low bidder fails to furnish the intended dredge's "Cutterhead Dredge and Attendant Plant Data Sheet" within his/her bid package, the apparent low bidder will have 3 hours after the time of the bid opening to provide the Contracting Officer a copy. If the apparent low bidder fails to furnish the intended dredge's "Cutterhead Dredge and Attendant Plant Data Sheet" to the Contracting Officer within the allotted time, the respective bidder will be declared non-responsible and the next apparent low bidder will be evaluated as stated in paragraphs (a) and (b) below. Upon receipt of the completed "Cutterhead Dredge and Attendant Plant Data Sheet" for the dredge plant that is intended to perform work under this solicitation, the "Cutterhead Dredge and Attendant Plant Data Sheet" will be evaluated to ensure that the dredge meets the equipment requirements as stated in Section 35 20 23.23, paragraph entitled "Size and Equipment of Dredge Plant".

(a) If, after review, the Government determines that the dredge on the "Cutterhead Dredge and Attendant Plant Data Sheet" does satisfy the equipment requirements as stated in Section 35 20 23.23, paragraph entitled "Size and Equipment of Dredge Plant", the Government will proceed with award of the contract to the apparent low bidder, provided all other requirements for award have been satisfied.

(b) If, after review, the Government determines that the dredge on the "Cutterhead Dredge and Attendant Plant Data Sheet" does not satisfy the equipment requirements as stated in Section 35 20 23.23, paragraph entitled "Size and Equipment of Dredge Plant", the Government will declare the apparent low bidder non-responsible. The Government will thereafter perform the described pre-award survey on the next apparent low bidder, and will do so with each successive apparent low bidder until it is determined that the otherwise responsive, apparent low bidder, has submitted a "Cutterhead Dredge and Attendant Plant Data Sheet" that does satisfy the equipment requirements as stated in Section 35 20 23.23, paragraph entitled "Size and Equipment of Dredge Plant".

4) The Contractor shall identify the current location of the dredge that will perform work under this contract in their bid.

Should the Contractor be unable to certify compliance with the provisions stated in paragraph 1.1.1.h, the Government will declare the apparent low bidder non-responsible and perform the described pre-award survey on the next apparent low bidder.

1.2 BIDDING

Bidders shall furnish unit prices for all items listed on the schedule of bid items that require unit prices. If the bidder fails to insert a unit price in the appropriate blank for required items but does furnish an extended total or an estimated amount for such items, the Government will deem the unit price to be the quotient obtained by dividing the extended estimated amount for that line item by the quantity. IF THE BIDDER OMITTS BOTH THE UNIT PRICE AND THE EXTENDED ESTIMATED AMOUNT FOR ANY REQUIRED ITEM, THE BID WILL BE DECLARED NON-RESPONSIVE.

1.3 EVALUATION OF BIDS

a. The hourly dredging quantities have been determined based on the estimated amount of dredge material to be removed to construct the saltwater barrier sill and the nominal production rates of the dredge. The production rates shown in the chart in paragraph entitled "Minimum Production Rate Requirements" located in the Dredging Region Section(s) was used to make this determination.

b. The nominal dredge production rates listed in this solicitation were conservatively estimated based on the dredge material face available in the borrow areas. It is the bidder's responsibility to make its own assessment of the actual dredging conditions in order to prepare a bid for this work.

c. Award will be made to that responsible bidder presenting the lowest priced responsive bid in response to this solicitation.

d. The hourly quantities shown on the bid (Bid Items "Dredging", "Option Dredging I", "Option Dredging II", and "Option Dredging III") are 100% pay time hours. The actual calendar duration of the contract may vary as a result of fractional pay time. Refer to Section 35 20 23.23, paragraph entitled "Dredging and Option Dredging Items", for additional information.

1.4 CONDITIONS OF CONTRACT AWARD

a. Award will be made as a whole to one bidder. The dredge and attendant plant offered in the bidding schedule shall be complete with full operating personnel and in operating status for the contract period. NOTE: All work under these specifications shall be performed in accordance with the provisions of EM 385-1-1 "Safety and Occupational Health Requirements", latest edition.

b. The Government may award the contract at the total bid price, comprised of the base items and option item(s); however, the Government will not be obligated to exercise any option item(s).

c. The number of hours stated in the bidding schedule is an estimated quantity. The dredge and attendant plant will be retained for an approximate number of days shown in the table below starting no later than 120 hours after issuance of the Notice to Proceed.

**APPROXIMATE CUTTERHEAD DREDGE
CONTRACT DURATION**

Dredge Discharge Size (ID, Inches)	Submerged Pump	Approx. Number of Contract Days for Item 0002	Approx. Number of Contract Days for Option Item 0003	Approx. Number of Contract Days for Option Item 0004	Approx. Number of Contract Days for Option Item 0005	Approx. Number of Contract Days for Option Item 0009
30 or greater	Yes	42	40	40	40	90

The time required for completion of the contract shall be established as the number of calendar days listed in column entitled "Approx. Number of Contract Days for Item 0002". In the event Option Item 0003 is fully exercised under the terms of the contract, the time required for completion of the contract shall be extended by 40 calendar days. In the event Option Item 0004 is fully exercised under the terms of the contract, the time required for completion of the contract shall be extended by 40 calendar days. In the event Option Item 0005 is fully exercised under the terms of the contract, the time required for completion of the contract shall be extended by 40 calendar days. In the event Option Item 0009 is fully exercised under the terms of the contract, the time required for completion of the contract shall be extended by 90 calendar days.

In the event Option Item 0003 is partially exercised, the contract completion date shall be extended using the following formula:

$$[(\text{partial option hours exercised}) / (\text{option hours listed in bid schedule})] \times [\text{calendar days listed in column "Approx. Number of Contract Days for Option Item 0003"}].$$

In the event Option Item 0004 is partially exercised, the contract completion date shall be extended using the following formula:

$$[(\text{partial option hours exercised}) / (\text{option hours listed in bid schedule})] \times [\text{calendar days listed in column "Approx. Number of Contract Days for Option Item 0004"}].$$

In the event Option Item 0005 is partially exercised, the contract completion date shall be extended using the following formula:

$$[(\text{partial option hours exercised}) / (\text{option hours listed in bid schedule})] \times [\text{calendar days listed in column "Approx. Number of Contract Days for Option Item 0005"}].$$

In the event Option Item 0009 is partially exercised, the contract completion date shall be extended by the number of days exercised.

d. The bidder shall be capable of providing for assignment of the dredge and all attendant plant, complete and in full operating condition in all respects, and to commence dredging no later than 120 hours after issuance of the Notice to Proceed.

1.5 BIDDER QUALIFICATIONS

a. Before the Government will award a contract based on this solicitation, the apparent low bidder shall establish that it is responsible and entitled to award of the contract. The Contractor must

establish responsibility by providing sufficient documentation for review and approval that its dredge meets the appropriate production rate for the dredging region, as listed in the table in paragraph entitled "Minimum Production Rate Requirements" located in the Dredging Region Section(s). The Contractor must prove the proposed dredge has performed at, or above, the listed production rate for a minimum of 30 days on a single contract within three years prior to the bid opening date of this solicitation. Failure to establish the dredge's capability to meet the required production rate will result in a finding of non-responsibility.

b. A bidder may be rejected as non-responsible if it cannot show the necessary capital, experience, or equipment needed to perform the work described under this solicitation (see "Responsible Prospective Contractors" FAR Subpart 9.1). The bidder must also show that the dredge and attendant plant are not already obligated for the performance of other work which would delay commencement, performance, and completion of the solicited work; and must show that delivery of the dredge and attendant plant to the site of work can be made within the time allowed in the specifications.

c. Bidders must register in the System for Award Management (SAM) database in accordance with FAR 52.204-7-OCT 2018.

1.6 PRE-AWARD INSPECTION OF PLANT

a. The apparent low bidder shall make the dredge and attendant plant available for inspection, to determine compliance with these specifications, as soon as practicable after bids are opened, and prior to contract award. If deficiencies are found during the inspection, the bidder will be notified in writing, which may be transmitted by email or facsimile. Upon receipt of such notice, the bidder shall correct all deficiencies at least two calendar days in advance of the projected contract award date.

b. Two calendar days before the projected award date, or upon notification by the bidder that the deficiencies have been corrected, a Government representative will re-inspect the dredge and attendant plant. If at that time the dredge and attendant plant do not meet the requirements of these specifications, the bidder will be rejected as non-responsible.

c. The Government may choose to waive the pre-award inspection. Waiver of the pre-award inspection does not relieve the bidder from the requirement to provide a dredge and attendant plant in full compliance with the specifications. By bidding on this solicitation, the bidder is stating that the provided dredge and attendant plant is in full compliance with the specifications and can perform all requirements as stated in the specifications.

1.7 OPTION ITEMS

a. The Government may require the delivery of, in whole or part, any Option Items. The Government may exercise an Option Item by written notice to the Contractor at any time after Notice to Proceed and up to 1 hour prior to the estimated completion date of the base line item or any previously exercised option.

(1) If "Option Dredging I" is exercised, it shall be performed as

a continuance of "Dredging", which shall be activated first. If "Option Dredging II" is exercised, it shall be performed as a continuance of "Option Dredging I", which shall be activated first. If "Option Dredging III" is exercised, it shall be performed as a continuance of "Option Dredging II", which shall be activated first.

(2) If Option Item "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005" is exercised, it shall be activated concurrently with either of the "Dredging", "Option Dredging I", "Option Dredging II", or "Option Dredging III" Items and only when required pumping distance exceeds 13,000 feet of pipeline.

(3) If Option Item "Mobilization and Demobilization of Additional Pumping Capability Equipment for Payment Item 0006" is exercised, it shall be activated concurrently with Option Item "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005".

b. No additional mobilization/demobilization will be paid to the Contractor for Option Item work performed within the work region, except for Option Item "Mobilization and Demobilization of Additional Pumping Capability Equipment for Payment Item 0006" and Option Item "Interim Demobilization and Interim Mobilization of Cutterhead Dredge".

c. The Contractor shall commence performance of optional work no more than three calendar days after the time the Contractor receives the Government's Notice to Proceed with the optional work.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

-- End of Section --

Section 00100 - Instructions

FAR Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
52.204-7	System for Award Management.	Nov 2024		
52.204-16	Commercial and Government Entity Code Reporting.	Aug 2020		
52.204-22	Alternative Line Item Proposal.	Jan 2017		
52.214-3	Amendments to Invitations for Bids.	Dec 2016		
52.214-4	False Statements in Bids.	Apr 1984		
52.214-5	Submission of Bids.	Dec 2016		
52.214-6	Explanation to Prospective Bidders.	Apr 1984		
52.214-7	Late Submissions, Modifications, and Withdrawals of Bids.	Nov 1999		
52.214-12	Preparation of Bids.	Apr 1984		
52.214-34	Submission of Offers in the English Language.	Apr 1991		
52.214-35	Submission of Offers in U.S. Currency.	Apr 1991		
52.222-5	Construction Wage Rate Requirements-Secondary Site of the Work.	May 2014		
52.225-12	Notice of Buy American Requirement-Construction Materials Under Trade Agreements.	May 2014		

DFARS Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
252.204-7019	Notice of NIST SP 800-171 DoD Assessment Requirements.	Nov 2023		
252.204-7024	Notice on the Use of the Supplier Performance Risk System.	Mar 2023		
252.215-7013	Supplies and Services Provided by Nontraditional Defense Contractors.	Jan 2023		

FAR Clauses Incorporated by Full Text

52.216-1 **Type of Contract.** **(Apr 1984)**

Type of Contract (Apr 1984)

The Government contemplates award of a firm fixed price[Contracting Officer insert specific type of contract] contract resulting from this solicitation.

(End of provision)

52.228-1 **Bid Guarantee.** **(Sep 1996)**

Bid Guarantee (Sept 1996)

(a) Failure to furnish a bid guarantee in the proper form and amount, by the time set for opening of bids, may be cause for rejection of the bid.

(b) The bidder shall furnish a bid guarantee in the form of a firm commitment, e.g., bid bond supported by good and sufficient surety or sureties acceptable to the Government, postal money order, certified check, cashier's check, irrevocable letter of credit, or, under Treasury Department regulations, certain bonds or notes of the United States. The Contracting Officer will return bid guarantees, other than bid bonds-

(1) To unsuccessful bidders as soon as practicable after the opening of bids; and

(2) To the successful bidder upon execution of contractual documents and bonds (including any necessary coinsurance or reinsurance agreements), as required by the bid as accepted.

(c) The amount of the bid guarantee shall be (20%) twenty percent of the bid price or \$3,000,000.00, whichever is less.

(d) If the successful bidder, upon acceptance of its bid by the Government within the period specified for acceptance, fails to execute all contractual documents or furnish executed bond(s) within 10 days after receipt of the forms by the bidder, the Contracting Officer may terminate the contract for default.

(e) In the event the contract is terminated for default, the bidder is liable for any cost of acquiring the work that exceeds the amount of its bid, and the bid guarantee is available to offset the difference.

(End of clause)

52.233-2 Service of Protest.

(Sep 2006)

Service of Protest (Sept 2006)

(a) Protests, as defined in section 33.101 of the Federal Acquisition Regulation, that are filed directly with an agency, and copies of any protests that are filed with the Government Accountability Office (GAO), shall be served on the Contracting Officer (addressed as follows) by obtaining written and dated acknowledgment of receipt from 7400 Leake Ave New Orleans, LA 70118 _____. [Contracting Officer designate the official or location where a protest may be served on the Contracting Officer.]

(b) The copy of any protest shall be received in the office designated above within oneday of filing a protest with the GAO.

(End of provision)

52.236-27 Site Visit (Construction).

(Feb 1995)

Site Visit (Construction) (Feb 1995)

(a) The clauses at 52.236-2, Differing Site Conditions, and 52.236-3, Site Investigations and Conditions Affecting the Work, will be included in any contract awarded as a result of this solicitation. Accordingly, offerors or quoters are urged and expected to inspect the site where the work will be performed.

(b) Site visits may be arranged during normal duty hours by contacting:

Name: Charles Freeman

Address: 7400 Leake Ave New Orleans, LA 70118 ____

Telephone: 504-862-1554

(End of Provision)

52.236-27 Site Visit (Construction). (Alternate I)

(Feb 1995) Alternate I (Feb 1995)

Alternate I (Feb 1995). If an organized site visit will be conducted, substitute a paragraph substantially the same as the following for paragraph (b) of the basic provision:

(b) An organized site visit has been scheduled for-

____[Insert date and time]

(c) Participants will meet at-

_____[Insert location]

52.252-1 Solicitation Provisions Incorporated by Reference.

(Feb 1998)

Solicitation Provisions Incorporated by Reference (Feb 1998)

This solicitation incorporates one or more solicitation provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. The offeror is cautioned that the listed provisions may include blocks that must be completed by the offeror and submitted with its quotation or offer. In lieu of submitting the full text of those provisions, the offeror may identify the provision by paragraph identifier and provide the appropriate information with its quotation or offer. Also, the full text of a solicitation provision may be accessed electronically at this/these address(es):

www.acquisition.gov_____[Insert one or more Internet addresses]

(End of provision)

52.252-3 Alterations in Solicitation.

(Apr 1984)

Alterations in Solicitation (Apr 1984)

Portions of this solicitation are altered as follows:

____ _

(End of clause)

Authorized Deviations in Provisions (Nov 2020)

(a) The use in this solicitation of any Federal Acquisition Regulation (48 CFR Chapter 1) provision with an authorized deviation is indicated by the addition of "(DEVIATION)" after the date of the provision.

(b) The use in this solicitation of any ____ [insert regulation name] (48 CFR Chapter ____) provision with an authorized deviation is indicated by the addition of "(DEVIATION)" after the name of the regulation.

(End of provision)

DFARS Clauses Incorporated by Full Text

ONLY ONE OFFER (DEC 2022)

(a) Cost or pricing data requirements. After initial submission of offers, if the Contracting Officer notifies the Offeror that only one offer was received, the Offeror agrees to-

(1) Submit any additional cost or pricing data that is required in order to determine whether the price is fair and reasonable (10 U.S.C. 3705) or to comply with the statutory requirement for certified cost or pricing data (10 U.S.C. 3702 and FAR 15.403-3); and

(2) Except as provided in paragraph (b) of this provision, if the acquisition exceeds the certified cost or pricing data threshold and an exception to the requirement for certified cost or pricing data at FAR 15.403-1(b)(2) through (5) does not apply, certify all cost or pricing data in accordance with paragraph (c) of DFARS provision 252.215-7010, Requirements for Certified Cost or Pricing Data and Data Other Than Certified Cost or Pricing Data, of this solicitation.

(b) Canadian Commercial Corporation. If the Offeror is the Canadian Commercial Corporation, certified cost or pricing data are not required. If the Contracting Officer notifies the Canadian Commercial Corporation that additional data other than certified cost or pricing data are required in accordance with DFARS 225.870-4(c), the Canadian Commercial Corporation shall obtain and provide the following:

(1) Profit rate or fee (as applicable).

(2) Analysis provided by Public Works and Government Services Canada to the Canadian Commercial Corporation to determine a fair and reasonable price (comparable to the analysis required at FAR 15.404-1).

(3) Data other than certified cost or pricing data necessary to permit a determination by the U.S. Contracting Officer that the proposed price is fair and reasonable ____ [U.S. Contracting Officer to provide description of the data required in accordance with FAR 15.403-3(a)(1) with the notification].

(4) As specified in FAR 15.403-3(a)(4), an offeror who does not comply with a requirement to submit data that the U.S. Contracting Officer has deemed necessary to determine price reasonableness or cost realism is ineligible for award unless the head of the contracting activity determines that it is in the best interest of the Government to make the award to that offeror.

(c) Subcontracts. Unless the Offeror is the Canadian Commercial Corporation, the Offeror shall insert the substance of this provision, including this paragraph (c), in all subcontracts exceeding the simplified acquisition threshold defined in FAR part 2.

(End of provision)

Section 00 22 00 - Supplementary Instructions

FAR Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
52.217-4	Evaluation of Options Exercised at Time of Contract Award.	Jun 1988		
52.217-5	Evaluation of Options.	Jul 1990		

Section 00600 - Representations and Certifications

FAR Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
52.204-24	Representation Regarding Certain Telecommunications and Video Surveillance Services or Equipment.	Nov 2021		
52.204-29	Federal Acquisition Supply Chain Security Act Orders-Representation and Disclosures.	Dec 2023		
52.209-7	Information Regarding Responsibility Matters.	Oct 2018		
52.209-13	Violation of Arms Control Treaties or Agreements-Certification.	Nov 2021		
52.229-12	Tax on Certain Foreign Procurements.	Feb 2021		

DFARS Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
252.203-7005	Representation Relating to Compensation of Former DoD Officials.	Sep 2022		
252.204-7008	Compliance with Safeguarding Covered Defense Information Controls.	Oct 2016		
252.204-7017	Prohibition on the Acquisition of Covered Defense Telecommunications Equipment or Services-Representation.	May 2021		
252.225-7055	Representation Regarding Business Operations with the Maduro Regime.	May 2022		
252.225-7057	Preaward Disclosure of Employment of Individuals Who Work in the People's Republic of China.	Aug 2022		
252.225-7059	Prohibition on Certain Procurements from the Xinjiang Uyghur Autonomous Region-Representation.	Jun 2023		

FAR Clauses Incorporated by Full Text

52.204-8 Annual Representations and Certifications. (Jan 2025)

Annual Representations and Certifications (Jan 2025)

(a)

(1) The North American Industry Classification System (NAICS) code for this acquisition is 237990[insert NAICS code].

(2) The small business size standard is 37,000,000.00[insert size standard].

(3) The small business size standard for a concern that submits an offer, other than on a construction or service acquisition, but proposes to furnish an end item that it did not itself manufacture, process, or produce is 500 employees, or 150 employees for information technology value-added resellers under NAICS code 541519 if the acquisition-

(i) Is set aside for small business and has a value above the simplified acquisition threshold;

(ii) Uses the HUBZone price evaluation preference regardless of dollar value, unless the offeror waives the price evaluation preference; or

(iii) Is an 8(a), HUBZone, service-disabled veteran-owned, economically disadvantaged women-owned, or women-owned small business set-aside or sole-source award regardless of dollar value.

(b)

(1) If the provision at 52.204-7, System for Award Management, is included in this solicitation, paragraph (d) of this provision applies.

(2) If the provision at 52.204-7, System for Award Management, is not included in this solicitation, and the Offeror has an active registration in the System for Award Management (SAM), the Offeror may choose to use paragraph (d) of this provision instead of completing the corresponding individual representations and certifications in the solicitation. The Offeror shall indicate which option applies by checking one of the following boxes:

(i) ☐ Paragraph (d) applies.

(ii) ☐ Paragraph (d) does not apply and the offeror has completed the individual representations and certifications in the solicitation.

(c)

(1) The following representations or certifications in SAM are applicable to this solicitation as indicated:

(i) 52.203-2, Certificate of Independent Price Determination. This provision applies to solicitations when a firm-fixed-price contract or fixed-price contract with economic price adjustment is contemplated, unless-

(A) The acquisition is to be made under the simplified acquisition procedures in part 13;

(B) The solicitation is a request for technical proposals under two-step sealed bidding procedures; or

(C) The solicitation is for utility services for which rates are set by law or regulation.

(ii) 52.203-11, Certification and Disclosure Regarding Payments to Influence Certain Federal Transactions. This provision applies to solicitations expected to exceed \$150,000.

(iii) 52.203-18, Prohibition on Contracting with Entities that Require Certain Internal Confidentiality Agreements or Statements-Representation. This provision applies to all solicitations.

(iv) 52.204-3, Taxpayer Identification. This provision applies to solicitations that do not include the provision at 52.204-7, System for Award Management.

(v) 52.204-5, Women-Owned Business (Other Than Small Business). This provision applies to solicitations that-

(A) Are not set aside for small business concerns;

(B) Exceed the simplified acquisition threshold; and

(C) Are for contracts that will be performed in the United States or its outlying areas.

(vi) 52.204-26, Covered Telecommunications Equipment or Services-Representation. This provision applies to all solicitations.

(vii) 52.209-2, Prohibition on Contracting with Inverted Domestic Corporations-Representation.

(viii) 52.209-5, Certification Regarding Responsibility Matters. This provision applies to solicitations where the contract value is expected to exceed the simplified acquisition threshold.

(ix) 52.209-11, Representation by Corporations Regarding Delinquent Tax Liability or a Felony Conviction under any Federal Law. This provision applies to all solicitations.

(x) 52.214-14, Place of Performance-Sealed Bidding. This provision applies to invitations for bids except those in which the place of performance is specified by the Government.

(xi) 52.215-6, Place of Performance. This provision applies to solicitations unless the place of performance is specified by the Government.

(xii) 52.219-1, Small Business Program Representations (Basic, Alternates I, and II). This provision applies to solicitations when the contract is for supplies to be delivered or services to be performed in the United States or its outlying areas, or when the contracting officer has applied part 19 in accordance with 19.000(b)(1)(ii).

(A) The basic provision applies when the solicitations are issued by other than DoD, NASA, and the Coast Guard.

(B) The provision with its Alternate I applies to solicitations issued by DoD, NASA, or the Coast Guard.

(C) The provision with its Alternate II applies to solicitations that will result in a multiple-award contract with more than one NAICS code assigned.

(xiii) 52.219-2, Equal Low Bids. This provision applies to solicitations when contracting by sealed bidding and the contract is for supplies to be delivered or services to be performed in the United States or its outlying areas, or when the contracting officer has applied part 19 in accordance with 19.000(b)(1)(ii).

(xiv) 52.222-22, Previous Contracts and Compliance Reports. This provision applies to solicitations that include the clause at 52.222-26, Equal Opportunity.

(xv) 52.222-25, Affirmative Action Compliance. This provision applies to solicitations, other than those for construction, when the solicitation includes the clause at 52.222-26, Equal Opportunity.

(xvi) 52.222-38, Compliance with Veterans' Employment Reporting Requirements. This provision applies to solicitations when it is anticipated the contract award will exceed the simplified acquisition threshold and the contract is not for acquisition of commercial products or commercial services.

(xvii) 52.223-1, Biobased Product Certification. This provision applies to solicitations that require the delivery or specify the use of biobased products in USDA-designated product categories; or include the clause at 52.223-2, Reporting of Biobased Products Under Service and Construction Contracts.

(xviii) 52.223-4, Recovered Material Certification. This provision applies to solicitations that are for, or specify the use of, EPA-designated items.

(xix) 52.223-22, Public Disclosure of Greenhouse Gas Emissions and Reduction Goals-Representation. This provision applies to solicitations that include the provision at 52.204-7.

(xx) 52.225-2, Buy American Certificate. This provision applies to solicitations containing the clause at 52.225-1.

(xxi) 52.225-4, Buy American-Free Trade Agreements-Israeli Trade Act Certificate. (Basic, Alternates II and III.) This provision applies to solicitations containing the clause at 52.225-3.

(A) If the acquisition value is less than \$50,000, the basic provision applies.

(B) If the acquisition value is \$50,000 or more but is less than \$100,000, the provision with its Alternate II applies.

(C) If the acquisition value is \$100,000 or more but is less than \$102,280, the provision with its Alternate III applies.

(xxii) 52.225-6, Trade Agreements Certificate. This provision applies to solicitations containing the clause at 52.225-5.

(xxiii) 52.225-20, Prohibition on Conducting Restricted Business Operations in Sudan-Certification. This provision applies to all solicitations.

(xxiv) 52.225-25, Prohibition on Contracting with Entities Engaging in Certain Activities or Transactions Relating to Iran-Representation and Certifications. This provision applies to all solicitations.

(xxv) 52.226-2, Historically Black College or University and Minority Institution Representation. This provision applies to solicitations for research, studies, supplies, or services of the type normally acquired from higher educational institutions.

(2) The following representations or certifications are applicable as indicated by the Contracting Officer:

[Contracting Officer check as appropriate.]

☐ (i) 52.204-17, Ownership or Control of Offeror.

☐ (ii) 52.204-20, Predecessor of Offeror.

☐ (iii) 52.222-18, Certification Regarding Knowledge of Child Labor for Listed End Products.

☐ (iv) 52.222-48, Exemption from Application of the Service Contract Labor Standards to Contracts for Maintenance, Calibration, or Repair of Certain Equipment- Certification.

☐ (v) 52.222-52, Exemption from Application of the Service Contract Labor Standards to Contracts for Certain Services-Certification.

☐ (vi) 52.227-6, Royalty Information.

☐ (A) Basic.

☐ (B) Alternate I.

☐ (vii) 52.227-15, Representation of Limited Rights Data and Restricted Computer Software.

(d) The offeror has completed the annual representations and certifications electronically in SAM website accessed through <https://www.sam.gov>. After reviewing the SAM information, the offeror verifies by submission of the offer that the representations and certifications currently posted electronically that apply to this solicitation as indicated in paragraph (c) of this provision have been entered or updated within the last 12 months, are current, accurate, complete, and applicable to this solicitation (including the business size standard applicable to the NAICS code referenced for this solicitation), as of the date of this offer and are incorporated in this offer by reference (see FAR 4.1201); except for the changes identified below

[offeror to insert changes, identifying change by clause number, title, date]. These amended representation(s) and/or certification(s) are also incorporated in this offer and are current, accurate, and complete as of the date of this offer.

FAR Clause # Title Date Change

Any changes provided by the offeror are applicable to this solicitation only, and do not result in an update to the representations and certifications posted on SAM.

(End of provision)

DFARS Clauses Incorporated by Full Text

252.204-7007 Alternate A, Annual Representations and Certifications.

(Oct 2024) Alternate A (Oct 2024)

ALTERNATE A, ANNUAL REPRESENTATIONS AND CERTIFICATIONS (OCT 2024)

Substitute the following paragraphs (b), (d), and (e) for paragraphs (b) and (d) of the provision at FAR 52.204-8:

(b)(1) If the provision at 52.204-7, System for Award Management, is included in this solicitation, paragraph (e) of this provision applies.

(2) If the provision at 52.204-7, System for Award Management, is not included in this solicitation, and the Offeror has an active registration in the System for Award Management (SAM), the Offeror may choose to use paragraph (e) of this provision instead of completing the corresponding individual representations and certifications in the solicitation. The Offeror shall indicate which option applies by checking one of the following boxes:

☐ (i) Paragraph (e) applies.

☐ (ii) Paragraph (e) does not apply and the Offeror has completed the individual representations and certifications in the solicitation.

(d)(1) The following representations or certifications in the SAM database are applicable to this solicitation as indicated:

(i) 252.204-7016, Covered Defense Telecommunications Equipment or Services-Representation. Applies to all solicitations.

(ii) 252.216-7008, Economic Price Adjustment-Wage Rates or Material Prices Controlled by a Foreign Government. Applies to solicitations for fixed-price supply and service contracts when the contract is to be performed wholly or in part in a foreign country, and a foreign government controls wage rates or material prices and may during contract performance impose a mandatory change in wages or prices of materials.

(iii) 252.225-7042, Authorization to Perform. Applies to all solicitations when performance will be wholly or in part in a foreign country.

(iv) 252.225-7049, Prohibition on Acquisition of Certain Foreign Commercial Satellite Services-Representations. Applies to solicitations for the acquisition of commercial satellite services.

(v) 252.225-7050, Disclosure of Ownership or Control by the Government of a Country that is a State Sponsor of Terrorism. Applies to all solicitations expected to result in contracts of \$150,000 or more.

(vi) 252.229-7012, Tax Exemptions (Italy)-Representation. Applies to solicitations and contracts when contract performance will be in Italy.

(vii) 252.229-7013, Tax Exemptions (Spain)-Representation. Applies to solicitations and contracts when contract performance will be in Spain.

(2) The following representations or certifications in SAM are applicable to this solicitation as indicated by the Contracting Officer: [Contracting Officer check as appropriate.]

☐ (i) 252.209-7002, Disclosure of Ownership or Control by a Foreign Government.

☐ (ii) 252.225-7000, Buy American-Balance of Payments Program Certificate.

☐ (iii) 252.225-7020, Trade Agreements Certificate.

☐ Use with Alternate I.

☐ (iv) 252.225-7031, Secondary Arab Boycott of Israel.

☐ (v) 252.225-7035, Buy American-Free Trade Agreements-Balance of Payments Program Certificate.

☐ Use with Alternate I.

[] Use with Alternate II.

[] Use with Alternate III.

[] Use with Alternate IV.

[] Use with Alternate V.

[](vi) 252.226-7002, Representation for Demonstration Project for Contractors Employing Persons with Disabilities.

[](vii) 252.232-7015, Performance-Based Payments-Representation.

(e) The Offeror has completed the annual representations and certifications electronically via the SAM website at <https://www.sam.gov>. After reviewing the SAM database information, the Offeror verifies by submission of the offer that the representations and certifications currently posted electronically that apply to this solicitation as indicated in FAR 52.204-8(c) and paragraph (d) of this provision have been entered or updated within the last 12 months, are current, accurate, complete, and applicable to this solicitation (including the business size standard applicable to the NAICS code referenced for this solicitation), as of the date of this offer, and are incorporated in this offer by reference (see FAR 4.1201); except for the changes identified below [Offeror to insert changes, identifying change by provision number, title, date]. These amended representation(s) and/or certification(s) are also incorporated in this offer and are current, accurate, and complete as of the date of this offer.

FAR/DFARS Provision #	Title	Date	Change
-----------------------	-------	------	--------

Any changes provided by the Offeror are applicable to this solicitation only, and do not result in an update to the representations and certifications located in the SAM database.

(End of provision)

Section 00700 - Conditions of the Contract

FAR Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
52.203-3	Gratuities.	Apr 1984		
52.203-5	Covenant Against Contingent Fees.	May 2014		
52.203-7	Anti-Kickback Procedures.	Jun 2020		
52.203-8	Cancellation, Rescission, and Recovery of Funds for Illegal or Improper Activity.	May 2014		
52.203-10	Price or Fee Adjustment for Illegal or Improper Activity.	May 2014		
52.203-12	Limitation on Payments to Influence Certain Federal Transactions.	Jun 2020		
52.203-13	Contractor Code of Business Ethics and Conduct.	Nov 2021		
52.204-10	Reporting Executive Compensation and First-Tier Subcontract Awards.	Jun 2020		
52.204-13	System for Award Management Maintenance.	Oct 2018		
52.204-18	Commercial and Government Entity Code Maintenance.	Aug 2020		
52.204-19	Incorporation by Reference of Representations and Certifications.	Dec 2014		
52.209-6	Protecting the Government's Interest When Subcontracting With Contractors Debarred, Suspended, Proposed for Debarment, or Voluntarily Excluded	Jan 2025		
52.209-9	Updates of Publicly Available Information Regarding Responsibility Matters.	Oct 2018		
52.209-10	Prohibition on Contracting with Inverted Domestic Corporations.	Nov 2015		
52.210-1	Market Research.	Nov 2021		
52.211-18	Variation in Estimated Quantity.	Apr 1984		
52.219-9	Small Business Subcontracting Plan. (Alternate I)	Jan 2025	Alternate I	Nov 2016
52.222-3	Convict Labor.	Jun 2003		
52.222-7	Withholding of Funds.	May 2014		
52.222-50	Combating Trafficking in Persons.	Nov 2021		
52.222-54	Employment Eligibility Verification.	Jan 2025		
52.225-11	Buy American-Construction Materials under Trade Agreements. (Alternate I)	Nov 2023	Alternate I	Nov 2023
52.225-12	Notice of Buy American Requirement-Construction Materials Under Trade Agreements. (Alternate II)	May 2014	Alternate II	Nov 2023
52.225-13	Restrictions on Certain Foreign Purchases.	Feb 2021		
52.232-16	Progress Payments. (Alternate III)	Nov 2021	Alternate III	Jun 2020
52.232-23	Assignment of Claims.	May 2014		
52.232-27	Prompt Payment for Construction Contracts.	Jan 2017		
52.232-39	Unenforceability of Unauthorized Obligations.	Jun 2013		
52.233-1	Disputes.	May 2014		
52.233-1	Disputes. (Alternate I)	May 2014	Alternate I	Dec 1991
52.233-3	Protest after Award.	Aug 1996		
52.233-4	Applicable Law for Breach of Contract Claim.	Oct 2004		
52.236-2	Differing Site Conditions.	Apr 1984		
52.236-3	Site Investigation and Conditions Affecting the Work.	Apr 1984		
52.236-5	Material and Workmanship.	Apr 1984		
52.236-6	Superintendence by the Contractor.	Apr 1984		
52.236-7	Permits and Responsibilities.	Nov 1991		
52.236-8	Other Contracts.	Apr 1984		
52.236-9	Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements.	Apr 1984		
52.236-10	Operations and Storage Areas.	Apr 1984		
52.236-11	Use and Possession Prior to Completion.	Apr 1984		
52.236-12	Cleaning Up.	Apr 1984		
52.236-13	Accident Prevention.	Nov 1991		
52.236-15	Schedules for Construction Contracts.	Apr 1984		
52.236-16	Quantity Surveys. (Alternate I)	Apr 1984	Alternate I	Apr 1984
52.236-17	Layout of Work.	Apr 1984		
52.236-21	Specifications and Drawings for Construction.	Feb 1997		
52.236-26	Preconstruction Conference.	Feb 1995		
52.240-1	Prohibition on Unmanned Aircraft Systems Manufactured or Assembled by American Security Drone Act-Covered Foreign Entities.	Nov 2024		
52.242-13	Bankruptcy.	Jul 1995		
52.242-14	Suspension of Work.	Apr 1984		
52.243-4	Changes.	Jun 2007		
52.249-2	Termination for Convenience of the Government (Fixed-Price).	Apr 2012		
52.249-2	Termination for Convenience of the Government (Fixed-Price). (Alternate I)	Apr 2012	Alternate I	Sep 1996
52.249-10	Default (Fixed-Price Construction).	Apr 1984		

DFARS Clauses Incorporated by Reference

Number	Title	Effective	Alternate/ Deviation	Variation Effective
--------	-------	-----------	-------------------------	------------------------

		Date	Deviation	Date
252.225-7056	Prohibition Regarding Business Operations with the Maduro Regime.	Jan 2023		
252.225-7060	Prohibition on Certain Procurements from the Xinjiang Uyghur Autonomous Region.	Jun 2023		
252.226-7003	Drug-Free Work Force.	Aug 2024		
252.232-7010	Levies on Contract Payments.	Dec 2006		
252.244-7000	Subcontracts for Commercial Products or Commercial Services.	Nov 2023		
252.247-7023	Transportation of Supplies by Sea.	Oct 2024		

FAR Clauses Incorporated by Full Text

52.204-1 Approval of Contract. (Dec 1989)

Approval of Contract (Dec 1989)

This contract is subject to the written approval of ____ [identify title of designated agency official here] and shall not be binding until so approved.

(End of clause)

52.211-10 Commencement, Prosecution, and Completion of Work. (Apr 1984)

Commencement, Prosecution, and Completion of Work (Apr 1984)

The Contractor shall be required to (a) commence work under this contract within 5[Contracting Officer insert number] calendar days after the date the Contractor receives the notice to proceed, (b) prosecute the work diligently, and (c) complete the entire work ready for use not later than the days described in Section 00010, paragraph entitled "Conditions of Contract Award.* The time stated for completion shall include final cleanup of the premises.

* The Contracting Officer shall specify either a number of days after the date the contractor receives the notice to proceed, or a calendar date.

(End of clause)

52.217-7 Option for Increased Quantity-Separately Priced Line Item. (Mar 1989)

Option for Increased Quantity-Separately Priced Line Item (Mar 1989)

The Government may require the delivery of the numbered line item, identified in the Schedule as an option item, in the quantity and at the price stated in the Schedule. The Contracting Officer may exercise the option by written notice to the Contractor within 3[insert in the clause the period of time in which the Contracting Officer has to exercise the option]. Delivery of added items shall continue at the same rate that like items are called for under the contract, unless the parties otherwise agree.

(End of clause)

52.219-28 Postaward Small Business Program Rerepresentation. (Alternate I) (Jan 2025) Alternate I (Mar 2020)

Alternate I (Mar 2020). As prescribed in 19.309 (c)(2), substitute the following paragraph (h)(1) for paragraph (h)(1) of the basic clause:

(h)(1) The Contractor represents its small business size status for each one of the NAICS codes assigned to this contract.

NAICS Code	Small business concern (yes/no)
_____	_____
_____	_____
_____	_____

[Contracting Officer to insert NAICS codes.]

52.232-5 Payments under Fixed-Price Construction Contracts. (May 2014)

Payments under Fixed-Price Construction Contracts (May 2014)

(a) Payment of price. The Government shall pay the Contractor the contract price as provided in this contract.

(b) Progress payments. The Government shall make progress payments monthly as the work proceeds, or at more frequent intervals as determined by the Contracting Officer, on estimates of work accomplished which meets the standards of quality established under the contract, as approved by the Contracting Officer.

(1) The Contractor's request for progress payments shall include the following substantiation:

- (i) An itemization of the amounts requested, related to the various elements of work required by the contract covered by the payment requested.
- (ii) A listing of the amount included for work performed by each subcontractor under the contract.
- (iii) A listing of the total amount of each subcontract under the contract.
- (iv) A listing of the amounts previously paid to each such subcontractor under the contract.
- (v) Additional supporting data in a form and detail required by the Contracting Officer.

(2) In the preparation of estimates, the Contracting Officer may authorize material delivered on the site and preparatory work done to be taken into consideration. Material delivered to the Contractor at locations other than the site also may be taken into consideration if-

- (i) Consideration is specifically authorized by this contract; and
 - (ii) The Contractor furnishes satisfactory evidence that it has acquired title to such material and that the material will be used to perform this contract.
- (c) Contractor certification. Along with each request for progress payments, the Contractor shall furnish the following certification, or payment shall not be made: (However, if the Contractor elects to delete paragraph (c)(4) from the certification, the certification is still acceptable.)

I hereby certify, to the best of my knowledge and belief, that-

- (1) The amounts requested are only for performance in accordance with the specifications, terms, and conditions of the contract;
- (2) All payments due to subcontractors and suppliers from previous payments received under the contract have been made, and timely payments will be made from the proceeds of the payment covered by this certification, in accordance with subcontract agreements and the requirements of Chapter 39 of Title 31, United States Code;
- (3) This request for progress payments does not include any amounts which the prime contractor intends to withhold or retain from a subcontractor or supplier in accordance with the terms and conditions of the subcontract; and
- (4) This certification is not to be construed as final acceptance of a subcontractor's performance.

____ (Name)

____ (Title)

____ (Date)

(d) Refund of unearned amounts. If the Contractor, after making a certified request for progress payments, discovers that a portion or all of such request constitutes a payment for performance by the Contractor that fails to conform to the specifications, terms, and conditions of this contract (hereinafter referred to as the "unearned amount"), the Contractor shall-

- (1) Notify the Contracting Officer of such performance deficiency; and
 - (2) Be obligated to pay the Government an amount (computed by the Contracting Officer in the manner provided in paragraph (j) of this clause) equal to interest on the unearned amount from the 8 thday after the date of receipt of the unearned amount until-
- (i) The date the Contractor notifies the Contracting Officer that the performance deficiency has been corrected; or
 - (ii) The date the Contractor reduces the amount of any subsequent certified request for progress payments by an amount equal to the unearned amount.

(e) Retainage. If the Contracting Officer finds that satisfactory progress was achieved during any period for which a progress payment is to be made, the Contracting Officer shall authorize payment to be made in full. However, if satisfactory progress has not been made, the Contracting Officer may retain a maximum of 10 percent of the amount of the payment until satisfactory progress is achieved. When the work is substantially complete, the Contracting Officer may retain from previously withheld funds and future progress payments that amount the Contracting Officer considers adequate for protection of the Government and shall release to the Contractor all the remaining withheld funds. Also, on completion and acceptance of each separate building, public work, or other division of the contract, for which the price is stated separately in the contract, payment shall be made for the completed work without retention of a percentage.

(f) Title, liability, and reservation of rights. All material and work covered by progress payments made shall, at the time of payment, become the sole property of the Government, but this shall not be construed as-

- (1) Relieving the Contractor from the sole responsibility for all material and work upon which payments have been made or the restoration of any damaged work; or
- (2) Waiving the right of the Government to require the fulfillment of all of the terms of the contract.

(g) Reimbursement for bond premiums. In making these progress payments, the Government shall, upon request, reimburse the Contractor for the amount of premiums paid for performance and payment bonds (including coinsurance and reinsurance agreements, when applicable) after the Contractor has furnished evidence of full payment to the surety. The retainage provisions in paragraph (e) of this clause shall not apply to that portion

of progress payments attributable to bond premiums.

(h) Final payment. The Government shall pay the amount due the Contractor under this contract after-

(1) Completion and acceptance of all work;

(2) Presentation of a properly executed voucher; and

(3) Presentation of release of all claims against the Government arising by virtue of this contract, other than claims, in stated amounts, that the Contractor has specifically excepted from the operation of the release. A release may also be required of the assignee if the Contractor's claim to amounts payable under this contract has been assigned under the Assignment of Claims Act of 1940 (31 U.S.C.3727 and 41 U.S.C.6305).

(i) Limitation because of undefinitized work. Notwithstanding any provision of this contract, progress payments shall not exceed 80 percent on work accomplished on undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in FAR subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes.

(j) Interest computation on unearned amounts. In accordance with 31 U.S.C.3903(c)(1), the amount payable under paragraph (d)(2) of this clause shall be-

(1) Computed at the rate of average bond equivalent rates of 91-day Treasury bills auctioned at the most recent auction of such bills prior to the date the Contractor receives the unearned amount; and

(2) Deducted from the next available payment to the Contractor.

(End of clause)

52.236-1 Performance of Work by the Contractor.

(Apr 1984)

Performance of Work by the Contractor (Apr 1984)

The Contractor shall perform on the site, and with its own organization, work equivalent to at least 20% twenty[insert the appropriate number in words followed by numerals in parentheses] percent of the total amount of work to be performed under the contract. This percentage may be reduced by a supplemental agreement to this contract if, during performing the work, the Contractor requests a reduction and the Contracting Officer determines that the reduction would be to the advantage of the Government.

(End of clause)

52.248-3 Value Engineering-Construction.

(Oct 2020)

Value Engineering-Construction (Oct 2020)

(a) General. The Contractor is encouraged to develop, prepare, and submit value engineering change proposals (VECP's) voluntarily. The Contractor shall share in any instant contract savings realized from accepted VECP's, in accordance with paragraph (f) of this clause.

(b) Definitions. "Collateral costs," as used in this clause, means agency costs of operation, maintenance, logistic support, or Government-furnished property.

Collateral savings, as used in this clause, means those measurable net reductions resulting from a VECP in the agency's overall projected collateral costs, exclusive of acquisition savings, whether or not the acquisition cost changes.

Contractor's development and implementation costs, as used in this clause, means those costs the Contractor incurs on a VECP specifically in developing, testing, preparing, and submitting the VECP, as well as those costs the Contractor incurs to make the contractual changes required by Government acceptance of a VECP.

Government costs, as used in this clause, means those agency costs that result directly from developing and implementing the VECP, such as any net increases in the cost of testing, operations, maintenance, and logistic support. The term does not include the normal administrative costs of processing the VECP.

Instant contract savings, as used in this clause, means the estimated reduction in Contractor cost of performance resulting from acceptance of the VECP, minus allowable Contractor's development and implementation costs, including subcontractors' development and implementation costs (see paragraph (h) of this clause).

Value engineering change proposal (VECP) means a proposal that-

(1) Requires a change to this, the instant contract, to implement; and

(2) Results in reducing the contract price or estimated cost without impairing essential functions or characteristics; provided, that it does not involve a change-

(i) In deliverable end item quantities only; or

(ii) To the contract type only.

(c) VECP preparation. As a minimum, the Contractor shall include in each VECP the information described in paragraphs (c)(1) through (7) of this clause. If the proposed change is affected by contractually required configuration management or similar procedures, the instructions in those procedures relating to format, identification, and priority assignment shall govern VECP preparation. The VECP shall include the following:

(1) A description of the difference between the existing contract requirement and that proposed, the comparative advantages and disadvantages of each, a justification when an item's function or characteristics are being altered, and the effect of the change on the end item's performance.

(2) A list and analysis of the contract requirements that must be changed if the VECP is accepted, including any suggested specification revisions.

(3) A separate, detailed cost estimate for (i) the affected portions of the existing contract requirement and (ii) the VECP. The cost reduction associated with the VECP shall take into account the Contractor's allowable development and implementation costs, including any amount attributable to subcontracts under paragraph (h) of this clause.

(4) A description and estimate of costs the Government may incur in implementing the VECP, such as test and evaluation and operating and support costs.

(5) A prediction of any effects the proposed change would have on collateral costs to the agency.

(6) A statement of the time by which a contract modification accepting the VECP must be issued in order to achieve the maximum cost reduction, noting any effect on the contract completion time or delivery schedule.

(7) Identification of any previous submissions of the VECP, including the dates submitted, the agencies and contract numbers involved, and previous Government actions, if known.

(d) Submission. The Contractor shall submit VECP's to the Resident Engineer at the worksite, with a copy to the Contracting Officer.

(e) Government action.

(1) The Contracting Officer will notify the Contractor of the status of the VECP within 45 calendar days after the contracting office receives it. If additional time is required, the Contracting Officer will notify the Contractor within the 45-day period and provide the reason for the delay and the expected date of the decision. The Government will process VECP's expeditiously; however, it will not be liable for any delay in acting upon a VECP.

(2) If the VECP is not accepted, the Contracting Officer will notify the Contractor in writing, explaining the reasons for rejection. The Contractor may withdraw any VECP, in whole or in part, at any time before it is accepted by the Government. The Contracting Officer may require that the Contractor provide written notification before undertaking significant expenditures for VECP effort.

(3) Any VECP may be accepted, in whole or in part, by the Contracting Officer's award of a modification to this contract citing this clause. The Contracting Officer may accept the VECP, even though an agreement on price reduction has not been reached, by issuing the Contractor a notice to proceed with the change. Until a notice to proceed is issued or a contract modification applies a VECP to this contract, the Contractor shall perform in accordance with the existing contract. The decision to accept or reject all or part of any VECP is a unilateral decision made solely at the discretion of the Contracting Officer.

(f) Sharing-

(1) Rates. The Government's share of savings is determined by subtracting Government costs from instant contract savings and multiplying the result by-

(i) 45 percent for fixed-price contracts; or

(ii) 75 percent for cost-reimbursement contracts.

(2) Payment. Payment of any share due the Contractor for use of a VECP on this contract shall be authorized by a modification to this contract to-

(i) Accept the VECP;

(ii) Reduce the contract price or estimated cost by the amount of instant contract savings; and

(iii) Provide the Contractor's share of savings by adding the amount calculated to the contract price or fee.

(g) Collateral savings. If a VECP is accepted, the Contracting Officer will increase the instant contract amount by 20 percent of any projected collateral savings determined to be realized in a typical year of use after subtracting any Government costs not previously offset. However, the

Contractor's share of collateral savings will not exceed the contract's firm-fixed-price or estimated cost, at the time the VECP is accepted, or \$100,000, whichever is greater. The Contracting Officer is the sole determiner of the amount of collateral savings.

(h) Subcontracts. The Contractor shall include an appropriate value engineering clause in any subcontract of \$75,000 or more and may include one in subcontracts of lesser value. In computing any adjustment in this contract's price under paragraph (f) of this clause, the Contractor's allowable development and implementation costs shall include any subcontractor's allowable development and implementation costs clearly resulting from a VECP accepted by the Government under this contract, but shall exclude any value engineering incentive payments to a subcontractor. The Contractor may choose any arrangement for subcontractor value engineering incentive payments; provided, that these payments shall not reduce the Government's share of the savings resulting from the VECP.

(i) Data. The Contractor may restrict the Government's right to use any part of a VECP or the supporting data by marking the following legend on the affected parts:

These data, furnished under the Value Engineering-Construction clause of contract ____, shall not be disclosed outside the Government or duplicated, used, or disclosed, in whole or in part, for any purpose other than to evaluate a value engineering change proposal submitted under the clause. This restriction does not limit the Government's right to use information contained in these data if it has been obtained or is otherwise available from the Contractor or from another source without limitations.

If a VECP is accepted, the Contractor hereby grants the Government unlimited rights in the VECP and supporting data, except that, with respect to data qualifying and submitted as limited rights technical data, the Government shall have the rights specified in the contract modification implementing the VECP and shall appropriately mark the data. (The terms "unlimited rights" and "limited rights" are defined in part 27 of the Federal Acquisition Regulation.)

(End of clause)

52.252-2 Clauses Incorporated by Reference.

(Feb 1998)

Clauses Incorporated By Reference (Feb 1998)

This contract incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of a clause may be accessed electronically at this/these address(es):

www.acquisition.gov ____ [Insert one or more Internet addresses]

(End of clause)

52.252-4 Alterations in Contract.

(Apr 1984)

Alterations in Contract (Apr 1984)

Portions of this contract are altered as follows:

(End of clause)

52.252-6 Authorized Deviations in Clauses.

(Nov 2020)

Authorized Deviations in Clauses (Nov 2020)

(a) The use in this solicitation or contract of any Federal Acquisition Regulation (48 CFR Chapter 1) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the date of the clause.

(b) The use in this solicitation or contract of any ____ [insert regulation name] (48 CFR ____) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the name of the regulation.

(End of clause)

Section 00 72 00 - General Conditions

FAR Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
52.202-1	Definitions.	Jun 2020		
52.203-6	Restrictions on Subcontractor Sales to the Government.	Jun 2020		
52.203-19	Prohibition on Requiring Certain Internal Confidentiality Agreements or Statements.	Jan 2017		
52.204-23	Prohibition on Contracting for Hardware, Software, and Services Developed or Provided by Kaspersky Lab Covered Entities.	Dec 2023		
52.204-25	Prohibition on Contracting for Certain Telecommunications and Video Surveillance Services or Equipment.	Nov 2021		
52.204-27	Prohibition on a ByteDance Covered Application.	Jun 2023		
52.214-18	Preparation of Bids-Construction.	Apr 1984		
52.214-19	Contract Award-Sealed Bidding-Construction.	Aug 1996		
52.214-26	Audit and Records-Sealed Bidding.	Jun 2020		
52.214-27	Price Reduction for Defective Certified Cost or Pricing Data-Modifications-Sealed Bidding.	Jun 2020		
52.214-28	Subcontractor Certified Cost or Pricing Data-Modifications-Sealed Bidding.	Jun 2020		
52.214-29	Order of Precedence-Sealed Bidding.	Jan 1986		
52.219-8	Utilization of Small Business Concerns.	Jan 2025		
52.219-9	Small Business Subcontracting Plan.	Jan 2025		
52.219-16	Liquidated Damages-Subcontracting Plan.	Sep 2021		
52.219-33	Nonmanufacturer Rule.	Sep 2021		
52.222-6	Construction Wage Rate Requirements.	Aug 2018		
52.222-8	Payrolls and Basic Records.	Jul 2021		
52.222-9	Apprentices and Trainees.	Jul 2005		
52.222-10	Compliance with Copeland Act Requirements.	Feb 1988		
52.222-11	Subcontracts (Labor Standards).	May 2014		
52.222-12	Contract Termination-Debarment.	May 2014		
52.222-13	Compliance with Construction Wage Rate Requirements and Related Regulations.	May 2014		
52.222-14	Disputes Concerning Labor Standards.	Feb 1988		
52.222-15	Certification of Eligibility.	May 2014		
52.222-32	Construction Wage Rate Requirements-Price Adjustment (Actual Method).	Aug 2018		
52.222-35	Equal Opportunity for Veterans.	Jun 2020		
52.222-36	Equal Opportunity for Workers with Disabilities.	Jun 2020		
52.222-37	Employment Reports on Veterans.	Jun 2020		
52.222-40	Notification of Employee Rights Under the National Labor Relations Act.	Dec 2010		
52.222-55	Minimum Wages for Contractor Workers Under Executive Order 14026.	Jan 2022		
52.222-62	Paid Sick Leave Under Executive Order 13706.	Jan 2022		
52.223-21	Foams.	May 2024		
52.223-23	Sustainable Products and Services.	May 2024		
52.226-7	Drug-Free Workplace.	May 2024		
52.226-8	Encouraging Contractor Policies to Ban Text Messaging While Driving.	May 2024		
52.228-2	Additional Bond Security.	Oct 1997		
52.228-11	Individual Surety-Pledge of Assets.	Feb 2021		
52.228-12	Prospective Subcontractor Requests for Bonds.	Dec 2022		
52.228-14	Irrevocable Letter of Credit.	Nov 2014		
52.228-15	Performance and Payment Bonds-Construction.	Jun 2020		
52.228-17	Individual Surety-Pledge of Assets (Bid Guarantee).	Feb 2021		
52.229-3	Federal, State, and Local Taxes.	Feb 2013		
52.229-11	Tax on Certain Foreign Procurements-Notice and Representation.	Jun 2020		
52.232-8	Discounts for Prompt Payment.	Feb 2002		
52.232-15	Progress Payments Not Included.	Apr 1984		
52.232-17	Interest.	May 2014		
52.232-33	Payment by Electronic Funds Transfer-System for Award Management.	Oct 2018		
52.232-40	Providing Accelerated Payments to Small Business Subcontractors.	Mar 2023		
52.242-5	Payments to Small Business Subcontractors.	Jan 2017		
52.244-6	Subcontracts for Commercial Products and Commercial Services.	Jan 2025		
52.246-12	Inspection of Construction.	Aug 1996		
52.247-12	Supervision, Labor, or Materials.	Apr 1984		
52.253-1	Computer Generated Forms.	Jan 1991		

DFARS Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
--------	-------	----------------	-------------------------	--------------------------------

252.201-7000	Contracting Officer's Representative.	Dec 1991
252.203-7000	Requirements Relating to Compensation of Former DoD Officials.	Sep 2011
252.203-7001	Prohibition on Persons Convicted of Fraud or Other Defense-Contract-Related Felonies.	Jan 2023
252.203-7002	Requirement to Inform Employees of Whistleblower Rights.	Dec 2022
252.203-7003	Agency Office of the Inspector General.	Aug 2019
252.203-7004	Display of Hotline Posters.	Jan 2023
252.204-7003	Control of Government Personnel Work Product.	Apr 1992
252.204-7012	Safeguarding Covered Defense Information and Cyber Incident Reporting.	May 2024
252.204-7018	Prohibition on the Acquisition of Covered Defense Telecommunications Equipment or Services.	Jan 2023
252.204-7020	NIST SP 800-171 DoD Assessment Requirements.	Nov 2023
252.205-7000	Provision of Information to Cooperative Agreement Holders.	Oct 2024
252.209-7004	Subcontracting with Firms that are Owned or Controlled by the Government of a Country that is a State Sponsor of Terrorism.	May 2019
252.219-7003	Small Business Subcontracting Plan (DoD Contracts).	Dec 2019
252.222-7006	Restrictions on the Use of Mandatory Arbitration Agreements.	Jan 2023
252.223-7008	Prohibition of Hexavalent Chromium.	Jan 2023
252.225-7012	Preference for Certain Domestic Commodities.	Apr 2022
252.225-7048	Export-Controlled Items.	Jun 2013
252.225-7058	Postaward Disclosure of Employment of Individuals Who Work in the People's Republic of China.	Jan 2023
252.226-7001	Utilization of Indian Organizations, Indian-Owned Economic Enterprises, and Native Hawaiian Small Business Concerns.	Jan 2023
252.232-7003	Electronic Submission of Payment Requests and Receiving Reports.	Dec 2018
252.236-7000	Modification Proposals--Price Breakdown.	Dec 1991
252.236-7002	Obstruction of Navigable Waterways.	Dec 1991
252.242-7004	Material Management and Accounting System.	Jan 2025
252.242-7006	Accounting System Administration.	Jan 2025
252.243-7001	Pricing of Contract Modifications.	Dec 1991
252.243-7002	Requests for Equitable Adjustment.	Dec 2022

FAR Clauses Incorporated by Full Text

52.219-28 Postaward Small Business Program Rerepresentation.

(Jan 2025)

Postaward Small Business Program Rerepresentation (Jan 2025)

(a) Definitions. As used in this clause-

Long-term contract means a contract of more than five years in duration, including options. However, the term does not include contracts that exceed five years in duration because the period of performance has been extended for a cumulative period not to exceed six months under the clause at 52.217-8, Option to Extend Services, or other appropriate authority.

Small business concern-

(1) Means a concern, including its affiliates, that is independently owned and operated, not dominant in its field of operation, and qualified as a small business under the criteria in 13 CFR part 121 and the size standard in paragraph (d) of this clause.

(2) Affiliates, as used in this definition, means business concerns, one of whom directly or indirectly controls or has the power to control the others, or a third party or parties control or have the power to control the others. In determining whether affiliation exists, consideration is given to all appropriate factors including common ownership, common management, and contractual relationships. SBA determines affiliation based on the factors set forth at 13 CFR 121.103.

(b) If the Contractor represented that it was any of the small business concerns identified in 19.000(a)(3) prior to award of this contract, the Contractor shall rerepresent its size and socioeconomic status according to paragraph (f) of this clause or, if applicable, paragraph (h) of this clause, upon occurrence of any of the following:

(1) Within 30 days after execution of a novation agreement or within 30 days after modification of the contract to include this clause, if the novation agreement was executed prior to inclusion of this clause in the contract.

(2) Within 30 days after a merger or acquisition that does not require a novation or within 30 days after modification of the contract to include this clause, if the merger or acquisition occurred prior to inclusion of this clause in the contract.

(3) For long-term contracts-

(i) Within 60 to 120 days prior to the end of the fifth year of the contract; and

(ii) Within 60 to 120 days prior to the date specified in the contract for exercising any option thereafter.

(c) If the Contractor represented its status as any of the small business concerns identified at 19.000(a)(3) prior to award of this contract, the Contractor shall rerepresent its size and socioeconomic status according to paragraph (f) of this clause or, if applicable, paragraph (h) of this clause, for the NAICS code assigned to an order (except that paragraphs (c)(1) through (3) of this clause do not apply to an order issued under a Federal Supply Schedule contract at subpart 8.4)-

(1) Set aside exclusively for a small business concern identified at 19.000(a)(3) that is issued under an unrestricted multiple-award contract, unless the order is issued under the reserved portion of an unrestricted multiple-award contract (e.g., an order set aside for a woman-owned small business under a multiple-award contract that is not set-aside, unless the order is issued under the reserved portion of the multiple-award contract);

(2) Issued under a multiple-award contract set aside for small businesses that is further set aside for a specific socioeconomic category that differs from the underlying multiple-award contract (e.g., an order set aside for a HUBZone small business concern under a multiple-award contract that is set aside for small businesses);

(3) Issued under the part of the multiple-award contract that is set aside for small businesses that is further set aside for a specific socioeconomic category that differs from the underlying set-aside part of the multiple-award contract (e.g., an order set aside for a WOSB concern under the part of the multiple-award contract that is partially set aside for small businesses); and

(4) When the Contracting Officer explicitly requires it for an order issued under a multiple-award contract, including for an order issued under a Federal Supply Schedule contract (see 8.405-5(b) and 19.301-2(b)(2)).

(d) The Contractor shall rerepresent its size status in accordance with the size standard in effect at the time of this rerepresentation that corresponds to the North American Industry Classification System (NAICS) code(s) assigned to this contract. The small business size standard corresponding to this NAICS code(s) can be found at <https://www.sba.gov/document/support--table-size-standards>.

(e) The small business size standard for a Contractor providing an end item that it does not manufacture, process, or produce itself, for a contract other than a construction or service contract, is 500 employees, or 150 employees for information technology value-added resellers under NAICS code 541519, if the acquisition-

(1) Was set aside for small business and has a value above the simplified acquisition threshold;

(2) Used the HUBZone price evaluation preference regardless of dollar value, unless the Contractor waived the price evaluation preference; or

(3) Was an 8(a), HUBZone, service-disabled veteran-owned, economically disadvantaged women-owned, or women-owned small business set-aside or sole-source award regardless of dollar value.

(f) Except as provided in paragraph (h) of this clause, the Contractor shall make the representation(s) required by paragraphs (b) and (c) of this clause by validating or updating all its representations in the Representations and Certifications section of the System for Award Management (SAM) and its other data in SAM, as necessary, to ensure that they reflect the Contractor's current status. The Contractor shall notify the contracting officer in writing within the timeframes specified in paragraph (b) of this clause, or with its offer for an order (see paragraph (c) of this clause), that the data have been validated or updated, and provide the date of the validation or update.

(g) If the Contractor represented that it was other than a small business concern prior to award of this contract, the Contractor may, but is not required to, take the actions required by paragraphs (f) or (h) of this clause.

(h) If the Contractor does not have representations and certifications in SAM, or does not have a representation in SAM for the NAICS code applicable to this contract, the Contractor is required to complete the following rerepresentation and submit it to the contracting office, along with the contract number and the date on which the rerepresentation was completed:

(1) The Contractor represents that it ☐ is, ☐ is not a small business concern under ____ NAICS Code assigned to ____ contract number.

(2) [Complete only if the Contractor represented itself as a small business concern in paragraph (h)(1) of this clause.] The Contractor represents that it ☐ is, ☐ is not, a small disadvantaged business concern as defined in 13 CFR 124.1001.

(3) [Complete only if the Contractor represented itself as a small business concern in paragraph (h)(1) of this clause.] The Contractor represents that it ☐ is, ☐ is not a women-owned small business concern.

(4) Women-owned small business (WOSB) joint venture eligible under the WOSB Program. The Contractor represents that it ☐ is, ☐ is not a joint venture that complies with the requirements of 13 CFR 127.506(a) through (c). [____ The Contractor shall enter the name and unique entity identifier of each party to the joint venture: ____.]

(5) Economically disadvantaged women-owned small business (EDWOSB) joint venture. The Contractor represents that it ☐ is, ☐ is not a joint venture that complies with the requirements of 13 CFR 127.506(a) through (c). [____ The Contractor shall enter the name and unique entity identifier of each party to the joint venture: ____.]

(6) [Complete only if the Contractor represented itself as a small business concern in paragraph (h)(1) of this clause.] The Contractor represents that it ☐ is, ☐ is not a veteran-owned small business concern.

(7) [Complete only if the Contractor represented itself as a veteran-owned small business concern in paragraph (h)(6) of this clause.] The Contractor represents that it ☐ is, ☐ is not a service-disabled veteran-owned small business concern.

(8) Service-disabled veteran-owned small business (SDVOSB) joint venture eligible under the SDVOSB Program. The Contractor represents that it ☐

is, [] is not an SDVOSB joint venture eligible under the SDVOSB Program that complies with the requirements of 13 CFR 128.402. [____] The Contractor shall enter the name and unique entity identifier of each party to the joint venture: ____.]

(9) [Complete only if the Contractor represented itself as a small business concern in paragraph (h)(1) of this clause.] The Contractor represents that-

(i) It [] is, [] is not a HUBZone small business concern listed, on the date of this representation, on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration, and no material changes in ownership and control, principal office, or HUBZone employee percentage have occurred since it was certified in accordance with 13 CFR part 126; and

(ii) It [] is, [] is not a HUBZone joint venture that complies with the requirements of 13 CFR part 126, and the representation in paragraph (h)(8)(i) of this clause is accurate for each HUBZone small business concern participating in the HUBZone joint venture. [____] The Contractor shall enter the names of each of the HUBZone small business concerns participating in the HUBZone joint venture: .] Each HUBZone small business concern participating in the HUBZone joint venture shall submit a separate signed copy of the HUBZone representation.

[____] Contractor to sign and date and insert authorized signer's name and title.]

(End of clause)

52.225-11 Buy American-Construction Materials under Trade Agreements.

(Nov 2023)

Buy American-Construction Materials under Trade Agreements (Nov 2023)

(a) Definitions. As used in this clause-

Caribbean Basin country construction material means a construction material that-

(1) Is wholly the growth, product, or manufacture of a Caribbean Basin country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a Caribbean Basin country into a new and different construction material distinct from the materials from which it was transformed.

Commercially available off-the-shelf (COTS) item-

(1) Means any item of supply (including construction material) that is-

(i) A commercial product (as defined in paragraph (1) of the definition of "commercial product" at Federal Acquisition Regulation (FAR) 2.101);

(ii) Sold in substantial quantities in the commercial marketplace; and

(iii) Offered to the Government, under a contract or subcontract at any tier, without modification, in the same form in which it is sold in the commercial marketplace; and

(2) Does not include bulk cargo, as defined in 46 U.S.C.40102(4), such as agricultural products and petroleum products.

Component means an article, material, or supply incorporated directly into a construction material.

Construction material means an article, material, or supply brought to the construction site by the Contractor or subcontractor for incorporation into the building or work. The term also includes an item brought to the site preassembled from articles, materials, or supplies. However, emergency life safety systems, such as emergency lighting, fire alarm, and audio evacuation systems, that are discrete systems incorporated into a public building or work and that are produced as complete systems, are evaluated as a single and distinct construction material regardless of when or how the individual parts or components of those systems are delivered to the construction site. Materials purchased directly by the Government are supplies, not construction material.

Cost of components means-

(1) For components purchased by the Contractor, the acquisition cost, including transportation costs to the place of incorporation into the construction material (whether or not such costs are paid to a domestic firm), and any applicable duty (whether or not a duty-free entry certificate is issued); or

(2) For components manufactured by the Contractor, all costs associated with the manufacture of the component, including transportation costs as described in paragraph (1) of this definition, plus allocable overhead costs, but excluding profit. Cost of components does not include any costs associated with the manufacture of the construction material.

Critical component means a component that is mined, produced, or manufactured in the United States and deemed critical to the U.S. supply chain. The list of critical components is at FAR 25.105.

Critical item means a domestic construction material or domestic end product that is deemed critical to U.S. supply chain resiliency. The list of critical items is at FAR 25.105.

Designated country means any of the following countries:

(1) A World Trade Organization Government Procurement Agreement (WTO GPA) country (Armenia, Aruba, Australia, Austria, Belgium, Bulgaria, Canada, Croatia, Cyprus, Czech Republic, Denmark, Estonia, Finland, France, Germany, Greece, Hong Kong, Hungary, Iceland, Ireland, Israel, Italy, Japan, Korea (Republic of), Latvia, Liechtenstein, Lithuania, Luxembourg, Malta, Moldova, Montenegro, Netherlands, New Zealand, North Macedonia, Norway, Poland, Portugal, Romania, Singapore, Slovak Republic, Slovenia, Spain, Sweden, Switzerland, Taiwan, Ukraine, or United Kingdom);

(2) A Free Trade Agreement (FTA) country (Australia, Bahrain, Chile, Colombia, Costa Rica, Dominican Republic, El Salvador, Guatemala, Honduras, Korea (Republic of), Mexico, Morocco, Nicaragua, Oman, Panama, Peru, or Singapore);

(3) A least developed country (Afghanistan, Angola, Bangladesh, Benin, Bhutan, Burkina Faso, Burundi, Cambodia, Central African Republic, Chad, Comoros, Democratic Republic of Congo, Djibouti, Equatorial Guinea, Eritrea, Ethiopia, Gambia, Guinea, Guinea-Bissau, Haiti, Kiribati, Laos, Lesotho, Liberia, Madagascar, Malawi, Mali, Mauritania, Mozambique, Nepal, Niger, Rwanda, Samoa, Sao Tome and Principe, Senegal, Sierra Leone, Solomon Islands, Somalia, South Sudan, Tanzania, Timor-Leste, Togo, Tuvalu, Uganda, Vanuatu, Yemen, or Zambia); or

(4) A Caribbean Basin country (Antigua and Barbuda, Aruba, Bahamas, Barbados, Belize, Bonaire, British Virgin Islands, Curacao, Dominica, Grenada, Guyana, Haiti, Jamaica, Montserrat, Saba, St. Kitts and Nevis, St. Lucia, St. Vincent and the Grenadines, Sint Eustatius, Sint Maarten, or Trinidad and Tobago).

Designated country construction material means a construction material that is a WTO GPA country construction material, an FTA country construction material, a least developed country construction material, or a Caribbean Basin country construction material.

Domestic construction material means-

(1) For construction material that does not consist wholly or predominantly of iron or steel or a combination of both-

(i) An unmanufactured construction material mined or produced in the United States; or

(ii) A construction material manufactured in the United States, if-

(A) The cost of its components mined, produced, or manufactured in the United States exceeds 60 percent of the cost of all its components, except that the percentage will be 65 percent for items delivered in calendar years 2024 through 2028 and 75 percent for items delivered starting in calendar year 2029.

(B) The construction material is a COTS item; or

(2) For construction material that consists wholly or predominantly of iron or steel or a combination of both, a construction material manufactured in the United States if the cost of foreign iron and steel constitutes less than 5 percent of the cost of all components used in such construction material. The cost of foreign iron and steel includes but is not limited to the cost of foreign iron or steel mill products (such as bar, billet, slab, wire, plate, or sheet), castings, or forgings utilized in the manufacture of the construction material and a good faith estimate of the cost of all foreign iron or steel components excluding COTS fasteners. Iron or steel components of unknown origin are treated as foreign. If the construction material contains multiple components, the cost of all the materials used in such construction material is calculated in accordance with the definition of "cost of components".

Fastener means a hardware device that mechanically joins or affixes two or more objects together. Examples of fasteners are nuts, bolts, pins, rivets, nails, clips, and screws.

Foreign construction material means a construction material other than a domestic construction material.

Foreign iron and steel means iron or steel products not produced in the United States. Produced in the United States means that all manufacturing processes of the iron or steel must take place in the United States, from the initial melting stage through the application of coatings, except metallurgical processes involving refinement of steel additives. The origin of the elements of the iron or steel is not relevant to the determination of whether it is domestic or foreign.

Free Trade Agreement country construction material means a construction material that-

(1) Is wholly the growth, product, or manufacture of a Free Trade Agreement (FTA) country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a FTA country into a new and different construction material distinct from the materials from which it was transformed.

Least developed country construction material means a construction material that-

(1) Is wholly the growth, product, or manufacture of a least developed country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a least developed country into a new and different construction material distinct from the materials from which it was transformed.

Predominantly of iron or steel or a combination of both means that the cost of the iron and steel content exceeds 50 percent of the total cost of all its components. The cost of iron and steel is the cost of the iron or steel mill products (such as bar, billet, slab, wire, plate, or sheet), castings, or forgings utilized in the manufacture of the product and a good faith estimate of the cost of iron or steel components excluding COTS fasteners.

Steel means an alloy that includes at least 50 percent iron, between 0.02 and 2 percent carbon, and may include other elements.

United States means the 50 States, the District of Columbia, and outlying areas.

WTO GPA country construction material means a construction material that-

(1) Is wholly the growth, product, or manufacture of a WTO GPA country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a WTO GPA country into a new and different construction material distinct from the materials from which it was transformed.

(b) Construction materials.

(1) This clause implements 41 U.S.C. chapter 83, Buy American, by providing a preference for domestic construction material. In accordance with 41 U.S.C. 1907, the domestic content test of the Buy American statute is waived for construction material that is a COTS item, except that for construction material that consists wholly or predominantly of iron or steel or a combination of both, the domestic content test is applied only to the iron and steel content of the construction material, excluding COTS fasteners. (See FAR 12.505(a)(2)). In addition, the Contracting Officer has determined that the WTO GPA and Free Trade Agreements (FTAs) apply to this acquisition. Therefore, the Buy American restrictions are waived for designated country construction materials.

(2) The Contractor shall use only domestic or designated country construction material in performing this contract, except as provided in paragraphs (b)(3) and (b)(4) of this clause.

(3) The requirement in paragraph (b)(2) of this clause does not apply to information technology that is a commercial product or to the construction materials or components listed by the Government as follows:

_____ [Contracting Officer to list applicable excepted materials or indicate "none"]

(4) The Contracting Officer may add other foreign construction material to the list in paragraph (b)(3) of this clause if the Government determines that-

(i) The cost of domestic construction material would be unreasonable.

(A) For domestic construction material that is not a critical item or does not contain critical components.

(1) The cost of a particular domestic construction material subject to the restrictions of the Buy American statute is unreasonable when the cost of such material exceeds the cost of foreign material by more than 20 percent;

(2) For construction material that is not a COTS item and does not consist wholly or predominantly of iron or steel or a combination of both, if the cost of a particular domestic construction material is determined to be unreasonable or there is no domestic offer received, and the low offer is for foreign construction material that does not exceed 55 percent domestic content, the Contracting Officer will treat the lowest offer of foreign construction material that is manufactured in the United States and exceeds 55 percent domestic content as a domestic offer and determine whether the cost of that offer is unreasonable by applying the evaluation factor listed in paragraph (b)(4)(i)(A)(1) of this clause.

(3) The procedures in paragraph (b)(4)(i)(A)(2) of this clause will no longer apply as of January 1, 2030.

(B) For domestic construction material that is a critical item or contains critical components.

(1) The cost of a particular domestic construction material that is a critical item or contains critical components, subject to the requirements of the Buy American statute, is unreasonable when the cost of such material exceeds the cost of foreign material by more than 20 percent plus the additional preference factor identified for the critical item or construction material containing critical components listed at FAR 25.105.

(2) For construction material that does not consist wholly or predominantly of iron or steel or a combination of both, if the cost of a particular

domestic construction material is determined to be unreasonable or there is no domestic offer received, and the low offer is for foreign construction material that does not exceed 55 percent domestic content, the Contracting Officer will treat the lowest offer of foreign construction material that is manufactured in the United States and exceeds 55 percent domestic content as a domestic offer, and determine whether the cost of that offer is unreasonable by applying the evaluation factor listed in paragraph (b)(4)(i)(B)(1) of this clause.

(3) The procedures in paragraph (b)(4)(i)(B)(2) of this clause will no longer apply as of January 1, 2030.

- (ii) The application of the restriction of the Buy American Act to a particular construction material would be impracticable or inconsistent with the public interest; or
- (iii) The construction material is not mined, produced, or manufactured in the United States in sufficient and reasonably available commercial quantities of a satisfactory quality.

(c) Request for determination of inapplicability of the Buy American statute.

(1)

(i) Any Contractor request to use foreign construction material in accordance with paragraph (b)(4) of this clause shall include adequate information for Government evaluation of the request, including-

(A) A description of the foreign and domestic construction materials;

(B) Unit of measure;

(C) Quantity;

(D) Price;

(E) Time of delivery or availability;

(F) Location of the construction project;

(G) Name and address of the proposed supplier; and

(H) A detailed justification of the reason for use of foreign construction materials cited in accordance with paragraph (b)(3) of this clause.

(ii) A request based on unreasonable cost shall include a reasonable survey of the market and a completed price comparison table in the format in paragraph (d) of this clause.

(iii) The price of construction material shall include all delivery costs to the construction site and any applicable duty (whether or not a duty-free certificate may be issued).

(iv) Any Contractor request for a determination submitted after contract award shall explain why the Contractor could not reasonably foresee the need for such determination and could not have requested the determination before contract award. If the Contractor does not submit a satisfactory explanation, the Contracting Officer need not make a determination.

(2) If the Government determines after contract award that an exception to the Buy American statute applies and the Contracting Officer and the Contractor negotiate adequate consideration, the Contracting Officer will modify the contract to allow use of the foreign construction material. However, when the basis for the exception is the unreasonable price of a domestic construction material, adequate consideration is not less than the differential established in paragraph (b)(4)(i) of this clause.

(3) Unless the Government determines that an exception to the Buy American statute applies, use of foreign construction material is noncompliant with the Buy American statute.

(d) Data. To permit evaluation of requests under paragraph (c) of this clause based on unreasonable cost, the Contractor shall include the following information and any applicable supporting data based on the survey of suppliers:

Foreign and Domestic Construction Materials Price Comparison			
Construction Material Description	Unit of Measure		Price (Dollars)*
Item1			
Foreign construction material	_____	_____	_____
Domestic construction material	_____	_____	_____
Item1			
Foreign construction material	_____	_____	_____
Domestic construction material	_____	_____	_____

[* Include all delivery costs to the construction site and any applicable duty (whether or not a duty-free entry certificate is issued)].

[List name, address, telephone number, and contact for suppliers surveyed. Attach copy of response; if oral, attach summary.]

[Include other applicable supporting information.]

(End of clause)

52.232-16 Progress Payments.

(Nov 2021)

Progress Payments (Nov 2021)

The Government will make progress payments to the Contractor when requested as work progresses, but not more frequently than monthly, in amounts of \$2,500 or more approved by the Contracting Officer, under the following conditions:

(a) Computation of amounts.

(1) Unless the Contractor requests a smaller amount, the Government will compute each progress payment as 80 percent of the Contractor's total costs incurred under this contract whether or not actually paid, plus financing payments to subcontractors (see paragraph (j) of this clause), less the sum of all previous progress payments made by the Government under this contract. The Contracting Officer will consider cost of money that would be allowable under Federal Acquisition Regulation (FAR) 31.205-10 as an incurred cost for progress payment purposes.

(2) The amount of financing and other payments for supplies and services purchased directly for the contract are limited to the amounts that have been paid by cash, check, or other forms of payment, or that are determined due and will be paid to subcontractors-

(i) In accordance with the terms and conditions of a subcontract or invoice; and

(ii) Ordinarily within 30 days of the submission of the Contractor's payment request to the Government.

(3) The Government will exclude accrued costs of Contractor contributions under employee pension plans until actually paid unless-

(i) The Contractor's practice is to make contributions to the retirement fund quarterly or more frequently; and

(ii) The contribution does not remain unpaid 30 days after the end of the applicable quarter or shorter payment period (any contribution remaining unpaid shall be excluded from the Contractor's total costs for progress payments until paid).

(4) The Contractor shall not include the following in total costs for progress payment purposes in paragraph (a)(1) of this clause:

(i) Costs that are not reasonable, allocable to this contract, and consistent with sound and generally accepted accounting principles and practices.

(ii) Costs incurred by subcontractors or suppliers.

(iii) Costs ordinarily capitalized and subject to depreciation or amortization except for the properly depreciated or amortized portion of such costs.

(iv) Payments made or amounts payable to subcontractors or suppliers, except for-

(A) Completed work, including partial deliveries, to which the Contractor has acquired title; and

(B) Work under cost-reimbursement or time-and-material subcontracts to which the Contractor has acquired title.

(5) The amount of unliquidated progress payments may exceed neither (i) the progress payments made against incomplete work (including allowable unliquidated progress payments to subcontractors) nor (ii) the value, for progress payment purposes, of the incomplete work. Incomplete work shall be considered to be the supplies and services required by this contract, for which delivery and invoicing by the Contractor and acceptance by the Government are incomplete.

(6) The total amount of progress payments shall not exceed 80 percent of the total contract price.

(7) If a progress payment or the unliquidated progress payments exceed the amounts permitted by paragraphs (a)(4) or (a)(5) of this clause, the Contractor shall repay the amount of such excess to the Government on demand.

(8) Notwithstanding any other terms of the contract, the Contractor agrees not to request progress payments in dollar amounts of less than \$2,500. The Contracting Officer may make exceptions.

(9) The costs applicable to items delivered, invoiced, and accepted shall not include costs in excess of the contract price of the items.

(b) Liquidation. Except as provided in the Termination for Convenience of the Government clause, all progress payments shall be liquidated by deducting from any payment under this contract, other than advance or progress payments, the unliquidated progress payments, or 80 percent of the amount invoiced, whichever is less. The Contractor shall repay to the Government any amounts required by a retroactive price reduction, after computing liquidations and payments on past invoices at the reduced prices and adjusting the unliquidated progress payments accordingly. The Government reserves the right to unilaterally change from the ordinary liquidation rate to an alternate rate when deemed appropriate for proper contract financing.

(c) Reduction or suspension. The Contracting Officer may reduce or suspend progress payments, increase the rate of liquidation, or take a

combination of these actions, after finding on substantial evidence any of the following conditions:

- (1) The Contractor failed to comply with any material requirement of this contract (which includes paragraphs (f) and (g) of this clause).
- (2) Performance of this contract is endangered by the Contractor's-
 - (i) Failure to make progress; or
 - (ii) Unsatisfactory financial condition.
- (3) Inventory allocated to this contract substantially exceeds reasonable requirements.
- (4) The Contractor is delinquent in payment of the costs of performing this contract in the ordinary course of business.
- (5) The fair value of the undelivered work is less than the amount of unliquidated progress payments for that work.
- (6) The Contractor is realizing less profit than that reflected in the establishment of any alternate liquidation rate in paragraph (b) of this clause, and that rate is less than the progress payment rate stated in paragraph (a)(1) of this clause.

(d) Title.

(1) Title to the property described in this paragraph (d) shall vest in the Government. Vestiture shall be immediately upon the date of this contract, for property acquired or produced before that date. Otherwise, vestiture shall occur when the property is or should have been allocable or properly chargeable to this contract.

(2) "Property," as used in this clause, includes all of the below-described items acquired or produced by the Contractor that are or should be allocable or properly chargeable to this contract under sound and generally accepted accounting principles and practices.

(i) Parts, materials, inventories, and work in process;

(ii) Special tooling and special test equipment to which the Government is to acquire title;

(iii) Nondurable (i.e., noncapital) tools, jigs, dies, fixtures, molds, patterns, taps, gauges, test equipment, and other similar manufacturing aids, title to which would not be obtained as special tooling under paragraph (d)(2)(ii) of this clause; and

(iv) Drawings and technical data, to the extent the Contractor or subcontractors are required to deliver them to the Government by other clauses of this contract.

(3) Although title to property is in the Government under this clause, other applicable clauses of this contract; e.g., the termination clauses, shall determine the handling and disposition of the property.

(4) The Contractor may sell any scrap resulting from production under this contract without requesting the Contracting Officer's approval, but the proceeds shall be credited against the costs of performance.

(5) To acquire for its own use or dispose of property to which title is vested in the Government under this clause, the Contractor must obtain the Contracting Officer's advance approval of the action and the terms. The Contractor shall (i) exclude the allocable costs of the property from the costs of contract performance, and (ii) repay to the Government any amount of unliquidated progress payments allocable to the property. Repayment may be by cash or credit memorandum.

(6) When the Contractor completes all of the obligations under this contract, including liquidation of all progress payments, title shall vest in the Contractor for all property (or the proceeds thereof) not-

(i) Delivered to, and accepted by, the Government under this contract; or

(ii) Incorporated in supplies delivered to, and accepted by, the Government under this contract and to which title is vested in the Government under this clause.

(7) The terms of this contract concerning liability for Government-furnished property shall not apply to property to which the Government acquired title solely under this clause.

(e) Risk of loss. Before delivery to and acceptance by the Government, the Contractor shall bear the risk of loss for property, the title to which vests in the Government under this clause, except to the extent the Government expressly assumes the risk. The Contractor shall repay the Government an amount equal to the unliquidated progress payments that are based on costs allocable to property that is lost (see 45.101).

(f) Control of costs and property. The Contractor shall maintain an accounting system and controls adequate for the proper administration of this clause.

(g) Reports, forms, and access to records.

(1) The Contractor shall promptly furnish reports, certificates, financial statements, and other pertinent information (including estimates to complete) reasonably requested by the Contracting Officer for the administration of this clause. Also, the Contractor shall give the Government reasonable opportunity to examine and verify the Contractor's books, records, and accounts.

(2) The Contractor shall furnish estimates to complete that have been developed or updated within six months of the date of the progress payment request. The estimates to complete shall represent the Contractor's best estimate of total costs to complete all remaining contract work required under the contract. The estimates shall include sufficient detail to permit Government verification.

(3) Each Contractor request for progress payment shall:

(i) Be submitted on Standard Form 1443, Contractor's Request for Progress Payment, or the electronic equivalent as required by agency regulations, in accordance with the form instructions and the contract terms; and

(ii) Include any additional supporting documentation requested by the Contracting Officer.

(h) Special terms regarding default. If this contract is terminated under the Default clause, (i) the Contractor shall, on demand, repay to the Government the amount of unliquidated progress payments and (ii) title shall vest in the Contractor, on full liquidation of progress payments, for all property for which the Government elects not to require delivery under the Default clause. The Government shall be liable for no payment except as provided by the Default clause.

(i) Reservations of rights.

(1) No payment or vesting of title under this clause shall-

(i) Excuse the Contractor from performance of obligations under this contract; or

(ii) Constitute a waiver of any of the rights or remedies of the parties under the contract.

(2) The Government's rights and remedies under this clause-

(i) Shall not be exclusive but rather shall be in addition to any other rights and remedies provided by law or this contract; and

(ii) Shall not be affected by delayed, partial, or omitted exercise of any right, remedy, power, or privilege, nor shall such exercise or any single exercise preclude or impair any further exercise under this clause or the exercise of any other right, power, or privilege of the Government.

(j) Financing payments to subcontractors. The financing payments to subcontractors mentioned in paragraphs (a)(1) and (a)(2) of this clause shall be all financing payments to subcontractors or divisions, if the following conditions are met:

(1) The amounts included are limited to-

(i) The unliquidated remainder of financing payments made; plus

(ii) Any unpaid subcontractor requests for financing payments.

(2) The subcontract or interdivisional order is expected to involve a minimum of approximately 6 months between the beginning of work and the first delivery; or, if the subcontractor is a small business concern, 4 months.

(3) If the financing payments are in the form of progress payments, the terms of the subcontract or interdivisional order concerning progress payments-

(i) Are substantially similar to the terms of this clause for any subcontractor that is a large business concern, or this clause with its Alternate I for any subcontractor that is a small business concern;

(ii) Are at least as favorable to the Government as the terms of this clause;

(iii) Are not more favorable to the subcontractor or division than the terms of this clause are to the Contractor;

(iv) Are in conformance with the requirements of FAR 32.504(e); and

(v) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if-

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(4) If the financing payments are in the form of performance-based payments, the terms of the subcontract or interdivisional order concerning payments-

(i) Are substantially similar to the Performance-Based Payments clause at FAR 52.232-32 and meet the criteria for, and definition of, performance-based payments in FAR part 32;

(ii) Are in conformance with the requirements of FAR 32.504(f); and

(iii) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if-

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(5) If the financing payments are in the form of commercial product or commercial service financing payments, the terms of the subcontract or interdivisional order concerning payments-

(i) Are constructed in accordance with FAR 32.206(c) and included in a subcontract for a commercial product or commercial service purchase that meets the definition and standards for acquisition of commercial products and commercial services in FAR parts 2 and 12;

(ii) Are in conformance with the requirements of FAR 32.504(g); and

(iii) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if-

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(6) If financing is in the form of progress payments, the progress payment rate in the subcontract is the customary rate used by the contracting agency, depending on whether the subcontractor is or is not a small business concern.

(7) Concerning any proceeds received by the Government for property to which title has vested in the Government under the subcontract terms, the parties agree that the proceeds shall be applied to reducing any unliquidated financing payments by the Government to the Contractor under this contract.

(8) If no unliquidated financing payments to the Contractor remain, but there are unliquidated financing payments that the Contractor has made to any subcontractor, the Contractor shall be subrogated to all the rights the Government obtained through the terms required by this clause to be in any subcontract, as if all such rights had been assigned and transferred to the Contractor.

(9) To facilitate small business participation in subcontracting under this contract, the Contractor shall provide financing payments to small business concerns, in conformity with the standards for customary contract financing payments stated in FAR 32.113. The Contractor shall not consider the need for such financing payments as a handicap or adverse factor in the award of subcontracts.

(k) Limitations on undefinitized contract actions. Notwithstanding any other progress payment provisions in this contract, progress payments may not exceed 80 percent of costs incurred on work accomplished under undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes. This limitation shall apply to the costs incurred, as computed in accordance with paragraph (a) of this clause, and shall remain in effect until the contract action is definitized. Costs incurred which are subject to this limitation shall be segregated on Contractor progress payment requests and invoices from those costs eligible for higher progress payment rates. For purposes of progress payment liquidation, as described in paragraph (b) of this clause, progress payments for undefinitized contract actions shall be liquidated at 80 percent of the amount invoiced for work performed under the undefinitized contract action as long as the contract action remains undefinitized. The amount of unliquidated progress payments for undefinitized contract actions shall not exceed 80 percent of the maximum liability of the Government under the undefinitized contract action or such lower limit specified elsewhere in the contract. Separate limits may be specified for separate actions.

(l) Due date. The designated payment office will make progress payments on the ____ [Contracting Officer insert date as prescribed by agency head; if not prescribed, insert "30th"] day after the designated billing office receives a proper progress payment request. In the event that the Government requires an audit or other review of a specific progress payment request to ensure compliance with the terms and conditions of the contract, the designated payment office is not compelled to make payment by the specified due date. Progress payments are considered contract financing and are not subject to the interest penalty provisions of the Prompt Payment Act.

(m) Progress payments under indefinite-delivery contracts. The Contractor shall account for and submit progress payment requests under individual orders as if the order constituted a separate contract, unless otherwise specified in this contract.

(End of clause)

DFARS Clauses Incorporated by Full Text

LIMITATION OF GOVERNMENT'S OBLIGATION (APR 2014)

(a) Contract line item(s) ____ [Contracting Officer insert after negotiations] is/are incrementally funded. For this/these item(s), the sum of \$ ____ [Contracting Officer insert after negotiations] of the total price is presently available for payment and allotted to this contract. An allotment schedule is set forth in paragraph (j) of this clause.

(b) For item(s) identified in paragraph (a) of this clause, the Contractor agrees to perform up to the point at which the total amount payable by the Government, including reimbursement in the event of termination of those item(s) for the Government's convenience, approximates the total amount currently allotted to the contract. The Contractor is not authorized to continue work on those item(s) beyond that point. The Government will not be obligated in any event to reimburse the Contractor in excess of the amount allotted to the contract for those item(s) regardless of anything to the contrary in the clause entitled "Termination for Convenience of the Government." As used in this clause, the total amount payable by the Government in the event of termination of applicable contract line item(s) for convenience includes costs, profit, and estimated termination settlement costs for those item(s).

(c) Notwithstanding the dates specified in the allotment schedule in paragraph (j) of this clause, the Contractor will notify the Contracting Officer in writing at least ninety days prior to the date when, in the Contractor's best judgment, the work will reach the point at which the total amount payable by the Government, including any cost for termination for convenience, will approximate 85 percent of the total amount then allotted to the contract for performance of the applicable item(s). The notification will state (1) the estimated date when that point will be reached and (2) an estimate of additional funding, if any, needed to continue performance of applicable line items up to the next scheduled date for allotment of funds identified in paragraph (j) of this clause, or to a mutually agreed upon substitute date. The notification will also advise the Contracting Officer of the estimated amount of additional funds that will be required for the timely performance of the item(s) funded pursuant to this clause, for a subsequent period as may be specified in the allotment schedule in paragraph (j) of this clause or otherwise agreed to by the parties. If after such notification additional funds are not allotted by the date identified in the Contractor's notification, or by an agreed substitute date, the Contracting Officer will terminate any item(s) for which additional funds have not been allotted, pursuant to the clause of this contract entitled "Termination for Convenience of the Government."

(d) When additional funds are allotted for continued performance of the contract line item(s) identified in paragraph (a) of this clause, the parties will agree as to the period of contract performance which will be covered by the funds. The provisions of paragraphs (b) through (d) of this clause will apply in like manner to the additional allotted funds and agreed substitute date, and the contract will be modified accordingly.

(e) If, solely by reason of failure of the Government to allot additional funds, by the dates indicated below, in amounts sufficient for timely performance of the contract line item(s) identified in paragraph (a) of this clause, the Contractor incurs additional costs or is delayed in the performance of the work under this contract and if additional funds are allotted, an equitable adjustment will be made in the price or prices (including appropriate target, billing, and ceiling prices where applicable) of the item(s), or in the time of delivery, or both. Failure to agree to any such equitable adjustment hereunder will be a dispute concerning a question of fact within the meaning of the clause entitled "Disputes."

(f) The Government may at any time prior to termination allot additional funds for the performance of the contract line item(s) identified in paragraph (a) of this clause.

(g) The termination provisions of this clause do not limit the rights of the Government under the clause entitled "Default." The provisions of this clause are limited to the work and allotment of funds for the contract line item(s) set forth in paragraph (a) of this clause. This clause no longer applies once the contract is fully funded except with regard to the rights or obligations of the parties concerning equitable adjustments negotiated under paragraphs (d) and (e) of this clause.

(h) Nothing in this clause affects the right of the Government to terminate this contract pursuant to the clause of this contract entitled "Termination for Convenience of the Government."

(i) Nothing in this clause shall be construed as authorization of voluntary services whose acceptance is otherwise prohibited under 31 U.S.C. 1342.

(j) The parties contemplate that the Government will allot funds to this contract in accordance with the following schedule:

On execution of contract	\$ ____	\$ ____	\$ ____
(month) (day), (year)	\$ ____	\$ ____	\$ ____
(month) (day), (year)	\$ ____	\$ ____	\$ ____
(month) (day), (year)	\$ ____	\$ ____	\$ ____

(End of clause)

CONTRACT DRAWINGS AND SPECIFICATIONS (AUG 2000)

(a) The Government will provide to the Contractor, without charge, one set of contract drawings and specifications, except publications incorporated into the technical provisions by reference, in electronic or paper media as chosen by the Contracting Officer.

(b) The Contractor shall-

(1) Check all drawings furnished immediately upon receipt;

- (2) Compare all drawings and verify the figures before laying out the work;
- (3) Promptly notify the Contracting Officer of any discrepancies;
- (4) Be responsible for any errors that might have been avoided by complying with this paragraph (b); and
- (5) Reproduce and print contract drawings and specifications as needed.

(c) In general--

- (1) Large-scale drawings shall govern small-scale drawings; and
- (2) The Contractor shall follow figures marked on drawings in preference to scale measurements.

(d) Omissions from the drawings or specifications or the misdescription of details of work that are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.

(e) The work shall conform to the specifications and the contract drawings identified on the following index of drawings:

Title	File	Drawing No.
_____	_____	_____

(End of clause)

252.236-7004 Payment for Mobilization and Demobilization. (Dec 1991)

PAYMENT FOR MOBILIZATION AND DEMOBILIZATION (DEC 1991)

(a) The Government will pay all costs for the mobilization and demobilization of all of the Contractor's plant and equipment at the contract lump sum price for this item.

- (1) (60%) Sixty percent of the lump sum price upon completion of the contractor's mobilization at the work site.
- (2) The remaining (40%) forty percent upon completion of demobilization.

(b) The Contracting Officer may require the Contractor to furnish cost data to justify this portion of the bid if the Contracting Officer believes that the percentages in paragraphs (a)(1) and (2) of this clause do not bear a reasonable relation to the cost of the work in this contract.

- (1) Failure to justify such price to the satisfaction of the Contracting Officer will result in payment, as determined by the Contracting Officer, of-
 - (i) Actual mobilization costs at completion of mobilization;
 - (ii) Actual demobilization costs at completion of demobilization; and
 - (iii) The remainder of this item in the final payment under this contract.

(2) The Contracting Officer's determination of the actual costs in paragraph (b)(1) of this clause is not subject to appeal.

(End of clause)

SECTION 00700
CONTRACT CLAUSES NOTES

1.1 COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (FAR 52.211-10 – APR 1984)

Note: The term "commence work" in this clause refers to commence dredging.

1.2 PAYMENT FOR MOBILIZATION AND DEMOBILIZATION (DFARS 252.236-7004 – DEC 1991)

Note: The term "lump sum" is synonymous with the unit of measure "job", as stated on the bid schedules and throughout the specifications.

Note 2: This clause applies to payment for Item "Mobilization and Demobilization" and Option Item "Mobilization and Demobilization of Additional Pumping Capability Equipment for Payment Item 0006".

1.3 LAYOUT OF WORK (FAR 52.236-17 - APR 1984)

Note 1: For the purpose of the contract, the Contractor shall layout the work from the Government established channel centerline and gages in lieu of baselines and benchmarks.

Note 2: For these specifications, there are no contract drawings. Refer to the dredging region section(s) for contract plates.

1.4 OPTION FOR INCREASED QUANTITY-SEPARATELY PRICED LINE ITEM (FAR 52.217-7 MAR 1989) Note: The word "schedule" in this clause refers to the bidding schedule.

1.5 QUANTITY SURVEYS (FAR 52.236-16 ALTERNATE 1 - APR 1984)

Note: Refer to Section 35 01 50.73 - Surveys, for details on surveying and quantity computations.

Section 00800 - Supplementary Conditions

Overall Contract Delivery Period

From date of lead time event to beginning of performance

15 Calendar Days

Date of Notice to Proceed Receipt

From date of lead time event to completion of performance

53 Calendar Days

Date of Notice to Proceed Receipt

DFARS Clauses Incorporated by Full Text

252.232-7006 Wide Area WorkFlow Payment Instructions.

(Jan 2023)

WIDE AREA WORKFLOW PAYMENT INSTRUCTIONS (JAN 2023)

(a) Definitions. As used in this clause-

"Department of Defense Activity Address Code (DoDAAC)" is a six position code that uniquely identifies a unit, activity, or organization.

"Document type" means the type of payment request or receiving report available for creation in Wide Area WorkFlow (WAWF).

"Local processing office (LPO)" is the office responsible for payment certification when payment certification is done external to the entitlement system.

"Payment request" and "receiving report" are defined in the clause at 252.232-7003, Electronic Submission of Payment Requests and Receiving Reports.

(b) Electronic invoicing. The WAWF system provides the method to electronically process vendor payment requests and receiving reports, as authorized by Defense Federal Acquisition Regulation Supplement (DFARS) 252.232-7003, Electronic Submission of Payment Requests and Receiving Reports.

(c) WAWF access. To access WAWF, the Contractor shall-

(1) Have a designated electronic business point of contact in the System for Award Management at <https://www.sam.gov>; and

(2) Be registered to use WAWF at <https://wawf.eb.mil/> following the step-by-step procedures for self-registration available at this web site.

(d) WAWF training. The Contractor should follow the training instructions of the WAWF Web-Based Training Course and use the Practice Training Site before submitting payment requests through WAWF. Both can be accessed by selecting the "Web Based Training" link on the WAWF home page at <https://wawf.eb.mil/>

(e) WAWF methods of document submission. Document submissions may be via web entry, Electronic Data Interchange, or File Transfer Protocol.

(f) WAWF payment instructions. The Contractor shall use the following information when submitting payment requests and receiving reports in WAWF for this contract or task or delivery order:

(1) Document type. The Contractor shall submit payment requests using the following document type(s):

(i) For cost-type line items, including labor-hour or time-and-materials, submit a cost voucher.

(ii) For fixed price line items-

(A) That require shipment of a deliverable, submit the invoice and receiving report specified by the Contracting Officer.

(Contracting Officer: Insert applicable invoice and receiving report document type(s) for fixed price line items that require shipment of a deliverable.)

(B) For services that do not require shipment of a deliverable, submit either the Invoice 2in1, which meets the requirements for the invoice and receiving report, or the applicable invoice and receiving report, as specified by the Contracting Officer.

(Contracting Officer: Insert either "Invoice 2in1" or the applicable invoice and receiving report document type(s) for fixed price line items for services.)

(iii) For customary progress payments based on costs incurred, submit a progress payment request.

(iv) For performance based payments, submit a performance based payment request.

(v) For commercial financing, submit a commercial financing request.

(2)) Fast Pay requests are only permitted when Federal Acquisition Regulation (FAR) 52.213-1 is included in the contract.

[Note: The Contractor may use a WAWF "combo" document type to create some combinations of invoice and receiving report in one step.]

(3) Document routing. The Contractor shall use the information in the Routing Data Table below only to fill in applicable fields in WAWF when creating payment requests and receiving reports in the system.

Routing Data Table*

Field Name in WAWF	Data to be entered in WAWF
Pay Official DoDAAC	_____
Issue By DoDAAC	_____
Admin DoDAAC	_____
Inspect By DoDAAC	_____
Ship To Code	_____
Ship From Code	_____
Mark For Code	_____
Service Approver (DoDAAC)	_____
Service Acceptor (DoDAAC)	_____
Accept at Other DoDAAC	_____
LPO DoDAAC	_____
DCAA Auditor DoDAAC	_____
Other DoDAAC(s)	_____

(*Contracting Officer: Insert applicable DoDAAC information. If multiple ship to/acceptance locations apply, insert "See Schedule" or "Not applicable.")

(**Contracting Officer: If the contract provides for progress payments or performance-based payments, insert the DoDAAC for the contract administration office assigned the functions under FAR 42.302(a)(13).)

(4) Payment request. The Contractor shall ensure a payment request includes documentation appropriate to the type of payment request in accordance with the payment clause, contract financing clause, or Federal Acquisition Regulation 52.216-7, Allowable Cost and Payment, as applicable.

(5) Receiving report. The Contractor shall ensure a receiving report meets the requirements of DFARS Appendix F.

(g) WAWF point of contact.

(1) The Contractor may obtain clarification regarding invoicing in WAWF from the following contracting activity's WAWF point of contact.

(Contracting Officer: Insert applicable information or "Not applicable.")

(2) Contact the WAWF helpdesk at 866-618-5988, if assistance is needed.

(End of clause)

SECTION TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

SECTION 00800

SUPPLEMENTARY CONDITIONS

PART 1 GENERAL

1.1 SCOPE

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

3.1 DELIVERY OF PLANT

3.2 PROSECUTION, OPTION AND COMPLETION

3.3 CONTRACTOR PERFORMANCE EVALUATIONS - CONSTRUCTION

3.4 CONSTRUCTION AND ARCHITECT-ENGINEER (A-E) CONTRACTS (UAI 5131.105)

3.5 VETERANS EMPLOYMENT EMPHASIS FOR U.S. ARMY CORPS OF ENGINEERS
CONTRACTS (UAI 5122.1302-100)

-- End of Section Table of Contents --

SECTION 00800

SUPPLEMENTARY CONDITIONS

PART 1 GENERAL

1.1 SCOPE

This Section includes supplements to the Federal Acquisition Regulations (FAR) requirements. Also included are applicable Department of Defense supplements (DFARS) and USACE Acquisition Instruction (UAI) to the FAR.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

3.1 DELIVERY OF PLANT

a. Delivery of the hydraulic dredge and attendant plant and commencement of dredging shall be completed no later than 120 hours after issuance of the Notice to Proceed. For bidding purposes, the delivery site will be Mississippi River Mile 63.7 AHP at the location of the saltwater barrier sill project; however, the starting assignment for the dredge may require initial mobilization to any of the locations in the Dredging Region Section(s), for which an equitable adjustment will be made for any additional costs under the contract clause entitled "Changes" (FAR 52.243-4). Upon arrival of the dredge and all of the attendant plant at the delivery site, the plant may be inspected by Government personnel to determine whether any deficiencies have developed since the time the plant was brought into compliance pursuant to the pre-award inspection. The Contractor will be notified of acceptance or rejection of the plant. The dredge will be given an assignment immediately upon acceptance, and will be expected to commence dredging at that time. The Notice to Proceed may be issued immediately upon receipt of acceptable Performance and Payment Bonds.

b. The Contracting Officer may waive the requirement for the Pre-award Inspection of Plant listed in the Bid Form Notes. Such waiver does not affect the inspection of the plant upon delivery.

3.2 PROSECUTION, OPTION AND COMPLETION

a. The estimated completion time of the contract will initially be determined as the date and time obtained by adding the hours in "Dredging" Payment Item to the date and time that the Contractor began start of pay time hours. During the course of work, the completion time may change as a result of fractional pay time (refer to Section 35 20 23.23, paragraph entitled "Dredging and Option Dredging Items") and/or award of option hours or any portion thereof.

b. This contract shall extend for an approximate duration as described in Section 00010, paragraph entitled "Conditions of Contract Award". If all specified work is completed prior to the approximate duration completion time, the Government will release the dredge and declare the contract complete.

c. Upon completion of the specified work, the dredge and attendant

plant will be released to the Contractor at the location of the last assignment. It should be noted that the location of the last assignment could be in another region within the New Orleans District as described in Section 35 20 23.23, paragraph entitled "Dredging in Secondary Regions". All cost of final demobilization will be paid as stated in Section 35 20 23.23, paragraph entitled "Measurement and Payment". No other payment will be made.

d. If the Contracting Officer so notifies the Contractor of the Government's intent to exercise an option, in whole or part, the Contractor shall continue work on that part of the option hours specified by the Contracting Officer at the option unit price specified in the bidding schedule, subject to the provisions of Section 35 20 23.23, paragraph entitled "Dredging and Option Dredging Items". Any exercise of the option in part does not obligate the Government to the full extent of the option.

3.3 CONTRACTOR PERFORMANCE EVALUATIONS - CONSTRUCTION

In accordance with the provisions of Subpart 36.201/42.1502(e) (Evaluation of Contractor Performance) of the Federal Acquisition Regulation (FAR), construction contractor's performance shall be evaluated throughout the performance of the contract. The United States Army Corps of Engineers (USACE) follows the procedures outlined in Engineering Regulation 415-1-17 to fulfill this FAR requirement. For construction contracts awarded at or above \$700,000.00, the USACE will evaluate contractor's performance and prepare a performance report using the Contractor Performance Assessment Reporting System (CPARS), which is now a web-based system. After an evaluation (interim or final) is written up by the USACE, the Contractor will have the ability to access, review and comment on the evaluation for a period of 30 days. Accessing and using CPARS requires specific software, called PKI certification, which is installed on the user's computer. The certification is a Department of Defense requirement and was implemented to provide security in electronic transactions. The certification software could cost approximately \$110 - \$125 per certificate per year and is purchased from an External Certificate Authorities (ECA) vendor. Current information about the PKI certification process and for contacting vendors can be found on the web site: www.cpars.gov. If the Contractor wishes to participate in the performance evaluation process, access to CPARS and PKI certification is the sole responsibility of the Contractor.

3.4 CONSTRUCTION AND ARCHITECT-ENGINEER (A-E) CONTRACTS (UAI 5131.105)

(d)(2)(i)(B) In accordance with FAR 31.105(d)(2)(i)(b), for the predetermined schedule of construction equipment use rates, use Engineer Pamphlet (EP) 1110-1-8, Construction Equipment Ownership and Operating Expense Schedule.

(End of special contract requirement)

Note 1: Costs for repairs or overhauling are not allowed.

Note 2: A copy of the "EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE" (Region III) can be obtained from the following website:
https://www.publications.usace.army.mil/Portals/76/Users/182/86/2486/EP%201110-1-8_RV1-12.pdf?ver=x6psY-gBPGg5dSOqQdjEMg%3d%3d.

3.5 VETERANS EMPLOYMENT EMPHASIS FOR U.S. ARMY CORPS OF ENGINEERS CONTRACTS (UAI 5122.1302-100)

In addition to complying with the requirements outlined in FAR Part 22.13, FAR Provision 52.222-38, FAR Clause 52.222-35, FAR Clause 52.222-37, DFARS 222.13 and Department of Labor regulations, U.S. Army Corps of Engineers (USACE) contractors and subcontractors at all tiers are encouraged to promote the training and employment of U.S. veterans while performing under a USACE contract. While no set-aside, evaluation preference, or incentive applies to the solicitation or performance under the resultant contract, USACE contractors are encouraged to seek out highly qualified veterans to perform services under this contract. The following resources are available to assist USACE contractors in their outreach efforts:

U.S. Department of Labor Veterans' Employment and Training Service (VETS):
<https://www.dol.gov/vets/>

Federal veteran employment information: www.fedshirevets.gov/index.aspx

Veterans Opportunity to Work (VOW) Program: <http://benefits.va.gov/vow/>

U.S. Army Warrior Transition Command Employment Index:
<https://wct.army.mil/modules/employers/index.html>

Hiring Our Heroes initiative: www.uschamberfoundation.org/hiring-our-heroes

(End of special contract requirement)

-- End of Section --

State: Louisiana

Construction Type: Heavy Dredging

Counties: Louisiana Statewide.

DREDGING PROJECTS ALONG THE GULF COAST AREA INCLUDING THE MISSISSIPPI RIVER AND ITS TRIBUTARIES TO THE OHIO RIVER

Note: Contracts subject to the Davis-Bacon Act are generally required to pay at least the applicable minimum wage rate required under Executive Order 14026 or Executive Order 13658. Please note that these Executive Orders apply to covered contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but do not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(1).

If the contract is entered into on or after January 30, 2022, or the contract is renewed or extended (e.g., an option is exercised) on or after January 30, 2022:	◆ Executive Order 14026 generally applies to the contract. ◆ The contractor must pay all covered workers at least \$17.75 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in 2025.
If the contract was awarded on or between January 1, 2015 and January 29, 2022, and the contract is not renewed or extended on or after January 30, 2022:	◆ Executive Order 13658 generally applies to the contract. ◆ The contractor must pay all covered workers at least \$13.30 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours performing on that contract in 2025.

The applicable Executive Order minimum wage rate will be adjusted annually. If this contract is covered by one of the Executive Orders and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must still submit a conformance request.

Additional information on contractor requirements and worker protections under the Executive Orders is available at <http://www.dol.gov/whd/govcontracts>.

Modification Number Publication Date
0 02/07/2025

SULA1994-001 04/01/1994

The following rates were revised pursuant to 29 CFR 1.6(c)(1) on 02/07/2025.

	Rates	Fringes
Derrick Operator.....	\$ 16.85	**
Dozer Operator.....	\$ 16.85	**
Dredge 16"" and Over		
Deckhand.....	\$ 16.85	**
Dredge tender operator.....	\$ 16.85	**
Fireman.....	\$ 16.85	**
First assistant engineer....	\$ 16.85	**
Leverman.....	\$ 16.85	**
Oiler.....	\$ 16.85	**
Second assistant engineer...	\$ 16.85	**
Shoreman.....	\$ 16.85	**
Third assistant engineer....	\$ 16.85	**
Truck driver.....	\$ 16.85	**
Welder.....	\$ 16.85	**
Dredge Under 16""		
Deckhand.....	\$ 16.85	**
Dredge tender operator.....	\$ 16.85	**
Leverman.....	\$ 16.85	**
Oiler.....	\$ 16.85	**
Welder.....	\$ 16.85	**
Hydraulic Dredging		
First cook.....	\$ 16.85	**
Handyman.....	\$ 16.85	**
Janitor, cabin person.....	\$ 16.85	**
Second cook.....	\$ 16.85	**
Marsh Buggy Dragline, Oiler.....	\$ 16.85	**
Marsh Buggy Dragline, Operator...	\$ 16.85	**
Self-Propelled Hopper Dredge, Drag Tender.....	\$ 22.55	8.02+a

FOOTNOTE: Fourteen paid vacation days and eight paid holidays: New Year's Day, Good Friday, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day & Christmas Day provided the employee has one year of service.

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

=====
** Workers in this classification may be entitled to a higher minimum wage under Executive Order 14026 (\$17.75) or 13658 (\$13.30). Please see the Note at the top of the wage determination for more information. Please also note that the minimum wage requirements of Executive Order 14026 are not currently being enforced as to any contract or subcontract to which the states of Texas, Louisiana, or Mississippi, including their agencies, are a party.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at <https://www.dol.gov/agencies/whd/government-contracts>.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than ""SU"", ""UAVG"", ?SA?, or ?SC? denotes that a union rate was prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for the classifications reflected union rates. EXAMPLE: UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number used in producing the wage determination. The date, 01/01/2024

in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The ""SU"" identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

?SU? wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The ""SA"" identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the ?SA? identifier took effect under state law in the state from which the rates were adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

- a) a survey underlying a wage determination
- b) an existing published wage determination
- c) an initial WHD letter setting forth a position on a wage determination matter
- d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division

U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.

=====

END OF GENERAL DECISION"

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 30 00

ADMINISTRATIVE REQUIREMENTS

PART 1 GENERAL

- 1.1 MEASUREMENT AND PAYMENT
- 1.2 ACCOMMODATIONS AND MEALS FOR INSPECTORS
- 1.3 SEAWORTHINESS CERTIFICATION
- 1.4 ENVIRONMENTAL LITIGATION
- 1.5 STATE TAXES
- 1.6 RIGHTS-OF-WAY
- 1.7 MOBILIZATION OF ATTENDANT PLANT
- 1.8 OBSTRUCTION OF CHANNEL
- 1.9 WORK BY OTHERS
- 1.10 CONTRACTOR'S RESPONSIBILITY
- 1.11 SUPERVISION
- 1.12 AS-BUILT DRAWINGS
- 1.13 FUEL CONSUMPTION REPORTING REQUIREMENTS
- 1.14 GENERAL SECURITY REQUIREMENTS AND GUIDANCE
- 1.15 SUSPICIOUS ACTIVITY REPORTING TRAINING (e.g. iWATCH, CorpsWatch,
or See Something, Say Something)
- 1.16 PRE-SCREEN CANDIDATES USING E-VERIFY PROGRAM

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

ATTACHMENTS:

Utility Summary Sheet

-- End of Section Table of Contents --

SECTION 01 30 00

ADMINISTRATIVE REQUIREMENTS

PART 1 GENERAL

1.1 MEASUREMENT AND PAYMENT

No separate measurement or payment will be made for administrative requirements as specified herein. All costs for the work covered under this section shall be distributed throughout the existing bid items, except as stated in the paragraph entitled "Accommodations and Meals for Inspectors".

1.2 ACCOMMODATIONS AND MEALS FOR INSPECTORS

a. The Contractor shall furnish to inspectors on board the dredge or other craft upon which they are employed a suitable separate room approximately 150 square feet in size for a Corps of Engineers field office. In the event that the dredge or other suitable craft with office facilities is not on site upon commencement of construction operations, the Contractor shall arrange for temporary office facilities on shore at a convenient location in the vicinity of the project. The office shall be fully equipped and maintained to the satisfaction of the Contracting Officer; it shall be properly heated, ventilated, air conditioned, and lighted, shall have sufficient electrical outlets with power surge protection to power a laptop computer and printer, shall have a desk which can be locked, and a drafting table measuring at least 4 feet by 6 feet (subject to room size suitability), a comfortable chair for each inspector, washing conveniences and daily janitorial services. The Contractor shall provide at least one cellular telephone and one satellite telephone aboard the dredge. The telephones shall be available to Government personnel for conducting official Government business 24 hours per day, seven days per week. The Contractor shall provide the Inspector's office with a cellular wireless Broadband / WiFi 802.11n capable router that accepts cellular data signals through satellite. The high speed internet service and associated equipment must be capable of providing adequate connection to allow the inspectors to import / export files through RMS (shall provide a minimum download speed of 10 Mbps and a minimum upload speed of 1.5 Mbps for the sole use of the Inspectors). The Contractor shall field verify that the service provider chosen has adequate continuous coverage throughout the site of work. The Contractor shall be responsible for the installation, maintenance of, and the monthly service fees necessary to provide continuous high speed internet service for the duration of the contract. Final approval of the plant will not be made until this equipment is installed and in good working order. Should the Contractor have a photocopy machine on the jobsite, the Contractor may allow the use of his own in lieu of providing a separate machine for use by the Government Inspector. All costs for furnishing, equipping, and maintaining the accommodations shall be included in the contract unit price per hour in the "Dredging", "Option Dredging I", "Option Dredging II", and "Option Dredging III" items on the bidding schedule. If the Contractor fails to meet these requirements, the facilities referred to above will be secured by the Contracting Officer, and the cost thereof will be deducted from payments to the Contractor.

b. If the Contractor maintains on this work an establishment for the subsistence of his/her own employees, he/she shall, when required, furnish to inspectors employed on the work, and to all Government agents who may visit the work on official business, meals of quality satisfactory to the Contracting Officer. All meals shall be available for purchase, by the Government's inspectors and agents, at the cost not to exceed \$3.25 per person for each meal.

c. Smoking shall not be allowed inside the lever room while occupied by Government personnel.

1.3 SEAWORTHINESS CERTIFICATION

All dredges and quarter boats not subject to USCG inspection and certification or not having a current American Bureau of Shipping (ABS) classification shall be inspected in the working mode annually by a marine surveyor accredited by the National Association of Marine Surveyors (NAMS) or the Society of Accredited Marine Surveyors (SAMS) and having at least five years experience in commercial marine plant and equipment. All other plant shall be inspected annually by a qualified person. The inspection shall be documented, and a copy of the most recent inspection report shall be posted in a public area on board the vessel and a copy shall be furnished to the designated authority upon request. The inspection shall be appropriate for the intended use of the plant and shall, as a minimum, evaluate structural integrity and compliance with NFPA 302, Fire Protection Standard for Pleasure and Commercial Motor Craft. See EM 385-1-1.

1.4 ENVIRONMENTAL LITIGATION

a. If the performance of all or any part of the work is suspended, delayed, or interrupted due to an order of a court of competent jurisdiction as a result of environmental litigation, then the Contracting Officer or his/her authorized representative, at the request of the Contractor, shall determine whether the order is due in any part to the acts or omissions of the Contractor or a Subcontractor at any tier and required by the terms of this contract. If it is determined that the order is not due in any part to acts or omissions of the Contractor or a Subcontractor at any tier, other than as required by the terms of this contract, then such suspension, delay, or interruption shall be considered as if ordered by the Contracting Officer or his/her authorized representative in the administration of this contract under the terms of the "Suspension of Work" (FAR 52.242-14) clause located in Section 00700 - Contract Clauses. The period of such suspension, delay or interruption shall be considered unreasonable, and an adjustment shall be made for any increase in the cost of performance of this contract (excluding profit) as provided in that clause, subject to all the provisions thereof.

b. The term "environmental litigation", as used herein, means a lawsuit alleging that the work has an adverse effect on the environment or that the Government has not duly considered, either substantively or procedurally, the effect of the work on the environment.

1.5 STATE TAXES

a. The bid submitted shall not include any amount whatever for payment of any of the following taxes, fees or charges:

(1) The Louisiana "Severance Tax" imposed by LSA R.S. 47:631 and

made applicable to the dredging of fill material from rivers and bodies of water within the State of Louisiana by the Severance Tax Regulations promulgated by the Collector of Revenue dated 31 March 1968.

(2) Any amounts claimed by the Louisiana Department of Wildlife and Fisheries for the privilege of removing fill from the water bottoms of the State of Louisiana.

b. If the Contractor is required to pay or bear the burden of any tax, fee or charge described in para. a.(1) and/or a.(2) above, the contract prices shall be increased by that amount which the Contractor is required to pay to the State of Louisiana; provided, however, that no increase in contract price shall be made for any liability the Contractor may incur as a result of his fault or negligence or his failure to follow the instructions of the Contracting Officer or his/her authorized representative.

c. The Contractor shall promptly notify the Contracting Officer or his/her authorized representative of all matters pertaining to taxes, fees, or charges as described herein which reasonably may be expected to affect the contract price and shall at all times follow the directions and instructions of the Contracting Officer or his/her authorized representative in regard to the payment of such taxes, fees, or charges.

d. Before any increase in contract price becomes effective in accordance with the provisions of this clause, the Contractor shall warrant in writing that no amount of such taxes, fees or charges was included in the contract price as a contingency reserve or otherwise.

1.6 RIGHTS-OF-WAY

a. The rights of entry required for the work to be constructed under this contract, within the rights-of-way limits indicated on the plates, have been obtained by the Government and are provided without cost to the Contractor. The Contractor shall make its own investigations to determine the conditions, restrictions, and difficulties, which may be encountered in the transportation of equipment and material to and from the work site. The proposed work, including rights-of-way, as defined by these specifications and as shown on the plates, is in compliance with all applicable Federal and state environmental laws and regulations. Upon completion of the Contractor's work, rights-of-way furnished by the Government shall be returned to its original condition prior to construction unless otherwise noted.

b. If the Contractor proposes a deviation from the Government furnished rights-of-way for his convenience, the Contractor shall notify the Contracting Officer or his/her representative in writing. The Contractor shall not provide any permanent rights-of-way for the project. The Contractor is cautioned that any deviation to the Government furnished rights-of-way is subject to all applicable Federal and state environmental laws and regulations. Compliance with these environmental laws and regulations may require additional National Environmental Policy Act (NEPA) documents, cultural resources surveys, coordination with the Louisiana State Historical Preservation Officer, water quality certification, modification of the Federal consistency determination, etc. The Government is ultimately responsible for environmental compliance; therefore, the Government will determine the

additional environmental coordination and documentation necessary for a proposed deviation to the Government furnished rights-of-way. For any environmental investigations the Government is to perform on areas outside of Government furnished rights-of-way, the Contractor shall provide sufficient rights of entry to the Government. The Contracting Officer will advise the Contractor of the additional environmental coordination and documentation that must be completed. The Government shall be responsible for any additional environmental compliance; however, the Contractor may conduct specific tasks identified by the Government. The Government will offer advice and assistance to the Contractor in conducting these tasks. Depending on the environmental impact of the proposed deviation, obtaining the coordination and documentation may not be approved or could take as much as 180 days for approval by the Government. The Government must review, approve, and ensure distribution of all environmental compliance documentation and ensure all comments on the same have been resolved before any utilization of any areas outside of the Government furnished rights-of-way. The Contractor shall reimburse the Government for actual expenses incurred for assistance in completing or attempting to complete additional environmental coordination and documentation, which expenses will not exceed one hundred thousand (\$100,000) dollars. There is no guarantee that environmental compliance will be obtained; therefore, the Contractor shall assume all risks and liabilities associated with pursuing a deviation. Any delays resulting from the deviation and/or the environmental coordination and documentation shall not be made the basis of any Contractor claim for increase in the contract cost and/or increase in contract time. Deviations will be at Contractor's sole risk and liability, including, but not limited to, such liabilities associated with items such as hazardous substances regulated under the Comprehensive Environmental Response, Compensation, and Liability Act (42 U.S.C. 9601 et. seq.), and at no cost to the Government. Government assistance in obtaining additional environmental clearances does not relieve the Contractor of responsibility for complying with other Federal, state or local licenses and permits.

c. Additional rights-of-way requirements specific to a particular dredging region will be located in the applicable Dredging Region Section(s).

1.7 MOBILIZATION OF ATTENDANT PLANT

Pursuant to Section 00800, paragraph entitled "Delivery of Plant", mobilization of all attendant plant, if required, shall be concurrent with dredge mobilization. Failure to timely mobilize such auxiliary/attendant plant may result in one or more of the following actions by the Contracting Officer or his/her authorized representative: reasonable suspension (without Government cost) of work until required plant is provided and/or formulation of credit to offset deficient plant. The Government's rights under any other Contract Clause are preserved.

1.8 OBSTRUCTION OF CHANNEL

The Government will not undertake to keep the channel free from vessels or other obstructions, except to the extent of such regulations, if any, as may be prescribed by the Secretary of the Army, in accordance with the provisions of Section 7 of the River and Harbor Act of 8 August 1917. The Contractor will be required to conduct the work in such a manner as to obstruct navigation as little as possible, and in the case the Contractor's

plant so obstructs the channel as to make difficult or endanger the passage of vessels, said plant shall be promptly moved on the approach of any vessel to such an extent as may be necessary to afford a practicable passage. Upon the completion of the work, the Contractor shall promptly remove its plant, including ranges, buoys, piles, and other markers placed under this contract in navigable waters or on shore.

1.9 WORK BY OTHERS

The Government may award other contracts for additional work in the area, or undertake work with its own personnel and equipment. The Contractor shall fully cooperate with such Contractors or Government forces, and shall neither commit nor permit any act that may interfere with the performance of work by any other Contractor or Government forces.

1.10 CONTRACTOR'S RESPONSIBILITY

The Contractor shall be responsible for ensuring that all its employees strictly comply with all laws that may apply to operations under this contract. Compliance with the provisions of this section by subcontractors will be the responsibility of the Contractor. The Contractor assumes full responsibility for the safety of its employees, plant, and materials and for any damage or injury done by or to them from any source or cause, except damage caused by negligent acts of the Government, its officers, agents, or employees. Such damages will be the responsibility of the Government in accordance with applicable Federal laws. The terms "officer", "agent", and "employee" of the Government do not include persons in the employ of the Contractor and whose services have been furnished to the Government. The Contractor shall be responsible for the dredge, attendant plant, and all additional equipment used for this contract. Should any of the aforementioned or parts thereof fall overboard or sink within the dredging region, the Contractor shall develop a plan to recover the sunken equipment or parts thereof at no additional cost to the Government. The Government will not be responsible to recover or assist in the recovery of the Contractor's sunken equipment or parts thereof.

1.11 SUPERVISION

At all times during performance of this contract and until the work is completed and accepted, the Contractor shall have on the worksite a competent superintendent who is satisfactory to the Contracting Officer and has authority to act for the Contractor. Inspectors appointed by the Contracting Officer will enforce strict compliance with the terms of the contract. The inspectors will keep a record of the work done, but neither the presence nor absence of inspectors shall relieve the Contractor of responsibility for the proper execution of the work in accordance with the contract and directives issued by the Contracting Officer.

1.12 AS-BUILT DRAWINGS

The Contractor will be furnished one set of plates for use in the preparation of properly scaled "As-Built" drawings. The Contractor shall submit an entire set of "As-built" drawings, regardless of whether or not any dredging, disposal, or changes were made on those plates. The "As-Built" drawings shall be a record of the construction as completed by the Contractor. "As-Built" drawings shall include the following:

- a. A Cover Page that shall include the project title, contract number and Contractor;

b. A Dredging Summary Sheet that shall include the following (at a minimum): dredging regions dredged, dredge name, dates dredged per each dredging region, credited yardage per each dredging region, gross yardage per each dredging region, and gross yardage per each disposal location. If multiple dredges were used, the information shall include what each dredge dredged by date, the credited and gross yardage in each dredging region, and gross yardage per each disposal location;

c. A Utility Summary Sheet that shall list every utility (for both the dredging channel and disposal areas). For every utility, the following verified information shall be provided: C/L station, C/L XY-coordinate, right descending bank toe XY-coordinate, left descending bank toe XY-coordinate, minimum elevation, all horizontal information required to determine actual alignments of all utilities, utility size, utility type, and POC information. In the notes column, state whether the utilities were dredged over, disposed on, skipped (state reason why), and any issues with the utility owner. A sample Utility Summary Sheet is included at the end of this section. If the Contractor worked in multiple dredging regions, the Contractor shall fill out a separate Utility Summary Sheet for each dredging region. The Contractor shall also submit a copy of all utility as-builts, surveys, etc received from the owner. All utility as-builts shall be labeled such that each as-built has the current owner's name and pipeline location (C/L Station and Mile #) on it;

d. All information shown on the contract plates and a record of all completed work, including any deviations, modifications or changes from those plates, however minor, which may have been incorporated into the work;

e. Borrow area(s) neat line and actual quantity by reach of dredging;

f. All additional work not appearing on the contract plates; and

g. Each various feature of work performed shall be distinguishable by color coding and/or symbology. As a minimum the following features shall be depicted on the as-built drawings:

- (1) Reaches of borrow area(s) dredged, including gross and net yards, and dates dredged.
- (2) Contract number, Contractor and dredge name.
- (3) Location of saltwater sill, including gross yardage placed on sill.
- (4) After dredging borrow area(s) sections and acceptance profiles.
- (5) Dates of dredging each borrow area cut.
- (6) Spill barge location(s) while constructing the saltwater sill.
- (7) Length of submerged and floating pipe used per day.
- (8) Vertical control utilized including any applicable conversions.
- (9) Utility locations as verified by owners including C/L station, C/L XY-coordinate, minimum elevation, utility size, utility type

and POC information.

(10) Channel markers, buoys, daymarkers, etc. surveyed during required preliminary survey efforts.

(11) Changes or modifications issued during the course of the contract.

(12) Final cross sections of the borrow area every 100-ft intervals bank to bank and all P.C's and P.T's.

(13) Final cross sections of the saltwater sill every 100-ft intervals bank to bank.

(14) Sill profile down sill centerline and each toe of the sill bank to bank.

(15) X-Y coordinates of the sill centerline every 100-ft intervals bank to bank.

(16) Final side slopes of sill every 100-ft intervals bank to bank.

(17) Overlays of sill cross sections of before, after, and theoretical.

The Government reserves the right to direct additional requirements. The Contractor shall submit the draft as-builts for review by email in PDF format to the respective area office personnel. Upon approval/acceptance of the draft as-builts, the Contractor shall submit the final as-builts in both CADD and PDF format into RMS as a closeout submittal. Failure to submit final as-built drawing files as specified shall be cause for withholding any payment due to the Contractor under this contract. Approval and acceptance of final as-built drawings shall be accomplished before final payment is made to the Contractor.

1.13 FUEL CONSUMPTION REPORTING REQUIREMENTS

On the first day of each month, the Contractor shall furnish, to the Government Inspector, a report of the quantities of fuel consumed during the previous month in execution of the work covered by the contract. The quantities reported shall include fuel consumed by the Contractor and all of his/her subcontractors for the main plant and all support plant during the preceding month. This information is to be included in the Report of Operations - Pipeline, Dipper or Bucket Dredges, MVN Form 4267.

1.14 GENERAL SECURITY REQUIREMENTS AND GUIDANCE

The security requirements described below apply to all contract personnel (including employees of the prime Contractor ("Contractor") and all subcontractor employees) supporting the performance requirements of this contract. The COR will develop and implement site-specific risk measures to maintain positive control of all contractors (Access-Screening Training Records) and be technically proficient in AT/OPSEC. The Contractor is responsible for compliance with these security requirements. Questions regarding security matters shall be addressed to the designated Government representative (e.g., Contracting Officer Representative (COR), Requiring Activity (RA) representative, or Contracting Officer (if a COR or other RA representative is not appointed)). Contract personnel are critical to the overall security and safety of US Army Corps of Engineers (USACE)

installations, facilities and activities, and security awareness training contributes to those efforts. The Department of Defense (DoD) and Army security training requirements specified below, if applicable, are performance requirements; all applicable contract personnel shall complete initial training within 30 days of contract award or the date new contract personnel begin performance on the contract. Within five business days from the completion of training, the Contractor shall provide written documentation (e.g., email or memorandum) to the Government representative. The documentation shall include the names of contract personnel trained and which training they completed; the Contractor shall maintain training records as part of their contract files and be prepared to provide copies of training certificates to the Government representative. Contractor personnel and vehicles are subject to search when entering federal installations. Additionally, all contract personnel shall comply with Force Protection Condition (FPCON) measures, Random Antiterrorism Measures (commonly referred to as "RAMs"), and Health Protection Condition (HPCON) measures. The Contractor is responsible for meeting performance requirements during elevated FPCON and/or HPCON levels in accordance with applicable RA plans and procedures --this includes identifying mission essential and non-mission essential personnel. In addition to the changes otherwise authorized by the changes clause of this contract, should the FPCON or HPCON levels at any individual facility or installation change, the Government may implement security changes that affect contract personnel. The Contractor shall ensure all contract personnel are aware of their security responsibilities, including any site-specific requirements identified in local policies or procedures.

1.15 SUSPICIOUS ACTIVITY REPORTING TRAINING (e.g. iWATCH, CorpsWatch, or See Something, Say Something)

All contract personnel shall receive initial and annual refresher training from the Requiring Activity (RA) representative on the local suspicious activity reporting program. This locally developed training provides contract personnel with general information on suspicious behavior, and guidance on reporting suspicious activity to the project manager, security representative, or law enforcement entity.

1.16 PRE-SCREEN CANDIDATES USING E-VERIFY PROGRAM

Contractors shall comply with the requirements set forth in FAR clause 52.222-54 Employment Eligibility Verification and FAR Subpart 22.18 in using the E-Verify Program at (<https://www.e-verify.gov/>) (website subject to change) to meet the contract employment eligibility requirements. Contractors are encouraged to cooperate with Federal and State agencies responsible for enforcing labor requirements to include eligibility for employment under United States immigration laws in accordance with FAR 22.102-1(i). An initial list of verified/eligible candidates shall be provided to the COR no later than three business days after the initial contract award. When contracts are with individuals, the individuals will be required to complete a Form I-9, Employment Eligibility Verification, and submit it to the Contracting Officer to become part of the official contract file.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

-- End of Section --

Contract #: _____

Date submitted: _____

Dredge Name: _____

Name of Dredging Region/Crossing: _____

Dredging Region Start Date: _____ , Dredging Region End Date: _____

Note: The Contractor shall fill out one sheet for each dredging region.

Utility Summary Sheet										
C/L Station/Mile #	C/L X, Y Coordinate	RDB Toe X, Y Coordinate	LDB Toe X, Y Coordinate	Minimum Elevation	Size of Utility	Type of Utility	Is utility line properly marked with signage (yes/no)?	Owner Name	Owner Point of Contacts (email address, phone number, and physical address)	Notes: (e.g. - was line dredged over, disposed on, skipped (discuss reason why), any issues with owner, etc)

Note: The Contractor shall fill out one sheet for each dredging region.

Version: April 2025

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 33 00

SUBMITTAL PROCEDURES

PART 1 GENERAL

- 1.1 SUMMARY
- 1.2 DEFINITIONS
 - 1.2.1 Submittal Identification Definitions
- 1.3 MEASUREMENT AND PAYMENT
- 1.4 SUBMITTAL CLASSIFICATION
 - 1.4.1 Government Approved
 - 1.4.2 Information Only
- 1.5 SUBMITTAL PREPARATION
 - 1.5.1 General
 - 1.5.2 Procedures
- 1.6 TRANSMITTAL FORM (ENG FORM 4025-R)
- 1.7 INFORMATION ONLY SUBMITTALS
- 1.8 DEVIATIONS
- 1.9 SUBMITTAL REGISTER (ENG FORM 4288-R)
- 1.10 SCHEDULING
- 1.11 CONTROL OF SUBMITTALS
- 1.12 GOVERNMENT APPROVED SUBMITTALS
- 1.13 DISAPPROVED SUBMITTALS
- 1.14 APPROVED SUBMITTALS
- 1.15 STAMPS

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

ATTACHMENTS:

Transmittal Form (ENG Form 4025-R)

Submittal Register (ENG FORM 4288-R)

-- End of Section Table of Contents --

SECTION 01 33 00

SUBMITTAL PROCEDURES

PART 1 GENERAL

1.1 SUMMARY

The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections.

Units of weights and measures used on all submittals shall be the same as those used in the contract.

Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements.

Each submittal shall be submitted with its complete backup material.

1.2 DEFINITIONS

1.2.1 Submittal Identification Definitions

Drawings

Submittals which graphically show relationship of various components of the work, schematic diagrams of systems, details of fabrication, layouts of particular elements, connections, and other relational aspects of the work.

Data

Submittals that provide calculations, descriptions, or documentation regarding the work.

Samples

Samples, including both fabricated and unfabricated physical examples of materials, products, and units of work as complete units or as portions of units of work.

Schedules

Tabular lists showing location, features, or other pertinent information regarding products, materials, equipment, or components to be used in the work.

Reports

Reports of inspections or tests, including analysis and interpretation of test results.

Certificates

Statement signed by an official authorized to certify on behalf of the manufacturer of a product, system or material, attesting that the

product, system or material meets specified requirements. The statement must be dated after the award of the contract, must state the Contractor's name and address, must name the project and location, and must list the specific requirements that are being certified.

Instructions

Preprinted material describing installation of a product, system or material, including special notices and material safety data sheets, if any, concerning impedances, hazards, and safety precautions.

Statements

A document, required of the Contractor, or through the Contractor, from a supplier, installer, manufacturer, or other lower tier Contractor, the purpose of which is to confirm the quality or orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel, qualifications, or other verifications of quality.

Operation and Maintenance Manuals

Data that forms a part of an operation and maintenance manual.

Records

Documentation to record compliance with technical or administrative requirements.

1.3 MEASUREMENT AND PAYMENT

No separate measurement or payment will be made for submittal requirements as specified herein. All costs for the work covered under this section shall be distributed throughout the existing bid items. Payment for materials incorporated in the work will not be made if required approvals have not been obtained.

1.4 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

1.4.1 Government Approved

Governmental approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction" (FAR 52.236-21), they are considered to be "shop drawings". Any reference to Government approval by the Contracting Officer (CO) includes the approving authority of the CO, the Administrative Contracting Officer (ACO), or the Contracting Officer's representative (COR).

1.4.2 Information Only

All submittals not requiring Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above.

1.5 SUBMITTAL PREPARATION

1.5.1 General

The Contractor shall submit all items listed on the Submittal Register (ENG Form 4288-R) or specified in the other sections of these specifications. The Contractor shall make submittals as required by the specifications. Submittals shall be made to the respective Area Office address listed in the provision entitled "Site Visit (Construction)" (FAR 52.236-27) in Section 00100 - Instructions to Bidders. Proposed deviations from the contract requirements shall be clearly identified. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. Samples remaining upon completion of the work shall be picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations.

1.5.2 Procedures

Procedures for submittals will be stipulated by the Contracting Officer or his/her authorized representative after Notice to Proceed is issued.

1.6 TRANSMITTAL FORM (ENG FORM 4025-R)

The sample Transmittal Form (ENG Form 4025-R) attached to this section shall be used for submitting both Government approved and information only submittals in accordance with the instructions on the reverse side of the form. This form shall be properly completed by filling out all the heading blank spaces and identifying each item submitted. Special care shall be exercised to ensure proper listing of the specification paragraph and/or plate number of the contract plates pertinent to the data submitted for each item.

1.7 INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.8 DEVIATIONS

For submittals that include proposed deviations requested by the Contractor, the column "variation" of ENG Form 4025-R shall be checked. The Contractor shall set forth in writing the reason for any deviations and annotate such deviations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted

deviations.

1.9 SUBMITTAL REGISTER (ENG FORM 4288-R)

The sample Submittal Register (ENG FORM 4288-R) at the end of this section lists items of equipment and materials for which submittals are required by the specifications; this list may not be all-inclusive and additional submittals may be required. Columns "c" thru "r" have been completed by the Government. The Contractor shall complete columns "a", "b", and "s" thru "x", and return the completed register to the Contracting Officer within 7 calendar days after Notice to Proceed for approval. The approved submittal register will become the scheduling document and will be used to control submittals throughout the life of the contract. The submittal register and the progress schedules shall be coordinated. The Contractor is responsible for maintaining an effective submittal control system by reviewing, updating, and submitting updated copies of the register to the Contracting Officer every 30 days.

1.10 SCHEDULING

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a minimum of 30 calendar days exclusive of mailing time) shall be allowed and shown on the register for review and approval. No delays, damages or time extensions will be allowed for time lost in late submittals.

1.11 CONTROL OF SUBMITTALS

The Contractor shall carefully control its procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "SUBMITTAL REGISTER".

1.12 GOVERNMENT APPROVED SUBMITTALS

Upon completion of review of submittals requiring Government approval, the submittals will be identified as having received approval via RMS. Any additional instructions will be provided by the Administrative Contracting Officer.

1.13 DISAPPROVED SUBMITTALS

The Contractor shall respond to all concerns expressed by the Contracting Officer and promptly make any corrections necessary to address those concerns. The Contractor shall promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" (FAR 52.243-4) shall be given promptly to the Contracting Officer.

1.14 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error that may exist; the Contractor is responsible for dimensions, the

design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.15 STAMPS

Stamps used by the Contractor on the submittal data to certify that the submittal meets contract requirements is to be similar to the following:

CONTRACTOR
(Firm Name)
_____ Approved
_____ Approved with corrections as noted on submittal data and/or attached sheet(s)
SIGNATURE: _____
TITLE: _____
DATE: _____

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

-- End of Section --

**TRANSMITTAL OF SHOP DRAWINGS, EQUIPMENT DATA, MATERIAL SAMPLES, OR
MANUFACTURER'S CERTIFICATES OF COMPLIANCE**

For use of this form, see ER 415-1-10; the proponent agency is CECW-CE.

DATE

TRANSMITTAL NO.

SECTION I - REQUEST FOR APPROVAL OF THE FOLLOWING ITEMS *(This section will be initiated by the contractor)*

TO:

FROM:

CONTRACT NO.

CHECK ONE:

☐ THIS IS A NEW TRANSMITTAL

☐ THIS IS A RESUBMITTAL OF

TRANSMITTAL _____

SPECIFICATION SEC. NO. *(Cover only one section with each transmittal)*

PROJECT TITLE AND LOCATION

THIS TRANSMITTAL IS FOR: *(Check one)*

☐ FIO ☐ GA ☐ DA ☐ CR ☐ DA/CR ☐ DA/GA

ITEM NO. <i>(See Note 3)</i> a.	DESCRIPTION OF SUBMITTAL ITEM <i>(Type size, model number/etc.)</i> b.	SUBMITTAL TYPE CODE <i>(See Note 8)</i> c.	NO. OF COPIES d.	CONTRACT DOCUMENT REFERENCE		CONTRACTOR REVIEW CODE g.	VARIATION Enter "Y" if requesting a variation <i>(See Note 6)</i> h.	USACE ACTION CODE <i>(Note 9)</i> i.
				SPEC. PARA. NO. e.	DRAWING SHEET NO. f.			

REMARKS

I certify that the above submitted items had been reviewed in detail and are correct and in strict conformance with the contract drawings and specifications except as otherwise stated.

NAME OF CONTRACTOR

SIGNATURE OF CONTRACTOR

SECTION II - APPROVAL ACTION

ENCLOSURES RETURNED *(List by item No.)*

NAME AND TITLE OF APPROVING AUTHORITY

SIGNATURE OF APPROVING AUTHORITY

DATE

INSTRUCTIONS

1. Section I will be initiated by the Contractor in the required number of copies.
2. Each Transmittal shall be numbered consecutively. The Transmittal Number typically includes two parts separated by a dash (-). The first part is the specification section number. The second part is a sequential number for the submittals under that spec section. If the Transmittal is a resubmittal, then add a decimal point to the end of the original Transmittal Number and begin numbering the resubmittal packages sequentially after the decimal.
3. The "Item No." for each entry on this form will be the same "Item No." as indicated on ENG FORM 4288-R.
4. Submittals requiring expeditious handling will be submitted on a separate ENG Form 4025-R.
5. Items transmitted on each transmittal form will be from the same specification section. Do not combine submittal information from different specification sections in a single transmittal.
6. If the data submitted are intentionally in variance with the contract requirements, indicate a variation in column h, and enter a statement in the Remarks block describing the detailed reason for the variation.
7. ENG Form 4025-R is self-transmitting - a letter of transmittal is not required.
8. When submittal items are transmitted, indicate the "Submittal Type" (*SD-01 through SD-11*) in column c of Section I.
Submittal types are the following:

SD-01 - Preconstruction	SD-02 - Shop Drawings	SD-03 - Product Data	SD-04 - Samples	SD-05 - Design Data	SD-06 - Test Reports
SD-07 - Certificates	SD-08 - Manufacturer's Instructions	SD-09 - Manufacturer's Field Reports	SD-10 - O&M Data	SD-11 - Closeout	
9. For each submittal item, the Contractor will assign Submittal Action Codes in column g of Section I. The U.S. Army Corps of Engineers approving authority will assign Submittal Action Codes in column i of Section I. The Submittal Action Codes are:

A -- Approved as submitted. B -- Approved, except as noted on drawings. Resubmission not required. C -- Approved, except as noted on drawings. Refer to attached comments. Resubmission required. D -- Will be returned by separate correspondence. E -- Disapproved. Refer to attached comments.	F -- Receipt acknowledged. X -- Receipt acknowledged, does not comply with contract requirements, as noted. G -- Other action required (<i>Specify</i>) K -- Government concurs with intermediate design. (<i>For D-B contracts</i>) R -- Design submittal is acceptable for release for construction. (<i>For D-B contracts</i>)
--	---
10. Approval of items does not relieve the contractor from complying with all the requirements of the contract.

SUBMITTAL REGISTER																	CONTRACT NO.									
(ER 415-1-10)																										
TITLE AND LOCATION													CONTRACTOR			SPECIFICATION SECTION										
Mississippi River Saltwater Barrier Sill Cutterhead Dredge #2-2025																										
ACTIVITY NO	TRANSMITTAL NO	ITEM NO	SPECIFICATION SECTION NUMBER	DESCRIPTION OF ITEM SUBMITTED	TYPE OF SUBMITTAL										CLASSIFICATION	REVIEWER	CONTRACTOR SCHEDULE DATES			CONTRACTOR ACTION			GOVERNMENT ACTION		REMARKS	
					DRAWINGS	INSTRUCTIONS	SCHEMATIC	STATEMENTS	REFERENCES	CERTIFICATES	SALES	RECORDS	O&M	INFORMATION			GOVERNMENT	SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	DATE	SUBMIT TO GOVERNMENT	DATE			
a.	b.	c.	d.	e.	f.	g.	h.	i.	j.	k.	l.	m.	n.	o.	p.	q.	r.	s.	t.	u.	v.	w.	x.	y.	z.	aa.
		1	01 30 00	As-Built Drawings	X											X	NOAO & ODT-D									
		2	01 35 26	Accident Prevention Program												X	SS									
		3	01 57 20.00 10	Environmental Protection Plan	X											X	ODT-E (Corbino)									
		4	35 01 50.73	Plan for Verification of Survey Equipment	X											X	NOAO & ODT-C (Oakman)									
		5	35 01 50.73	Calibration of Fathometer	X											X	NOAO & ODT-C (Oakman)									
		6	35 01 50.73	Calibration of Horizontal Positioning Equipment	X											X	NOAO & ODT-C (Oakman)									
		7	35 01 50.73	Cross Sections	X	X										X	NOAO									
		8	35 01 50.73	Quantity Computations	X											X	X	NOAO								
		9	35 01 50.73	Profiles	X	X										X	X	NOAO								
		10	35 20 23.23	Pump curve(s)	X											X		ODT-D								
		11	35 20 23.23	Plant Data Sheet	X											X		ODT-D								
		12	35 20 23.23	Plan of Operations for Utility Crossing					X							X		NOAO								
		13	35 20 23.23	Utility As-builts and Surveys Received from the Owners	X	X										X		ODT-D								
		14	35 20 23.23 16	Construction Plan		X			X							X		ODC (Kornick,Jennings) & ODT-D								
		15	35 20 23.33	Letter of National Dredging Quality Management Program Certification							X					X		ODT-D								

ENG FORM 4288-R, JAN 97

EDITION OF MAR 95 IS OBSOLETE.

PAGE_1_ OF _1_ PAGES

(PROPONENT: CEMP-CE)

NOTE: THIS REGISTER IS NOT NECESSARILY COMPLETE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEVELOPING A COMPREHENSIVE REGISTER

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS

PART 1 GENERAL

- 1.1 SAFETY PROVISIONS
- 1.2 MEASUREMENT AND PAYMENT
- 1.3 SITE QUALIFICATIONS, DUTIES AND MEETINGS
 - 1.3.1 Personnel Qualifications
 - 1.3.1.1 Site Safety and Health Officer (SSHO)
 - 1.3.1.1.1 SSHO Staffing for USACE Dredging Contracts
 - 1.3.1.1.2 SSHO Requirements for Dredging
 - 1.3.1.1.3 Designated Representative (DR) Requirements for Dredging
 - 1.3.1.1.4 Safety Personnel Training Requirements
 - 1.3.1.2 Equipment Operator Authorization
 - 1.3.1.3 Crane/Derrick and Dragline Certification
 - 1.3.2 Personnel Duties
 - 1.3.2.1 Daily Inspections
- 1.4 ACCIDENT PREVENTION PROGRAM
- 1.5 DIVE PLAN
- 1.6 SAFETY SIGN
- 1.7 PROJECT SIGN
- 1.8 MEANS OF ESCAPE FOR PERSONNEL QUARTERED OR WORKING ON FLOATING PLANT
- 1.9 EMERGENCY ALARMS, SIGNALS AND DRILLS
 - 1.9.1 Alarms
 - 1.9.2 Signals
 - 1.9.2.1 Fire Alarm Signals
 - 1.9.2.2 Abandon Ship Signals
 - 1.9.2.3 Man Overboard Signal
 - 1.9.3 Drills
- 1.10 SIGNAL LIGHTS
- 1.11 REPORTS
 - 1.11.1 Accident Investigation and Reporting
- 1.12 HURRICANE PLAN
- 1.13 COMPREHENSIVE HAZARD COMMUNICATION PROGRAM

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

- 3.1 GROUND FAULT PROTECTION
- 3.2 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)
- 3.3 RADIATION

ATTACHMENTS:

Safety Sign

Project Sign

-- End of Section Table of Contents --

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS

PART 1 GENERAL

1.1 SAFETY PROVISIONS

All work under these specifications shall be performed in accordance with the provisions of EM 385-1-1 "Safety and Occupational Health Requirements", the latest edition. USCG Rules and regulations also are applicable.

1.2 MEASUREMENT AND PAYMENT

No separate measurement or payment will be made for governmental safety requirements as specified herein. All costs for the work covered under this section shall be distributed throughout the existing bid items.

1.3 SITE QUALIFICATIONS, DUTIES AND MEETINGS

1.3.1 Personnel Qualifications

1.3.1.1 Site Safety and Health Officer (SSHO)

1.3.1.1.1 SSHO Staffing for USACE Dredging Contracts

a. Dredging contracts may include several project sites; this contract will require a minimum of one full time level 1 SSHO(s) assigned per project site. SSHO may be level 2 or level 3 collateral duty in specific conditions listed below.

b. Example of one dredging project site is reflected in each of the following:

1) a mechanical dredge, tug(s) and scow(s), scow route, and material placement site; or

2) a hydraulic pipeline dredge, attendant plant, and material placement site; or,

3) a hopper dredge (include land-based material placement site - if applicable.)

c. On individual dredging project sites with work force less than 8 employees, the SSHO may be a level 2 or level 3 collateral duty, with the same responsibilities of a full time level 1 SSHO.

1.3.1.1.2 SSHO Requirements for Dredging

a. In addition to requirements stated elsewhere in this specification, the SSHO shall be present at the project site, located so they have full mobility and reasonable access to all major work operations, for at least one shift in each 24 hour period when work is being done. The SSHO, or Alternate SSHO, shall be available during all shifts for immediate verbal consultation and notification, either by phone or radio. The SSHO shall be a full-time, dedicated position, except as noted above. The SSHO (level 1 and level 2) shall report to a senior project (or corporate) official.

b. The SSHO shall inspect all work areas and operations during initial set-up and at least monthly observe and provide personal oversight on each shift during dredging operations for projects with many work sites, more often for those with less work sites.

c. For projects with multiple shifts or when SSHO is temporarily off-site, an Alternate level 2 SSHO will be assigned to ensure SSHO coverage for the project at all times work activities are conducted. The Alternate SSHO must meet the same requirements and assume the responsibilities of the project SSHO. The Alternate SSHO position may be a collateral duty.

d. If the SSHO is off-site for a period longer than 24 hours, a qualified replacement SSHO shall be provided and shall fulfill the same roles and responsibilities as the primary/ initial SSHO.

1.3.1.1.3 Designated Representative (DR) Requirements for Dredging

a. Designated Representatives (DR) are level 2 or level 3 collateral duty safety personnel, with safety duties in addition to their full-time occupation, and support and supplement the SSHO efforts in managing, implementing and enforcing the Contractor's Safety and Health Program. DRs shall be individual(s) with work oversight responsibilities, such as masters, mates, fill foremen, and superintendents. DRs should not be positions requiring continuous mechanical or equipment operations, such as equipment operators.

b. A DR shall be appointed for all remote work locations more than 45 minutes' travel time from the SSHO's duty location, typically including dredged material placement sites, towing and scow operations, and other operations.

c. The DRs will perform safety program tasks as designated by the SSHO and report safety findings to the level 1 or level 2 SSHO/Alternate SSHO. The SSHO shall document results of safety findings and provide information for inclusion in the CQC reports to the Government Representative on a daily basis.

1.3.1.1.4 Safety Personnel Training Requirements

The SSHO shall meet the training and experience requirements of EM 385-1-1, Chapter 2-3.b. Level 1 SSHOs are not permitted to supervise non-safety personnel at the site of work.

1.3.1.2 Equipment Operator Authorization

The Contractor shall submit a list of designated personnel qualified and authorized to operate machinery and mechanized equipment in accordance with EM 385-1-1.

1.3.1.3 Crane/Derrick and Dragline Certification

The Contractor shall submit a copy of certification and performance test in accordance with EM 385-1-1.

1.3.2 Personnel Duties

1.3.2.1 Daily Inspections

The Contractor shall institute a daily inspection program to assure that safety requirements are being fulfilled. Reports of daily inspections shall be maintained at the jobsite. The reports shall be records of the daily inspections and resulting corrective actions. Each report shall include, as a minimum, the following:

- a. Phase(s) of construction underway during the inspection.
- b. Location(s) of areas where inspections were made.
- c. Results of inspections shall be reported in a deficiency tracking log in accordance with EM 385-1-1, including nature of deficiencies observed and corrective action taken or to be taken, date, and signature of the person responsible for its contents. The Contractor shall submit to the Government a copy of the daily inspection report form that's intended to be used as part of the Accident Prevention Plan for execution of the work.

1.4 ACCIDENT PREVENTION PROGRAM

Refer to the Contract Clause in Section 00700 - Contract Clauses, entitled "Accident Prevention" (FAR 52.236-13). Within 24 hours after receipt of Notice of Award of the contract, the Accident Prevention Program shall be submitted to the Contracting Officer or his/her authorized representative for review and acceptance. The Accident Prevention Plan must include a statement that describes the: Description, Magnitude, Major Scope of Work and Location(s). The program shall be submitted in the following format:

- a. The Contractor shall submit ENG Form 6206 (Activity Hazard Analysis (AHA)), ENG Form 6292 (Site-Specific Safety & Occupational Health Plan Worksheet), ENG Form 6293 (Accident Prevention Plan (APP) Worksheet), and ENG Form 6282 (Site Safety and Health Officer Designation Letter). These ENG forms can be obtained from:
<https://www.publications.usace.army.mil/USACE-Publications/Engineer-Forms/>.
- b. The Contractor shall submit a copy of company policy statement regarding accident prevention.
- c. When marine plant and equipment are in use under a contract, the method of fuel oil transfer shall be included on MVN Form 385-10R, Fuel Oil Transfer. The Fuel Oil Transfer form can be obtained from:
<https://www.mvn.usace.army.mil/About/Offices/Safety/Safety-Forms/>.

The Contractor shall not commence physical work at the site until the program has been accepted by the Contracting Officer or his/her authorized representative. The Contractor may submit its Activity Hazard Analysis only for the first phase of construction provided that it is accompanied by an outline of the remaining phases of construction. All remaining phases shall be submitted and accepted prior to the beginning of work in each phase. See EM 385-1-1.

1.5 DIVE PLAN

A Dive Plan shall be submitted as a safety submittal item of the contract Accident Prevention Plan. All contract diving operations shall be

performed in accordance with EM 385-1-1, Chapter 30. At a minimum, the dive plan will address items in EM 385-1-1.

1.6 SAFETY SIGN

The Contractor shall furnish, erect, and maintain a Safety Sign at the site where indicated by the Contracting Officer. The sign shall conform to the requirements of this paragraph and the drawings included at the end of this section. The lettering shall be black, the safety circle and cross green, and the background white. When placed on a floating plant, the sign may be half size. The sign shall be erected as soon as practicable, but not later than 15 calendar days after the date established for commencement of work. The data required shall be current. The sign coordinator is Timothy Lacoste at (504) 862-2663. Upon completion of the work, the sign shall become the property of the Contractor and shall be removed from the job site.

1.7 PROJECT SIGN

Prior to commencement of work, the Contractor shall construct a Project Sign at the site of the work at a location directed by the Contracting Officer. The sign, which will identify the work with the Corps of Engineers shall be 4 feet by 6 feet in size and shall conform to the requirements of this paragraph and the drawings included at the end of this section. The lettering for the 2 feet by 4 feet section of the sign with the Corps logo and Army Star shall be white; all other lettering shall be black. Lettering for the project name shall be Helvetica Bold, all other lettering shall be Helvetica Regular. The sign coordinator is Timothy Lacoste at (504) 862-2663. Upon completion of the work, the sign shall become the property of the Contractor and shall be removed from the job site.

1.8 MEANS OF ESCAPE FOR PERSONNEL QUARTERED OR WORKING ON FLOATING PLANT

Two means of escape shall be provided for assembly, sleeping, and messing areas on floating plants. For areas involving ten or more persons, both means of egress shall be through standard-sized doors opening to different exit routes. Where nine or fewer persons are involved, one of the means of escape may be a window (minimum dimensions 24" x 36") that leads to a different exit route than the door. See EM 385-1-1.

1.9 EMERGENCY ALARMS, SIGNALS AND DRILLS

1.9.1 Alarms

Emergency alarms shall be installed and maintained on all floating plant requiring a crew where it is possible for either a passenger or crewman to be out of sight or hearing from any other person. The alarm system shall be operated from the primary electrical system with standby batteries on trickle charge that will automatically furnish the required energy during an electrical system failure. A sufficient number of signaling devices shall be placed on each deck so that the sound can be distinctively heard at any point above the usual background noise. All signaling devices shall be so interconnected that actuation can occur from at least one strategic point on each deck.

1.9.2 Signals

1.9.2.1 Fire Alarm Signals

The general fire alarm signal shall be in accordance with 46 CFR Ch. I; Subpart E. 109.503 of the US Coast Guard Rules and Regulations for Cargo and Miscellaneous Vessels, Subchapters I & Ia, 1 Oct 98 (CG 257).

1.9.2.2 Abandon Ship Signals

The signal for abandon ship shall be in accordance with paragraph 109.503(b) of the publication cited in paragraph entitled "Fire Alarms Signals".

1.9.2.3 Man Overboard Signal

Hail and pass the word to the bridge. All personnel and vessels capable of rendering assistance shall respond.

1.9.3 Drills

Drills shall be in accordance with EM 385-1-1.

1.10 SIGNAL LIGHTS

The Contractor shall display signal lights and conduct its operations in accordance with U. S. Coast Guard regulations governing lights and day signals to be displayed, as set forth in Commandant, U. S. Coast Guard Instruction M16672.2C, Navigation Rules, International - Inland (COMDTINST M16672); 33 CFR 81, Appendix A (International); and 33 CFR 84 through 33 CFR 90 (Inland) as applicable.

1.11 REPORTS

1.11.1 Accident Investigation and Reporting

The reporting and associated investigation of accidents and near misses is considered a leading indicator. The Contractor shall utilize the ENG Form 3394 (Mishap Notification and Investigation) to report accidents and near misses. ENG Form 3394 can be obtained from:
<https://www.publications.usace.army.mil/USACE-Publications/Engineer-Forms/>.

1.12 HURRICANE PLAN

A detailed plan for protection and evacuation of personnel and plant in the event of an impending hurricane or storm is required as an enclosure to the Contractor's Accident Prevention Program. This plan shall be submitted to the Contracting Officer or his/her authorized representative for review and approval as part of the Accident Prevention Plan prior to the pre-construction conference. Work being performed to satisfy the Hurricane Plan will not be measured for payment. All costs for the work associated with the Hurricane Plan and providing the equipment required throughout the contract duration shall be distributed throughout the existing bid items. The plan shall include at least the following:

- a. The time each phase will be put into effect. The time shall be the number of hours remaining for the storm to reach the worksite if it continues at the predicted speed and direction.

- b. The safe harbor for personnel and plant specifically identified.
- c. The name of the boat that will be used to move the plant, its type, capacity, speed, and availability.
- d. The estimated time necessary to move the plant to the safe harbor after movement is started.
- e. An on-site review by the Contractor's supervisory personnel and the Government Inspector shall be conducted at the Government Inspector's discretion.

1.13 COMPREHENSIVE HAZARD COMMUNICATION PROGRAM

The Contractor shall develop, implement, and maintain at the workplace a written, Comprehensive Hazard Communication Program (see EM 385-1-1) that includes identification of potential hazards as prescribed in 29 CFR Part 1910.1200 and/or 1926.59, effects of exposure and control measures to be used for chemical products and physical agents that may be encountered during the performance of work on this contract, provisions for container labeling, Material Safety Data Sheets, and employee training program, and other criteria in accordance with 29 CFR Part 1910.1200, 1926.59. Training shall include communication methods and systems to be used (i.e., voice, hand signals, radios or other means), and training in the use and understanding of material safety data sheets and chemical product hazard warning labels. Prior to bringing hazardous substances, as defined in 29 CFR 1910.1200 and/or 1926.59, onto the job site, a copy of the Hazard Communication Program and the Material Safety Data Sheet of each substance shall be provided to the Contracting Officer or his/her authorized representative and made available to the Contractor's employees as part of the Contractor's Accident Prevention Program.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

3.1 GROUND FAULT PROTECTION

All electrical equipment used on this contract shall be equipped with ground fault circuit interrupters, in accordance with EM 385-1-1.

3.2 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)

The Contractor shall develop, implement, and maintain at the workplace a written control of hazardous energy (lockout/tagout) system, in accordance with EM 385-1-1.

3.3 RADIATION

If a production meter that uses nuclear materials is being used aboard the dredge, the Contractor shall perform the following requirements. The production meter nuclear device system designer and installer shall be qualified in these fields of expertise by the Nuclear Regulatory Commission (NRC). The Contractor shall obtain licensing and training as required by the NRC for its personnel aboard the dredge for the use of those components of the production meter containing or are affected by the nuclear source. The Contractor shall implement a nuclear device awareness program as required by the NRC for all personnel aboard the dredge not directly involved in the activities of the nuclear device. The Contractor shall

submit a nuclear device safety plan to the Government within 24 hrs after receipt of Notice to Proceed by the Contractor. While a nuclear device is present aboard the dredge, the Contractor shall strictly adhere to all applicable NRC rules and regulations.

-- End of Section --

Project Identification Sign

Below are two samples of the construction project identification sign showing how this panel is adaptable for use to identify either military (top), or civil works projects (bottom). The graphic format for this 4' x 6' sign panel follows the legend guidelines and layout as specified below. The large

4' x 4' section of the panel on the right is to be white with black legend. The 2' x 4' section of the sign on the left with the full Corps signature (reverse version) is to be screen printed Communications Red on the white background.

This sign is to be placed with the Safety Performance Sign shown on the following

page. Mounting and fabrication details are provided on page 16.4.

Special applications or situations not covered in these guidelines should be referred to the District/Division sign coordinator.

Legend Group 1: One- to two-line description of Corps relationship to project.
Color: White
Typeface: 1.25" Helvetica Regular
Maximum line length: 19"

Legend Group 2: Division or District Name (optional). Placed below 10.5" Reverse Signature (6" Castle).
Color: White
Typeface: 1.25" Helvetica Regular



Legend Group 3: One- to three-line project title legend describes the work being done under this contract.
Color: Black
Typeface: 3" Helvetica Bold
Maximum line length: 42"

Legend Group 4: One- to two-line identification of project or facility (civil works) or name of sponsoring department (military).
Color: Black
Typeface: 1.5" Helvetica Regular
Maximum line length: 42"

Cross-align the first line of Legend Group 4 with the first line of the Corps Signature (US Army Corps) as shown.

Legend Groups 5a-b: One- to five-line identification of prime contractors including: type (architect, general contractor, etc.), corporate or firm name, city, state. Use of Legend Group 5 is optional.
Color: Black
Typeface: 1.25" Helvetica Regular
Maximum line length: 21"

All typography is flush left and rag right, upper and lower case with initial capitals only as shown. Letter- and word-spacing to follow Corps standards as specified in Appendix D.



Sign Type	Legend Size	Panel Size	Post Size	Specification Code	Mounting Height	Color Bkg/Lgd
CID-01	various	4" x 6"	4" x 4"	HDO-3	48"	WH-RD/BK

Safety Performance Sign

Each contractor's safety record is to be posted on Corps managed or supervised construction projects and mounted with the construction project identification sign specified on page 16.2.

The graphic format, color, size and typefaces used on the sign are to be reproduced exactly as specified below. The title

with First Aid logo in the top section of the sign, and the performance record captions are standard for all signs of this type. Legend Groups 2 and 3 below identify the project and the contractor and are to be placed on the sign as shown.

Safety record numbers are mounted on individual metal plates and are screw-mounted to the background to allow for

daily revisions to posted safety performance record.

Special applications or situations not covered in these guidelines should be referred to the District/Division sign coordinator.

Legend Group 1: Standard two-line title "Safety is a Job Requirement", with (8" od.) Safety Green First Aid logo. Color: To match PMS 347 Typeface: 3" Helvetica Bold Color: Black


Legend Group 2: One- to two-line project title legend describes the work being done under this contract and name of host project. Color: Black Typeface: 1.5" Helvetica Regular Maximum line length: 42"

Legend Group 3: One- to two-line identification: name of prime contractor and city, state address. Color: Black Typeface: 1.5" Helvetica Regular Maximum line length: 42"

Legend Group 4: Standard safety record captions as shown. Color: Black Typeface: 1.25" Helvetica Regular

Replaceable numbers are to be mounted on white .060 aluminum plates and screw-mounted to background. Color: Black Typeface: 3" Helvetica Regular Plate size: 2.5" x .5"

All typography is flush left and rag right, upper and lower case with initial capitals only as shown. Letter- and word-spacing to follow Corps standards as specified in Appendix D.



Sign Type	Legend Size	Panel Size	Post Size	Specification Code	Mounting Height	Color Bkg/Lgd
CID-02	various	4" x 4"	4" x 4"	HDO-3	48"	WH/BK-GR



Fabrication and Mounting Guidelines

All Construction Project Identification signs and Safety Performance signs are to be fabricated and installed as described below. The signs are to be erected at a location designated by the contracting officer and shall conform to the size, format, and typographic standards shown on

pages 16.2-3. Detailed specifications for HDO plywood panel preparation are provided in Appendix B.

Shown below the mounting diagram is a panel layout grid with spaces provided for project information. Photocopy this page and use as a worksheet when preparing sign legend orders.

For additional information on the proper method to prepare sign panel graphics, contact the District sign coordinator.

The sign panels are to be fabricated from .75" High Density Overlay Plywood. Panel preparation to follow HDO specifications provided in Appendix B.

Sign graphics to be prepared on a white non-reflective vinyl film with positionable adhesive backing.

All graphics except for the Communications Red background with Corps signature on the project sign are to be die-cut or computer-cut non-reflective vinyl, pre-spaced legends prepared in the sizes and typefaces specified and applied to the background panel following the graphic formats shown on pages 16.2-3.


The 2' x 4' Communications Red panel (to match PMS-032) with full Corps signature (reverse version) is to be screen printed on the white background. Identification of the District or Division may be applied under the signature with white cut vinyl letters prepared to Corps standards. Large scale reproduction artwork for the signature is provided on page 4.8 (photographically enlarge from 6.875" to 10.5").

Drill and insert six (6) .375" T-nuts from the front face of the HDO sign panel. Position holes as shown. Flange of T-nut to be flush with sign face.

Apply graphic panel to prepared HDO plywood panel following manufacturers' instructions.

Sign uprights to be structural grade 4" x 4" treated Douglas Fir or Southern Yellow Pine, No.1 or better. Post to be 12' long. Drill six (6) .375" mounting holes in uprights to align with T-nuts in sign panel. Countersink (.5") back of hole to accept socket head cap screw (4" x .375").

Assemble sign panel and uprights. Imbed assembled sign panel and uprights in 4' hole. Local soil conditions and/or wind loading may require bolting additional 2" x 4" struts on inside face of uprights to reinforce installation as shown.



Construction Project Sign Legend Group 1: Corps Relationship

1. _____
2. _____

Legend Group 2: Division/District Name

1. _____
2. _____

Legend Group 3: Project Title

1. _____
2. _____
3. _____

Legend Group 4: Facility Name

1. _____
2. _____

Legend Group 5a: Contractor/A&E

1. _____
2. _____
3. _____
4. _____
5. _____

Legend Group 5b: Contractor/A&E

1. _____
2. _____
3. _____
4. _____
5. _____

Safety Performance Sign Legend Group 1: Project Title

1. _____
2. _____

Legend Group 2: Contractor/A&E

1. _____
2. _____

Design and Construction Supervised by:  US Army Corps of Engineers New Orleans District 	Replacement of North Spillway Gates x Vertically center the featured text group for the project location (below), depending on the number of text lines in the above project title. Lock and Dam 12 Mississippi River Contractor: Oscar Construction Co. Kansas City, Missouri Consulting Engineer: Wilmington, Rotheau, and Eddings Engineering, Inc. Chicago, Illinois
---	---

	3"	31"	3"	8"	3"														
6"	Safety is a Job Requirement  Gap Closures at Pump Station #3, Interim Protection Plan, Phase 1 U.D.H. Builders, Inc. Baton Rouge, Louisiana This project started <table border="1"> <tr> <td></td><td>3</td> <td></td><td>5</td> <td>0</td><td>4</td> </tr> </table> Date since last Lost time accident <table border="1"> <tr> <td></td><td></td> <td></td><td></td> <td></td><td></td> </tr> </table> Total lost time injuries <table border="1"> <tr> <td></td><td>0</td> </tr> </table>						3		5	0	4								0
						3		5	0	4									
						0													
4.5"																			
10.5"																			
2.25"																			
3"																			
2.25"	Example																		
3"																			
4.875"																			
4.875"																			
5"																			
	3"	21"	24"																

(NOT TO SCALE)

.75"	0	0	0
3"	5	0	4
.75"	0	0	0
	2.5"	1.25"	2.5"

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 45 00.15 10

RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM)

PART 1 GENERAL

- 1.1 MEASUREMENT AND PAYMENT
- 1.2 CONTRACT ADMINISTRATION
 - 1.2.1 Correspondence and Electronic Communications
 - 1.2.2 Other Factors
- 1.3 RMS SOFTWARE
- 1.4 CONTRACT DATABASE - GOVERNMENT
- 1.5 CONTRACT DATABASE - CONTRACTOR
 - 1.5.1 Administration
 - 1.5.1.1 Contractor Information
 - 1.5.1.2 Subcontractor Information
 - 1.5.1.3 Correspondence
 - 1.5.1.4 Equipment
 - 1.5.1.5 Reports
 - 1.5.1.6 Request For Information (RFI)
 - 1.5.2 Finances
 - 1.5.2.1 Pay Activity Data
 - 1.5.2.2 Payment Requests
 - 1.5.3 Quality Control (QC)
 - 1.5.3.1 Quality Control (QC) Reports
 - 1.5.3.2 Deficiency Tracking
 - 1.5.3.3 Three-Phase Control Meetings
 - 1.5.3.4 Labor and Equipment Hours
 - 1.5.3.5 Accident/Safety Reporting
 - 1.5.3.6 Definable Features of Work
 - 1.5.3.7 Activity Hazard Analysis
 - 1.5.4 Submittal Management
 - 1.5.5 Schedule
 - 1.5.6 Closeout
- 1.6 IMPLEMENTATION
- 1.7 NOTIFICATION OF NONCOMPLIANCE

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

-- End of Section Table of Contents --

SECTION 01 45 00.15 10

RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM)

PART 1 GENERAL

1.1 MEASUREMENT AND PAYMENT

No separate measurement or payment will be made for providing and maintaining a Resident Management System as described herein. All costs for the work covered under this section shall be distributed throughout the existing bid items.

1.2 CONTRACT ADMINISTRATION

The Government will use the Resident Management System (RMS) to assist in its monitoring and administration of this contract. The Government accesses the system using the Government Mode of RMS (RMS GM) and the Contractor accesses the system using the Contractor Mode (RMS CM). The term RMS will be used in the remainder of this section for both RMS GM and RMS CM. The joint Government-Contractor use of RMS facilitates electronic exchange of information and overall management of the contract. The Contractor shall access RMS to record, maintain, input, track, and electronically share information with the Government throughout the contract period in the following areas:

- Administration
- Finances
- Quality Control
- Submittal Monitoring
- Scheduling
- Closeout
- Import/Export of Data

1.2.1 Correspondence and Electronic Communications

For ease and speed of communications, the Contractor shall exchange correspondence and other documents in electronic format to the maximum extent feasible. Some correspondence, including pay requests and payrolls, are also to be provided in paper format with original signatures. Paper documents will govern, in the event of discrepancy with the electronic version.

1.2.2 Other Factors

Other portions of this document have a direct relationship to the reporting accomplished through RMS. Particular attention is directed to Contract Clause 52.236-15 "Schedules for Construction Contracts"; Contract Clause 52.232-27 "Prompt Payment for Construction Contracts"; Contract Clause 52.232-5 "Payments Under Fixed-Price Construction Contracts"; Section 01 33 00 entitled "Submittal Procedures"; and Section 01 35 26 entitled "Governmental Safety Requirements".

1.3 RMS SOFTWARE

RMS is a web-based application. The Contractor shall download, install,

and be able to utilize the latest version of the RMS software within 7 calendar days of receipt of the Notice to Proceed. RMS software, system requirements, user manuals, access and installation instructions, program updates, and training information are available from the RMS website (<http://rms.usace.army.mil>). The Government and the Contractor will have different access authorities to the same contract database through RMS. The common database will be updated automatically each time a user finalizes an entry or change.

1.4 CONTRACT DATABASE - GOVERNMENT

The Government will enter the basic contract award data in RMS prior to granting the Contractor access. The Government entries into RMS will generally be related to submittal reviews, correspondence status, and Quality Assurance (QA) comments, as well as other miscellaneous administrative information.

1.5 CONTRACT DATABASE - CONTRACTOR

Contractor entries into RMS establish, maintain, and update data throughout the duration of the contract. Contractor entries generally include prime and subcontractor information, daily reports, submittals, RFI's, schedule updates, and payment requests. RMS includes the ability to import attachments and export reports in many of the modules, including submittals. The contractor responsibilities for entries in RMS typically include the following items:

1.5.1 Administration

1.5.1.1 Contractor Information

The Contractor shall enter all current Contractor administrative data and information into RMS within 7 calendar days of receiving access to the contract in RMS. This includes, but is not limited to, Contractor's name, address, telephone numbers, management staff, and other required items.

1.5.1.2 Subcontractor Information

The Contractor shall enter all missing subcontractor administrative data and information into RMS CM within 7 calendar days of receiving access to the contract in RMS or within 7 calendar days of the signing of the subcontractor agreement for agreements signed at a later date. This includes name, trade, address, phone numbers, and other required information for all subcontractors. A subcontractor is listed separately for each trade to be performed.

1.5.1.3 Correspondence

The Contractor shall identify all Contractor correspondence to the Government with a serial number. The Contractor shall prefix correspondence initiated by the Contractor's site office with "S" and shall prefix letters initiated by the Contractor's home (main) office with "H". Letters shall be numbered starting from 0001 (e.g., H-0001 or S-0001). The Government's letters to the Contractor will be prefixed with "C" or "RFP".

1.5.1.4 Equipment

The Contractor shall enter and maintain a current list of equipment planned for use or being used on the jobsite, including the most recent and planned

equipment inspection dates.

1.5.1.5 Reports

The Contractor shall track the status of the project utilizing the reports available in RMS. The value of these reports is reflective of the quality of the data input. These reports include the Progress Payment Request worksheet, Quality Control (QC) comments, Submittal Register Status, and Three-Phase Control worksheets.

1.5.1.6 Request For Information (RFI)

The Contractor shall create and track all Requests For Information (RFI) in the RMS Administration Module for Government review and response.

1.5.2 Finances

1.5.2.1 Pay Activity Data

The Contractor shall develop and enter a list of pay activities. The sum of pay activities equals the total contract amount, including modifications. Each pay activity must be assigned to a Contract Line Item Number (CLIN). The sum of the activities assigned to a CLIN equals the amount of each CLIN.

1.5.2.2 Payment Requests

The Contractor shall prepare all progress payment requests using RMS and shall update the work completed under the contract at least monthly, measured as percent or as specific quantities. After the update, the Contractor shall generate a payment request and prompt payment certification using RMS. The Contractor shall submit the signed prompt payment certification and payment request as well as supporting data either electronically or by hard copy. Unless waived by the Contracting Officer, a signed paper copy of the approved payment certification and request is also required and will govern in the event of discrepancy with the electronic version.

1.5.3 Quality Control (QC)

The Contractor shall identify in his/her Quality Control Plan persons assigned as CQC System Manager and Alternate CQC System Manager. These individuals, within the onsite work organization, shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System Manager shall be a construction person with a minimum of 3 years (full time) experience in related equivalent work. This CQC System Manager shall be onsite at all times during construction and shall be employed by the prime contractor. The CQC System Manager shall not have any duties other than quality control. When the alternate for the CQC System Manager is activated, he/she shall also have no duties other than quality control.

1.5.3.1 Quality Control (QC) Reports

The Contractor's Quality Control (QC) Daily Report in RMS is the official report. The Contractor can use other supplemental formats to record QC data, but information from any supplemental formats are to be consolidated and entered into the RMS QC Daily Report. Any supplemental information may be entered into RMS as an attachment to the report. QC Daily Reports must

be finalized and signed in RMS within 24 hours after the date covered by the report. The Contractor shall provide the Government a printed signed copy of the QC Daily Report, unless waived by the Contracting Officer.

1.5.3.2 Deficiency Tracking

The Contractor shall use the QC Daily Report Module to enter and track deficiencies. Deficiencies identified and entered into RMS by the Contractor or the Government will be sequentially numbered with a QC or QA prefix for tracking purposes. The Contractor shall enter each deficiency into RMS the same day that the deficiency is identified and shall monitor, track, and resolve all QC and QA entered deficiencies. A deficiency is not considered to be corrected until the Government indicates concurrence in RMS.

1.5.3.3 Three-Phase Control Meetings

The Contractor shall maintain scheduled and actual dates and times of preparatory and initial control meetings in RMS. Worksheets for the three-phase control meetings are generated within RMS.

1.5.3.4 Labor and Equipment Hours

The Contractor shall enter labor and equipment exposure hours on a daily basis and shall roll up the labor and equipment exposure data into a monthly exposure report.

1.5.3.5 Accident/Safety Reporting

Both the Contractor and the Government enter safety related comments in RMS as a deficiency. The Contractor shall monitor, track, and show resolution for safety issues in the QC Daily Report area of the RMS QC Module. In addition, the Contractor shall follow all reporting requirements for accidents and incidents as required in EM 385-1-1, Section 01 35 26 entitled "Governmental Safety Requirements", and as required by any other applicable Federal, State or local agencies.

1.5.3.6 Definable Features of Work

The Contractor shall enter each feature of work into the RMS QC Module. A feature of work may be associated with a single or multiple pay activities; however, a pay activity is only to be linked to a single feature of work.

1.5.3.7 Activity Hazard Analysis

The Contractor shall import activity hazard analysis electronic document files into the RMS QC Module utilizing the document package manager.

1.5.4 Submittal Management

The Contractor shall enter all current submittal register data and information into RMS within 7 calendar days of receiving access to the contract in RMS. The information shown on the submittal register in Section 01 33 00 entitled "Submittal Procedures" will already be entered into the RMS database when access is granted. The Contractor shall group electronic submittal documents into transmittal packages to send to the Government, except very large electronic files, samples, spare parts, mock ups, color boards, or where hard copies are specifically required. The Contractor shall track transmittals and update the submittal register in

RMS on a daily basis throughout the duration of the contract. The Contractor shall submit hard copies of all submittals unless waived by the Contracting Officer.

1.5.5 Schedule

The Contractor shall enter and update the contract project schedule in RMS by either manually entering all schedule data or by importing the Standard Data Exchange Format (SDEF) file.

1.5.6 Closeout

Closeout documents, processes and forms are managed and tracked in RMS by both the Contractor and the Government. The Contractor shall ensure that all closeout documents are entered, completed, and documented within RMS.

1.6 IMPLEMENTATION

Use of RMS as described in the preceding paragraphs is mandatory. The Contractor shall ensure that sufficient resources are available to maintain contract data within the RMS system. RMS is an integral part of the Contractor's required management of quality control.

1.7 NOTIFICATION OF NONCOMPLIANCE

The Contractor shall take corrective action within 7 calendar days after receipt of notice of RMS non-compliance by the Contracting Officer.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 57 20.00 10

ENVIRONMENTAL PROTECTION

PART 1 GENERAL

- 1.1 SCOPE
- 1.2 APPLICABLE REGULATIONS
- 1.3 MEASUREMENT AND PAYMENT
- 1.4 ENVIRONMENTAL PROTECTION PLAN
 - 1.4.1 General
 - 1.4.2 Implementation and Reporting
- 1.5 NOTIFICATION OF NONCOMPLIANCE
- 1.6 SUBCONTRACTORS
- 1.7 ENVIRONMENTAL ASSESSMENT OF CONTRACT DEVIATIONS

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

- 3.1 PROTECTION OF LAND OR SUBMERGED RESOURCES
- 3.2 PROTECTION OF WATER RESOURCES
 - 3.2.1 Contamination of Water
 - 3.2.2 Water Quality Monitoring
- 3.3 PROTECTION OF FISH AND WILDLIFE
 - 3.3.1 Manatee Considerations
 - 3.3.2 Sturgeon
- 3.4 DISPOSAL OF MATERIALS
- 3.5 MAINTENANCE OF POLLUTION CONTROL FACILITIES
- 3.6 POLYSTYRENE AND OTHER CHEMICALLY-FORMED FLOTATION COLLAR MATERIAL
USED FOR DREDGE PIPELINES
- 3.7 JANITOR SERVICES
- 3.8 REPORTING OF POLLUTION SPILLS (33 CFR 153.203)

-- End of Section Table of Contents --

SECTION 01 57 20.00 10

ENVIRONMENTAL PROTECTION

PART 1 GENERAL

1.1 SCOPE

a. The work covered by this section consists of furnishing all labor, materials, and equipment, and performing all work required for the prevention of environmental pollution during and as a result of dredging operations and related activities, except for those measures set forth in other technical portions of the Specifications.

b. Environmental pollution is defined as the presence of chemical, physical, or biological elements or agents which:

- (1) Adversely affect human health or welfare;
- (2) Unfavorably alter ecological balances of importance to human life;
- (3) Affect other species of importance to man; or
- (4) Degrade the utility of the environment for aesthetic and recreational purposes.

c. The control of environmental pollution requires consideration of air, water, and land, and involves noise abatement, solid waste management, management of radiant energy, and management of radioactive materials, as well as other pollutants.

1.2 APPLICABLE REGULATIONS

In order to prevent, and to provide for abatement and control of any environmental pollution arising from construction activities in the performance of this contract, the Contractor and his/her subcontractors shall comply with all applicable Federal, State, and Local laws, and regulations concerning environmental pollution control and abatement.

1.3 MEASUREMENT AND PAYMENT

No separate measurement or payment will be made for environmental protection as described herein. All costs for the work covered under this section shall be distributed throughout the existing bid items.

1.4 ENVIRONMENTAL PROTECTION PLAN

1.4.1 General

The Contractor shall establish and maintain a plan for environmental protection, to assure compliance with contract specifications. The Contractor shall also maintain records of environmental protection for all dredging operations, including but not limited to the following:

- a. Environmental pollution control plan;

- b. Applicable Federal, State, and Local pollution control regulations;
- c. Air Pollution - dust, smoke, noise, etc.;
- d. Water Pollution - disposal of water, oil, etc.;
- e. Land Pollution - debris disposal, restoration of temporary construction sites, etc.;
- f. Training course for employees;
- g. Corrective actions taken.

1.4.2 Implementation and Reporting

- a. Within 24 hours after receiving notice to proceed, the Contractor shall submit, in writing, proposals for environmental pollution control, disposal of debris and trash, an Environmental Protection Plan; and
- b. When directed by the Contracting Officer to a Secondary Dredging Region, the Contractor shall re-submit the endangered species portion of the Environmental Protection Plan applicable to that region.

1.5 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor, in writing, of any noncompliance with the environmental clauses and the corrective action to be taken. Such notice, when delivered to the Contractor or the Contractor's authorized representative at the site of work, shall be deemed sufficient for this purpose. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work, until satisfactory corrective action has been taken. No part of time lost due to such a stop order shall be made the subject of a claim for time extensions or for excess costs or damages by the Contractor.

1.6 SUBCONTRACTORS

The Contractor shall be responsible for ensuring that all subcontractors comply with these environmental clauses.

1.7 ENVIRONMENTAL ASSESSMENT OF CONTRACT DEVIATIONS

See Section 01 30 00, paragraph entitled "Rights-of-Way" for a deviation from the government furnished plates or specifications (e.g., proposed borrow, disposal areas, staging areas, alternate access route, etc.).

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

3.1 PROTECTION OF LAND OR SUBMERGED RESOURCES

Discovery of Previously Unknown Archaeological Remains and Artifacts. If during the course of work, archaeological artifacts (prehistoric or historic), watercraft, unmarked graves, burials, human remains, or items of cultural patrimony are discovered, the Contractor shall stop work in the vicinity of the discovery and take all reasonable measures to avoid or minimize harm to the finds. The Contractor shall inform the Government

Inspector, the Contracting Officer Representative and the Administrative Contracting Officer, who will in turn contact CEMVN Historic Preservation (HP) staff. The Contractor shall not proceed with work in the vicinity until CEMVN HP completes consultation with the State Historic Preservation Offices and others unless notified otherwise.

3.2 PROTECTION OF WATER RESOURCES

3.2.1 Contamination of Water

The Contractor shall not pollute any body of water with fuels; oils; bitumens; calcium chlorides; herbicides; insecticides; other materials harmful to fish, shellfish, or wildlife; or with materials that may be a detriment to outdoor recreation. The redistribution or reinjection of pollutants pre-existing in dredged material or river water will not be considered as pollution caused by the Contractor.

3.2.2 Water Quality Monitoring

The Contractor shall assist the Government, using available on-site plant and manpower, in monitoring the water quality aspects of the dredging and disposal operations.

3.3 PROTECTION OF FISH AND WILDLIFE

The Contractor shall keep construction activities under surveillance, management, and control to minimize interference with, disturbance to, and damage of fish and wildlife. The Contractor shall not alter natural water flows or otherwise disturb natural habitat adjacent to or within the project area that are critical to fish or wildlife.

3.3.1 Manatee Considerations

The West Indian manatee may be present in the project vicinity. The Contractor shall instruct all personnel associated with the project of the potential presence of manatees in the area, and the need to avoid collisions with these animals. All construction personnel shall be advised that there are civil and criminal penalties for harming, harassing, or killing manatees. Manatees are protected under the Marine Mammal Protection Act of 1972, and the Endangered Species Act of 1973. The Contractor shall be held responsible for any manatee harmed, harassed, or killed as a result of construction activities not conducted in accordance with these specifications.

Manatee Signs. Prior to commencement of construction, each vessel involved in construction activities shall display at the vessel control station or in a prominent location, visible to all employees operating the vessel, a temporary sign at least 8-1/2" x 11" reading, "CAUTION BOATERS: MANATEE AREA/ IDLE SPEED IS REQUIRED IN CONSTRUCTION AREA AND WHERE THERE IS LESS THAN FOUR FOOT BOTTOM CLEARANCE WHEN MANATEE IS PRESENT". In the absence of a vessel, a temporary 3' x 4' sign reading "CAUTION: MANATEE AREA" shall be posted adjacent to the issued construction permit. A second temporary sign measuring 8-1/2" x 11" reading "CAUTION: MANATEE AREA/ EQUIPMENT MUST BE SHUTDOWN IMMEDIATELY IF A MANATEE COMES WITHIN 50 FEET OF OPERATION" shall be posted at the dredge operator control station and at a location prominently adjacent to the issued construction permit. The Contractor shall remove the signs upon completion of construction.

- a. Special operating conditions if manatees are present in the project

area.

(1) All work, equipment, and vessel operation shall cease if a manatee is spotted within a 50-foot radius (buffer zone) of the active work area. Once the manatee has left the buffer zone on its own accord (manatees must not be herded or harassed into leaving), or after 30 minutes have passed without additional sightings of manatee(s) in the buffer zone, in-water work can resume under careful observation for manatee(s).

(2) If a manatee(s) is sighted in or near the project area, all vessels associated with the project shall operate at "no wake/idle" speeds within the construction area and at all times while in waters where the draft of the vessel provides less than a 4-foot clearance from the bottom. Vessels shall follow routes of deep water whenever possible.

(3) If used, siltation or turbidity barriers shall be properly secured, made of material in which manatees cannot become entangled, and be monitored to avoid manatee entrapment or impeding their movement.

b. Manatee Sighting Reports. Any sightings of manatees or collisions with a manatee shall be immediately reported to the Corps of Engineers. The point of contact within the Corps of Engineers will be Mr. Jeff Corbino, PHONE (504) 862-1958, EMAIL: Jeffrey.M.Corbino@usace.army.mil.

3.3.2 Sturgeon

The Contractor shall ensure that the following are done to reduce the likelihood of sturgeon entrainment:

(1) When lowering the ladder, the pumping rate should be reduced to the slowest speed feasible while the cutterhead is being lowered.

(2) The cutterhead remains completely buried in the channel bottom during dredging operations.

(3) If pumping water through the cutterhead is deemed necessary to dislodge material, or to clean the pumps, the pumping rate should be reduced to the lowest rate feasible while raising the ladder until the cutterhead is at least at mid-depth at which point the pumping rate can be increased.

3.4 DISPOSAL OF MATERIALS

a. The Contractor shall provide daily trash collection and cleanup of the dredge and attendant plant.

b. Disposal locations for waste materials, effluents, trash, garbage, oil, grease, chemicals, etc., shall be such that harmful debris will not enter the waterway, adjacent wetlands, or the disposal areas; prevent the use of the area for recreation; or present a hazard to wildlife. Debris disposal shall be in accordance with applicable Federal, State, and Local regulations, and shall be performed in a manner approved by the Contracting Officer.

3.5 MAINTENANCE OF POLLUTION CONTROL FACILITIES

During the life of this contract, the Contractor shall maintain all facilities constructed for pollution control for as long as the operations creating the particular pollutant are being carried out, or until the material concerned has become stabilized to the extent that pollution is no longer being created. Early in the contract period the Contractor shall conduct a training course that will emphasize all phases of environmental protection. This course shall involve all Contractor personnel working on the contract. The Contractor shall notify the Contracting Officer of the scheduled time for this course so that the Contracting Officer's representative can attend.

3.6 POLYSTYRENE AND OTHER CHEMICALLY-FORMED FLOTATION COLLAR MATERIAL USED FOR DREDGE PIPELINES

The Contractor shall remove all debris caused by the use of polystyrene (styrofoam or similar material) floating pipelines, at the dredge site or any other locations used to install, store, or repair the floating pipeline. Suitable banding, mesh, or other covering shall be placed on the polystyrene floating pipeline to prevent deterioration during normal dredging operations. The discharge line shall conform to lighting requirements set forth by the US Coast Guard in the "Rules of the Road, International-Inland" <http://www.uscg.mil/hq/g-m/nmc/navrules/pdf>.

3.7 JANITOR SERVICES

The Contractor shall furnish daily janitorial services for the dredge and attendant plant during the entire life of the contract. The bathroom facilities shall be kept clean and sanitary at all times. Facilities for the storage, preparation, and serving of food will likewise be kept clean and sanitary. Services shall be performed at such a time and in such a manner to least interfere with operations, and need only be accomplished when the facilities are in daily use.

3.8 REPORTING OF POLLUTION SPILLS (33 CFR 153.203)

If an oil spill or chemical release occurs during the performance of this contract, the Contractor shall contact the National Response Center at 1-800-424-8802, as soon as possible. If telephone communications are not possible, the nearest US Coast Guard office may be contacted by radio to report the spill. The Contractor shall comply with the instructions from the responding agency concerning containment and cleanup of the spill, and shall provide the Contracting Officer with a complete written report of the incident.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 35 - WATERWAY AND MARINE CONSTRUCTION

SECTION 35 01 50.73

SURVEYS

PART 1 GENERAL

- 1.1 SCOPE
- 1.2 MEASUREMENT AND PAYMENT
- 1.3 QUALITY CONTROL
- 1.4 PROFESSIONAL CERTIFICATION

PART 2 PRODUCTS

- 2.1 SURVEY EQUIPMENT
 - 2.1.1 Survey Boat
 - 2.1.2 Fathometer
 - 2.1.2.1 General
 - 2.1.2.2 Calibration
 - 2.1.3 Low Frequency Signal Parameters
 - 2.1.4 Horizontal Positioning Equipment
 - 2.1.5 Water Surface Elevation Measurement

PART 3 EXECUTION

- 3.1 SURVEYS
 - 3.1.1 General
 - 3.1.2 Horizontal and Vertical Control Points
 - 3.1.3 Preliminary Field Surveys
 - 3.1.4 Cross Sections
 - 3.1.5 Profiles
 - 3.1.6 Quantity Computations
 - 3.1.7 Survey Data
 - 3.1.8 Collecting, Recording, Processing, and Transmitting Data

-- End of Section Table of Contents --

SECTION 35 01 50.73

SURVEYS

PART 1 GENERAL

1.1 SCOPE

The work provided for herein consists of furnishing all plant, labor, equipment, and materials, and performing all operations necessary for surveying as specified herein and as indicated on the contract plates. Unless otherwise specified, surveys and surveying shall be in accordance with the latest edition of EM 1110-2-1003, Engineering and Design, Hydrographic Surveying.

1.2 MEASUREMENT AND PAYMENT

No separate measurement or payment will be made for surveys, survey equipment (survey boat, electronic positioning equipment, depth sensors, and appurtenant items), or quantity computations as specified herein. All costs for the work covered under this section shall be distributed throughout existing bid items.

1.3 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with the contract requirements and maintain records of his quality control for all surveying including but not limited to the following:

a. Layouts and Surveys. Daily log of layout work and surveys consisting of type and location using the Government established baselines and gages as stated in the Contract Clause in Section 00700 - Contract Clauses, entitled "Layout of Work (FAR 52.236-17)".

b. Reporting. The original and two copies of these reports and tests as well as the records of corrective action taken, shall be furnished daily to the Government. The report shall include a record of times and dates surveys were run, the horizontal control stations used and their coordinates, the vertical control points used and their elevations, and weather conditions.

1.4 PROFESSIONAL CERTIFICATION

All surveys shall be performed in the presence of the Government Representative. All surveys shall be performed under the direction of and certified by a Professional Land Surveyor currently licensed by any state in the United States of America. In addition, the surveyor shall document at least three years of experience in hydrographic surveying of navigable channels.

PART 2 PRODUCTS

Although listed under PART 2 PRODUCTS, the equipment described herein remains the property of the Contractor at all times.

2.1 SURVEY EQUIPMENT

The Contractor shall submit, to the Contracting Officer for review, a plan for the verification of surveying equipment described herein. The plan shall include types, certifications, calibration checks, etc., for the surveying equipment.

2.1.1 Survey Boat

a. The Contractor shall furnish survey vessel(s), diesel or gasoline powered, twin engine, not less than 30-ft in length, and equipped with the following:

- Enclosed cabin;
- Space for four (4) passengers;
- Heating/air conditioning;
- Fully operated;
- U.S. Coast Guard (USCG) certified;
- Navigation radar, as described in Section 35 20 23.23, paragraph entitled "Navigation Radar";
- Operable radio (same frequency as the dredge) for each dredge in operation;
- A surveying lead line as described in EM 1110-2-1003, paragraph B-2.
- Hydrographic Surveying System: Hydrographic surveying software (HYPACK or equivalent) and electronic horizontal positioning (Differentially corrected Global Positioning, DGPS), depth sounding and data acquisition instrumentation. The use of motion compensation (a heave/pitch/roll sensor) is optional; however, if it is not used, then the conduct of the survey will be restricted by roll/pitch/heave sea-state limits [>10 degrees (roll-pitch), $>.5$ ft (heave)] as interpreted by the on-site Government Representative. Additionally, if the survey system utilizes motion compensation, then a side, bow or stern mounting of the fathometer transducer is acceptable; however, if motion compensation is not available, then the transducer must be hull mounted.
- The vessel(s) must, at minimum, have a fathometer bar check apparatus as described in EM 1110-2-1003, paragraph 4-10.

b. The height of the fathometer transducer face while the vessel(s) is static (draft) and in motion (settlement, squat) must be determined as described in EM 1110-2-1003, paragraph 4-13. A method must be established to determine and correct for any vessel draft changes during the surveying period [ex: RTK observations at static draft to increasing engine RPM (paragraph 4-13c)].

c. Prior to surveying operations, a hydrographic system latency bias calibration test must be performed and the latency correctors must be applied (EM 1110-2-1003, paragraph 4-15).

d. "No Smoking" signs shall be posted and no smoking will be allowed when occupied by Government personnel.

2.1.2 Fathometer

2.1.2.1 General

All survey soundings shall be taken with a precision, high-resolution (0.1 ft) fathometer. The acoustic ping rate shall be, at minimum, 10 soundings per second. To limit signal attenuation in areas of unconsolidated bottom

sediments, the acoustic frequency utilized shall be within the range of 24-28 KHz and the Low Frequency Low Pulse Width shall be in accordance with the Manufacturers recommended settings for unconsolidated bottom sediments in shallow water depths (i.e., 0 to 150 feet). If a dual frequency fathometer is utilized, then the low frequency shall be within the 24-28 KHz range. At minimum, the equipment shall be capable of recording depths of water ranging from 3-feet under the transducer face(s) to a maximum of 100 feet. At this maximum depth, the sounding accuracy must be 0.5 ft (28 KHz transducer). Acoustic returns shall be recorded on thermal chart paper by a fixed, high-resolution printing element (no stylus). A digital fathometer may be used instead of paper charts as directed by the Contracting Officer's Representative, but the Contractor must still be capable of producing paper charts unless otherwise directed by the Contracting Officer's Representative. The paper chart scaling shall be in English units, no greater than 0-100 ft full-scale and graduated in 1 ft increments with numeric depth annotations at the 0, 10, 20, 30, 40, 50, 60, 70, 80, 90, 100 ft chart levels or as directed by the Government Representative. The instrument shall, at minimum, be capable of adjusting transmit power, receiver sensitivity and time-varied gain settings and of inputting the correct speed-of-sound, vessel draft and tide values. Additionally, the surveyor shall print the control parameter settings on the chart paper at the start of all surveys and when any control settings are changed and before and after all bar checks. Prior to the Contractor taking preliminary field surveys, control parameter settings shall be turned into the Government Inspector for review to ensure the settings meet the surveying parameters. During the surveying of run lines, the fathometer shall be capable of annotating periodic event marks on the paper chart as directed by other surveying system components (positioning, controlling software) and be capable of transmitting each event sounding back to these system components for horizontal position tagging and data storage.

2.1.2.2 Calibration

Hydrographic fathometer calibrations shall be performed at the survey site by methods described in EM 1110-2-1003, paragraphs 4-10 through 4-15 and at a frequency listed in table 4-6 for navigation and dredging support surveys with soft bottom materials. The acoustic traces of the bar or ball check calibrations shall be captured on the fathometer paper chart (at the 10, 20, 30, 40, 50, 60, 70, 80, 90, and 100 ft depths or as directed by the Government Representative) along with a notation indicating the site location (i.e. station, lat/long, x, y), the date and time. Additionally, if a velocity meter probe is utilized, the average speed-of-sound reading for the entire water column and the location, date and time of the probe sounding must also be noted on the fathometer paper chart. All calibration and soundings shall be made in the presence and to the satisfaction of the Government Representative at the job site.

2.1.3 Low Frequency Signal Parameters

The Low Frequency Pulse Width range of cycles (i.e., 1 to 10) used shall not produce signal lengths less than 35 microseconds or greater than 125 microseconds.

For example, using an Odom MKIII 24 KHz transducer with a LF Pulse Width Setting of 2, will result in an 83.3 microsecond long signal.

2 cycles (i.e., LF Pulse Width Setting = 2) / 24,000 Hz = 83.3 microseconds

2.1.4 Horizontal Positioning Equipment

The hydrographic surveying vessel(s) must meet or exceed horizontal accuracy of U.S. Coast Guard (USCG) Maritime Differential Global Positioning System (DGPS) instrumentation for determining horizontal positioning during surveying operations in accordance with EM 1110-2-1003, paragraph 7-3. This DGPS instrumentation must have a positioning accuracy of 1-3 meters 2DRMS. Commercial DGPS Subscription Services or the USCG DGPS Radiobeacon Navigation Service may be used for real-time pseudo-range (differential) corrections. If the USCG system is to be utilized, then the English Turn beacon site shall be the source for differential corrections. The GPS antenna on the survey vessel(s) must be physically positioned directly above the fathometer transducer or the hydrographic surveying software suite must be capable of aligning the horizontal and vertical sensors.

2.1.5 Water Surface Elevation Measurement

The hydrographic surveying vessel(s) must reduce final survey elevations relative to project datum using tide staffs referenced in the Dredging Region Section(s). As directed by the Contracting Officer's Representative, visual water level observations, Real-Time Kinematic (RTK), Real-Time Networks (RTN), or post-processed kinematic elevation computations shall be used in accordance with EM 1110-2-1003, paragraphs 7-11 through 7-14. Real-time or post-processed methods must include a static observation adjacent to the tide staff(s) for calibration of orthometric heights to project datum.

PART 3 EXECUTION

3.1 SURVEYS

Surveys will include but will not be limited to the following surveys.

3.1.1 General

Surveys for all fixed stations shall be performed in accordance with EM 1110-2-1003, chapter 4 - section IV "Data Collection, Editing, and Processing". Survey data provided herein is presented in NAD 83, US Feet format. The Contractor shall be able to use this data to lay out the work and subsequently provide completed work as specified herein to the Government. Prior to initiating positioning surveys using electronic survey equipment, a calibration test of the electronic measuring device shall be performed according to the manufacturer's instructions in the presence of the Contracting Officer's Representative. Calibration checks shall be run at the beginning and completion of each day's survey or portion thereof. Results shall be furnished daily to the Contracting Officer's Representative. All electronic surveys shall be tied to a fixed station. The station may be a Government-furnished point or a temporary point established by the Contractor and approved by the Contracting Officer's Representative. Should the electronic measuring device fail to indicate the known distance within the factory-defined error range for the device, the device shall not be used for determining survey positions. CEMVN Navigation Condition Surveys can be obtained from the following: <https://www.mvn.usace.army.mil/Missions/Navigation/Channel-Surveys/>.

3.1.2 Horizontal and Vertical Control Points

Horizontal and vertical control points for the work described herein are

located in the Dredging Region Section(s).

3.1.3 Preliminary Field Surveys

Prior to taking any original cross sections of the borrow area(s) and saltwater barrier sill, the Contractor shall run a preliminary field survey electronically locating the borrow area baseline and sill centerline, towers, all buoys and channel markers within the limits of the survey area. In addition, controlled cross sections of the borrow area(s) shall be 100-ft intervals along the borrow area(s) (normal to the river centerline) and at all channel markers, utility crossings, P.C.'s, P.T.'s, P.I.'s and P.O.T.'s. The data from this survey shall be plotted on plan sheet and submitted to the Contracting Officer for confirmation of correct alignment of the borrow area(s) limits. The Contractor shall not proceed with any dredging work until the Contracting Officer determines the borrow area(s) limits and furnishes the information to the Contractor.

3.1.4 Cross Sections

a. For the borrow areas, before and after dredging cross sections of the channel shall be taken at approximately 100-ft intervals along the channel, as well as at all utility crossings and at all P.C.'s, P.T.'s, P.I.'s and P.O.T.'s. Depth soundings shall be made with the hydrographic surveying system (as described in the paragraph entitled "Survey Equipment") and the recorded sounding density shall be one sounding for every 5 ft along the cross section run lines (normal to the cut centerline). The recorded depths shall be to a resolution of 0.1 ft. The sensitivity/gain control setting that is selected for the survey area bottom material-type must also be used for the bar check calibrations and must not be adjusted during hydrographic surveying (EM 1110-2-1003, paragraph 4-6). In areas of consolidated bottom material, the digitized and recorded depth soundings shall indicate the true channel bottom. However, in survey areas containing unconsolidated bottom materials, acoustic measurements must be calibrated with lead line measurements. These lead line measurements must be notated on the fathometer paper chart and taken at a minimum of 500-ft intervals, on the cut centerline and both edges of cut, or as determined by the Government Representative on the jobsite. The procedures for surveying in unconsolidated bottom material areas are outlined and described in EM 1110-2-1003, appendix P and more specifically P-8a. The real-time fathometer paper charting of the surveying runs, to include calibration and lead line events and all survey notations, shall be furnished to the Government. A digital fathometer may be used instead of paper charts as directed by the Contracting Officer's Representative, but the Contractor must still be capable of producing paper charts unless otherwise directed by the Contracting Officer's Representative. Stored hydrographic data (x,y,z) shall also be furnished to the Government in a structured ASCII format on compact disk (CD) media.

b. A chart layout of the before dredging cross sections shall be prepared by the Contractor and approved by the Contracting Officer's Representative. This graphical chart must represent a scaled plan view of the survey area with the recorded 5-ft interval depth soundings (0.1-ft resolution) plotted at their x,y positions.

c. The actual location of each sounding taken on each before dredging cross section range shall be provided. This information shall be in the form of printout tabulation giving the actual distance of the soundings from the baseline (on an azimuth normal to the centerline of

the cut). Soundings shall be to the nearest 0.1-ft referred to the water surface. This information shall also be plotted on a printout sheet, horizontal vertical scale, along with a section showing the required dredging dimensions. The time and date taken shall be shown and the gage reading applicable to the survey shall be shown. The applicable gage shall be read to the nearest 0.1-ft prior to and after each day's survey. More frequent readings may be required when directed by the Government Representative.

d. For the saltwater barrier sill, before and after dredging cross sections and daily cross sections shall be taken, processed, and submitted along the entire length of the sill from bank to bank. The daily cross sections shall be taken and processed a minimum of 4 surveys per day along the entire length of the sill from bank to bank. The daily cross section surveys shall be taken in approximately 6-hour intervals in order to capture the change in the sill throughout the day. Cross sections shall be taken at approximately 50-ft intervals along the sill with ± 20 ft tolerance from the perpendicular to the sill centerline, and distance between soundings shall be 5 ft with section widths to go a minimum 150 ft beyond the toe of the sill upstream and a minimum of 300 ft beyond the toe of the sill downstream.

e. At the completion of all work, an after-completion survey of the borrow areas and sill shall be provided and meet the survey requirements of the paragraphs above.

f. Before and after dredging cross sections shall be provided for secondary dredging regions as directed by the Contracting Officer if these regions are utilized.

3.1.5 Profiles

a. For the saltwater barrier sill, daily survey profiles shall be taken, processed, and submitted a minimum of 4 surveys per day along the entire length of the sill from bank to bank. The surveys shall be taken in approximately 6-hour intervals in order to capture the change in the sill throughout the day. This profile shall run along the entire length of the sill from bank to bank as directed by the Contracting Officer. Distances between soundings on each profile shall be 5 ft.

b. For the borrow areas, upon completion of dredging in a designated reach, waterway profiles shall be taken over the same dredging reach. Distances between soundings on each profile shall be 5 ft. Controlled profiles of the waterway shall be made along the dredge cut centerline and one at each outside bottom edge of the cut. The Government reserves the right to direct additional soundings to be taken along ranges normal to the above-defined profiles at no additional cost to the Government. This information shall be plotted on a printout sheet, 1 in. = 300 ft horizontal: 1 in. = 10 ft vertical scale.

c. At the completion of all work, three (3) sill profiles of the sill shall be taken. Controlled profiles shall be made down the sill centerline and each toe of the sill. These profiles shall run along the entire length of the sill from bank to bank as directed by the Contracting Officer. Distances between soundings on each profile shall be 5 feet.

d. Waterway profiles shall be performed for secondary dredging regions

as directed by the Contracting Officer if these regions are utilized.

3.1.6 Quantity Computations

Reference Section 35 20 23.23, paragraph entitled "Dredging Performance Pay Adjustments". For the purpose of computing the average actual production rate, the actual quantity of dredged material removed shall be measured by the cubic yard by computing the volume along the centerline of cut between the before and after dredging cross sections using the average end area method and limited by the allowable dredging tolerances described in Section 35 20 23.23, paragraph entitled "Required Production and Dredging Tolerances". The Contractor shall make dredging volume computations which shall be furnished to the Government with the before and after survey data described in the paragraph entitled "Dredging Cross Sections". In computing end areas and volumes for the purpose of computing the average actual production rate payment, the Contractor shall translate all cross section survey shots to the correct azimuth normal to the centerline of the cut and shall insert a shot at the actual station C/L with an interpolated elevation. The Government will check and verify the computations using this data, which will be used to compute the actual dredging rate in accordance with Section 35 20 23.23, paragraph entitled "Dredging Performance Pay Adjustments". No before dredging cross sections will be allowed to be taken and used for quantity computations within 500 ft in front of the dredge.

3.1.7 Survey Data

Each field book shall be given an identification number, which shall be noted on each page of the book. The information shown in the field notes shall meet the requirements of the Contracting Government Representative. The Contractor shall promptly plot the channel cross sections on a scale of 1 in. = 100 ft horizontal and 1 in. = 10 ft vertical. Plotted cross sections, profiles, and duplicate notes shall be kept at the jobsite at all times and made available to the Government Representative upon request. The Contractor shall furnish to the Contracting Officer's Representative the plotted original cross sections for a minimum distance of 500 ft ahead of the dredging location in the direction of work progression. One copy of all plotted cross sections shall be kept in the lever room of the dredge at all times.

3.1.8 Collecting, Recording, Processing, and Transmitting Data

The data obtained from the electronic positioning/control system and the fathometer shall be collected, recorded and processed. Soundings shall be recorded to the nearest 0.1-foot and the X and Y coordinates of these soundings shall be recorded to the nearest foot. The applicable gage shall be read to the nearest 0.1 foot prior to and after each day's survey. More frequent readings will be required when directed by the Government Inspector. From the processed data, the Contractor shall provide certain survey information taken for the purpose of computing the total amount of work to be paid for. The Contractor must furnish the required data on e-mail containing ASCII character set. The information received should be free of errors and in the following format: (a) the X-coordinate in feet of a recognized Louisiana Lambert grid system, (b) the Y-coordinate in feet of same recognized Louisiana grid system, (c) the elevation, and (d) remarks such as the station number (i.e. 1+00), CL (for centerline), ES (for end of station), EJ (end of file), and direction of survey (either "L" for + or "R" for -, followed by Station No., i.e. L 30+00). The time and date the cross section was taken and the gage reading applicable to the

section must be included. The electronically recorded data files, along with a hard copy of the track plotter surveys, plotted on the chart to show compliance with alignment, and quantity computations shall be presented to the Government Representative on site no later than two days after the survey is taken. Under no circumstances shall the information be edited for the purpose of eliminating incorrect soundings. Not submitting the data in accordance to the specifications and within the allotted time will be cause to withhold progress payment. The Contractor shall provide a separate file listing all incorrect soundings to be eliminated. Additional format requirements for these files will be discussed, and sample formatted files will be made available at the pre-work coordination meeting. The Contractor shall submit a separate survey file for each 2,000 feet acceptance reach (or portion less than 2,000 feet for the final reach of an assignment) unless directed otherwise by the Government Inspector. The beginning station for each file shall be the repeated ending station from the previous file (i.e., Sta. 820+00 to 840+00, Sta. 840+00 to 860+00, etc.). Format for survey file(s) to be submitted to the Government will be discussed and sample sheets will be given at the Pre-work Coordinating Meeting.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 35 - WATERWAY AND MARINE CONSTRUCTION

SECTION 35 20 23.23

HYDRAULIC DREDGING

PART 1 GENERAL

- 1.1 SCOPE
- 1.2 MEASUREMENT AND PAYMENT
 - 1.2.1 Mobilization and Demobilization
 - 1.2.2 Dredging and Option Dredging Items
 - 1.2.3 Option Item: Dredge Towing Service
 - 1.2.4 Option Item: Additional Pumping Capability for Dredging
Payment Items 0002, 0003, 0004, and 0005
 - 1.2.5 Option Item: Mobilization and Demobilization of Additional
Pumping Capability Equipment for Payment Item 0006
 - 1.2.6 Option Item: Interim Demobilization and Interim Mobilization of
Cutterhead Dredge
 - 1.2.7 Option Item: Standby of Attendant Plant
 - 1.2.8 Option Item: Standby of Additional Pumping Capability for
Dredging Payment Items 0002, 0003, 0004, and 0005
 - 1.2.9 Additional Measurement and Payment Items
 - 1.2.10 Work for Others
- 1.3 REPORT OF OPERATIONS
 - 1.3.1 Daily Report of Operations
 - 1.3.2 Monthly Report of Operations
 - 1.3.3 Final Report
 - 1.3.4 Distribution of Reports
- 1.4 DREDGE AND ATTENDANT PLANT DATA SHEET
- 1.5 DREDGE CREW
- 1.6 HYDROGRAPH DATA

PART 2 PRODUCTS

- 2.1 PLANT
 - 2.1.1 Dredge Plant
 - 2.1.2 Size and Equipment of Dredge Plant
 - 2.1.3 Dredge Attendant Plant
 - 2.1.3.1 General Requirements
 - 2.1.3.2 Tenders
 - 2.1.3.3 Crew Boat
 - 2.1.3.4 Dredge Towing Service
 - 2.1.4 Dredge Discharge Pipeline
 - 2.1.5 Navigation Radar
 - 2.1.6 Global Positioning System (GPS) Equipment
 - 2.1.7 Services to be Furnished to the Government
 - 2.1.8 Substitution of Plant
 - 2.1.9 Addition of Plant
- 2.2 COMMUNICATIONS EQUIPMENT
 - 2.2.1 Cellular Telephone
 - 2.2.2 Satellite Telephone

- 2.2.3 Marine VHF-FM Radio
- 2.2.4 Automatic Identification System (AIS)

PART 3 EXECUTION

- 3.1 DREDGING
 - 3.1.1 Description of Work
 - 3.1.2 Dredging Region
 - 3.1.3 Secondary Dredging Regions
 - 3.1.3.1 Dredging in Secondary Regions
 - 3.1.4 Order of Work
 - 3.1.5 Deficient Dredge Performance
 - 3.1.5.1 Performance Evaluation
 - 3.1.5.2 Government Actions for Failed Production
- 3.2 MOVEMENT OF NAVIGATION AIDS
- 3.3 WORKING IN THE VICINITY OF STRUCTURES AND UTILITY CROSSINGS
 - 3.3.1 General
 - 3.3.2 Existing Structures or Utilities
 - 3.3.3 Location of Submerged Objects
- 3.4 CUTTERHEAD DREDGE AND ATTENDANT PLANT DATA SHEET

ATTACHMENTS:

Form MVN 322 - Work Sheet for Preparing Consolidated Form 4267

MVN Form 4267 - Report of Operations - Pipeline, Dipper or Bucket Dredges

Sample Pump Curve

-- End of Section Table of Contents --

SECTION 35 20 23.23

HYDRAULIC DREDGING

PART 1 GENERAL

1.1 SCOPE

It is the purpose of these specifications to secure for the Government the hire and operation of one cutterhead dredge, with a dredge discharge size of 30 inches or greater inside diameter (ID), complete in all respects, including all attendant plant, and crew. The dredge shall be efficient and effective for all work described in these specifications. All floating plant shall comply with applicable US Coast Guard and US Public Health Service regulations. The Contractor shall furnish all plant, materials, equipment, supplies, labor, and transportation, and perform all work in strict accordance with these specifications. All work, materials, and services not expressly called for in these specifications, but which may be necessary for complete and proper operations to carry out the contract in good faith shall be performed, furnished, or installed by the Contractor at no increase in cost to the Government. All work under these specifications shall be performed in accordance with the provisions of EM 385-1-1 "Safety and Occupational Health Requirements", latest edition.

1.2 MEASUREMENT AND PAYMENT

1.2.1 Mobilization and Demobilization

An item to cover the cost of initial mobilization and final demobilization of the Contractor's dredge and all attendant plant under this contract is included and will be paid for as stipulated in the Contract Clause entitled "Payment for Mobilization and Demobilization" (DFARS 252.236-7004), which is located in Section 00700. The Contractor shall be responsible for staking its own approach for initial and interim mobilization and demobilization, for its dredge and attendant plant, from the plants location where last employed, to the dredging region(s), as described in the applicable Dredging Region Section(s). The Government will not provide any payments to the Contractor, in addition to the contract job price.

1.2.2 Dredging and Option Dredging Items

All costs for a fully operated cutterhead dredge shall be included in the contract unit price per hour in the "Dredging", "Option Dredging I", "Option Dredging II", and "Option Dredging III" items on the bidding schedule. Payment for a fully operated cutterhead dredge will be made at the contract unit price per hour for "Dredging", "Option Dredging I", "Option Dredging II", and "Option Dredging III" at the pay times stipulated in the following subparagraphs. Price and payment shall constitute full compensation for furnishing all necessary plant, labor, fuel, supplies, safety equipment and procedures, crew, furnishing and maintaining communication equipment, crew boat, survey boat and operator, surveys, satisfactory disposal of dredged material and all operational incidentals thereto.

a. Payment Hours. The hours listed in the bid lot(s) for dredging payment items are payment hours and are equivalent to 100% Pay Time Hours. For the purposes of determining payment, elapsed time and the

completion time of the contract, actual hours worked in the 100% pay time status will be converted to adjusted payment hours in accordance with the paragraph entitled "Dredging Performance Pay Adjustments". Actual hours worked in the 70% pay time status, 60% pay time status, and 35% pay time status will be converted to base payment hours by multiplying by 0.70, 0.60, and 0.35, respectively. All converted base payment hours will be paid at the contract hourly rate for dredging payment items. Converted 70%, 60%, and 35% base pay time hours will not be adjusted for dredging performance as specified in the paragraph entitled "Dredging Performance Pay Adjustments". Total payment hours as shown on the bidding schedule under dredging payment items shall be the sum of adjusted payment hours for effective dredging time adjusted for performance, as specified in this section, converted 70% base pay time hours, converted 60% base pay time hours, and converted 35% base pay time hours. The contract total price will not be exceeded for adjustments made to contract payment hours.

b. Required Production and Dredging Tolerances. Dredging shall be performed at or above the required minimum production rate as specified herein unless assignments involve non-standard dredging, as described in the paragraph entitled "Dredging in Non-Standard Reaches and Conditions". To avoid excessive unnecessary dredging at each assignment, quantities shall be measured to the actual elevation of dredging, not to exceed 1 foot below the dredging assignment's specified elevation and the actual swing width, not to exceed 10 feet beyond the specified swing width on each side.

c. Start of Pay Time. Pay time for the dredge shall begin on the date and time when material begins flowing out of the discharge pipeline.

d. 100% Pay Time Hours. When the dredge is operating with the cutterhead effectively moving material through and out of the discharge pipeline, and meeting the minimum production requirements specified in the applicable Dredging Region Section(s), and the paragraph entitled "Dredge Plant", the Contractor will be paid at the applicable contract price per hour, to the nearest minute, after adjusting for performance. Actual dredging hours shall be converted to adjusted payment hours in accordance with the paragraph entitled "Dredging Performance Pay Adjustments" when working in "Standard" dredging reaches and conditions. If the Contractor's dredge is working in a "Non-Standard" dredging reach or condition as defined in the paragraph entitled "Dredging in Non-Standard Reaches and Conditions", and the dredge is producing at rates less than the required minimum, then payment for 100% pay time hours will be made at the contract hourly rate for the dredging payment items without downward adjustment. The Contractor will receive upward performance adjustments in "Non-Standard" dredging reaches/conditions, if the contract minimum dredging rate is exceeded.

e. 70% Pay Time Hours. The following will be considered non-effective dredge time. The actual hours clocked as 70% pay time hours that fall within the definition of this subparagraph will be measured to the nearest minute and converted to base payment hours as specified in the paragraph entitled "Payment Hours".

- (1) Changing location of plant within a job assignment;
- (2) Movement of the dredge and attendant plant from one assignment to another assignment within the same dredging region

or from one dredging region to another, using dredge towing services paid under the towing service payment item(s). All 70% pay time under this subparagraph shall be measured from the time material stops flowing out of the discharge pipeline, until the time material is flowing out of the discharge pipeline at the new location. The pay time shall include preparations time and time to move the dredge to the new dredging location with the preparation time limited to 6 hours each to stop and start up. Payment for the dredge moving time shall be the actual hours not to exceed the following: (the shortest distance, regardless of dredge size or configuration, from the current dredging location to the new dredging location) / (the minimum tow rate of 3 mph for moving upstream and 5 mph moving downstream);

(3) Stopping work to permit the passage of other vessels, or allowing vessels to dock or depart from a wharf. The Contractor shall make such openings upon signal of any vessel or craft desiring to pass;

(4) Moving swing anchors and wires, and adjusting spud slings made necessary by the progress of the work;

(5) Up to two hours for the purpose of adding or removing floating discharge pipeline;

(6) Up to four hours for the purpose of handling in-place submerged pipeline in the event it becomes necessary to relocate or reconfigure the discharge pipeline to maximize pipeline length;

(7) Time for the purpose of handling shore discharge pipeline;

(8) Up to four hours at a time for the purpose of changing/modifying the cutterhead to a different size or type, or for the purpose of replacing the pump impeller with a different size or type, or for replacing blades in the pump or wipers on the cutter;

(9) Removal of debris and obstructions from the pump, pipeline, and cutterhead, and washing out the pipeline before handling;

(10) Repair or replacement of floating pipeline sections when pontoons are damaged through no fault or no negligence of the Contractor;

(11) Changing to spuds of different lengths, up to four 70% hours at a time;

(12) Seeking a harbor of refuge because of an approaching hurricane or tropical storm. The plant shall be placed on 70% pay time hours when material stops flowing out of the discharge pipeline in order to begin preparations to move the plant to the harbor of refuge site approved by the Contracting Officer. Pay time will remain at 70% pay time hours for up to 36 hours. All hours over 36 hours shall be 0% pay time hours. Towing costs for moving to and from harbor of refuge will be at the Contractor's expense. Refer to the paragraph entitled "35% Pay Time Hours" for payment of time during ordinary inclement weather on an assignment or while en-route between assignments;

(13) Up to 36 hours for delays caused by others, which are beyond the control of the Contractor, at the direction of the Contracting Officer, or due to lack of a dredging assignment. All hours over 36 hours shall be considered as 60% pay time hours.

(14) Stopping of dredging to perform surveys of the sill;

(15) Moving the spill barge to perform surveys of the sill;

(16) Up to two hours at a time for the purpose of removing sections of pipeline on the spill barge discharge.

f. 60% Pay Time Hours. The following will be considered non-effective dredge time. The actual hours clocked as 60% pay time hours that fall within the definition of this subparagraph will be measured to the nearest minute and converted to base payment hours as specified in the paragraph entitled "Payment Hours".

(1) Over 36 hours of delays caused by others, which are beyond the control of the Contractor, at the direction of the Contracting Officer, or due to lack of a dredging assignment.

g. 35% Pay Time Hours. The following will be considered non-effective dredge time. The actual hours clocked as 35% pay time hours that fall within the definition of this subparagraph will be measured to the nearest minute and converted to base payment hours as specified in the paragraph entitled "Payment Hours".

(1) Ordinary inclement weather on an assignment or while en-route between assignments, except for hurricanes and tropical storms, shall be considered as 35% pay time hours and shall be measured to the nearest minute and converted to base payment hours as specified in the paragraph entitled "Payment Hours". The plant shall be placed on 35% pay time hours when material stops flowing out of the discharge pipeline in order to begin preparations to move the plant to the harbor of refuge site approved by the Contracting Officer. The plant will remain on 35% pay time hours until material starts flowing out of the discharge line at the previously assigned or newly assigned location. No payment, or division of payment, shall be made for other items or work from the time when the Contracting Officer places the plant in inclement weather status to the time it is removed from that status by the Contracting Officer. Towing costs for moving to and from harbor of refuge shall be at the Contractor's expense. Refer to the paragraph entitled "70% Pay Time Hours" for payment of time during hurricanes and tropical storms.

(2) When the Contractor needs more than 48 hours to degrade the sill to the assigned sill elevation. See Section 35 20 23.23, paragraph entitled "Degrading Over-Constructed Saltwater Barrier Sill".

h. 0% Pay Time Hours. No payment for dredge time will be made for time lost:

(1) at the direction of the Contractor;

(2) when, through the fault or negligence of the Contractor, part of the necessary equipment is unserviceable or not available;

- (3) due to shutdowns for the repair or replacement of worn-out or unserviceable equipment;
- (4) when the plant is idle because the Contractor has failed to give notice of assignment completion;
- (5) due to late arrival of towboats;
- (6) for removing misplaced material or obstructions;
- (7) due to shutdowns for nonconformance with safety requirements;
- (8) for refueling operations that interfere with dredging operations;
- (9) from accidents resulting in injury to Contractor or Government personnel or others;
- (10) due to dredge standby during repairs of failed retaining dikes or pipelines, or leakage in pipelines which must be corrected;
- (11) in excess of the various limits specified in the paragraph entitled "70% Pay Time Hours";
- (12) for reasons not covered by the paragraphs entitled "100% Pay Time Hours", "70% Pay Time Hours", "60% Pay Time Hours", and "35% Pay Time Hours";
- (13) for time spent traveling to the location of a new dredging assignment when the dredge does not use the shortest route, regardless of dredge size or configuration, to mobilize from its current location to the new dredging assignment. In this case, the Contractor will be paid for the time that would have applied if the dredge had traveled the shortest route, as per the paragraph entitled "70% Pay Time Hours".

i. Classification of Pay Time. When conditions are such that more than one pay status (100%, 70%, 60%, 35%, 0%) is appropriate, then pay time shall remain under the lowest applicable classification, until the cause of the lower classification is removed.

j. Accounting for Dredge Time. The Contractor should note that the dredge must account for the full 24 hours of each day, including the first and last day of work. All time will either be 100% time, 70% time, 60% time, 35% time, or 0% time. When considering daylight savings time changes, only elapsed time will be accounted for.

k. See the paragraph entitled "Deficient Dredge Performance" for cases of rate adjustment.

l. Dredging Performance Pay Adjustments. Throughout the duration of this contract, 100% pay time hours shall be adjusted based on actual dredging. The adjustment of all 100% pay time hours to adjusted payment hours shall be made by multiplying the actual hours worked in a 100% pay time status by the ratio of the actual hourly production rate to the minimum required production rate specified in the applicable Dredging Region Section(s). Dredging performance pay adjustments will be made for each 14-day period of dredging or shorter periods thereof

when deemed appropriate by the Contracting Officer. Partial payments will be made monthly based on the cumulative results of each 14-day evaluation.

(1) Computation of the Average Actual Production Rate. The Contracting Officer will compute the average actual dredge production rate. This rate will equal the ratio of the actual quantity of dredged material divided by the actual amount of effective dredging time (100% pay time hours) and will be computed for those periods classified as "Standard" dredging reaches by the Contracting Officer and where the minimum production rate is exceeded in non-standard dredging reaches. The actual quantity of material dredged will consist of the difference between "before" and "after" dredging end areas that lie within the tolerances described in the paragraph entitled "Required Production and Dredging Tolerances". Hydrographic survey data must be in accordance with the requirements specified in Section 35 01 50.73, Surveys. These Contractor-performed surveys, witnessed by the Government, shall be provided to the Contracting Officer within 24 hours after they are taken.

(2) Hours Adjusted for Performance. Adjusted payment hours shall be computed for all effective dredging time (100% pay time hours) for standard dredging reaches and where the minimum production rate is exceeded in non-standard dredging reaches during each partial pay estimate period as follows, except as noted in paragraph entitled "Dredging in Non-Standard Reaches and Conditions". Once this adjustment is made for a partial pay estimate period it will not be changed or combined with computations of another pay estimate period.

Adjusted Payment Hrs =

$$\frac{(\text{Average Actual Production Rate}) \times (\text{Actual Effective Dredging Time})}{(*\text{Contract Minimum Production Rate})}$$

*Different Contract Minimum Production Rates. Payment hours for all effective dredging time will be computed using the appropriate minimum production rates specified in the applicable Dredging Region Section(s).

m. Standard Dredging Conditions. Standard dredging conditions include all assignments except those specifically defined as "Non-Standard" in the paragraph entitled "Dredging in Non-Standard Reaches and Conditions". When dredging in standard dredging conditions, the Contractor shall attain at least the minimum production rate specified. Should the Contractor fail to meet this minimum required production rate, the Government will take action as specified in the paragraph entitled "Deficient Dredge Performance".

n. Dredging in Non-Standard Reaches and Conditions.

(a) Non-Standard dredging reaches are defined as:

When the assignment or portions thereof yield less than the Cross Sectional Quantity per foot of channel as defined below, the assignment or portions thereof will be considered Non-Standard.

The Cross Sectional Quantity represents an average Quantity per

foot of channel and is not to be associated with any minimum or maximum height of material.

$$\text{Cross Sectional Quantity (cy/ft)} = (4w + 16s) / 27$$

Where w = Bottom swing width of dredging template as directed by Contracting Officer

s = Side slope of dredging template as directed by Contracting Officer

Where s conforms to the following dimension: 1 vertical on s horizontal

(b) Non-Standard dredging conditions are defined as:

(1) When the specified elevation of the dredging assignment is less than 11 feet below the water surface;

(2) All dredging in the vicinity of underground utilities.

(c) See the Dredging Region Section(s) for additional Non-Standard conditions within each specific Dredging Region.

(d) Should production in these reaches and/or conditions exceed the minimum required by the contract when averaged over a standard 24-hour day report period, then the 100% pay time hours for that day shall be adjusted for performance.

(e) When dredging in reaches or conditions determined to be non-standard by the Contracting Officer and the minimum production rate is not attained, the actual dredging time shall be considered as 100% pay time hours and paid at the contract price per hour without adjustment for performance, provided that the Contractor has made every effort to maintain the maximum possible production and the Contracting Officer concurs that the Contractor has in fact made such satisfactory effort.

o. At approximately, but not less than 120 hours before exhaustion of the base dredging hours, the Contracting Officer will compute the average production rate that has been attained by the dredge during all periods when the 100% pay time hours have been adjusted for performance. This computed average production rate will be used to determine the contract time remaining and will fix the production rate for payment purposes of all remaining work in Standard dredging reaches. Should the actual production rate fall below 90 percent of this computed rate, the Contracting Officer will adjust downward the 100% pay time hours based on the latest actual average dredging rate attained. If the Government elects to exercise the optional dredging item at approximately, but not less than 120 hours before exhaustion of the base dredging hours, the pay for performance adjustment mechanisms will remain in force from this point onward until approximately, but not less than 120 hours before exhaustion of the optional dredging hours. At approximately 120 hours before completion of the final dredging assignment, the Contracting Officer will compute the average production rate that has been attained by the dredge during all periods when the 100% pay time hours have been adjusted for performance. This computed average production rate will be used to determine the contract time remaining and will fix the production rate for payment purposes of all remaining work in Standard dredging reaches. Should the actual production rate fall below 90 percent of this computed rate, the

Contracting Officer will adjust downward the 100% pay time hours based on the latest actual average dredging rate attained.

p. When the Government does not receive from the Contractor, the hydrographic survey data used to determine actual production within specified time requirements, 100% pay time hours shall be paid at the basic hourly rate specified in the bid schedule for the dredging payment items. Once the required hydrographic survey data is received by the Government, the payment hours will be re-computed for the pay estimate period in question and any adjustments due will be paid in the next partial pay estimate.

1.2.3 Option Item: Dredge Towing Service

a. General. The Contractor shall furnish towing services described in the paragraph entitled "Dredge Attendant Plant" to move the dredge and equipment between dredging locations on approximately 12 hours advance notice.

b. Measurement. Measurement for towing services will be made by the mile, not for each towboat by the mile, measured to the nearest 0.1 mile along the channel centerline. Miles for towing the dredge will be limited to the actual amount of all towing miles. No additional measurement will be made when the towboat does not use the shortest route, regardless of dredge size or configuration, to mobilize from its current location to the new dredging assignment. In this case, the measurement will only include the miles that would have applied if the towboat had traveled the shortest route. No measurement will be made for towboat(s) delivery miles to the worksite from their respective location(s) where last employed, nor for miles used in returning the towboat(s) to their respective location(s) where last employed.

c. Payment. Payment for dredge towing service will be made at the contract unit price per mile for Option Item "Dredge Towing Service". No additional payment will be made for any towboats and/or towing miles that may be necessary to move attendant or auxiliary plant. No payment will be made for towing service required in moving the dredge and attendant plant to or from a harbor of refuge, due to an approaching hurricane or tropical storm.

1.2.4 Option Item: Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005

All subparagraphs in the paragraph entitled "Dredging and Option Dredging Items" are applicable to the Option Item "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005". When Option Item "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005" is activated, it shall be used in addition to and concurrently with the Dredging, Option Dredging I, Option Dredging II, and Option Dredging III Item, whichever is applicable. All costs for providing and operating additional pumping capability equipment as specified in this Section shall be included in Option Item "Additional Pumping Capability for Dredging Payments Items 0002, 0003, 0004, and 0005", paid at the contract unit price per hour. Upon the exercise of this option, the Contractor shall retain the plant and equipment required for additional pumping capability on site for the duration of the contract. Retainage of additional pumping capability equipment while not under payment status, as defined under all subparagraphs in the paragraph entitled "Dredging and Option Dredging Items", shall be provided at no additional cost to the

government.

1.2.5 Option Item: Mobilization and Demobilization of Additional Pumping Capability Equipment for Payment Item 0006

All costs associated with mobilization and demobilization of the additional pumping capability equipment for Option Item "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005" shall be included in this Option Item, paid at the contract job price.

1.2.6 Option Item: Interim Demobilization and Interim Mobilization of Cutterhead Dredge

a. General. This item is only applicable when the Government approves the cutterhead dredge to perform an interim demobilization and interim mobilization. While the cutterhead dredge is on an interim demobilization, the Contractor shall remain on-call and shall be able to recommence dredging on the contract within 120 hours after notification. The Contractor is only allowed to demobilize the cutterhead dredge and any tow boats needed to tow it. All other attendant plant shall remain at the project site (see paragraph entitled "Standby of Attendant Plant").

b. Measurement. Measurement for this item will be made by the mile, not for each towboat by the mile, measured to the nearest 0.1 mile along the channel centerline. Miles for towing the cutterhead dredge will be limited to the actual amount of all towing miles. No additional measurement will be made when the towboat does not use the shortest route, regardless of dredge size or configuration. In this case, the measurement will only include the miles that would have applied if the towboat had traveled the shortest route.

c. Payment. Payment to move the cutterhead dredge under an interim demobilization and an interim mobilization will be made at the contract unit price per mile for Option Item "Interim Demobilization and Interim Mobilization of Cutterhead Dredge". Payment for an interim demobilization will be made upon completion of interim demobilization. Payment for an interim mobilization will be made upon completion of interim mobilization.

1.2.7 Option Item: Standby of Attendant Plant

This item is only applicable when the Government approves the cutterhead dredge and necessary tow boats to perform an interim demobilization. All other attendant plant, discharge pipeline, and auxiliary equipment shall remain at the project site and readily available. All costs for standby of the attendant plant, discharge pipeline, and auxiliary equipment at the project site shall be included in Option Item "Standby of Attendant Plant", paid at the contract unit price per day or portion thereof. Pay time will be calculated to the nearest one-sixtieth (1/60) hour for payment. Pay time starts at the time that the cutterhead dredge departs the project location. Pay time ends at the time the cutterhead dredge arrives back at the project location or as directed by the Contracting Officer. Daily surveys shall be taken and processed along the entire length of the sill from bank to bank as detailed in Section 35 01 50.73, paragraphs entitled "Cross Sections" and "Profiles". This item shall not include any standby for additional pumping capability for dredging payment items 0002, 0003, 0004, and 0005 (see paragraph entitled "Standby of Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005").

1.2.8 Option Item: Standby of Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005

This item is only applicable when the Government approves the cutterhead dredge and necessary tow boats to perform an interim demobilization and Option 0006 "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005" has been exercised and required prior to the cutterhead dredge interim demobilization. All additional pumping capability discharge pipeline, attendant plant and auxiliary equipment shall remain at the project site and readily available. All costs for standby of the additional pumping capability discharge pipeline, attendant plant and auxiliary equipment at the project site shall be included in Option Item "Standby of Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005", paid at the contract unit price per day or portion thereof. Pay time will be calculated to the nearest one-sixtieth (1/60) hour for payment. Pay time starts at the time that the cutterhead dredge departs the project location. Pay time ends at the time the cutterhead dredge arrives back at the project location or as determined by the Contracting Officer. If Option 0006 "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005" has not been exercised and required, then no payment will be made.

1.2.9 Additional Measurement and Payment Items

See applicable Dredging Region Section(s) for additional measurement and payment items.

1.2.10 Work for Others

The dredge may be released from this contract for the convenience of the Contractor, upon approval of the Contracting Officer. The dredge shall remain on 72 hour call by the Contracting Officer during the release period. Regardless of the pay status of the dredge at the time it is released, the dredge will immediately go to a non-pay status, and remain so until it is recalled to work. Demobilization at the time of release, and mobilization at the time of recall, will not be paid. Payment will cease at the time dredge material stops flowing out of the discharge pipeline. Payment will resume:

- a. If the dredge returns to an assignment in the same dredging region, when dredged material starts flowing through the discharge pipeline;
- b. If the dredge returns to an assignment in another dredging region, when the dredge in tow enters the route that would have been taken had the dredge not been released;
- c. If the dredge returns to an assignment in another dredging region and the dredge in tow never enters the route that would have been taken had the dredge not been released, when dredged material starts flowing through the discharge pipeline; or
- d. If the dredge is already located at some point along the route between the previous and new assignments, upon departure for the new assignment.

1.3 REPORT OF OPERATIONS

1.3.1 Daily Report of Operations

The Contractor shall prepare and submit a Daily Report of Operations (MVN Form 4267) and the Original Leverman's Log signed by each shift leverman, for each dredge working. The MVN Form 4267 provided at the end of this section shall be used in lieu of the RMS Form 4267 and uploaded to RMS separately. These documents shall be submitted electronically on a daily basis and not in groups, e.g. several daily reports packaged together at one time. The original and one (1) copy of these records in report form shall be submitted to the Government Inspector daily within 12 hours after the date covered by the report. Each daily report shall only include the information beginning at 0000 hours and ending at 2400 hours of that day. All calendar days shall be accounted for throughout the life of the contract. A sample of MVN Form 4267 is attached at the end of this section.

1.3.2 Monthly Report of Operations

The Contractor shall also prepare a report of operations for each month or partial month's work on MVN Form 322 (Work Sheet for Preparing Consolidated Form 4267). The monthly report shall be submitted electronically on or before the 7th of each month, consolidating the previous month's work. MVN Form 322 can be computer generated and shall be approved by the Contracting Officer's Representative on site. A sample of Form MVN 322 - Work Sheet for Preparing Consolidated Form 4267 and MVN Form 4267 - Report of Operations - Pipeline, Dipper or Bucket Dredges are attached at the end of this section.

1.3.3 Final Report

Upon completion of the work, the Contractor shall electronically submit information for a final report, which consolidates all of the monthly reports, within 7 calendar days of contract completion.

1.3.4 Distribution of Reports

The Contractor shall distribute one electronic copy of all reports (daily, monthly, and final) to the Administrative Contracting Officer, Contracting Officer's Representative, and Government Inspector. Each Report of Operations shall be maintained by the Contractor on the dredge. Any additional instructions will be provided by the Administrative Contracting Officer. Upon completion of the job, the Contractor shall also submit a consolidated job report, combining the monthly reports in accordance with the previously listed distribution.

1.4 DREDGE AND ATTENDANT PLANT DATA SHEET

The Contractor shall complete the plant data sheet located in paragraph entitled "Cutterhead Dredge and Attendant Plant Data Sheet" for the cutterhead dredge and attendant plant the Contractor will use to perform the work under this contract. The completed data sheet shall be submitted in the Contractor's bid package as stated in Section 00010, paragraph entitled "Bid Form Notes". The cutterhead dredge and attendant plant data sheet submittal shall constitute a certification that the described plant is available to, and under control of, the Contractor, and shall be for official Government use only. If the Contractor is a joint venture, all parties of the joint venture shall sign the data sheet, with the party owning the dredge and attendant plant identified in the data sheet. If the

Contractor requests a substitution of plant or addition of plant during the contract, the plant data sheet of the substituted plant or the additional plant must be submitted at the time of the request. The Contractor shall submit the request timely in order to provide the Government at least 14 calendar days to review the request and complete all necessary paperwork.

1.5 DREDGE CREW

No additional payment will be made for crew in excess of required minimums.

a. Contractor Responsibility. The Contractor shall furnish, subsist if necessary, and pay all crew required for the satisfactory and efficient operation of the dredge and attendant plant, and for handling of pipelines. Subsistence and per diem travel expenses for the crew shall be the responsibility of the Contractor. Minimum crew will be in accordance with US Coast Guard requirements. The Contractor shall be responsible for all accidents to crew and plant and for compliance with all laws pertaining to labor on dredges and attendant plant. Each crewman, when absent, shall be relieved by a qualified replacement. The Contractor shall remove from duty any crewman who, in the opinion of the Contracting Officer, is objectionable or incompetent. This requirement shall not be made the basis of any claim for compensation or damages against the United States or any of its officers or agents.

b. Boat Operators. All operators of boats exceeding 25 feet in length shall possess a current operator's license, issued by the US Coast Guard, for the class of vessel being operated. The Contractor is responsible for ensuring that subcontractors comply with this requirement.

c. Tank Barges. Tank barges need not be manned unless in the opinion of the Officer-in-Charge, Marine Inspection Office, US Coast Guard, such manning is necessary for the protection of life and property and for the safe operation of the vessels; provided, however, that towing vessels, while towing barges which need not be manned, shall carry in the regular complement of the towing vessel and shall have on board at all times while towing, at least one licensed officer or certified tankerman (CG 123, para. 35.35-1, 1 Aug 77, or 46 CFR Subchapter D).

d. Fuel Transfer Operations. A sufficient number of crew shall be on duty to perform transfer operations. In the case of unmanned barges, the owners or operators of such barges shall insure that a person holding a valid license as master, mate, pilot, engineer, or a certified tankerman is on duty to perform the transfer operation, which licensed person or certified tankerman shall be considered as the person in charge of the unmanned tank barge (CG 123, para. 35.35-1, 1 Aug 77, or 46 CFR Subchapter D). MVN 385-10R (latest edition), Fuel Oil Transfer form shall be submitted to the Contracting Officer's Representative for each fuel transfer operation.

e. Minimum Crew. The following personnel are the minimum crew required for the dredge to comply with the contract. Additional crew will be required for the survey boat. No additional payment will be made for providing additional crew. The listed day-shift crew is in addition to the minimum crew each shift.

Minimum Crew Each Shift	Additional Crew Required for Day Shift Only
1 - Leverman 1 - Engineer 1 - Mate 2 - Tender Operators 3 - Deck Hands	1 - Captain 1 - Chief Engineer 1 - Field Survey Engineer 1 - Deck Captain 1 - Welder 1 - Deck Hand 3 - Laborers

1.6 HYDROGRAPH DATA

Real time stage hydrograph data of the Mississippi River Basin may be obtained from the New Orleans District website at:
<https://www.mvn.usace.army.mil/Missions/Engineering/Stage-and-Hydrologic-Data/>.

PART 2 PRODUCTS

Although listed under PART 2 PRODUCTS, the equipment described herein remains the property of the Contractor at all times.

2.1 PLANT

2.1.1 Dredge Plant

a. Plant shall be kept in condition for efficient work at all times. Award of this contract shall not be construed as a guarantee by the Government that the plant, which the Contractor intends to use, is adequate for the performance of the work. No reduction in the capacity of the dredge plant shall be made except by prior written permission of the Contracting Officer.

b. If the Contracting Officer determines that any item of plant, or any part thereof:

- (1) is inadequate for the service required;
- (2) is not being operated at full capacity, according to the paragraph entitled "Deficient Dredge Performance";
- (3) has become unserviceable or incapable of efficient work; or
- (4) is not being effectively operated because of reduced crew below that necessary as defined in the paragraph entitled "Dredge Crew", or incompetent crew, then the Contracting Officer shall notify the Contractor in writing of his decision. The Contractor shall then replace any unsatisfactory plant and correct any defects, including incompetent crew.

c. The Contractor or a representative with full authority to act for him/her, in the care and operations of the plant, shall be on the site of the work at all times.

d. The Government will not be responsible for the dredge and attendant

plant or any damage thereto during the period of the contract. The Contractor shall release the Government, and its officers and agents, from responsibility for damages ordinarily covered by fire and marine insurance.

2.1.1.2 Size and Equipment of Dredge Plant

a. The dredge plant length measured horizontally from the digging spud to the cutterhead's location while dredging at a channel depth of 95 feet, measured from the water surface, shall be no less than 325 feet to meet the swing requirements specified in paragraph 2.1.2.e. If the Contractor's dredge plant length, as described above, cannot meet 325 feet, the Contractor shall include an idler barge that enables the dredge plant length to meet or exceed 325 feet. Dredge plant that cannot meet the minimum required dredge plant length will not be allowed to perform work under this contract.

b. The dredge discharge size is considered to be the least inside diameter of the following: the main pump discharge, the submerged pump discharge, the booster pump discharge, or the discharge pipeline. Dredges shall meet or exceed the minimum production rate requirements listed in the table located in the Dredging Region Section(s).

c. Submerged pumps shall meet the following conditions in order for the dredge to be classified as utilizing a submerged pump:

- (1) The submerged pump shall be located on the cutterhead ladder and shall be placed at a distance of no more than two-thirds the length of the ladder from the cutterhead.
- (2) The submerged pump shall be fully immersed.
- (3) The submerged pump is operating.

d. The Option Item "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005" shall include the cost of additional pumping capacity which may be provided by the dredge's on-board equipment and/or any booster/ancillary pumping plant having a discharge size of at least that of the dredge as required to maintain the specified minimum production rates for discharge pipeline lengths up to the maximum listed in the additional pumping capability option item. The Contractor shall make the determination for assembling the equipment necessary to perform dredging at the specified rates for each of these regions and conditions upon activation of the additional pumping capability optional item. The Contractor shall have the specified additional pumping capacity equipment available for use at the site within 120 hours of notification. Equipment for handling this optional pumping capacity equipment shall conform to the requirements for the dredge and attendant plant as specified herein. Costs for the additional pumping capacity equipment and its handling shall be included as designated in the additional pumping capability optional item. This item shall also include all costs for equipment used to handle disposal areas.

e. The cutterhead ladder shall be of sufficient length to provide a uniformly dredged channel depth of 95 feet, measured from the water surface. The spuds shall be of sufficient length to perform dredging operations in water depths from 11 to 100 feet. The dredge shall be capable, from each setting of the spud, of dredging a channel at least

375 foot wide, while swinging through an arc of 35 degrees to either side of the centerline of the cut (total arc 70 degrees or less). The Contractor shall fulfill the requirements of this subparagraph and subparagraph (a) while achieving or exceeding the minimum production rate requirements listed in the tables at the end of the applicable Dredging Region Section(s).

f. The Contractor shall have available for use at all times a variety of interchangeable pump impellers to permit the dredge to operate under the varying conditions described in the applicable Dredging Region Section(s). The Contractor at all times shall have available additional serviceable basket type 5- or 6- blade cutterhead, serviceable sand-type cutterhead, and serviceable cone-type cutterhead to efficiently and effectively dredge. The Contractor shall also have available replacement blades and knives for the dredge pump and wipers for the cutter.

g. The dredge shall be equipped with recording vacuum and pressure gauges and a print out of the electronic data recording of engine and pump functions, and a pump engine recording tachometer. During dredging, these instruments shall record data on control chart paper consisting of pipeline pressure and pump vacuum (lbs/cu in.), and pump RPM at rated drive of the prime mover. The Contractor shall deliver completed recordings to the Inspector on watch at the time of removal from the recording devices, each day of operation. On dredges equipped with and using a ladder pump, the vacuum gage and vacuum chart will not be required.

h. The dredge shall be equipped with a gyro-compass.

i. Dredging sensory equipment calibration. All gauges, meters, and other dredging sensory equipment, shall have a valid and current calibration certificate sticker. Re-calibration where applicable and as necessary shall be performed whenever dredging conditions change in a manner affecting equipment calibration. The Government Inspector may require the Contractor to perform a new calibration on this equipment if the Inspector suspects output data from this equipment to be inaccurate. Dredging sensory equipment shall be in good operating condition during dredging, and shall be mounted in plain sight of the dredge leverman. The dredge leverman shall use the aforementioned required gauges, meters, and all other available sensory equipment, to maximize dredge production during dredging operations.

j. The dredge shall be equipped with a degasser.

2.1.3 Dredge Attendant Plant

2.1.3.1 General Requirements

Attendant plant shall be composed of such fuel barges, derrick barges, water barges, and other attendant or auxiliary plant as may be required for operations under these specifications, whether or not items are specifically mentioned. The attendant plant shall be in good condition and of sufficient size and capacity to efficiently serve the dredge. Fuel barges and water barges shall comply with applicable US Coast Guard and US Public Health Service Regulations. All skiffs used on this contract shall have a minimum of 22 feet.

2.1.3.2 Tenders

The attendant plant shall include a minimum of three tenders per dredge for 24 hours a day operations. Each of the tenders shall be a minimum length of 35 ft, have twin screws, inboard, diesel powered engines with a minimum of 140 horsepower on each screw, and shall be capable of working efficiently in the water depths for the particular dredging region where work is assigned. They shall be maintained in operating condition at all times regardless of the pay status of the dredge.

2.1.3.3 Crew Boat

The Contractor shall furnish, throughout the contract period, for the exclusive use of the Government, one diesel-powered or gas-powered crew boat, with twin propellers, capable of maintaining and traveling no less than the minimum speed of 25 miles per hour / 22 knots, not less than 40 feet in overall length, with enclosed space for at least six passengers after installation of all required equipment. The crew boat shall meet or exceed all applicable US Coast Guard regulations for vessels 65 feet or less in length, and shall be certified by the US Coast Guard. The crew boat shall be equipped with the following:

- (1) air conditioning and heating;
- (2) VHF-FM marine radio transceiver for ship-to-ship communications, described in the paragraph entitled "Communications Equipment";
- (3) Navigation radar, as described in the paragraph entitled "Navigation Radar";
- (4) Safety equipment meeting the inspection requirements of the US Coast Guard Auxiliary and EM 385-1-1.
- (5) Global Positioning Equipment (GPS), as described in the paragraph entitled "Global Positioning System (GPS) Equipment".

Equipment, which fails to perform because of insufficient power or other mechanical deficiencies, or due to inexperienced operators, shall be replaced, or the operator replaced, as the case may be, within 12 hours after the Contractor is directed to do so by the Contracting Officer's Representative. The crew boat will be used solely for providing the Government Inspectors and government agents transportation, and not for conducting surveys, providing transportation for the Contractor's personnel, or transporting the Contractor's supplies. The Contractor shall make provisions to obtain a separate crew boat or vessel for conducting Contractor-related operations. The crew boat shall be operated and available 24 hours a day. Refer to EM 385-1-1 for additional crew and equipment requirements. Smoking shall not be allowed inside the cabin and operator's space while occupied by Government personnel. NO SMOKING signs shall be posted.

2.1.3.4 Dredge Towing Service

The service of one or more towboats, in addition to the regularly-assigned plant, shall be required to provide towing service as described in the paragraph entitled "Option Item: Dredge Towing Service". The towboat(s) shall have horsepower to provide a minimum towing speed of 3 miles per hour upriver against a current of 5 miles per hour for moving a single tow

consisting of the dredge and necessary attendant plant to commence dredging at a new location. Further, the towboat(s) utilized shall be capable of safely handling and moving the dredge and attendant plant in currents of up to 5 miles per hour. The towboat shall have radio equipment to communicate with other vessels in the vicinity of the dredge.

2.1.4 Dredge Discharge Pipeline

(a) All discharge pipeline shall be maintained in good condition. Leaks occurring in the pipeline shall be promptly stopped.

(b) All pipelines and associated equipment shall be considered as part of the dredge attendant plant.

(c) The Contractor shall have a minimum of 13,000 feet of serviceable floating and/or submerged pipeline in any usable combination. The Contractor shall have enough submerged pipeline so that all navigation traffic can transit up and down the Mississippi River and that the Contractor does not block any navigation traffic due to the construction of the saltwater barrier sill (other than the agreed upon river closure to lay the submerged pipeline and river closure to remove the submerged pipeline). The submerged pipeline shall be placed in such a way that it does not create a hazard to navigation. When the submerged pipeline is placed in shallow water, where the possibility exists for small out board skiffs to cross over the pipeline, the pipeline shall be marked every 150' throughout the length of the submerged pipeline with U.S. Coast Guard approved fluorescent buoys and signs stating "DANGER SUBMERGED PIPELINE". While in use, floating pipeline shall be secured at intervals not to exceed 400-ft. The pipeline shall include two elbow pontoons (one each right and left). The Contractor shall furnish a baffle floating pipeline section when determined to be necessary by the Government. The Contractor shall provide adequate numbers of anchors or skidder barges on the floating pipeline to eliminate the possibility of pipeline separation due to river currents. Floating pipeline shall have navigation lights as specified in Section 01 35 26, paragraph entitled "Signal Lights".

(d) Floating pipeline shall be placed to provide a minimum hazard to navigation. Furthermore, the Contractor may be required to disconnect all or part of his pipeline to allow the passage of other vessels, if the pipeline would otherwise be a hazard to navigation.

(e) In connection with Option Item "Additional Pumping Capability for Dredging Payment Items 0002, 0003, 0004, and 0005", the Contractor shall have an additional 12,000 feet of serviceable floating and/or submerged pipeline in any usable combination available for use at the site within 120 hours of notification in any amount up to the required maximum. Equipment for handling this optional pipeline shall respectively conform to the requirements of floating and submerged pipeline handling equipment, as specified in this paragraph. All costs for furnishing this optional pipeline, and respective optional handling equipment shall be as designated in Part 1 of this section.

2.1.5 Navigation Radar

The dredge, survey boat, and crew boat shall be equipped with navigation radar for use in inclement weather and at night. All radar equipment used under this contract shall be installed so that it will continue functioning on battery power in the event of generator failure. Any additional

attendant plant to be operated at night must be radar-equipped as well. No separate payment will be made for radar equipment.

2.1.6 Global Positioning System (GPS) Equipment

The crew boat shall be equipped with Global Positioning System (GPS) equipment capable of using 12 satellites simultaneously. The GPS unit shall be fully gasketed for exposure protection and differential ready with a beacon receiver. The unit shall have a minimum of 250 alphanumeric waypoints and a minimum of 20 reversible routes and waypoints capability. In addition, the unit shall have electronic charting with inland and offshore coverage using the most current imagery available.

2.1.7 Services to be Furnished to the Government

a. The Contractor shall be required to furnish, on the request of the Contracting Officer or any inspector:

(1) The use of such boats, boatmen, laborers, and material forming a part of the ordinary and usual equipment and crew of the floating plant, as may be reasonably necessary in inspecting and supervising the work.

(2) Suitable transportation between the worksite and all points on shore designated by the Contracting Officer, to and from the various pieces of plant, and to and from the floating discharge pipeline by means of the required tenders, survey boat or crew boat.

(3) Furnish, as required by the inspectors, a competent three-man survey crew at all times, including survey boat operator, to work under the Government Inspector's direction. Competent crew shall be knowledgeable in conducting electronic positioning surveys using the Contractor-furnished equipment, tying utility crossings to the baseline, offsetting the utility crossings, and setting dredging location buoys if necessary, without immediate supervision of the Government Inspectors. The survey crew shall be prepared to perform survey work within a 1-hour notice from Government Inspectors.

b. Should the Contractor refuse, neglect, or delay compliance with these requirements, the specific facilities may be furnished and maintained by the Contracting Officer, and the cost will be deducted from any amounts due or to become due the Contractor.

2.1.8 Substitution of Plant

Substitution of the dredge may be allowed provided the Contractor furnishes written justification, the Contracting Officer agrees in writing to the substitution, and the following conditions are met:

a. The substitute dredge meets all of the requirements of this contract and that the Contractor submits clear evidence that the substitute dredge meets the plant requirements specified in the paragraph entitled "Size and Equipment of Dredge Plant" and that the substitute dredge performs at the rate set forth in the table located in the applicable Dredging Region Section(s), on work similar to that of this contract. Compliance of the substitute dredge with the contract requirements shall be determined as per the paragraphs in Section 00010 entitled "Bidder Qualifications" and "Pre-Award

Inspection of Plant". The substitute dredge will be ready to begin pumping material as soon as the original dredge is removed from service.

- b. The Government is reimbursed all costs in connection with inspection of the substitute dredge, if such is required.
- c. The substitute dredge is delivered to the worksite before the original dredge is shut down and moved off the worksite. This requirement does not apply to substitutions made during release periods.
- d. If the substitute dredge does not fit the same bid lot as the original dredge, then rates for the substitute dredge will be computed separately for the Dredging Payment Items as follows:

Substitute Dredge Hourly Rate =
$$\frac{(\text{Original Base Item Estimated Quantity}) \times (\text{Original Base Item Unit Price})}{\text{Estimated Quantity From Base Item Bid Schedule of Applicable Bid Lot for Substitute Dredge}}$$

The remaining hours, if any, on the Basic Payment Items will be prorated so that payments available to the Contractor will remain unchanged. Option dredging payment hours will also be prorated separately so that the total payments available to the Contractor for exercised options remains unchanged.

- e. Mobilization and demobilization costs for the substitute dredge shall be borne by the Contractor.

- f. Payment will resume for the substituting dredge:

- (1) If the dredge returns to an assignment in the same dredging region, when the dredge material begins flowing out of the discharge pipeline; or
- (2) If the dredge returns to an assignment in a different dredging region, when the dredge material begins flowing out of the discharge pipeline at the new assignment;

2.1.9 Addition of Plant

- a. At the Contractor's option and with the approval of the Contracting Officer, an additional cutterhead dredge or dredges with attendant plant may work simultaneously with the primary cutterhead dredge and its attendant plant provided the criteria below is met.

- (1) Whenever two or more dredges are approved for simultaneous work on the contract, the dredge that commences dredging operations first will be considered the primary dredge.
- (2) The Contractor shall submit clear evidence that the additional dredge(s) can perform at the rate(s) shown in the chart in paragraph entitled "Minimum Production Rate Requirements" located in the Dredging Region Section(s) on work similar to that of this contract.
- (3) The additional dredge(s) shall provide its own attendant plant as described in paragraph entitled "Dredge Attendant Plant" at no additional costs to the Government.

(4) The additional dredge(s) shall provide its own survey equipment as described in Section 35 01 50.73, paragraph entitled "Survey Equipment" at no additional costs to the Government.

(5) The additional dredge(s) shall provide its own dredge discharge pipeline as described in paragraph entitled "Dredge Discharge Pipeline" at no additional costs to the Government.

(6) The additional dredge(s) shall conform to the same environmental requirements of the primary dredge.

b. Furthermore, the following conditions will apply to the additional dredge(s).

(1) No payment will be made for mobilization and demobilization to/from the dredging region(s) for the additional dredge(s).

(2) If the additional dredge(s) is not the same bid lot size as the primary dredge, payment for the additional dredge(s) will be determined using a rate computed as follows:

Additional Dredge Hourly Rate =
$$\frac{(\text{Original Base Item Estimated Quantity}) \times (\text{Original Base Item Unit Price})}{\text{Estimated Quantity From Base Item Bid Schedule of Applicable Bid Lot for Additional Dredge}}$$

(3) Upon commencement of dredging operations by the additional dredge(s), the remaining hours on the basic payment items will be prorated to each dredge so that total contract payments will remain unchanged. Option dredging payment hours will also be prorated separately so that the total contract payments for the exercised options will remain unchanged.

2.2 COMMUNICATIONS EQUIPMENT

The Contractor shall furnish and maintain the following communications equipment for the dredge, throughout the period of the contract. Final approval of the plant will not be made until this equipment is installed and in good working order.

2.2.1 Cellular Telephone

The Contractor shall provide a portable cellular telephone aboard the dredge, with two rechargeable power packs and all necessary recharging equipment and cables. The telephone shall be made available for official use by the Government Inspectors on a 24-hour per day basis to exclusively conduct Government business and emergency calls.

2.2.2 Satellite Telephone

The Contractor shall provide functioning 24-hour satellite telephone service with voice and facsimile capability aboard the dredge located in the corps office. The satellite telephone service shall have, as a minimum, voice capability of 4.8 kb/s (kilobytes per second) voice coding and fax speed of 2.4 kb/s. The satellite telephone shall be made available for official use by the Government Inspectors on a 24-hour per day basis to exclusively conduct Government business and emergency calls.

2.2.3 Marine VHF-FM Radio

The Contractor shall furnish and maintain one VHF-FM ship's radio transceiver for the dredge, with power not in excess of 25 watts, and output of at least 15 watts on the maritime frequencies of 156.800 (Channel 16) and 156.375 (Channel 67) MHz 16F3 emission, with plus or minus 5 KHz at 100% modulation. Marine radio equipment shall be operated in accordance with applicable FCC regulations.

2.2.4 Automatic Identification System (AIS)

The dredge shall be equipped with an Automatic Identification System (AIS) in accordance with the Code of Federal Regulations, 33 CFR 164, reference the note to 164.46(a). The system shall be operable at all times throughout the contract period. For further information, go to: http://edocket.access.gpo.gov/cfr_2005/julqtr/pdf/33cfr164.46.pdf.

PART 3 EXECUTION

3.1 DREDGING

3.1.1 Description of Work

a. The Contractor's plant shall be used to construct the saltwater sill in connection with maintenance dredging operations in the navigable channels of the US Army Engineer District, New Orleans.

b. The work shall consist of removing and satisfactorily disposing of material from the dredging regions described herein or from secondary dredging regions as directed by the Contracting Officer or his authorized representative. The materials to be dredged may consist of gravel, sand, silt, mud, or clay. Debris may be encountered in the course of dredging operations, including trash, roots, logs, rope, chain, various-sized metal objects, rip rap, etc. Areas that are affected by any of the Contractor's dredging or disposal practices not performed in accordance with these specifications shall be promptly restored by the Contractor to the original conditions at his own expense.

c. The Contractor shall be responsible for detecting and reporting to the Government Inspector, materials or obstructions, located within the assigned dredging areas ahead of dredging operations, which will cause damage, or has the potential to cause damage to the dredge and/or attendant plant and equipment. The Government Inspector will evaluate the situation, based on detection data submitted by the Contractor, which shall show evidence of the obstruction(s). Based on this evaluation, the Government Inspector will direct the Contractor's dredging activities. The Government will not be responsible for damage to the Contractor's dredge and/or attendant plant and equipment, due to its contact with materials or obstruction(s), which cause such damage, or have the potential to cause such damage.

3.1.2 Dredging Region

Please see applicable Dredging Region Section(s).

3.1.3 Secondary Dredging Regions

3.1.3.1 Dredging in Secondary Regions

Dredging at another region in the New Orleans District may become necessary during the term of this contract. If other dredging regions are utilized, additional information will be provided related to the secondary dredging region. Payment for work performed in secondary dredging regions will be made at the applicable contract unit prices, as described in the paragraph entitled "Dredging and Option Dredging Items". The contract clause entitled "Changes" (FAR 52.243-4) shall be invoked and an equitable adjustment made for any increase or decrease to the contract unit price.

3.1.4 Order of Work

a. The order of work to be performed under this contract cannot be determined except as the work progresses. Successive dredging location assignments may be either upstream or downstream and may not be at consecutive or contiguous locations. Repetitive assignments may be required at the same locations.

b. Assignments will be determined by the Administrative Contracting Officer and will be given to the Contractor's representative aboard the dredge. Assignments will be made as early as possible, but may be changed at any time without any prior notice. The Contractor may be required to stop work at any time without completing an assignment, to move to a new assignment.

c. No less than 24 hours prior to completion of dredging operations at an assigned dredging area, the Contractor shall notify the Contracting Officer, during normal US Army Corps of Engineers, New Orleans District office business hours (7:00am to 5:30pm) and not later than noon on Friday, of his estimated completion time on that particular assignment.

d. The Contractor shall endeavor to meet the schedule of dredging operations as determined by the Contracting Officer. Operations shall be performed 24 hours a day, 7 days a week, including those days, which have been declared by Congress to be legal holidays for per diem employees of the Federal Government.

3.1.5 Deficient Dredge Performance

3.1.5.1 Performance Evaluation

a. The dredge's production will be monitored and evaluated every 14 calendar days or shorter periods thereof in standard dredging reaches, when deemed appropriate by the Contracting Officer, to determine if the dredge is attaining the required minimum production rate required. If the production rate averaged over the evaluation period, as determined by the Contracting Officer, is found to be deficient in comparison to the minimum required production rate specified herein, the Government will take action as outlined in the paragraph entitled "Government Actions for Failed Production". The Contractor may elect to conduct a performance evaluation to assess the dredge's production rate and submit a written report within five calendar days after the evaluation period justifying why the minimum production rate cannot be obtained. If, after evaluation of the Contractor's report by the Government, the Contracting Officer determines that the minimum production rate for the evaluation period is inappropriate, then the reach in question may be

re-classified as "Non-Standard" by the Contracting Officer and the actual dredging time shall be considered as 100% pay time hours and paid at the contract price per hour without adjustment for performance. If the Contractor cannot support a justification to waive the minimum production rate or fails to submit it within five calendar days after the evaluation period, then the Government will maintain its action taken in accordance with the paragraph entitled "Government Actions for Failed Production" as appropriate and the Contractor will not be allowed a waiver.

b. Dredge Physical Data.

(1) Dredge physical data is required for submittal in the data sheets located at the end of this section. If any of the data submitted in the plant data sheets changes during the execution of the contract, the Contractor shall submit new data to the Government within 48 hours thereafter, showing the changes made to the equipment, along with the date(s) the changes were made.

(2) The Contractor shall submit both a hard copy and electronic version of the manufacturer's pump curve for each pump to be used during the project within 3 calendar days after issuance of the Notice to Proceed. This includes the dredge's main pump, ladder pump if applicable and booster pump(s) if applicable. If the Contractor requests a substitution of plant or addition of plant during the contract, the pump curve(s) of the substituted plant or the additional plant must be submitted at the time of the request. Each pump curve submitted shall be clearly designated with the dredge's name, contract number, pump function (main pump, ladder pump, or booster pump, etc.) pump HP and RPM's. The pump curve shall consist of the pump's performance for water plotted against hydraulic head and discharge velocity and GPM's. A Sample Pump Curve is included at the end of this section. One copy of this information shall be sent to the USACE Office and address listed in the paragraph entitled "Report of Operations".

c. Dredge Performance Indicators. Dredge performance indicators shall be maintained by the Contractor and provided to the Government on a daily basis on MVN Form 4267. Dredge performance indicators shall consist of the following data (in English units of measurement):

- (1) Dredge cut swing width;
- (2) Discharge pipeline length;
- (3) Dredge length of advance (0000-2400 hour time);
- (4) Elevation of cut, referenced to Low Water Reference Plane (LWRP);
- (5) Amount of material dredged per dredge advance length, in cy/hr, based on quantity surveys.

d. If the Contractor's performance evaluation indicates that the dredge may be capable of dredging at or above the minimum required production rate in a Standard dredging reach if the dredge plant is modified, the Contractor may be allowed to modify the dredge at no additional cost to the Government. Any time extension granted shall not exceed three calendar days. Time in excess of this will be grounds

for contract termination by default. If the dredge produces at or above the minimum required production rate after modification, then the dredge will then be considered to meet the specification requirements and the contract will continue in force. The Government will not pay for any costs associated with such a modification, even if the dredge fails to meet the minimum required production rate after being modified. If the dredge plant fails to meet the required minimum production rate after any such modification, the dredge will again be considered to fail the production rate requirement.

e. If the Contractor elects to make adjustments and/or modifications to the dredge plant and the performance evaluation indicates that the dredge is capable of dredging at the minimum required production rate, but one or more of the parameters (maximum depth, width of cut, currents, obstructions, maximum length of discharge pipeline, or material) has changed so as to prevent the dredge from attaining the minimum required production rate, then the reach will be considered "Non Standard" dredging and the actual time shall be considered as 100% pay time hours and paid at the contract price per hour without adjustment for performance.

3.1.5.2 Government Actions for Failed Production

If the Contractor's dredge fails to meet the minimum required production rate, the Contracting Officer may require one of the following remedies without additional cost to the Government.

- (1) Require the Contractor to stop work and bring his dredge into compliance with the minimum production rate criteria stated in the applicable Dredging Region Section(s) and with the dredge requirements stated in the paragraph entitled "Size and Equipment of Dredge Plant", by modifying the dredge.
- (2) Require the Contractor to replace the deficient dredge with another dredge that meets the production rate criteria.
- (3) Terminate the contract for default.
- (4) Allow the contract to continue in force with a downward adjustment in the hourly rate for the 14 day evaluation period, in accordance with the performance pay adjustment method described in the paragraph entitled "Dredging Performance Pay Adjustments".

3.2 MOVEMENT OF NAVIGATION AIDS

The Contractor shall not relocate any navigation aids (buoys, markers, etc.) during this contract. The Contractor shall conduct a survey of navigation aids to determine if any must be temporarily relocated to accomplish the work. For navigation aids in which the Contractor determines that relocation is necessary, the Contractor shall notify the Contracting Officer or his/her authorized representative and the U.S. Coast Guard, Aids to Navigation (985-384-7000) at least 21 days prior to the need for relocation. All relocation of navigation aids shall be performed by the Coast Guard. The Government will not be responsible for any delays to the work due to the Contractor giving less than a 21-day notification to the Coast Guard.

3.3 WORKING IN THE VICINITY OF STRUCTURES AND UTILITY CROSSINGS

3.3.1 General

a. The Contractor shall exercise caution when working in the vicinity of structures, such as bridges, and utility crossings, such as pipelines and cables. If dredging to the assigned elevation has the potential to endanger a particular structure or utility, the Contracting Officer, upon request, may elect to reduce the extent of the required excavation in the vicinity of the structure or utility.

b. Unless otherwise directed, the Contractor shall provide at least project channel dimensions over all structures and utility crossings. Upon issuance of an assignment, the Contractor shall contact Louisiana One Call at 811 to verify all utilities within the assignment, including the borrow area(s). Within 24 hours after issuance of Notice to Proceed, the Contractor shall submit a detailed plan of operation at each structure/utility crossing within the dredging region(s). The plan shall contain at least the following:

(1) Louisiana One Call ticket number along with the utility's size, elevation, owner information and type of utility.

(2) The Contractor shall investigate the current nautical charts published by NOAA and any other pertinent information or databases available.

(3) The Contractor shall notify the owners of structures/utilities electronically and in writing by certified mail at least 7 calendar days prior to operating within 500 feet of the particular structure or utility. The Contractor shall provide a copy of this notification letter to the area engineer of the respective Area Office. The letter shall reference the following:

(a) The anticipated date the dredge will work over the utility.
(b) The anticipated elevation and width of dredge cut over the utility.

(c) Point(s) of contact and telephone number(s).

(d) Emergency procedures.

(e) Any other information from the Contractor the utility owner would consider significant for safe dredging operations over the utility crossing.

(f) Request that the owner verify the location of the utility and provide the most recent as-built plan and profile surveys.

(4) Emergency measures to be taken in the event of an accident.

The Contractor shall also provide transportation, meals, and/or lodging for any representatives of owners of structures or utility crossings who are deemed necessary to be present for safety reasons, by the Contracting Officer's Representative, to remain aboard the dredge while the Contractor is working in the vicinity of these crossings.

c. The Government will not be responsible for any damages to structures or utilities, loss of service costs of such structures/utilities, or damage to the Contractor's plant.

d. UTILITY MARKING REQUIRED. Prior to dredging within 1,000 feet of a

utility crossing, the Contractor shall mark the established location of utility by placing one Coast Guard approved yellow flashing buoy on each side and outside of the authorized channel to accurately mark the location of the utility within view of the Dredge Leverman. The Contractor shall immediately remove such buoys upon completion of dredging in the area of the utility.

3.3.2 Existing Structures or Utilities

Information pertaining to existing structures, such as bridges, and utility crossings, such as pipelines and cables, within the dredging and disposal areas is detailed within the applicable Dredging Region Section(s). The listed data herein has been provided by the owners, or taken from permit applications, and has not been confirmed by the Government. The Contractor shall verify this data prior to working in the vicinity of the structures or utilities. If the Contractor detects a discrepancy in the data with actual conditions, he/she shall notify the Contracting Officer of the discrepancy within 24 hours of this occurrence. Large-scale drawings with utility crossings will be available to the Contractor upon request. The Government will provide structure and utility information prior to any work performed at secondary dredging regions that are not addressed.

Additional abandoned structures and utilities may also exist within the dredging and disposal areas. The Contractor should make his own investigation of submerged, surface and overhead structures in the work areas and other locations he finds necessary to traverse. The exact location, depths and heights of submarine cables, pipes, powerlines, docks, piers, bulkheads, bridges, etc. (as applicable) are not known and it may be necessary for the Contractor to ascertain interference problems and notify the respective owners in advance of dredging operations.

Upon completion of a dredging assignment, the Contractor shall submit to the Contracting Officer's Representative, the following:

- a. A listing of all structures and utilities within the dredging reach, including owner name, location, elevation of utilities and owner point of contact.
- b. A copy of any structure or utility as-builts, surveys, etc. received from the owner.

3.3.3 Location of Submerged Objects

a. If the Contractor should locate a submerged object within the area of work, which endangers dredging operations or poses a hazard to general navigation, the Contractor shall note the location of the object, as determined from the electronic positioning system aboard its vessel. This location shall be reported to the Government Inspector. Dredging in the immediate vicinity of the reported object shall be curtailed until the nature of the object and the degree of hazard can be determined. Dredging shall resume at the location of the reported object when the Contracting Officer determines that a hazard no longer exists.

b. If the Contractor issues a false report of a sunken object, the cost of the investigation shall be deducted from any amounts due, or to become due, the Contractor.

c. This clause applies in the case of submerged objects which are

created by others. Submerged objects or hazards created by the Contractor shall be considered an obstruction of navigable waterways as described in the clause entitled "Obstruction of Navigable Waterways" (DFARS 252.236-7002) in the Section 00700.

3.4 CUTTERHEAD DREDGE AND ATTENDANT PLANT DATA SHEET

Submittal Date:

CUTTERHEAD DREDGE AND ATTENDANT PLANT DATA SHEET (Version Apr 2025)

In compliance with the contract requirements to submit plant data and subject to all conditions thereof, the undersigned _____, a corporation/joint venture/individual (indicate appropriate status) organized and existing under the laws of the City of _____ and the State of _____, hereby correctly describes the Contractor's plant to the Government, which is performing work under the following named Contract _____ and Solicitation No. and Contract No. _____.

Printed: _____ Signed: _____
Certifying Officer of the Contractor's Firm

Title: _____

One cutterhead dredge and attendant plant with the following characteristics (in English units of measurement):

1. DREDGE INFORMATION:

- (a) Bid lot number: _____
- (b) Dredge name: _____ Dredge official number: _____
- (c) Minimum width of channel in which dredge can successfully operate and make a 180-degree turn around: _____
- (d) Maximum draft of dredge: _____
- (e) Vertical clearance necessary at minimum draft of dredge: _____
- (f) Loaded freeboard: _____
- (g) Minimum depth of both freshwater and saltwater in which the dredge the dredge can successfully operate: _____
- (h) Elevation range to which the dredge will dig:
Maximum: _____, Minimum: _____
- (i) Maximum effective dredge swing at 70 degrees (35 degrees from center), in feet: _____
- (j) Length of dredge spuds: _____
- (k) Length and beam of dredge hull: _____
- (l) Length of digging spud to trunnion
With an idler barge: _____,
Without an idler barge: _____

The Contractor shall note if the idler barge will be attached at commencement of dredging.

- (m) Length of dredge ladder
Overall: _____, From trunnion to cutter: _____
- (n) Length of suction and boat lines: _____
- (o) Dredge Discharge Size (this is considered to be the least inside diameter of the following: the main pump discharge, the submerged pump discharge, the booster pump discharge, or the discharge pipeline). This item must agree with the bid lot used: _____
- (p) Inside diameter of main pump suction discharge:
Main 1: _____, Main 2: _____
- (q) Inside diameter of main pump suction inlet:
Main 1: _____, Main 2: _____
- (r) Suction lift (elevation of main pump(s) relative to the water surface level): _____
- (s) Diameter of main pump impeller eye:
Main 1: _____, Main 2: _____
- (t) Outside diameter of main pump impeller:
Main 1: _____, Main 2: _____
- (u) Brake horsepower and corresponding engine RPM's (during dredging operations) applied to the main pump impeller at rated drive of the prime mover, during dredging operations: Main 1: _____, Main 2: _____
- (v) Inside diameter of submerged pump discharge: _____
- (w) Inside diameter of submerged pump inlet: _____
- (x) Suction lift (elevation of submerged dredge pump relative to the water surface level): _____
- (y) Diameter of submerged pump impeller eye: _____
- (z) Outside diameter of submerged pump impeller: _____
- (aa) Distance submerged pump is located above cutter: _____
- (ab) Brake horsepower and corresponding engine RPM's (during dredging operations) applied to submerged pump impeller at rated drive of the prime mover, during dredging operations: _____
- (ac) Location of DQM pump sensor: _____
- (ad) Cutterhead type and diameter: _____
- (ae) Brake horsepower applied to cutterhead during dredging operations: _____
- (af) Pump engine(s) horsepower and corresponding RPM: _____
- (ag) Completion date of each dredge pump engine re-build: _____

(ah) Total installed engine(s) horsepower on the dredge (including the engine(s), generator engine(s), etc.): _____

(ai) Type(s) of production rate monitoring equipment on-board the dredge (measuring CY/HR of material dredged): _____

(aj) Indicate type of dredge advance mechanism (e.g. walking spuds, spud carriage or wires, etc.): _____

(ak) Least inside diameter of the discharge pipeline: _____

2. BOOSTER PLANT INFORMATION:

(a) Length of suction and boat lines: _____

(b) Inside diameter of pump discharge:
Booster 1: _____, Booster 2: _____

(c) Inside diameter of pump suction inlet: :
Booster 1: _____, Booster 2: _____

(d) Suction lift (elevation of booster pump(s) relative to the water surface level): _____

(e) Diameter of pump impeller eye:
Booster 1: _____, Booster 2: _____

(f) Outside diameter of pump impeller:
Booster 1: _____, Booster 2: _____

(g) Brake horsepower and corresponding engine RPM's (during dredging operations) applied to pump impeller at rated drive of the prime mover, during dredging operations: Booster 1: _____,
Booster 2: _____

(h) Pump engine(s) horsepower and corresponding RPM:

(i) Completion date of booster pump engine re-build:

3. THE DREDGE MAY BE INSPECTED AT (List location of equipment):

4. IDLER BARGE:

(a) Name: _____

(b) Length and beam: _____

(c) Indicate type of advance mechanism (e.g. walking spuds, spud carriage or wires, etc.): _____

(d) Length of idler barge spuds: _____

(e) Owner, name and address: _____

(f) The idle barge may be inspected at the following location:

5. TENDER NO. 1:

(a) Name: _____

(b) Length and beam: _____

(c) Owner, name and address: _____

(d) Total propulsion horsepower: _____

(e) The tender may be inspected at the following location:

6. TENDER NO. 2:

(a) Name: _____

(b) Length and beam: _____

(c) Owner, name and address: _____

(d) Total propulsion horsepower: _____

(e) The tender may be inspected at the following location:

7. SURVEY BOAT:

(a) Name: _____

(b) Length and beam: _____

(c) Owner, name and address: _____

(d) Total propulsion horsepower: _____

8. SURVEY SKIFF:

(a) Length and beam: _____

(b) Owner, name and address: _____

9. PICKET BOAT:

(a) Name: _____

(b) Length and beam: _____

(c) Owner, name and address: _____

(d) Total propulsion horsepower: _____

10. CREW BOAT:

(a) Name: _____

(b) Length and beam: _____

(c) Owner, name and address: _____

(d) Total propulsion horsepower: _____

11. ELECTRONIC POSITIONING EQUIPMENT (Model and Type):
_____12. DEPTHSOUNDER (Model and Type):

13. DREDGE OWNER INFORMATION:

Firm name: _____

Point of contact: _____

Title: _____

Business address:

Street _____

City _____

Parish/County _____

State _____ Zip+4 _____

Telephone no. (_____) _____

Facsimile no. (_____) _____

(Additional signature block to be used for joint venture partner(s))

Firm name _____
Point of contact _____
Title _____
Business address _____
Street _____
City _____
Parish/County _____
State _____ Zip+4 _____
Telephone no. (_____) _____
Facsimile no. (_____) _____

(Additional signature block to be used for joint venture partner(s))

Firm name _____
Point of contact _____
Title _____
Business address _____
Street _____
City _____
Parish/County _____
State _____ Zip+4 _____
Telephone no. (_____) _____
Facsimile no. (_____) _____

-- -- End of Section -- --

REPORT OF OPERATIONS -- PIPELINE, DIPPER OR BUCKET DREDGES												REPORTS CONTROL SYMBOL ENG CW-0-13	
THRU:		TO:				FROM:			DATE OR PERIOD		REPORT NO.		
[]		[]				[]			[]		[]		
CHARACTER OF REPORT	[]	MAINTENANCE	[]	DAILY	[]	COMPLETION	DREDGE PUMPS OPERATING & CORRESPONDING RPM	[]	MAIN 1	RPM	DREDGE TYPE:		
	[]	NEW WORK	[]	ANNUAL	[]			[]	MAIN 2	RPM	[]	BUCKET	
DREDGE	NAME			DREDGE ADVANCE MECHANISM			DREDGE PUMPS OPERATING & CORRESPONDING RPM	[]	MAIN 1	RPM	[]	BUCKET	
	DREDGE DISCHARGE SIZE (ID), IN			CUTTER, HP				[]	MAIN 2	RPM	[]	CUTTERHEAD	
	DREDGE DISCHARGE SIZE (ID), IN			CUTTER, HP				[]	MAIN 2	RPM	[]	CUTTERHEAD	
	DREDGE DISCHARGE SIZE (ID), IN			CUTTER, HP				[]	MAIN 2	RPM	[]	CUTTERHEAD	
NUMBER OF CREWMEMBERS		DREDGE		SHORE		OTHER		TOTAL		WORK SCHEDULE		DAYS PER WEEK	
PROJECT AND ASSIGNMENT		LOCATION (INCLUDE STATIONS NUMBERS)		>		WIDTH OF SWING		RANGES - RT, CL, LT		OVERDEPTH			
C/L STATIONS		>		WIDTH OF SWING		RANGES - RT, CL, LT		OVERDEPTH					
CHARACTER OF MATERIAL (leave blank if grab samples aren't taken)		ABSOLUTE DENSITY		IN PLACE DENSITY		VOIDS RATIO							
GRAIN SIZE		GMS/liter		GMS/liter		VISUAL MATERIAL CLASSIFICATION		TYPE					
MM		MM		MM		TYPE							
CONTRACT OR ORDER NUMBER		NUMBER		CONTRACTOR		HIRED LABOR		TOTAL NUMBER OF DAYS ON WHICH WORK WAS DONE:					
CHANNEL CONDITION		AVERAGE DEPTH		BEFORE DREDGING		AFTER DREDGING		MINIMUM SOUNDING		BEFORE DREDGING		AFTER DREDGING	
RIVER STAGE		MINIMUM		TIME		MAXIMUM		TIME		GAGE LOCATION			
WEATHER CONDITION		(clear, cloudy, rain, snow, and fog)		VISIBILITY		miles		WIND (maximum velocity & direction)					
WORK PERFORMED						DISTRIBUTION OF TIME							
ITEM		UNIT		QUANTITY		EFFECTIVE WORKING TIME (chargeable to cost of work)		AMOUNT					
AVERAGE WIDTH OF CUT (SWING)		FEET				PUMPING OR DREDGING							
TOTAL ADVANCE THIS PERIOD		FEET				PCT. OF EFFECTIVE TIME							
TOTAL ADVANCE PREVIOUS TO THIS PERIOD		FEET				BOOSTER (in line):							
TOTAL ADVANCE TO DATE		FEET				NON-EFFECTIVE WORKING TIME (chargeable to cost of work)		NO. OF TIMES		AMOUNT			
TOTAL LENGTH OF DISCHARGE PIPELINE: *SEE REVERSE SIDE						HANDLING PIPELINES		HPL					
AVERAGE LIFT		FEET				HANDLING ANCHOR LINES		HAL					
AVERAGE PUMP SPEED		RPM				CLEARING PUMP AND PIPELINE		CPPL					
AVERAGE GROSS CY'S DREDGED PER PUMP HOUR		CY/HR				CLEARING CUTTER OR SUCTION HEAD		CCSH					
AVERAGE NET CY'S DREDGED PER PUMP HOUR		CY/HR				WAITING FOR SCOWS		WFS					
AVERAGE LINEAR FOOT PER HOUR		LF/HR				TO AND FROM WHARF OR ANCHORAGE		TFWA					
CUBIC YARDS REMOVED						CHANGING LOCATION OF PLANT ON JOB		CLPJ					
AMOUNT DREDGED THIS PERIOD:						LOSS DUE TO OPPOSING NATURAL ELEMENTS		LDNE					
(1) CREDITED (pay place)						LOSS DUE TO PASSING VESSELS		WVP					
(2) GROSS (computed amount)						SHORELINE AND SHORE WORK		SLSW					
AMOUNT PREVIOUSLY REPORTED:						WAITING FOR BOOSTER		WFB					
(1) CREDITED (pay place)						MINOR OPER. REPAIRS (explain in remarks)		MOR					
(2) GROSS (computed amount)						WAITING FOR ATTENDANT PLANT		WAP					
TOTAL AMOUNT DREDGED TO DATE:						PREPARATION AND MAKING UP TOW		PMUT					
(1) CREDITED (pay place)						TRANSFERRING PLANT BETWEEN WORKS		TPBW					
(2) GROSS (computed amount)						LAY TIME OFF SHIFT AND SATURDAYS		LTOSS					
ATTENDANT PLANT						SUNDAYS AND HOLIDAYS		SH					
ITEM		NAME OR NUMBER		HOURS		FIRE DRILL		FD					
DREDGE						MISCELLANEOUS (explain in remarks)		MISC					
TENDER #1						TOTAL NON-EFFECTIVE WORKING TIME							
TENDER #2						PCT. OF NON-EFFECTIVE TIME							
SKIFF						TOTAL EFFECTIVE AND NON-EFFECTIVE TIME (chargeable to cost of work)							
CREW						PCT. OF TOTAL TIME IN PERIOD							
SURVEY						LOST TIME (not chargeable to cost of work)							
BARGES						MAJOR REPAIRS AND ALTERATIONS							
CRANE BARGE						CESSATION							
IDLER BARGE						COLLISIONS							
CUTTER-TYPE						MISCELLANEOUS (explain in remarks)							
SPUD LENGTH						TOTAL LOST TIME							
NUMBER OF INSPECTIONS		BY DISTRICT PERSONNEL		BY DIV & OCE PERSONNEL		PERCENTAGE OF TOTAL TIME							
CONTRACT USE ONLY		HAS ANYTHING DEVELOPED WHICH MIGHT LEAD TO A CHANGE ORDER OR CLAIM?		()		NO							
(If "YES", explain under remarks on back)		()		YES									
						TOTAL TIME IN PERIOD							

ATTENDANT PLANT											
DREDGE DISCHARGE PIPELINE						DISPOSAL AREA EQUIPMENT		ANCHORING SYSTEMS			
FLOATING Pontoons	AMOUNT	SUBMERGED	AMOUNT	SHORE	AMOUNT	TOTAL COMBINED DISCHARGE, LF	Marsh Trackhoes-30'		Skidder Barges		
Metal		Metal		Metal			ANCHORS	Marsh Trackhoes-60'			
PVC		PVC		PVC			Breast	Marsh Buggies			
Flexifloat		Other		Other			Head	Dozers			
TOTAL LF							Line	Front End Loaders			
ELBOWS	Stiff			LEAST INSIDE DIAMETER OF DISHARGE PIPELINE, IN			Air Boats		Other		
	Swivel						ATV's				
							Y-Valves				
							Spreaders				
DISPOSAL AREA SUMMARY											
NAME/LOCATION COORDINATE	SHORE CONNECTION	DATE START	DATE FINISH	TOTAL GROSS CYS	TOTAL ACREAGE	REMARKS					

	100%	70%	35%	0%	0% - MISC (Mob)	TOTAL	
BASE HRS							
OPTION HRS							
PREVIOUS HRS							
TOTAL HRS							

		TODAY QUANTITY	PREVIOUS QUANTITY	QUANTITY TO DATE
FUEL (diesel)	GAL.			
LUBRICANT (oil)	GAL.			
LUBRICANT (grease)	LBS.			
WATER	GAL.			

NAME:	
TITLE:	


[illegible]

Contract Number: 05 -C-XXXX

Dredge Name: _____

Pump Function: (main, ladder, or booster, etc.)

MANUFACTURER'S PERFORMANCE CURVE



SAMPLE

SECTION TABLE OF CONTENTS

DIVISION 35 - WATERWAY AND MARINE CONSTRUCTION

SECTION 35 20 23.23 16

HYDRAULIC DREDGING - MISSISSIPPI RIVER SALTWATER BARRIER SILL DREDGING REGION

PART 1 GENERAL

- 1.1 SCOPE
- 1.2 DEFINITIONS
- 1.3 MEASUREMENT AND PAYMENT
- 1.4 ADDITIONAL PLANT
 - 1.4.1 Spill Barge
 - 1.4.2 Landing Barge
- 1.5 ADDITIONAL RIGHTS-OF-WAY
- 1.6 NAVIGATION REQUIREMENTS
- 1.7 CONSTRUCTION PLAN
- 1.8 EXISTING STRUCTURES OR UTILITIES

PART 2 PRODUCTS

PART 3 EXECUTION

- 3.1 DREDGING
 - 3.1.1 Borrow Areas
 - 3.1.2 Saltwater Barrier Sill
 - 3.1.3 Previous Dredging Contract
- 3.2 CONTRACTOR COMMUNICATION WITH NAVIGATION PDT
- 3.3 DEGRADING OVER-CONSTRUCTED SALTWATER BARRIER SILL
- 3.4 MONITORING CHANNEL BUOYS
- 3.5 MINIMUM PRODUCTION RATE REQUIREMENTS
- 3.6 HORIZONTAL AND VERTICAL CONTROL POINTS
 - 3.6.1 Horizontal Control Points
 - 3.6.2 Vertical Control Points
- 3.7 MISSISSIPPI RIVER DGPS CALIBRATION POINTS

ATTACHMENTS:

Plates

-- End of Section Table of Contents --

SECTION 35 20 23.23 16

HYDRAULIC DREDGING - MISSISSIPPI RIVER SALTWATER BARRIER SILL DREDGING REGION

PART 1 GENERAL

1.1 SCOPE

This section details specific requirements which are in addition to the general requirements set forth in the specifications for the Mississippi River Saltwater Barrier Sill Dredging Region. The work covered by this section consists of furnishing all labor, materials, and equipment, and performing all work required for dredging in the specified dredging region, except for those measures set forth in other technical portions of the Specifications.

1.2 DEFINITIONS

AHP = Above Head of Passes
LDB = Left Descending Bank
RDB = Right Descending Bank

1.3 MEASUREMENT AND PAYMENT

No separate Measurement or Payment will be made for dredging region requirements as described herein. All costs for the work covered under this section shall distributed throughout exisiting bid items.

1.4 ADDITIONAL PLANT

1.4.1 Spill Barge

A spill barge with a submerged vertical pipe shall be used to discharge material below the water surface. The spill barge shall be of sufficient size to accommodate a length of vertical discharge pipe able to deliver material to elevations varying from -30 to -100 feet LWRP. The vertical pipe shall be able to be lowered and raised to accommodate varying sill height placements (e.g., a crane placed on the spill barge to raise or lower the vertical pipe and then the Contractor shackles the pipeline to the desired height). Also, the vertical pipe shall be built in such a way as to efficiently spread and direct material (e.g., a baffle or a 10 foot bell-shape pipe piece attached to the end of the submerged pipe).

1.4.2 Landing Barge

The Contractor shall furnish a landing barge for personnel access, located at the work site by the Contracting Officer and positioned by the Contractor. The landing barge shall be capable of access from the levee crown to the barge dock. Stairways will consist of sections with not more than a 12-ft. vertical rise each, and including a connecting stair landing, stair top platform and gangway. The gangway shall be capable of vertical and horizontal movement. The landing barge, railing, and stairway shall conform to the requirements of EM 385-1-1.

1.5 ADDITIONAL RIGHTS-OF-WAY

The landing barge, crew boat, survey boat, and parking spaces for government personnel and contract personnel shall be stationed within the Rights-of-Way provided. The Right-of-Way boundary extends from Mississippi River Mile 63.5 AHP to Mile 64.5 AHP on the right descending bank between the batture and levee crown.

1.6 NAVIGATION REQUIREMENTS

a. Traffic Coordinator (Contact Pilot). In order to minimize the risk of collision between shipping/towing interests and the dredging Contractor, the Contractor shall provide a traffic coordinator on a 24-hour per day basis while the dredge, attendant plant, or any equipment is in the navigable portion of the Mississippi River. The coordinator for each shift shall be a licensed U.S. Coast Guard Master Pilot. Unless otherwise directed by the Contracting Officer, a coordinator shall be located aboard the dredge at all times. The coordinator shall use the appropriate communication equipment to advise shipping, towing interests, and the dredge crew of the current status of traffic and other pertinent information. No dredge crew member shall be used in a dual capacity to satisfy this requirement.

b. Vessel Traffic Service (VTS). VTS is currently operating on the Mississippi River in the New Orleans District. The Contractor shall comply with VTS while the Contractor's dredge, attendant plant, or any equipment is in the Mississippi River (i.e., during mobilization and set-up of the Contractor's dredge, attendant plant, and all equipment; during the entire duration of the contract; and until the Contractor's dredge, attendant plant, and all equipment have demobilized from the dredging region). The Contractor shall notify the New Orleans VTS of their location and the nature of the navigation impairment caused by their dredging operations. Point of contact for the 24-hour New Orleans VTS Watch Supervisor is 504-365-2514. If the VTS office cannot be reached, contact the 24-hour New Orleans Sector Operations Center at 504-365-2533.

1.7 CONSTRUCTION PLAN

Within 24 hours after issuance of the Notice to Proceed, the Contractor shall submit a Construction Plan to the Contracting Officer or his/her authorized representative for review and acceptance. The plan shall be reviewed and accepted prior to any Mississippi River closure to lay the submerged dredge discharge pipeline and prior to commencement of dredging. The Construction Plan shall show the layout of all the Contractor's plant and equipment for the first assignment. At a minimum, the layout shall include the Contractor's dredge, anchors, submerged pipeline, floating pipeline, spill barge, anchor wires, risers, buoys and all other attendant plant that will be in the river as well as the sill location, the borrow area, and river miles. It shall also include a plan for coordinating with the Government, US Coast Guard, River Pilots, VTS and mariners.

1.8 EXISTING STRUCTURES OR UTILITIES

The structures, such as bridges, and utility crossings, such as pipelines and cables, listed are known to be located within the dredging region. Additional abandoned structures and utilities may also exist within the area. The locations and vertical clearances in the table were provided by the utility owners, and have not been confirmed by the Government. The

Contractor shall verify these clearances and locations. If the Contractor detects a discrepancy in the data with actual conditions, the Contractor shall notify the Contracting Officer's Representative of the discrepancy within 24 hours of this occurrence.

Structure or Utility	Owner and Contact Phone Number	Location	Elevation (feet)
30-Inch Water Discharge Pipe	Harvest Midstream Richard Rousselle 15551 Hwy 23 Belle Chasse, LA 70037 504-460-7585 Richard.rousselle@harvestmidstream.com	Mile 63.0 AHP, RDB	Unknown
20-Inch Fuel Oil Pipeline	Colonial Pipeline Company Kiley Williams 409-291-5655, 409-658-3047 kwilliams@colpipe.com Philip McDonald pmcdonald@colpipe.com Ross Ferguson rferguson@colpipe.com	Mile 63.4 AHP	Unknown
(4) Electrical Cables	Entergy Brad Nicholas 504-365-2879 bnichol@entergy.com Derek Maxie 985-240-7402 dmaxie@entergy.com Holly Houston 504-365-2945 hhousto@entergy.com Alexander James Engle 504-365-3607 aengle@entergy.com Parris Chavis 504-365-2925 pchavil@entergy.com	Mile 63.4 AHP	Unknown
24-Inch Oil Pipeline	Harvest Midstream (see above)	Mile 63.4 AHP	Unknown

Structure or Utility	Owner and Contact Phone Number	Location	Elevation (feet)
Water Siphon	Plaquemines Parish Patrick Harvey 8056 Louisiana 23, Suite 308 Belle Chasse, LA 70037 504-912-1007 pharvey@ppgov.net Robert Spears 504-491-1607 rspears@ppgov.net	Mile 63.9 AHP, RDB	Unknown
6-Inch PVC Water Siphon	Saxon Becnel and Sons Ricky Becnel 13949 Louisiana 23 Belle Chasse, LA 70037 504-432-3007 rickybecnel@gmail.com	Mile 65.4 AHP, RDB	Unknown
(2) 10-3/4-Inch Gas Pipelines	Unknown	Mile 66.1 AHP	Unknown
12-Inch Propylene Pipeline	Chalmette Louisiana Liquids Parrish Coleman 662-571-8999 pcoleman@sulphurriver.com Greg Vujovich 214-382-0235 gvujovich@sulphurriver.com	Mile 66.2 AHP	Unknown
(2) 12-Inch Gas Pipelines	Unknown	Mile 66.2 AHP	Unknown
(3) 12-Inch Gas Pipelines	Black Bear Transmission Larry Bonner 601-433-9458 lbonner@blackbearllc.com Todd Solomon 318-355-3439 tsolomon@blackbearllc.com Nicholas Dobias 504-656-0194, 504-495-0170 ndobias@blackbearllc.com	Mile 66.3 AHP	Unknown

PART 2 PRODUCTS

Although listed under PART 2 PRODUCTS, the equipment described herein remains the property of the Contractor at all times.

PART 3 EXECUTION

3.1 DREDGING

3.1.1 Borrow Areas

The dredging region for this contract consists of two borrow areas located on the bottom of the Mississippi River. Elevation of the borrow areas lie between approximately -30 feet and -90 feet LWRP. Borrow Area 1 is located between Mile 64 AHP and Mile 65 AHP on the right descending half of the river channel and is approximately 5,800 feet long by 1,000 feet wide. Borrow Area 2 is located at Mile 67 AHP and is approximately 2,000 feet long by 200 feet wide. The Government will direct what borrow area(s) the Contractor shall dredge. Plates, located at the end of this section, show the location and a typical section for each borrow area.

3.1.2 Saltwater Barrier Sill

The Contractor's dredge and attendant plant will primarily be used in connection with the construction and possible maintenance of a saltwater barrier sill located between Mile 63 and Mile 64 AHP on the Mississippi River. The work will consist of satisfactorily placing hydraulically dredged material which shall be taken from a borrow area located on the river bottom. The contract plates show the approximate location of the sill and configuration of the sill (should the sill need to be built to -30' LWRP with a 620' notch to -55' LWRP) and borrow area. Further details of the location, size, and configuration of the sill and borrow area required will be given in the dredging assignments. The Contractor shall be aware that there is no sill height tolerance. If the Contractor places dredge material above the assigned sill elevation, the Contractor shall degrade the over-constructed sill. See paragraph below entitled "Degrading Over-constructed Saltwater Barrier Sill". If a partial or full removal of the saltwater barrier sill is required after the Low Water season is over, more information will be provided.

Dredging/construction that may disrupt navigation shall be coordinated with USACE, US Coast Guard, and River Pilots.

3.1.3 Previous Dredging Contract

Location: Mississippi River Mile 63.7 AHP
Contract: W912P824C0028

3.2 CONTRACTOR COMMUNICATION WITH NAVIGATION PDT

Throughout the duration of the contract, the Contractor shall coordinate construction operations with the Navigation PDT (including personnel from USACE, US Coast Guard, River Pilots, etc) to ensure minimal impacts to the navigation industry. The Contractor shall participate in daily conference calls with the Navigation PDT. USACE will provide the Contractor a list of contacts to be included in the daily conference calls and email updates. Two hours before each conference call, the Contractor shall send the Navigation PDT the construction plan for the day and recent multibeam sill

surveys as well as a 24-hour look ahead summary and 48-hour look ahead summary. Also, the Contractor shall maintain a navigation corridor that is acceptable with USACE, US Coast Guard, and River Pilots.

3.3 DEGRADING OVER-CONSTRUCTED SALTWATER BARRIER SILL

If the Contractor places dredge material above the assigned sill elevation, the Contractor will be given 100% pay time for up to 48 hours for the purpose of degrading the over-constructed sill while the dredge is on standby. Any additional hours the Contractor uses to degrade the sill to the assigned sill elevation will be paid at 35% pay time hours.

3.4 MONITORING CHANNEL BUOYS

Should it become necessary to build the Saltwater Barrier Sill above -55' LWRP, the Contractor shall properly mark the one-way navigation channel with buoys that meet the US Coast Guard requirements and maintain the buoys in the proper location while one-way traffic is required throughout the contract duration.

3.5 MINIMUM PRODUCTION RATE REQUIREMENTS

- a. The following table shows the minimum production rates required for the dredge. The dredge shall meet or exceed the production rates.

DREDGE WITH AN OPERABLE SUBMERGED PUMP

Dredge Discharge Size (ID, Inches)	Submerged Pump	Minimum Output (CY/HR)	
		Borrow Area #1	Borrow Area #2
30 or greater	Yes	3,415	2,500

- b. If the dredge's submerged pump becomes inoperable and the Contractor elects to continue dredging, then the Contractor will be allowed 96 hours to operate without the submerged pump provided the dredge meets the minimum production rate shown on the table below and as specified in Section 35 20 23.23, paragraph entitled "Required Production and Dredging Tolerances". For a dredge with an inoperable submerged pump, the unit price per hour for "Dredging", "Option Dredging I", "Option Dredging II", and "Option Dredging III" shall be computed as follows:

New unit price per hour = (Original Dredging Unit Price Per Hour)x(0.754)

DREDGE WITH AN INOPERABLE SUBMERGED PUMP

Dredge Discharge Size (ID, Inches)	Submerged Pump	Minimum Output (CY/HR)	
		Borrow Area #1	Borrow Area #2
30 or greater	Inoperable	2,575	1,885

If the submerged pump is still inoperable after the allotted 96 hours, the Contractor will be placed on 0% pay time until the dredge's submerged pump is operable and fully immersed.

3.6 HORIZONTAL AND VERTICAL CONTROL POINTS

3.6.1 Horizontal Control Points

Horizontal Control Points are located on the contract plates located at the end of this section.


3.6.2 Vertical Control Points

The vertical control point for this dredging region is the Alliance, Louisiana gage located at Latitude 29-41-04.36 and Longitude 89-58-11.65. Hydrographic information at the Alliance, Louisiana gage (Gage ID: 01390) may be found at RiverGages.com, <https://rivergages.mvr.usace.army.mil/WaterControl/new/layout.cfm>.

3.7 MISSISSIPPI RIVER DGPS CALIBRATION POINTS

DGPS Calibration Point	Approximate Mississippi River Mile	Coordinates (NAD83)	
		X	Y
H.O.P JCT. LIGHT	1.1 LDB	3945370.4	241680.2
Light #7 (West Point)	7.7 RDB	3923750.8	277208.6
Light #17	9.0 RDB	3917438.8	195386.8
Light #11	14.0 RDB	3906934.1	180351.1
Old Quarantine Sta. LT #6	17.5 LDB	3938652.7	261241.6

-- End of Section --



BORROW AREA 1 TOE COORDINATES



1	X=3708304.4 Y=446030.1	Lat 29°43'10.5065" Lon 89°59'11.7785"	6	X=3708890.7 Y=441869.6	Lat 29°42'29.2537" Lon 89°59'05.6848"
2	X=3710702.3 Y=439932.9	Lat 29°42'09.8710" Lon 89°58'45.4020"	7	X=3708466.4 Y=443291.3	Lat 29°42'43.3765" Lon 89°59'10.3065"
3	X=3709878.2 Y=439588.9	Lat 29°42'06.5621" Lon 89°58'54.7922"	8	X=3708110.3 Y=444032.8	Lat 29°42'50.7580" Lon 89°59'14.2458"
4	X=3709621.5 Y=440139.5	Lat 29°42'12.0424" Lon 89°58'57.6292"	9	X=3708032.7 Y=444339.4	Lat 29°42'53.8020" Lon 89°59'15.0849"
5	X=3709505.1 Y=440367.1	Lat 29°42'14.3090" Lon 89°58'58.9187"	10	X=3707655.5 Y=445175.3	Lat 29°43'02.1204" Lon 89°59'19.2512"
			11	X=3700785.2 Y=445230.3	Lat 29°43'2.6497" Lon 89°59'17.7730"
			12	X=3707586.8 Y=445695.1	Lat 29°43'7.2738" Lon 89°59'19.9611"

BORROW AREA 1 BASELINE COORDINATES

A	x=3708547.6 y=446189.1	Lat 29°43'12.052" Lon 89°59'8.999"
B	x=3711068.0 y=439658.6	Lat 29°42'7.113" Lon 89°58'41.292"

SUBMERGED OBSTRUCTIONS / SYMBOL - O

Submerged Anchor	X 3707700.7	Y 444920.2
Unknown	X 3707928.3	Y 444819.5
Unknown	X 3708386.5	Y 443554.0
Unknown	X 3708396.6	Y 443488.6
Unknown	X 3707709.7	Y 445446.6
Unknown	X 3707927.04	Y 444858.69
Unknown	X 3709882.01	Y 441597.07





NOTES:

- 1) THE POSITION OF POINTS 1 THROUGH 10 REPRESENT -90' LWRP TOE COORDINATES.
- 2) THE EXACT LOCATION, SIZE, AND CONFIGURATION OF THE SALTWATER BARRIER SILL WILL BE GIVEN IN AN ASSIGNMENT.
- 3) THE CONTRACTOR SHALL NOT DIG IN BORROW AREA 1 ANY CLOSER THAN 500' OF THE TOE OF THE SALTWATER BARRIER SILL TEMPLATE.

SALTWATER BARRIER SILL
CUTTERHEAD DREDGE

(LOCATION OF BARRIER SILL
AND BORROW AREA 1)
PLATE 2

FILE NAME: SWBBA_PLATE 2.dgn




NOTES:

1) THE CONTRACTOR SHALL USE GAGE 01390 "MISSISSIPPI RIVER AT ALLIANCE". THE GAGE IS LOCATED AT LATITUDE 29-41-04.36, LONGITUDE 89-58-11.64 ON UPSTREAM END OF COKE DOCK OF ALLIANCE REFINERY, RIGHT BANK AT MILE 62.5 (1962 SURVEY). THE GAGE IS AUTOMATIC WIRE WEIGHT AND SET AT 0.0 GAGE DATUM AND SHALL BE USED IN LIEU OF BENCHMARKS. 2015 DATUM RELATIONSHIPS ARE AS FOLLOWS:

0.0' GAGE = 0.0' NAVD88 (2009.55)
= -0.4' LWRP07


2) ALL ELEVATIONS ARE IN LWRP.

3) ALL SLOPES ARE 1V:3H EXCEPT FOR LANDSIDE LEVEE SIDE CUT SLOPES WHICH ARE 1V:5H (AS SHOWN ON THIS PLATE).




CUTTERHEAD DREDGE
SALTWATER BARRIER SILL
(TYPICAL SECTIONS
FOR BORROW AREAS)
PLATE 3

FILE NAME: SWBBA_PLATE 3.DGN



NOTE:

SALTWATER BARRIER SILL HEIGHT WILL RANGE BETWEEN -30.0' to -55.0' LWRP.
THE SIZE AND CONFIGURATION OF THE SILL WILL BE GIVEN IN AN ASSIGNMENT.



CUTTERHEAD DREDGE
SALTWATER BARRIER SILL
(TYPICAL SECTION FOR
SALTWATER BARRIER SILL)
PLATE 4

FILE NAME: SWBBA_PLATE 4.DGN

SECTION TABLE OF CONTENTS

DIVISION 35 - WATERWAY AND MARINE CONSTRUCTION

SECTION 35 20 23.33

NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM PIPELINE HYDRAULIC DREDGE

PART 1 GENERAL

- 1.1 DESCRIPTION
- 1.2 MEASUREMENT AND PAYMENT
- 1.3 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM CERTIFICATION
- 1.4 DREDGE PLANT INSTRUMENTATION PLAN (DPIP)

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

- 3.1 REQUIREMENTS FOR REPORTED DATA
 - 3.1.1 Message Bundle Data
 - 3.1.1.1 Messages
 - 3.1.1.1.1 Message Time
 - 3.1.1.1.2 Comment
 - 3.1.1.2 Dredge Events - Work Event
 - 3.1.1.2.1 Vertical Correction
 - 3.1.1.2.2 Cutter/Suction Head Location and Movement
 - 3.1.1.2.2.1 Cutter/Suction Head Horizontal Position
 - 3.1.1.2.2.2 Cutter/Suction Invert Depth
 - 3.1.1.2.2.3 Cutter/Suction Head Heading
 - 3.1.1.2.3 Dredge Activity
 - 3.1.1.2.3.1 Slurry Velocity
 - 3.1.1.2.3.2 Slurry Density
 - 3.1.1.2.3.3 Pump RPM
 - 3.1.1.2.3.4 Pump Vacuum
 - 3.1.1.2.3.5 Pump Outlet Pressure
 - 3.1.1.2.4 Outfall Information (Open Water/Spill Barge Disposal)
 - 3.1.1.2.4.1 Discharge Horizontal Position
 - 3.1.1.3 Dredge Events - State Event
 - 3.1.1.3.1 Message Time
 - 3.1.1.3.2 Contract Event
 - 3.1.1.3.2.1 Contract Number
 - 3.1.1.3.2.2 Contract Start and End
 - 3.1.1.3.3 Tide Station/River Stage Gage Event
 - 3.1.1.3.3.1 Station Name
 - 3.1.1.3.4 Length of Pipe Event
 - 3.1.1.3.4.1 Floating Pipe
 - 3.1.1.3.4.2 Submerged Pipe
 - 3.1.1.3.4.3 Shore Pipe
 - 3.1.1.3.5 Booster Pump Event
 - 3.1.1.3.5.1 Number of Booster Pumps
 - 3.1.1.3.6 Dredge Advance
 - 3.1.1.3.7 Outfall Information
 - 3.1.1.3.7.1 Discharge Location
 - 3.1.1.3.7.2 Discharge Horizontal Position

- 3.1.1.3.7.3 Discharge Outfall Heading
- 3.1.1.3.7.4 Discharge Pipe Elevation
- 3.1.1.3.8 Non-effective Work Event
 - 3.1.1.3.8.1 Non-effective Work Interval
 - 3.1.1.3.8.2 Dredge Function Code
 - 3.1.1.3.8.3 Additional Comments
- 3.2 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM SYSTEM REQUIREMENTS
 - 3.2.1 Option 1: Computer Requirements
 - 3.2.2 Software
 - 3.2.3 UPS
 - 3.2.4 Option 2: Direct Data Transmissions to the DQM Web Service
 - 3.2.5 Internet Access
 - 3.2.6 Data Routing Requirements
- 3.3 DREDGE MONITORING DATA
 - 3.3.1 General
 - 3.3.2 Data Measurement Frequency
 - 3.3.2.1 Work Event Messages
 - 3.3.2.2 State Event Messages
 - 3.3.3 Parameter Transmission to the Web Service
 - 3.3.4 Contractor Data Backup
- 3.4 PERFORMANCE REQUIREMENTS
- 3.5 LIST OF ITEMS PROVIDED BY THE CONTRACTOR

-- End of Section Table of Contents --

SECTION 35 20 23.33

NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM
PIPELINE HYDRAULIC DREDGE

PART 1 GENERAL

1.1 DESCRIPTION

The work under this contract requires use of the US Army Corps of Engineers (USACE) National Dredging Quality Management Program (DQM) to monitor the dredge's status at all times during the contract duration and manage data history.

This performance-based specification section identifies the minimum required output as well as the precision and instrumentation requirements. The requirements may be satisfied using equipment and technical procedures selected by the Contractor.

1.2 MEASUREMENT AND PAYMENT

No separate measurement or payment shall be made for the installation, operation, and maintenance of the DQM-certified system as specified herein for the duration of the dredging operations; all costs in connection therewith shall be considered a subsidiary obligation of the Contractor and shall be included in the contract unit price per hour for "Dredging", "Option Dredging I", "Option Dredging II", and "Option Dredging III" items on the bidding schedule.

1.3 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM CERTIFICATION

The Contractor shall have a current certification from the DQM Program for the cutter/suction head hydraulic dredge instrumentation system to be used under this contract. Standard Operating Procedures (SOP) and criteria for certification are presented on the DQM website at <https://dqm.usace.army.mil>.

1.4 DREDGE PLANT INSTRUMENTATION PLAN (DPIP)

The Contractor shall have a digital copy of the Dredge Plant Instrumentation Plan (DPIP) on file with the DQM Support Center. While working on site, the Contractor shall also maintain on the dredge a copy of the DPIP, which is easily accessible to Government personnel at all times. This document shall accurately describe the sensors used, the configuration of the system, how sensor data will be collected, how quality control on the data will be performed, and how the sensors/data-reporting equipment will be calibrated and repaired if it fails. A description of the computed dredge-specific data and how the sensor data will be transmitted to the DQM database shall also be included. Prior to the start of work, the Contractor shall submit to the DQM Support Center any addendum or modifications made to the plan subsequent to its original submission. Requirements and a template for the DPIP are available on the DQM website at <https://dqm.usace.army.mil>.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 REQUIREMENTS FOR REPORTED DATA

The Contractor shall provide, operate, and maintain all hardware and software to meet these specifications. The Contractor shall also be responsible for the replacement, repair, and calibration of the sensors and other necessary data acquisition equipment needed to supply the required data.

The procedure to complete a repair shall be documented and completed as soon as practical. If repair is not possible within two business days of any sensor failure, a plan and timeline to complete the repair shall be submitted. Upon completion of a repair, replacement, installation, modification, or calibration, the Contractor shall notify the Contracting Officer's Representative (COR). The COR may request recalibration of the sensors or other hardware components at any time during the contract as deemed necessary.

The Contractor shall keep a log of sensor repair, replacement, installation, modification, and calibration in the dredge's onboard copy of the DPIP. The log shall contain a three-year history of sensor maintenance, including the time of the sensor failures (and subsequent repairs), the time and results of sensor calibrations, the time of sensor replacements, and the time that backup sensor systems were initiated to provide the required data. It shall also contain the name of the person responsible for the sensor work.

Sensors installed shall be capable of collecting parameters within the specified accuracies and resolutions indicated in the following subparagraphs and transmit these parameters to the DQM database. All data shall be transmitted in JSON message bundles. Each bundle can contain multiple message types. Sensor data shall be transmitted as work event messages, and data which relates to the operational state of the dredge or its sensors shall be transmitted as state event messages. See paragraph entitled "Parameter Transmission to the Web Service".

3.1.1 Message Bundle Data

Every message bundle shall contain descriptive data that relates the message to a given dredge plant and date/time. The start of a message bundle shall be identified by the tag "DQM_data".

3.1.1.1 Messages

Messages contain operational data that populates the DQM database for a dredge plant. A message shall consist of an event type and its associated data (as defined in paragraph entitled "Dredge Events"), a date/time stamp indicating when the event occurred or started, and a comment providing clarification or metadata about the situation. There are multiple event types, but they all fall into one of two categories - work events and state events.

3.1.1.1.1 Message Time

In a work event message, message time is the date and time that the data is collected from the sensors; in a state event message, message time is the

date and time that the state event begins. The message time shall be reported to the nearest second and referenced to Coordinated Universal Time (UTC) time based on a 24-hour format (YYYY-MM-DD HH:MM:SS). In order to ensure accuracy and reliability, the time stamp shall be synchronized to UTC format from an accurate, unchangeable source (for example, a GPS National Marine Electronics Association [NMEA] datastring). Message time shall be identified by the tag "msg_time".

3.1.1.1.2 Comment

Comments concerning the work event or state event messages being transmitted provide descriptive information that relates to the data. An example of a comment for work event data is information about a sensor issue; an example of a comment for state event data is a description of operations. A comment shall be identified by the introductory tag "comment", and the comment shall consist of no more than 250 characters.

3.1.1.2 Dredge Events - Work Event

There are two types of dredge event messages - work event messages and state event messages. Work event messages contain data that are instantaneously collected or calculated from sensors and are logged as a series of events. Work events are triggered by a time interval change (as described in paragraph entitled "Work Event Messages"). All work event messages shall be initiated by the header tag "work_event".

Sensor values reported in a work event shall represent a weighted average with the highest and lowest values not included in the calculated average for the given interval. The averaging routine used shall be consistent across all event triggers. This information shall be documented in the DPIP sections that say "Calculations done external to the instrumentation".

3.1.1.2.1 Vertical Correction

The variation of the water level from the vertical datum for the river stage or tidal gage described in the state events shall be obtained using appropriate equipment to give the water level with an accuracy of +/- 0.1 ft. Vertical correction values above project datum described in the dredging specification shall be entered with a positive sign and those below with a negative sign. The tag for vertical correction shall be "vert_correction".

3.1.1.2.2 Cutter/Suction Head Location and Movement

The X, Y, and Z components of the cutter/suction head location shall be monitored. Additional calculations made from the observed values determine the rates of movement to track the progress of the dredge.

3.1.1.2.2.1 Cutter/Suction Head Horizontal Position

The forwardmost point of the cutter/suction head shall be obtained using a positioning system operating with a minimum accuracy level of 3-10 feet horizontal Circular Error Probable (CEP). It shall be reported as Latitude/Longitude WGS 84 in decimal degrees with West Longitude and South Latitude values reported as negative. Position values shall be identified by the tags "ch_latitude" and "ch_longitude".

3.1.1.2.2.2 Cutter/Suction Invert Depth

Cutter/suction invert depth is the depth of the invert of the suction mouth relative to the surface of the water. Instrumentation shall be capable of reporting to an accuracy of +/- 0.5 foot and a resolution to the nearest 0.1 foot with no tidal adjustments. Minimum accuracies are conditional to relatively calm water. The tag "ch_depth" shall be used to identify the cutter/suction head depth.

3.1.1.2.2.3 Cutter/Suction Head Heading

The cutter/suction head heading is the angle of the centerline of the cutter/suction head and dredge ladder measured relative to true north. All headings shall be provided using industry-standard equipment. The heading shall be accurate to within 5 degrees and reported to the nearest whole degree with values from 000 (true north) to 359 degrees referenced to a clockwise positive direction convention. The tag "ch_heading" shall be used to identify the cutter/suction head heading.

3.1.1.2.3 Dredge Activity

Dredge activity shall be monitored using a combination of the following parameters.

3.1.1.2.3.1 Slurry Velocity

A flow-metering device, calibrated according to the manufacturer's specifications, shall be used to record the slurry velocity to the nearest 0.01 fps with an accuracy of + 0.1 fps. If the manufacturer does not specify a frequency of recalibration, calibration shall be conducted prior to the commencement of work. The slurry velocity shall be measured for the same pipeline inside diameter as that used for the slurry density measurement. The tag "slurry_velocity" shall be associated with this value.

3.1.1.2.3.2 Slurry Density

A density-metering device, calibrated according to the manufacturer's specifications, shall be used to record the slurry density of material being moved to the nearest 0.01 g/cc. It is understood that the accuracy of this sensor can vary based on several factors, including the type of material, the magnitude of the cut, and the length of time since calibration. If the manufacturer does not specify a frequency of recalibration, calibration shall be conducted prior to the commencement of work. Continuous monitoring of this sensor ensures that drift and other factors inherent in the dredging process can be accounted for in monitoring dredge activity. The tag "slurry_density" shall be associated with this value.

3.1.1.2.3.3 Pump RPM

The pump rpm is the number of revolutions per minute measured for the slurry pump shaft. The shaft revolution rate (rev/min) shall be measured with the highest level of accuracy that is standard on the vessel's operational displays either at the bridge or in the engine room. This value shall be identified by the tag "rpm".

3.1.1.2.3.4 Pump Vacuum

The vacuum pressure of the dredge pump(s) (inches of mercury) shall be

measured as near to the eye as practicable in the pump's suction pipe with the highest level of accuracy that is standard on the vessel's operational displays either at the leverman's controls or in the engine room. Vacuum pressure shall be identified by the tag "vacuum".

3.1.1.2.3.5 Pump Outlet Pressure

The pump outlet pressure shall be measured in the discharge line on the pump side of the flap valve in terms of pounds per square inch (psi) on a gauge. Pump outlet pressure shall be identified by the tag "outlet_psi".

3.1.1.2.4 Outfall Information (Open Water/Spill Barge Disposal)

The X and Y position of the terminal end of the outfall pipe shall be monitored continuously and the position reported as part of the work event string.

3.1.1.2.4.1 Discharge Horizontal Position

The horizontal position of the outfall end of the discharge pipe shall be obtained using a positioning system operating with a minimum accuracy level of 3-10 feet horizontal Circular Error Probable (CEP). It shall be reported as Latitude/Longitude WGS 84 in decimal degrees with West Longitude and South Latitude values being reported as negative. Position values shall be identified by the tags "outfall_latitude" and "outfall_longitude".

3.1.1.3 Dredge Events - State Event

There are two types of dredge event messages - work event messages and state event messages. State event messages provide information about the current state of the dredge equipment or operations. They are created and sent only when a state changes. Since state events often cannot be collected in real time, state events are tagged with a date time stamp (referenced to Coordinated Universal Time [UTC]) that indicates when the state change happened relative to the work event message tag. This data is considered to be "true" until another state event tag of the same type is received. Each type of state event message shall be indicated by a specific header tag as enumerated in the following subparagraphs. State events can be transmitted along with work event message bundles directly by the contractor using the indicated format, or they can be entered on the "State" tab in the DQM-provided software. However, they should be sent only if the state value changes.

3.1.1.3.1 Message Time

The state event time is the date and time that the event starts. The leverman's time shall be entered to the nearest second as local time and automatically converted to and reported in UTC based on a 24-hour format (YYYY-MM-DD HH:MM:SS). Message time shall be identified by the tag "msg_time".

3.1.1.3.2 Contract Event

Information concerning the contract under which dredging is being performed shall be reported at the start and completion of each contract using the header tag "contract_event".

3.1.1.3.2.1 Contract Number

The USACE-assigned contract number for the project shall be reported using the tag "contract_number".

3.1.1.3.2.2 Contract Start and End

The start and end of a contract shall be reported using the tag "event_type" with the appropriate value of "start" or "end".

3.1.1.3.3 Tide Station/River Stage Gage Event

Properties associated with the vertical correction (see paragraph entitled "Vertical Correction") for the tide station/river stage gage shall be grouped together under the header tag "station_event". This information shall be sent at the start of the contract and each time the dredge has moved enough to change the station being used.

3.1.1.3.3.1 Station Name

The station name is a concise name defining the tide station/river stage gage begin referred to. It shall be introduced by the tag "station_name", and it shall consist of a descriptor of no more than 25 characters.

3.1.1.3.4 Length of Pipe Event

The leverman's estimate of the length of pipe downflow from the dredge pump, measured to the nearest whole foot, shall be reported under the header tag "pipe_length_event". This information shall be sent at the start of the contract and at the completion of each 24-hour period ending at midnight local time.

3.1.1.3.4.1 Floating Pipe

The total length of floating pipe shall be reported with the tag "length_floating".

3.1.1.3.4.2 Submerged Pipe

The total length of submerged pipe shall be reported with the tag "length_submerged".

3.1.1.3.4.3 Shore Pipe

The total length of shore pipe shall be reported with the tag "length_land".

3.1.1.3.5 Booster Pump Event

Information concerning the booster pumps being used shall be included under the header tag "booster_pump_event". A message shall be sent to indicate any change in the status of the booster pumps being used.

3.1.1.3.5.1 Number of Booster Pumps

Upon the addition or removal of a booster pump, the total number of booster pumps being used shall be reported with the tag "booster_total".

3.1.1.3.6 Dredge Advance

The dredge advance, the total forward progress of the dredge relative to the centerline of the cut, shall be measured to the nearest whole foot and cumulatively calculated over a 24-hour period from midnight to midnight local time. It shall be identified by the tag "advance_daily". The msg_time associated with this tag shall be reported as the first timestamp of the following 24-hour period (based on the local time) rather than as midnight of the day for which the value was calculated, and it shall be reported in Greenwich Mean Time (GMT).

3.1.1.3.7 Outfall Information

The X and Y position of the terminal end of the outfall pipe shall be monitored and sent at the start of the contract and thereafter according to the following table. Discharge Heading and Pipe Elevation may be omitted if the dredge is not discharging into an upland disposal site. For beach nourishment, the horizontal X and Y position of the outfall shall be sent at the start of the contract and at the completion of each 24-hour period ending at midnight local time.

Discharge Location	Horizontal Position	Discharge Pipe Elevation	Discharge Outfall Heading
Open Water	Continuous Work Event	N/A	N/A
Scow	Upon Change	N/A	N/A
Beach	Every 24 Hours	N/A	N/A
Upland	Upon Change	Upon Change	Upon Change

3.1.1.3.7.1 Discharge Location

Information on where the slurry is being discharged shall be reported with the tag "outfall_location". Acceptable values include "upland", "open water", "beach", and "scow".

3.1.1.3.7.2 Discharge Horizontal Position

The horizontal position of the outfall end of the discharge pipe shall be obtained using a positioning system operating with a minimum accuracy level of 3-10 feet horizontal Circular Error Probable (CEP). It shall be reported as Latitude/Longitude WGS 84 in decimal degrees with West Longitude and South Latitude values being reported as negative. Position values shall be identified by the tags "outfall_latitude" and "outfall_longitude".

3.1.1.3.7.3 Discharge Outfall Heading

The discharge outfall heading is the angle relative to true north measured from the centerline of the pipe in the direction of discharge. All headings shall be provided using industry-standard equipment. They shall be accurate to within 5 degrees and reported to the nearest whole degree with values from 000 (true north) to 359 degrees referenced to a clockwise positive direction convention. The discharge heading shall be identified by the tag "outfall_heading".

3.1.1.3.7.4 Discharge Pipe Elevation

The discharge pipe elevation is the height of the outfall measured in feet and tenths of a foot relative to the project datum. The required accuracy is contingent upon contract requirements. The tag "outfall_elevation" shall be used to identify this elevation.

3.1.1.3.8 Non-effective Work Event

Delays and dredge downtime shall be reported at the conclusion of the event. The reason for the non-effective work time shall be submitted under the header tag "non_eff_event" within 24 hours of the event.

3.1.1.3.8.1 Non-effective Work Interval

The start and end times for the non-effective work event shall be reported using the tags "msg_start_time" and "msg_end_time".

3.1.1.3.8.2 Dredge Function Code

The dredge operator indication of production delays, as listed on Form 4267, shall be transmitted at the end of the non-effective interval. Dredge function event messages shall be identified by the tag "function_code" and shall consist of one of the following standardized entries to indicate the operation:

AGV	Assisting Grounded Vessels
CCH	Change Cutterhead
CCSH	Clear Cutter Suction
CLPJ	Change Location Bar
COLL	Collision
CPPL	Clear Pump Pipeline
CPR	Change Impeller
DR	Dike Repair
FBD	Fire Boat Drills
HPL	Handling Pipe Line
HSL	Handling Swing Line
HSP	Handling Shore Pipe
LDNE	Loss Due to Natural Elements
LDPV	Loss Due to Passing Vessel
LNL	Transfer to New Location
MISC	Miscellaneous
MOB	Mobilization & Demobilization
MSC	Miscellaneous/Non-pay
OC	Out of Commission
OR	Operating Repairs
P	Preparation
PREP	Preparation & Making Up Tow
RPL	Repair Pipeline
SB	Sounding & Buoying
SBT	Stand-By Time as Directed
SH	Sundays-Holidays
TFS	Taking on Fuel & Supplies
TOW	Time on Tow
WAP	Waiting Attendant Plant

3.1.1.3.8.3 Additional Comments

The "comment" tag shall be used to provide additional explanation for the

noted delays or downtimes. For example, when the code "LDPV" (Loss Due to Passing Vessel) is indicated, the name of the vessel and the number of tows shall be listed with the "comment" tag.

3.2 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM SYSTEM REQUIREMENTS

The Contractor's DQM system shall be capable of collecting and transmitting data to the DQM system. The applicable parameters from paragraph entitled "Requirements for Reported Data" shall be recorded as events locally and continuously transmitted to the DQM database anytime an Internet connection is available.

To accomplish this transmission, there are two options. The first option is to equip the vessel with a DQM computer system consisting of a computer, monitor, keyboard, mouse, data modem, Universal Power Supply (UPS), and network hub. The required system is outlined in paragraphs 3.2.1 "Option 1: Computer Requirements" through 3.2.3 "UPS". The computer system shall be a standalone system, exclusive to the DQM monitoring system, and shall have USACE DQM software installed on it. If a hardware problem occurs, or if a part of the system is physically damaged, then the Contractor shall be responsible for repairing it within two business days of the determination of the condition or submitting a plan and timeline for repair if the repair will take more than two business days.

The second option is to send data directly to DQM's web endpoint as outlined in paragraph entitled "Option 2: Direct Data Transmissions to the DQM Web Service".

3.2.1 Option 1: Computer Requirements

The Contractor shall provide a dedicated onboard computer for use by the Dredging Quality Management system. This computer shall run the USACE DQM software and receive data from the Contractor's data-reporting interface. This computer must meet or exceed the following performance specifications:

CPU	Intel or AMD processor with a (non-overclocked) clock speed of at least 1.6 gigahertz (GHz)
Hard drive	250 gigabytes (GB); internal
RAM	4 gigabytes (GB)
Ethernet adapter	Internal network card with a RJ-45 connector
Ports	1 free serial ports with standard 9-pin connectors; 1 free USB port
Other hardware	Keyboard, mouse, monitor

The Contractor shall install a fully licensed copy of Windows 10 Professional Operating System or later on the computer specified above. The Contractor shall also install any necessary manufacturer-provided drivers for the installed hardware.

This computer shall be located and oriented to allow data entry and data viewing as well as to provide access to data ports for connection of external hardware.

3.2.2 Software

The DQM computer's primary function is to transmit data to the DQM shoreside database. No other software which conflicts with this function shall be installed on it. The DQM computer shall also have the USACE-provided Dredging Quality Management Onboard Software (DQMOBS) installed on it by DQM personnel.

3.2.3 UPS

The Contractor shall supply an Uninterruptible Power Supply (UPS) for the computer and networking equipment. It shall interface with the DQM computer to communicate UPS status, and it shall provide backup power at 1 kVA for a minimum of 10 minutes. The Contractor shall ensure that sufficient power outlets are available to run all specified equipment.

3.2.4 Option 2: Direct Data Transmissions to the DQM Web Service

A web service shall be used to report sensor data to the DQM database. Data shall be transmitted as it is collected in real time and pushed to the DQM web service. If the web service is not available or returns an error message, the data shall be stored in a queue and transmitted upon re-establishment of the connection, starting with the oldest data in the queue and continuing until real-time transmission is restored.

Contact dqm-support@usace.army.mil to obtain the web service URL and the appropriate key credentials and communication protocol.

If this option is chosen, a display of the raw data being transmitted to DQM must be easily accessible and visible onboard the dredge.

3.2.5 Internet Access

The Contractor shall maintain an Internet connection capable of transmitting real-time data to the DQM server as well as enough additional bandwidth to clear historically queued data when a connection is re-established. The telemetry system shall always be available and have connectivity in the contract area. If connectivity is lost, unsent data shall be queued and transmitted upon restoration of connectivity. Delays in pushing real-time data to the DQM database shall not exceed twenty-four hours. Delays in pushing real-time data to the DQM database should not exceed four hours. Exceptions to these requirements may be granted by the DQM Support Center on a case-by-case basis with consideration for contract-specific requirements, site-specific conditions, and extreme weather events.

The Contractor shall acquire and install all necessary hardware and software to make the Internet connection available for data transmission to the DQM web service. The hardware and software shall be configured to allow the DQM Support Center remote access to this computer, and the telemetry system shall be capable of meeting these minimum reporting requirements in all operating conditions.

In areas with poor cellular service and at the local District's discretion, it may be required to manually download the data on a daily basis using the protocol for retrieving and submitting backup files provided by the DQM Support Center. This method of data transmission should be used only if Internet connectivity is unavailable at the dredging site, and it should be considered a temporary measure.

3.2.6 Data Routing Requirements

Onboard sensors continually monitor dredge conditions, operations, and efficiency and route this information to the shipboard dredge-specific system (DSS) computer to assist in guiding dredge operations. Portions of this Contractor-collected information, as described in this specification, shall be routed to the DQM computer on a real-time basis, utilizing one of the options outlined in paragraphs 3.2.1 "Option 1: Computer Requirements" through 3.2.5 "Internet Access". If the serial transmission option is used, sensor data shall be sent to the DQM computer via an RS-232 serial interface with a baud rate of 9600 or 19200 bps. The serial interface shall be configured as 8 bits, no parity, and no flow control.

Information regarding changes in the state of the dredge shall be digitally logged and transmitted as close to the time of the occurrence as possible. These events can be included in a separate message bundle transmitted to DQM, entered on the "State" tab in the DQM Pipeline Software, or entered online in the DQM State Data Tool.

3.3 DREDGE MONITORING DATA

3.3.1 General

Onboard sensors continuously collect dredging data in support of the dredge Contractor's operations. Portions of this Contractor-collected information, as described in this specification, and calculations based on them shall be stored and transmitted to the DQM database on a near real-time basis. Additionally, information regarding the state of the dredge shall be digitally logged and transmitted.

3.3.2 Data Measurement Frequency

The frequency of data transmission is dependent on the type of message being sent. Work Event messages contain data that are instantaneously collected or calculated from sensors and are logged as a series of events. State event messages are activated by a change in the dredge state.

3.3.2.1 Work Event Messages

Data shall be logged as a series of events. Each event shall consist of a dataset containing dredge information (as defined in paragraph entitled "Requirements for Reported Data"). Each set of measurements (for example, time and position) shall be considered an event, and there shall be a 6-12 second interval between work events. This interval shall remain consistent across event types for the dredge plant.

A standard data string shall be recorded within one second of an event trigger with the time stamp and all parameters reflecting when the event happened.

3.3.2.2 State Event Messages

A set of descriptive information (event name, time, description, comment) shall be considered a state event. These events shall be recorded within 24 hours of a change in state with the time stamp reflecting when the event happened.

3.3.3 Parameter Transmission to the Web Service

The data shall be formatted as JSON (JavaScript Object Notation, as defined at <http://www.json.org>) strings of arbitrary length. These JSON strings represent a hierarchical data structure consisting of a message bundle which may contain 0-3 automatic data messages and any number of manual data messages.

A tag/parameter is reported only when it contains a value. No "Null" value strings shall be included in a message bundle.

```
*****
Message bundle
*****
```

```
{
  "DQM_Data": {
    "plant_identifier":      <integer value 0000-9999>,
    "transmission_time":    <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
    "messages": [
      {
        "work_event": {
          "msg_time":        <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
          "vert_correction": <floating point 100th decimal place>,
          "ch_latitude":     <decimal to 6 decimal places>,
          "ch_longitude":    <decimal to 6 decimal places>,
          "ch_depth":        <floating point 100th decimal place>,
          "ch_heading":      <integer value 000-359>,
          "slurry_velocity": <floating point 100th decimal place>,
          "slurry_density":  <floating point 100th decimal place>,
          "pump_rpm":        <integer>,
          "vacuum":           <floating point 100th decimal place>,
          "outlet_psi":       <floating point 100th decimal place>,
          "comment":         <string>},
        },
      {
        "contract_event": {
          "msg_time":        <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
          "contract_number": <string>,
          "event_type":      <string - "start" or "end">,
          "comment":         <string>
        },
      {
        "station_event": {
          "msg_time":        <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
          "station_name":    <string>,
          "comment":         <string>
        },
      {
        "pipe_length_event": {
          "msg_time":        <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
          "length_floating": <integer>,
          "length_submerged": <integer>,
          "length_land":     <integer>,
          "comment":         <string>
        }
      }
    ]
  }
}
```

```

    },
    {
      "booster_pump_event": {
        "msg_time":      <24-hour UTC time YYYY-MM-DDHH:MM:SS>,
        "booster_total": <integer>,
        "comment":       <string>
      }
    },
    {
      "advance_Event": {
        "msg_time":      <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
        "advance_daily": <integer>,
        "comment":       <string>
      }
    },
    {
      "outfall_position": {
        "msg_time":      <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
        "outfall_location": <string-"upland", "beach", "scow", "open
water">
        "outfall_latitude": <decimal to 6 decimal places>,
        "outfall_longitude": <decimal to 6 decimal places>,
        "outfall_heading": <integer value 000-359>,
        "outfall_elevation": <floating point 10th decimal place>,
        "comment":       <string>
      }
    },
    {
      "non_eff_event": {
        "msg_start_time": <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
        "msg_end_time":   <24-hour UTC time YYYY-MM-DD HH:MM:SS>,
        "function_code":  <string - 1 to 4 characters>,
        "comment":       <string>
      }
    }
  ]
}

```

3.3.4 Contractor Data Backup

The Contractor shall maintain an archive of all data sent to the DQM computer during the dredging contract. The COR may require, at no increase in the contract price, that the Contractor provide a copy of these data covering specified time periods. The data shall be provided in the same JSON format as would have been transmitted to the DQM computer. There shall be no line breaks between the parameters, and each record string shall be on separate line. The naming convention for the files shall be <dredgename>_<StartYYYYMMddhhmmss>_<EndYYYYMMddhhmmss>.txt.

Data submission shall be via a storage medium acceptable to the COR.

At the end of the dredging contract, the Contractor shall call the DQM Support Center prior to discarding the data. The DQM Support Center will verify that all data has been received and appropriately archived before giving the Contractor discard permission. The Contractor shall record the following information in a separate section at the end of the dredge's onboard copy of the DPIIP:

- Person who called the DQM Support Center
- Date of the call
- DQM representative who gave permission to discard the data

3.4 PERFORMANCE REQUIREMENTS

The Contractor's National Dredging Quality Management Program's data transmission shall be fully operational at the start of dredging operations. To meet contract requirements for operability, the Contractor's system shall provide an accurate data string return and be compliant with hardware requirements. Data string return is defined as the number of quality records within an event or state tag sent by the contractor's system to the DQM database. Quality data strings are considered to be those providing accurate values for all parameters reported when operating according to the specification. Repairs necessary to restore data return compliance shall be made within two business days, or a plan and timeline for repair shall be submitted to the DQM Data Acquisition and Analysis Team if the repair will take more than two business days. Failure by the Contractor to report quality data within the specified time window for dredge measurements as stated in the specifications (see paragraphs entitled "Internet Access", "Data Measurement Frequency" and "Parameter Transmission to the Web Service") will result in withholding of up to 10% of the contract progress payment per clause 52.232-5.

3.5 LIST OF ITEMS PROVIDED BY THE CONTRACTOR

DPIP	https://dqm.usace.army.mil
DQM System	Paragraph entitled "National Dredging Quality Management Program System Requirements"
Dredge Data	Paragraph entitled "Dredging Monitoring Data"

-- End of Section --