

REQUEST FOR QUOTATION (THIS IS NOT AN ORDER)		THIS RFQ ☒ IS ☐ IS NOT A SMALL BUSINESS SET-ASIDE		PAGE 1 OF 91 PAGES		
1. REQUEST NO. W912WJ26QA095	2. DATE ISSUED 07 MAY 2026	3. REQUISITION/PURCHASE REQUEST NO.	4. CERT. FOR NAT. DEF. UNDER BDSA REG. 2 AND/OR DMS REG. 1	RATING		
5a. ISSUED BY W2SD ENDIST NEW ENGLAND KO CONTRACTING DIVISION, 696 VIRGINIA ROAD CONCORD, MA 01742-2751 UNITED			6. DELIVER BY (Date)			
5b. FOR INFORMATION CALL (NO COLLECT CALLS)			7. DELIVERY			
NAME		TELEPHONE NUMBER		☐ FOB DESTINATION ☐ OTHER (See Schedule)		
ALICIA LACROSSE		AREA CODE	NUMBER	9. DESTINATION		
		978	318-8902	a. NAME OF CONSIGNEE		
8. TO:						
a. NAME		b. COMPANY		b. STREET ADDRESS		
c. STREET ADDRESS				c. CITY		
d. CITY		e. STATE	f. ZIP CODE	d. STATE	e. ZIP CODE	
10. PLEASE FURNISH QUOTATIONS TO THE ISSUING OFFICE IN BLOCK 5a ON OR BEFORE CLOSE OF BUSINESS (Date)		IMPORTANT: This is a request for information and quotations furnished are not offers. If you are unable to quote, please so indicate on this form and return it to the address in Block 5a. This request does not commit the Government to pay any costs incurred in the preparation of the submission of this quotation or to contract for supplies or service. Supplies are of domestic origin unless otherwise indicated by quoter. Any representations and/or certifications attached to this Request for Quotation must be completed by the quoter.				
26 MAY 2026						
11. SCHEDULE (Include applicable Federal, State and local taxes)						
ITEM NO. (a)	SUPPLIES/ SERVICES (b)		QUANTITY (c)	UNIT (d)	UNIT PRICE (e)	AMOUNT (f)
	SEE SCHEDULE					
12. DISCOUNT FOR PROMPT PAYMENT			a. 10 CALENDAR DAYS (%)	b. 20 CALENDAR DAYS (%)	c. 30 CALENDAR DAYS (%)	d. CALENDAR DAYS
						NUMBER PERCENTAGE
NOTE: Additional provisions and representations ☐ are ☒ are not attached.						
13. NAME AND ADDRESS OF QUOTER			14. SIGNATURE OF PERSON AUTHORIZED TO SIGN QUOTATION		15. DATE OF QUOTATION	
a. NAME OF QUOTER						
b. STREET ADDRESS			16. SIGNER			
c. COUNTY			a. NAME (Type or print)		b. TELEPHONE	
					AREA CODE	
d. CITY		e. STATE	f. ZIP CODE	c. TITLE (Type or print)		
				NUMBER		

Section B - Supplies or Services & Prices or Costs

Additional Information/Notes

Item	Supplies/Service	Quantity	Unit	Unit Price	Amount
0001	Contractor shall provide all labor, materials, equipment and transportation to provide HVAC System repairs to Buffumville Lake, Charlton, MA in accordance with the Statement of Work. North American Industry Classification System (NAICS): 238220 Pricing Arrangement: Firm Fixed Price	1	Job		

Section C - Description/Specifications/Statement of Work

INTERESTED VENDORS SHALL REVIEW SECTION L AND SECTION M OF THE SOLICITATION FOR INSTRUCTIONS AND EVALUATION CRITERIA. VENDORS ARE RESPONSIBLE FOR ENSURING THEIR QUOTE SUBMISSION MEETS ALL REQUIREMENTS. FAILURE TO DO SO MAY RESULT IN QUOTES BEING DEEMED NON-RESPONSIVE AND REMOVED FROM CONSIDERATION.

THE MANDATORY SOLICITATION SURVEY SHALL BE COMPLETED IN ITS ENTIRETY AND RETURNED WITH QUOTES. FAILURE TO DO SO MAY RESULT IN QUOTES BEING DEEMED NON-RESPONSIVE AND REMOVED FROM CONSIDERATION.

STATEMENT OF WORK:

HVAC SYSTEM REPAIRS

U.S. ARMY CORPS OF ENGINEERS

BUFFUMVILLE LAKE

CHARLTON, MA

STATEMENT OF WORK

A. General Description of the Work to be Performed

1. Location and Background of Project: The dam at Buffumville Lake lies across the Little River in Charlton, about eight miles northeast of Southbridge and 50 miles southwest of Boston. From Worcester, the dam can be reached by traveling south on U.S. Route 395 to exit 4B, then two miles on Charlton Street. Construction of Buffumville Lake started in September 1956 and was completed in June 1958.

2. Description of Work: The general description below is given to indicate the approximate scope of this project only. It does not limit the work required under the specifications.

The work of this project involves replacing aging HVAC systems and solving issues with thermal comfort. Both Fan coil units and condensing units shall be replaced with new heat pump systems, with ceiling hung electric unit heaters for auxiliary heat. New heat pump systems should be controlled via programmable thermostats. Air ventilation shall be provided to the building through a new energy recovery ventilator. All existing finned tube shall be cleaned. All existing and new heating hot water piping and domestic hot and cold-water piping shall be insulated. The existing radiant slab is not currently working, and the accessible components shall be removed with the existing under slab piping abandoned in place.

3. Time of Year Restrictions on Site Work: No restrictions.

4. Photographs: Attached at the end of this document are drawings with photographs taken at the project site during a recent site visit during 2025. The photographs are intended to show the approximate conditions existing at the site. Items shown are not generally shown in their entirety. The Government does not guarantee that the conditions shown in the photographs will exist at the time of the performance of the work, and the Contractor is advised to make his own investigation of existing conditions. (during the preconstruction site visit)

5. Site Visits and Requests for Information: No extra payment will be allowed for perceived additional work caused by unfamiliarity with site conditions and requirements. Scheduled site visits will be provided for all interested vendors, with a date and time to be listed in the solicitation. The Technical Point of Contact (TPOC) for this project is Park Manager Nicole Giles: (978) 318-8411 (Office line) or via email at Nicole.C.Giles@usace.army.mil.

6. Schedule: The period of performance shall be 180 days from Notice to Proceed. Work shall be performed Monday through Friday between the hours of 7:00 AM and 3:30 PM unless otherwise approved by the TPOC. Any proposed changes to an approved schedule must be submitted to the TPOC in writing and are not finalized until approved. No work shall be done on weekends or government holidays.

B. Measurement and Payment

The Payment item for the work of this contract for which contract job payments will be made is listed in the Bidding Schedule and is described below. The job price payment made for the item listed shall constitute full compensation for furnishing all labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and performing all work required for which separate payment is not otherwise provided. All costs for items of work which are not specifically mentioned to be included shall be included in this item.

a. Item Number 0001, "HVAC Repairs".

All costs for labor, equipment, and materials for all work required for the HVAC repairs, in accordance with the Statement of Work and the technical specifications.

C. General Project Requirements

1. Work Site. The site of the work is at the US Army Corps of Engineers New England District Facility at Buffumville Lake, in Charlton, Massachusetts. All rules and regulations of the facility covering general safety, security, sanitary requirements, pollution control and traffic regulations shall be observed by the Contractor. Information regarding these requirements may be obtained by contacting the Technical Point of Contact (TPOC), who will provide such information.

2. Security. The Contractor shall report any vandalism, suspicious activities or devices to the TPOC or local police as soon as possible. The TPOC will notify the Contractor of any heightened security measures and will expect vigilant monitoring of equipment, grounds and security fencing

while working. At a heightened security posture, there may be work areas that are restricted. The TPOC will notify the Contractor of these restricted areas, and work may be delayed or restricted or will be performed in these areas under the direct supervision of U.S. Army Corps of Engineers personnel.

At the close of each workday, Government facilities, equipment, and materials shall be secured. The Contractor shall be responsible for maintaining a secure construction site and ensure the area of the scope of this contract is secure at all times during and after work hours.

All project work and conduct of construction activity shall comply with security requirements, regulations, and policies as directed by the TPOC.

No alcoholic beverages or drugs are allowed on the project site. If found in violation the violator shall be requested to leave the premises immediately.

3. Identification of Equipment and Tools. Affix to Contractor or Subcontractor-owned machinery, motor vehicles, equipment, and tools, clearly legible identification showing the Contractor's or Subcontractor's name, and where space permits, address and telephone number, so as to distinguish them from Government-owned items and can be returned to the rightful owner if inadvertently left on Government property.

4. Contractor's Responsibility. The Contractor shall furnish all labor, equipment and materials and carry out all operations as necessary to accomplish the work of this project as described in this document and on the contract drawings.

5. Commencement, Prosecution and Completion of Work. The Contractor shall employ ample personnel and sufficient equipment to accomplish the work of this project within the prosecution period specified in the SPECIAL CONTRACT REQUIREMENTS, Subpart COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (APR 1984) FAR 52.211-10. Restrictions concerning the prosecution and completion of work are as follows:

a. The Contractor shall attend a Preconstruction Conference within 14 days after the Notice to Proceed prior to the start of on-site construction work (see paragraph entitled "Preconstruction Conference", below).

b. The on-site work is restricted to 0700 (7:00 AM) to 1530 (3:30 PM), Monday through Friday. See Paragraph B.12 "Hours of Operation" for additional information.

6. Superintendence by the Contractor. At all times during the performance of the contract and until the work is completed and accepted, the Contractor shall directly superintend the work or assign and have on the worksite a competent project superintendent who has the authority to act for the Contractor.

The qualified superintendent, and competent alternate, shall be capable of reading, writing, and conversing fluently in the English language.

The project superintendent must have a minimum of five years' experience in construction with at least two of those years as a superintendent on projects similar in scope, size, and complexity. The individual must be familiar with the requirements of EM 385-1-1 and have experience in the areas of hazard identification and safety compliance. The individual must be capable of interpreting a critical path schedule and construction drawings. The qualification requirements for the alternate superintendent are the same as for the project superintendent. The TPOC may request proof of the superintendent's qualifications at any point in the project if the performance of the superintendent is in question. The superintendent may have duties as CQC Manager and/or SSHO but must meet the specified requirements for those positions.

The project superintendent is primarily responsible for managing and coordinating day-to-day production and schedule adherence on the project. The superintendent is required to attend quality control meetings.

The project superintendent shall always maintain a physical presence at the site when work is in progress and be responsible for all construction and related activities at the site. Failure to comply with these requirements shall be deemed as cause for a non-compensatory stoppage and suspension of work until the deficiency is remedied.

7. Contractor Personnel Conduct. The Contractor personnel's conduct shall not reflect discredit upon the Government. The Contractor shall ensure that personnel present a professional appearance. Contractor's employees shall observe and comply with all local policies and procedures concerning fire, safety, environmental protection, sanitation, security, and possession of firearms or other lethal or illegal weapons or substances. The Contractor is responsible for ensuring that any Contractor employees providing services under this contract conduct themselves and perform services in a professional, safe, and responsible manner. The Contractor shall remove from the job site any employee for reasons of misconduct or security. The Contractor shall ensure no Contractor employees conduct political related activities or events on Government Property.

8. Traffic Regulation and Control. During construction the Contractor shall provide access as necessary to maintain traffic and to provide vehicle access to all residential and commercial structures in the project area.

9. Access to the Project Site. Access to the project site is currently available for construction. The Contractor shall be responsible for providing and maintaining access necessary for his equipment to and from the work site.

10. Construction Site Plan. Prior to the start of work, the Contractor shall submit a site plan showing the locations and dimensions of temporary facilities including layouts and details, equipment and material storage areas, access and haul routes, avenues of ingress/egress to fenced areas (e.g., the assigned storage and staging area), details of the fence installation (if used), and the number of trailers to be used. Identify any areas which may have to be graveled to prevent the tracking of mud. Indicate if the use of a supplemental or other staging area is desired. Show locations of safety and construction fences, site trailers, construction entrances, trash

dumpsters, temporary sanitary facilities, and worker parking areas, as appropriate. The plan shall also show where temporary utility hook-ups are to be located, if required, and how grounding of equipment and trailers will be achieved, as appropriate. The storage and staging area will be discussed at the Preconstruction Conference. Any items removed from the property shall be recycled to the furthest extent possible.

11. Hours of Operation. On-site work hours are as stated in Part B.5.b, above. The Contractor will not be permitted to perform on-site work on Saturdays, Sundays, or legal holidays, unless otherwise authorized by the TPOC. The exclusion of work on Saturdays, Sundays, and legal holidays has been considered in computing the performance time of this contract. The following legal holidays are observed:

January 1st

Third Monday in January

Third Monday in February

Last Monday of May

June 19th

July 4th

1st Monday of September

2nd Monday of October

11th of November

Fourth Thursday of November

25th of December

When one of the above designated legal holidays falls on a Sunday, the following Monday will be observed as a legal holiday. When a legal holiday falls on a Saturday, the preceding Friday is observed as a holiday.

Work outside the hours of operation requires TPOC approval. The request to work outside the hours of operation shall be made in writing to the TPOC 10 calendar days prior to such work to allow arrangements to be made by the Government. The request application shall include specific dates, hours, location, type of work to be performed, contract number and project title, and names of all individuals who will be working outside the hours of operations. If work is performed during periods of darkness, the different parts of the work shall be lighted in a manner approved by the TPOC.

12. Initial Progress Schedule. The initial project schedule shall be in the form of a chart graphically indicating the sequence proposed to accomplish each work feature or operation. The chart shall be prepared to show the starting and completion dates of all work features on a linear horizontal time scale beginning with date of Notice to Proceed and indicating calendar days to completion. The Contractor shall indicate on the chart the important work features or operations that are critical to the timely overall completion of the project. Key dates for such important work features and portions of work features are milestone dates and should be so indicated on the chart. This schedule will be the medium through which the timeliness of the Contractor's construction effort is appraised. Anticipated adverse weather delay days shall be included in the schedule.

13. Periodic Schedule Updates. An updated schedule showing actual progress shall be submitted monthly and with each pay request. Changes to the base-line schedule shall be outlined in a narrative describing the reason for the change.

14. Weekly Progress Meetings. Conduct a weekly meeting with the Government (or as otherwise mutually agreed to) for the purpose of jointly reviewing the actual progress of the project as compared to the as planned progress, and to review planned activities for the upcoming two weeks. Use the current

approved schedule update for the purposes of this meeting and for the production and review of reports. At the weekly progress meeting, address the status of RFIs, RFPs and Submittals.

15. Rate of Progress. Should the Contractor fail to maintain a satisfactory rate of progress in accordance with the Contractor's approved progress schedule, the TPOC may require additional personnel and equipment be placed on the work and that weekend and overtime work be performed, in order that the work be brought up to schedule and maintained at no additional cost to the Government.

16. Preconstruction Conference. The TPOC will conduct a Preconstruction Conference after receipt of Notice to Proceed by the Contractor and prior to the start of on-site construction activities. The date, time, and place for this conference shall be mutually agreed upon by the Contractor and the TPOC. It is mandatory that the Contractor's project site supervisory personnel assigned to this project attend the conference; no personnel substitutions will be permitted. The purpose of the conference is to review contract requirements and to establish a working relationship between the Contractor's staff and the U.S. Army Corps of Engineers personnel who will be closely associated with the project. During the conference, the TPOC will inform the Contractor concerning job safety, project phasing, work hour restrictions, traffic control, quality control, labor relations, and environmental protection. The Preconstruction Conference will be arranged by the TPOC.

17. Material Substitutions. This contract is based on the materials and methods as shown on the contract drawings and as described in this document. The Contractor shall not substitute materials or methods unless such substitution has been specifically approved in writing by the TPOC.

18. Quality Assurance. All items of work not addressed in the contract documents shall be completed in strict accordance with the manufacturers' specifications.

The Government is not obligated to inspect the Contractor's work, or to protect the Contractor from the consequences of its work. Government inspections are a general examination of the Contractor's conduct and workmanship and are solely for the purpose of the Government. Government-designated Quality Assurance Representatives (QARs) do not have the authority to accept work, nor is a Government inspection to be construed as conclusive.

Government agents including QARs and project engineers are not authorized to change the contract without the written approval of the TPOC; this lack of authority extends to all situations in which the action of these agents could be construed as constituting a change.

The quality of workmanship is subject to audit by Government or Government-designated QARs at any time during the contract. The Contractor shall cooperate fully and provide all information necessary for this audit.

The Contractor shall submit all requests for changes in writing to the TPOC. Do not proceed with changes without possession of written authorization of the TPOC.

The Contractor shall not conceal any work unless the TPOC has approved all items of work which are to be concealed. The Contractor shall notify the TPOC of its intention to conceal work at least 24 hours in advance of concealment.

19. Utility Outages and Interruptions. Make utility outages and interruptions, if required, during hours that will cause least impact to daily operations. Coordinate all utility outages and interruptions, and utility cutovers with the TPOC.

Where applicable, Utility Outage/Interruption Requests and Utility Cutover Requests shall be submitted in writing at least 5 calendar days in advance of the date desired for outages, interruptions, and cutovers; include at least one alternate date. Services shall not be interrupted or cutover until permission of the requested hours and dates is received from the TPOC. The request (s) shall include the following information: Location(s) of outages and interruption(s), hours and dates of interruption(s), and which facilities, utilities and services are affected. The Contractor is cautioned that outages and/or interruptions may not be granted on the date(s) requested.

Interruptions shall be defined as any Contractor operation that interferes with services such as, but not limited to, building systems, heating and cooling equipment, electrical service, medical equipment, water, sanitary sewer, fire alarms, telephone service and data, interior and exterior lighting, generators, or roads.

Ensure that new utility lines are complete, except for the final connection or cutover before interrupting existing utility service(s).

The Contractor shall not be entitled to additional or overtime payment for utility outages, interruptions, and connections required to be performed outside the regular work hours.

20. Utilities. The Government will furnish water and electricity from existing points of supply on the facility. The Contractor shall make his own investigations as to the location and suitability of these supplies for use on this project. Water and electricity required in the prosecution of the work in excess of that available from existing points of supply shall be furnished by the Contractor at his own expense. The Contractor shall conserve Government furnished water and electricity.

21. Temporary Electrical Equipment and Connections. The Contractor, at his own expense and in a workmanlike manner satisfactory to the TPOC, shall install and maintain all necessary temporary connections and distribution lines. All required temporary electrical equipment and lines shall be furnished, installed, connected, and maintained by the Contractor according to EM 385-1-1, NFPA 241 and NFPA 70, Article 305-6(b), "Assured Equipment Grounding Conductor Program". All temporary equipment and lines shall be removed prior to final acceptance of the work. Materials and equipment need not be new but must be in good repair and serviceable condition. Periodic inspections of systems and devices will be made by the Contractor at intervals not to exceed one week.

22. Location of Underground Facilities. Should excavation of any sort become necessary, obtain necessary digging permits prior to the start of excavation. Verify the elevations of existing piping, utilities, or any type of underground obstruction in locations to be impacted by the work. For excavation work, call "Dig Safe" at 811 or 1-888-DIGSAFE or visit www.digsafe.com. Notification shall not be earlier than 30 days prior, or later than 3 days prior, to the planned excavation.

23. Environmental Protection. The Contractor shall minimize environmental pollution and damage that may occur as the result of construction operations. The environmental resources within the project boundaries and those affected outside the limits of permanent work shall be protected during the entire duration of this contract. Comply with all applicable environmental Federal, State, and local laws and regulations. Any delays resulting from failure to comply with environmental laws and regulations will be the Contractor's responsibility.

a. Environmental Protection Plan: Prior to commencing construction activities or delivery of materials and equipment to the site, the Contractor shall submit an Environmental Protection Plan for review and approval by the TPOC. The purpose of the Environmental Protection Plan is to present a comprehensive overview of known or potential environmental issues which the Contractor must address during construction. Issues of concern shall be defined within the Environmental Protection Plan. The Contractor shall address each topic at a level of detail commensurate with the environmental issue and required construction task(s). The Environmental Protection Plan shall be current and maintained onsite by the Contractor.

24. Waste Management. The Contractor shall provide on-site containers for the collection of demolition debris, waste materials, construction debris, and rubbish. The Contractor shall clean the project site on a daily basis to prevent the accumulation of waste materials and rubbish resulting from construction activities. The Contractor shall transport all solid waste off the project site and dispose of it in compliance with Federal, State and local requirements for solid waste disposal.

Upon completion of the construction work, the project site shall be returned to its pre-work condition. No waste shall enter the stream from work. Any accidental discharge shall be fully mitigated at Contractor's expense and no additional cost to the project.

25. Drawings. Drawings showing the work required by this contract are included with this document.

26. Damages. The Contractor shall exercise caution and follow sound construction practices in the conduct of the work to avoid construction-related damage to existing features to remain.

27. Sequence of Work. The work shall be performed in the following sequence: existing conditions verification, preparation of submittals, material procurement, establish site safety, construct new work, and project close out. Coordinate this sequence with the requirements of Paragraph 13, "Progress Schedule".

28. Contractor's Receipt of Supplies. The Contractor shall be responsible for all arrangements for the receipt of materials and supplies at the job site. Government personnel are not permitted to receive or sign for items delivered to the site.

29. Storage Area. An area for storage and staging storage and staging area is available for use by the Contractor for work, storage of equipment, materials and trailers during the life of this contract. This area is shown in the contract drawings. The storage area is in the general vicinity of the work area within the limits of the Buffumville Lake facility and will be discussed at the Preconstruction Conference. The Contractor shall confine his storage area to the limits as designated or approved by the TPOC and shall be responsible for the security of the area. Upon completion of the contract, the Contractor shall remove all equipment and materials, except as otherwise specified, and restore the site to its original condition as approved by the TPOC at no additional cost to the Government.

Trailers, equipment, or materials must not be open to public view with the exception of those items which are in support of ongoing work on any given day. Do not stockpile materials outside the storage area in preparation for the next day's work. Park mobile equipment, such as tractors, wheeled lifting equipment, cranes, trucks, and like equipment within the storage area at the end of each workday.

The Contractor may construct a temporary six-foot-high galvanized chain link fence around trailers and materials at the storage/staging area if desired. Galvanized chain-link fence shall have a minimum height of six feet. The fence posts shall be placed in concrete or metal bases on the ground. Fence posts shall not be driven. Except for equipment and materials which are in support of ongoing work on any given day or unless such equipment or materials are assigned a separate and distinct storage area by the TPOC away from the vicinity of the construction site but within the project site boundaries, equipment and materials shall be stored and placed inside the temporary chain-link fencing, if used.

Trailers, if utilized by the Contractor for administrative or material storage purposes, shall present a clean and neat exterior appearance and shall be in a state of good repair. Trailers which, in the

opinion of the TPOC, require exterior painting or maintenance will not be allowed on the project site.

The temporary six-foot-high chain link fence, if used, shall be kept in a state of good repair and proper alignment. Should the Contractor elect to traverse, with construction equipment or other vehicles, grassed or unpaved areas which are not established roadways, such areas shall be covered with a layer of gravel as necessary to prevent rutting and the tracking of mud onto paved or established roadways; gravel gradation shall be at the Contractor's discretion. Grass located within the boundaries of the construction site shall be mowed for the duration of the project. Grass and vegetation along fences, buildings, under trailers, and in areas not accessible to mowers shall be edged or trimmed neatly.

30. Restoration of Storage Area and Other Areas. Upon completion of the project remove barricades, temporary utilities, sanitation facilities, construction vehicles, materials and equipment, temporary chain-link fencing if used, and any other temporary equipment, materials, or products from within and around the work areas and temporary storage areas and all other impacted areas. Clean and repair damage caused by installation or removal of temporary materials, equipment, or utilities. Areas used by the Contractor for the storage of equipment or material, or other use, shall be restored to the original or better condition, including pavement repair, or topsoil and seeding as necessary.

31. Contractor Use of Premises. Work shall be restricted to the project office, and related adjacent areas as needed to complete the work, access routes to the work site, and to storage areas assigned to this Contractor. Access to the project site is currently available for construction traffic. The Contractor shall be responsible for providing and maintaining access necessary for his equipment and plant to and from the work site.

32. Protection and Security of Property and Personnel: Protection to Contractor personnel or their equipment cannot be provided by the Government at the worksite nor at the travel routes to/from the worksite.

The Contractor shall protect all workmen, civilian and Government personnel and the general public from injury. The Contractor shall coordinate and schedule all work with the TPOC.

The Contractor shall conduct all work so as to cause the least interference possible with the normal activities of the Buffumville Lake facility and the surrounding areas.

33. Subcontractors and Personnel Contacts. Furnish a list of contact personnel of the Contractor and subcontractors including addresses and telephone numbers. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

34. Work Limits. Work shall be restricted to the immediate area of the HVAC repair work, in addition to storage areas assigned to this Contractor. Travel through any other parts of the installation or into any other buildings by Contractor personnel will not be permitted unless under escort by a Government employee.

35. Damaged Property. Work shall proceed in a manner which will minimize disturbance or risk of damage to surrounding structures, interior finishes, personal belongings, equipment, or infrastructure. The Contractor shall repair such items damaged by the Contractor in the course of carrying out the work at no additional cost to the Government. All repairs shall match adjacent similar existing items in all aspects. All replacements will be in kind.

36. Emergency Contacts. The Contractor shall have competent personnel trained and capable of dealing with minor personnel injuries. Contractor personnel shall immediately notify their supervisor of any accident requiring emergency medical treatment. The Contractor shall, in turn, notify the TPOC as required by EM 385-1-1.

Emergency medical treatment and services for Contractor personnel is the responsibility of the Contractor.

The Contractor shall prepare and submit a list of emergency contacts to be used in the event of an emergency. The list shall include the contact names, addresses, and telephone numbers. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

37. Cleaning Up. The Contractor shall, at all times, keep the premises free from accumulation of waste materials or rubbish caused by work under this contract. At the end of each workday and upon the completion of all work, the Contractor shall leave interior and exterior property in the condition in which it was found just prior to start of work.

38. No Smoking Policy. Smoking is prohibited within and outside of all buildings of the Buffumville Lake site, except in designated smoking areas. Discarding tobacco materials other than into designated tobacco receptacles is considered littering and is subject to fines. The TPOC will identify designated smoking areas.

39. Snow Removal. The Contractor shall be responsible for snow removal in their assigned exterior storage area(s).

40. Sanitary Facilities. In accordance with EM 385-1-1, provide, maintain, and make available to all workers provisions for sanitation. Maintain these provisions at all times without nuisance. Upon completion of the work, all sanitary provisions and facilities shall be removed from the premises by the Contractor, leaving the premises clean and free from nuisance.

In accordance with EM 385-1-1, The Contractor shall provide, maintain, and make available to all workers an adequate supply of potable water for both drinking and personal cleansing. During hot weather, the Contractor shall provide cool drinking water.

In accordance with EM 385-1-1, provide, maintain, and make available to all workers adequate minimum field-type portable toilets. Portable toilets shall be properly secluded from public observation in such a manner as required or approved by the TPOC. Periodically empty wastes into a municipal, district, station sanitary sewage system, or a commercial facility. Include provisions for pest control and elimination of odors. Any penalties and/or fines associated with

improper discharge of wastewater shall be the responsibility of the Contractor. Government toilet facilities will not be provided.

41. Sustainability. In accordance with the provisions of the various technical specifications, and as otherwise appropriate to the work, all reasonable efforts shall be made to use recycled, recovered and biobased materials in the execution of this work. Deliverables shall be printed double-sided on paper that contains post-consumer fiber content. To the extent feasible, materials with recycled content per EPA-Designated Recovered Materials Requirements as described at <https://www.epa.gov/smm/comprehensive-procurement-guidelines-construction-products> shall be used. Also the Contractor shall meet the USDA-Designated Bio-preferred Program requirements at <https://biopreferred.gov/BioPreferred/faces/pages/ProductCategories.xhtml> as feasible.

42. Preparation of As-Built and Record Drawings: Maintain at the jobsite one set of full-size contract drawings marked to show all deviations which have been made from the contract drawings, including buried or concealed construction and utility features revealed during the course of construction. Record the horizontal and vertical location of all buried utilities that differ from the contract drawings. Upon completion of the work, submit the original marked set of prints to the TPOC for approval. In the event there are no changes to the drawings, the Contractor shall submit a clean copy of the design documents stamped "RECORD DRAWINGS" to the TPOC.

The entries shall be made in the jobsite set of prints at the time field changes are made, pertinent information collected, or need for corrections established, as a continuing process during the life of the contract. As revised drawings are issued by the TPOC, revised prints shall be introduced into the set to replace the superseded drawings and all applicable notations previously made on the superseded drawings transferred to the current prints. Carefully prepared sketches, not less than 8-1/2 inch by 11 inches, may be used to depict changes or added information in lieu of notations on the actual prints. Staple sketches to the prints affected by the change. All plan views, sections, elevations, profiles, diagrams, details, or schedules affected by a change shall be marked up as required to reflect the change. All notations or changes made to the prints shall be in sufficient detail to clearly depict the change. Colored pens or pencils shall be used to make notations on the record prints as follows:

Red pen or pencil shall be employed to indicate added or corrected work or information.

Green pen or pencil shall be used to show the deleted or incorrectly depicted work or information.

Blue or black pen or pencil shall be used to show information not to be recorded on the drawings but included on the marked-up prints for explanatory or clarification purposes for the benefit of the TPOC.

D. Safety

1. Accident Prevention Plan: The Contractor shall prepare an Accident Prevention Plan (APP) specific to the activities being performed. It shall include an Activity Hazard Analysis (AHA) as described in 2 below. All work shall be conducted in accordance with the APP, the U.S. Army Corps of Engineers Safety and Health requirements Manual (EM 385-1-1, most recent edition),

and all applicable Federal, State, and local safety and health requirements. A copy of EM 385-1-1 can be accessed electronically at Headquarters USACE website under publications using the following link:

https://www.publications.usace.army.mil/Portals/76/Eng_Form_6293_Aug%202024%20-%20FINAL.pdf

The APP shall detail how safety and health will be managed during the project. The APP shall address the requirements of applicable Federal, State, and local safety and health laws, rules, and regulations. The Contractor shall comply with Federal Acquisition Regulation Clause No. 52.236-13 for Accident Prevention, which is added by reference. Special attention shall focus on the requirements of EM 385-1-1, specifically Chapter 2. The APP shall be developed by a Competent Person using mandatory ENG Form 6293. The contractor shall be responsible for documenting the Competent Person's credentials. Work shall not proceed until the APP has been reviewed by the TPOC and deemed acceptable for use on the project.

The APP shall interface with the Contractor's overall safety and health program. Any portions of the Contractor's overall safety and health program referenced in the APP shall be included in the applicable APP element and made site-specific. The Government considers the Prime Contractor to be the "controlling authority" for safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the contract, the penalties for noncompliance, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out.

The contractor shall provide on-going evaluations of the APP throughout the life of the project. Changes to the accepted APP must be made with the knowledge and concurrence of the TPOC. For projects that exceed 12 months in duration, the APP shall be reviewed annually with a signed copy submitted to the TPOC.

2. APP Appendices:

a. Activity Hazard Analysis. An Activity Hazard Analysis (AHA) shall be submitted for each major phase of work. A major phase of work is defined as an operation involving a type of work presenting hazards not experienced in previous operations or where a new subcontractor or work crew is to perform the work. The AHA shall be developed in accordance with EM 385-1-1, Chapter 2, Section 2-6. Work shall not proceed on a phase of work until the AHA has been accepted by the TPOC. A preparatory meeting shall be conducted by the contractor to discuss the AHA contents with all engaged in the activity. The preparatory meeting shall be conducted by the prime contractor and shall include all subcontractors and Government on-site representatives. The AHA shall be continuously reviewed and revised to address changing site conditions or operations as appropriate.

b. Fall Prevention Plan. The Contractor's Fall Competent Person shall develop and submit a site-specific Fall Prevention Plan outlining the methods, procedures, and systems to be implemented to eliminate or control new or existing fall hazards. Written Fall Protection Procedures and Rescue

Plan shall adhere to EM 385-1-1, Chapter 21 and ANSI Z359.2. These requirements are applicable to all contractor personnel when employees are working at heights or are exposed to fall hazards and/or using fall protection equipment. Workers exposed to fall hazards shall be protected from falling to a lower level by the use of standard guardrails, work platforms, temporary floors, safety nets, engineered fall protection systems, personal fall arrest systems, or the equivalent, where a fall hazard exists.

c. Hazardous Energy Control Program. The contractor shall prepare a Hazardous Energy Control Program (HECP) in accordance with EM 385-1-1 Chapter 12, 29 CFR 1910.147, ANSI Z244.1, and ANSI A10.44.

3. Site Safety and Health Officer (SSHO): The Contractor shall designate one individual as the Level Two SSHO who shall have the qualifications detailed in EM 385-1-1, Chapter 2, Section 2-3b:

Level Two SSHO: A designated employee with Level Two SSHO responsibility that meets and follows the requirements of EM 385-1-1. Level Two SSHOs cannot be assigned to projects that have a residual Risk Assessment Code (RAC) of high or extremely high.

All SSHOs will be designated on Form 6282, provided by the TPOC prior to initiating work or can be accessed electronically using the following link:

https://www.publications.usace.army.mil/Portals/76/Eng_Form_6282_2023Aug28.pdf

4. Safety Reporting:

a. Safety Briefing and Equipment Inspection Documentation. The Contractor shall conduct a safety meeting at the project site on the first day of work, whenever a new activity or phase of work begins, or at least weekly during the progress of work. All safety meetings shall be documented. A copy of a suggested weekly safety meeting form will be provided by the TPOC's Representative. Records of the safety briefings shall be submitted to the TPOC weekly.

b. Incident Reporting. All work-related incidents, including injuries, illnesses, near misses, and property related accidents (excluding on the road- vehicle accidents), shall be immediately reported to the TPOC and documented appropriately. All incidents shall be investigated to identify all root causes and recommended hazard control measures.

ENG Form 3394 shall be completed for all OSHA recordable injuries or illnesses and property damage accidents, for which property damage exceeds \$5,000.00 and submitted to the TPOC within seven (7) business days. A Lessons Learned Document shall also be submitted separately within seven (7) business days of the incident.

c. Exposure Hour Reporting. The Contractor shall complete the attached "USACE Contractor Monthly Summary Record of Injuries/Illness and Work Hour Exposure" (for prime and its

subcontractors) and forward the completed form to the TPOC no later than close of business on the 5th calendar day of the following month. The method of transmission by the prime contractor to the TPOC shall be electronically.

E. General and Administrative Submittals Required

1. Items for Submission. The Contractor shall submit the items identified below for approval to the TPOC. Government acceptance, as defined in EM 385-1-1, is required for safety related submittals (identified below with an "S" after the submittal name). The Contractor shall submit an electronic PDF copy of each submittal item (unless otherwise indicated) using a completed ENG FORM 4025-R cover sheet (a blank copy of this form is attached at the end of these specifications). The Contractor will be informed at the Preconstruction Conference to send all submittals to the TPOC.

2. Preconstruction Submittals. The following submittals shall be made by the Contractor and review action completed by the TPOC prior to the commencement of work at the site.

Construction Site Plan: Prior to the start of work, the Contractor shall submit a site plan showing the locations and dimensions of temporary facilities.

Initial Progress Schedule: In accordance with the contract clauses, the Contractor shall, within 30 calendar days after receipt of Notice to Proceed (NTP), or as otherwise determined by the TPOC, submit for approval a practicable Initial Project Schedule.

Emergency Contact List.

Accident Prevention Plan (APP) (S): The Contractor shall prepare an Accident Prevention Plan (APP) specific to the activities being performed. It shall include an Activity Hazard Analysis (AHA) for each major phase of work, and all appropriate appendices as per Paragraph D.2 of this document.

SSHO Qualifications (S): Documentation of SSHO qualifications shall be submitted for approval.

3. Other Submittals: The following submittals shall be made by the Contractor to allow sufficient time for review action to be taken by the TPOC and to comply with the approved Project Schedule, as appropriate.

Request to Work Outside Hours of Operations: The Contractor shall submit a written request, subject to approval by the TPOC, when work is to be performed outside the normal hours of operations as described in this document.

Periodic Project Schedule Updates: Monthly, and when payment is requested, or when changes are authorized that result in contract time extensions, the Contractor shall submit a revised project schedule for approval by the TPOC.

Utility Outage/Interruption Requests.

Utility Cutover Requests.

As Built/Record Drawings.

4. Approved Submittals. The TPOC's approval of submittals shall not be construed as a complete check but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Quality Control requirements of this contract is responsible for the satisfactory construction of all work. The Government reserves 21 calendar days for review and approval action on all submittals from the time of receipt of the submittal by the Government. After submittals have been approved by the TPOC, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

5. Disapproved Submittals. The Contractor shall make all corrections required by the TPOC and promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice shall be given promptly to the TPOC.

F. Technical Submittals Required

Submittals addressing the technical requirements of this project are listed in this paragraph. The Contractor shall follow the procedures outlined in Part E "General and Administrative Submittals Required", above, when making technical submittals. All submittals listed below are for Government approval. Submittals are grouped by technical discipline and sub-discipline (mechanical or electrical) and description of type (SD-xx) of submittal.

MECHANICAL SUBMITTALS:

23 05 93 Testing, Adjusting, and Balancing:

SD-03 Product Data

i. Equipment and performance data

SD-06 Test Reports:

i. TAB execution

ii. Calibration and TAB Verification

iii. TAB report

iv. DALT report

23 07 00 Thermal Insulation for Mechanical Systems

SD-03 Product Data:

- i. Pipe Insulation Systems Manufacturers Data and Instructions
- ii. Duct Insulation Systems Manufacturer Data and Instructions

23 09 53 Space Temperature Control Systems

SD-02 Shop Drawings:

- i. Control Systems Diagram for Each System
- ii. Sequence of Operation for Each System

SD-06 Test Reports:

- i. Performance Verification Test Plans and Procedures

SD-07 Certificates:

- i. Certificate Of Completion
- ii. Maintenance Manuals

23 30 00 HVAC Air Distribution

SD-03 Product Data:

- i. Manufacturers Installation Instructions

S-06 Test Reports:

- i. Performance Tests,

SD-07 Certificates:

- i. Manual Balancing Dampers
- ii. Operation and Maintenance Manuals

23 81 00 Decentralized Unitary HVAC Equipment

SD-02 Shop Drawings

SD-03 Product Data:

- i. Unitary Heat Pumps

SD-06 Test Reports:

- i. Refrigerant Tests, Charging, and Start-Up

SD-07 Certificates:

- i. Operation and Maintenance Manuals
- ii. Ozone Depleting Substances
- iii. Quality Assurance Submittals

ELECTRICAL SUBMITTALS:

SD-02 Shop Drawings:

- i. Marking Strips Drawings

SD-03 Product Data:

- i. Conductors
- ii. Switches
- iii. Circuit Breakers
- iv. Manual Motor Starters

Firestopping Materials

SD-06 Test Reports:

- i. 600-volt Wiring Test

SD-07 Certificates:

- i. Firestopping Materials

G. Technical Requirements

1. MECHANICAL REQUIREMENTS

23 05 93 Testing, Adjusting, and Balancing:

- A. Submittals: See Paragraph "F. Technical Submittals Required".

B. Quality Assurance: Ensure the tab agency is a first-tier subcontractor who is not affiliated with any other company participating in work on this contract, including design, furnishing equipment, or construction. Perform tab in accordance with the requirements of the standard under which the tab firm's qualifications are approved, i.e., AABC MN-1, NEBB procedural standards, or SMACNA 1780. Use the provisions of the tab standard, including checklists, report forms, etc., as nearly as practical, to satisfy the contract requirements. All quality assurance provisions of the tab standard such as performance guarantees are part of this contract. The contractor is responsible for ensuring compliance with the requirements of this section.

C. Warranty: Furnish workmanship and performance warranty for the tab system work performed for a period not less than 1 year from the date of government acceptance of the work; issued directly to the government. Include provisions that if within the warranty period the system shows evidence of major performance deterioration, or is significantly out of tolerance, resulting from defective TAB or DALT workmanship, the corrective repair or replacement of the defective materials and correction of the defective workmanship is the responsibility of the tab firm. Failure to perform repairs within the specified time period constitutes grounds for having the corrective action and repairs performed by others and the cost billed to the tab firm. The contractor must also provide a 1-year contractor installation warranty.

D. Execution

1. Provide instruments, consumables and personnel required to accomplish the DALT field work. Follow the same basic procedure specified below for tab field work, including maintenance and calibration of instruments, accuracy of measurements, preliminary procedures, field work, workmanship and treatment of deficiencies. Calibrate and maintain instruments in accordance with manufacturer's written procedures.
2. After completion of the DALT work, prepare a DALT report.
3. Test, adjust, and balance the HVAC systems until measured flow rates (air and water flow) are within plus or minus 5 percent of the design flow rates as specified or indicated on the contract documents. Provide instruments and consumables required to accomplish the TAB work.
4. Report heating and cooling performance capacity tests. Determine the apparent coil capacity by calculations using single point measurement of entering and leaving wet and dry bulb temperatures; submit the calculations with the TAB reports.
5. In addition to the tab proportionate balancing work on the air distribution systems and the water distribution systems, accomplish tab work on the HVAC systems which directly transfer thermal energy. Tab the operational performance of the heating systems and cooling systems.
6. For refrigeration compressors/condensers/condensing units, report data as required by NEBB form tab 15-83, NEBB procedural standards, including refrigeration operational data.
7. Strive to meet the intent of this section to maximize the performance of the equipment as designed and installed. However, if deficiencies in equipment design or installation prevent tab

work from being accomplished within the range of design values specified, provide written notice as soon as possible to the contractor and the owner describing the deficiency and recommended correction.

8. Upon the final tab work approval, permanently mark the settings of HVAC adjustment devices including valves, gauges, splitters, and dampers so that adjustment can be restored if disturbed at any time. Provide permanent markings clearly indicating the settings on the adjustment devices which result in the data reported correctly

23 07 00 Thermal Insulation for Mechanical Systems

A. Submittals: See Paragraph "F. Technical Submittals Required".

B. Quality Assurance: Deliver materials in the manufacturer's unopened containers. Protect materials delivered and placed in storage from weather, humidity, dirt, dust and other contaminants.

C. Products

1. Provide insulation systems in accordance with the approved mica national insulation standards plates as supplemented by this specification. Provide field-applied insulation for heating, ventilating, and cooling (HVAC) air distribution systems and piping systems that are located within, on, under, and adjacent to buildings, and for plumbing systems.

2. Provide insulation that meets or exceed the requirements of ASHRAE 90.1 - IP. Ensure insulation exterior is cleanable, grease resistant, non-flaking and non-peeling. Provide compatible materials that do not contribute to corrosion, soften, or otherwise attack surfaces to which applied in either wet or dry state. Use materials on stainless steel surfaces meeting ASTM C795 requirements.

3. Pipe insulation systems: Closed-cell, foam- or expanded-rubber materials containing anti-microbial additive, complying with ASTM C534/C534M, grade 1, type I or II. Type I, grade 1 for tubular materials. Type II, grade 1, for sheet materials. Ensure type I and II have vapor retarder /vapor barrier skin on one or both sides of the insulation.

4. Fittings: Fabricated fittings are the prefabricated fittings for flexible elastomeric pipe insulation systems in accordance with ASTM C1710. Together with the flexible elastomeric tubes, they provide complete system integrity for retarding heat gain and controlling condensation drip from chilled-water and refrigeration systems. Flexible elastomeric, fabricated fittings provide thermal protection (0.25 k) and condensation resistance (0.05 water vapor transmission factor)

5. Duct insulation systems: Mineral-fiber blanket insulation: mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C553, type II and ASTM C1290, type III with factory-applied FSK jacket. Minimum thickness in accordance with ASHRAE 90.1 - IP.

D. Execution

1. Keep insulation clean and dry. Do not remove insulation from its shipping containers until the day it is ready to use and return to like containers or equally protect from dirt and moisture at the end of each workday. Thoroughly clean insulation that becomes dirty prior to use. If insulation becomes wet or if cleaning does not restore the surfaces to like new condition, reject the insulation, and immediately remove from the jobsite.
2. Install flexible elastomeric cellular insulation with seams and joints sealed with rubberized contact adhesive.
3. Insulation is required on all pipes and ducts.
4. Ensure insulation, whether hot or cold application, is continuous through hangers. Support all horizontal pipes 2 inches and smaller on hangers with the addition of a type 40 protection shield to protect the insulation in accordance with MSS SP-58.
5. Provide vapor barrier for all ductworks.
6. After duct systems have been tested, adjusted, and balanced, repair breaks in the insulation and jacket. After the insulation is repaired, identify on the outside of the insulation with marker, sticker, or other means "tab test ports."

23 09 53 Space Temperature Control Systems

A. Submittals: See Paragraph "F. Technical Submittals Required".

B. Quality Assurance: Submit operation and maintenance manuals for items of equipment listed under paragraph product data. Manual shall contain full hardware support documentation, which shall include but not be limited to the following:

1. General description and specifications
2. Installation and initial checkout procedures
3. Detailed electrical and logical description
4. Troubleshooting procedures, diagrams, and guidelines
5. Alignment and calibration procedures for components
6. Preventive maintenance requirements and a maintenance checklist
7. Detailed schematics and assembly drawings
8. Spare parts list data, including required tool kits and suggested method of repairs such as field repair, factory repair, or item replacement
9. Signal identification and timing diagrams

10. Complete as-built control drawings, schedules, and sequence of operation
11. Controller configuration and parameter setting procedures
12. Step-by-step procedures required for each startup of HVAC control systems, operation, shutdown, recovery, and fault diagnosis
13. Manufacturer supplied operator manuals for equipment
14. Qualified service organization list

C. Products

1. Actuators: Provide electric, or electronic actuators. Actuators shall function as required within 85 to 110 percent of their power supply rating. Actuators shall fail to their spring return positions on signal or power failure unless indicated as timed, power return actuators.
2. Damper Actuators: Damper actuators shall be rated for at least 125 percent of the motive power necessary to operate the connected damper. Actuators shall be provided with mounting and connecting hardware.
3. Valve Actuators: Valve actuators shall be rated for at least 125 percent of the motive power necessary to operate the valves over their full range of operation against the total and differential pressures.
4. Valves: Valves shall have stainless steel stems and stuffing boxes with extended necks to clear the piping insulation. Valve bodies shall be designed for not less than 125 pounds per square inch gauge(PSIG)working pressure or 150 percent of the system operating pressure, whichever is greater. Class 125 copper alloy valves shall conform to ASME B16.5 as a minimum.
5. Valves for Hot Water Serv: Valves for hot water service below 250 degrees f shall conform to ASME B16.1. Bodies for valves 2 inches and smaller shall be brass or bronze, with threaded-end or union-end connections.
6. Dampers: Damper shall conform to SMACNA 1966. Dampers shall be tested in accordance with AMCA 500-D. Operating links external to dampers, such as crankarms, connecting rods, and line shafting for transmitting motion from damper actuators to dampers, shall withstand a load equal to at least twice the maximum required damper-operating force.
7. Thermostats: Provide adjustable thermostats.
8. Heat Pump System Controls: Heat pump system controls shall be manufacturer provided to reach zone temperature setpoints and shall include scheduling capabilities for occupied and unoccupied mode.

D. Execution: Provide components for a complete and operational control system. Provide control system complete and ready for operation, as specified and indicated.

1. Control drawings: provide laminated copies of as-built control system drawings to owner.
2. Calibrate instrumentation and controls and verify specified accuracy using test equipment traceable to National Institute for Science and Technology (NIST) standards. Adjust controls and equipment to maintain conditions indicated, to perform the functions indicated.
3. Field Quality Control: Demonstrate compliance of HVAC control systems. Furnish personnel, equipment, instrumentation, and supplies necessary to perform calibration and site testing. Testing shall include field tests and the performance verification test. Field tests shall demonstrate proper calibration of instrumentation, input and output devices, and operation of specific equipment. The performance verification test shall ensure proper execution of sequence of operation and proper tuning of control loops. Submit original copies of data produced, including results of each test procedure, to the government at the conclusion of each phase of testing. After completion or termination of field tests and again after the performance verification test, identify, determine causes, replace, repair, or calibrate equipment which fails to meet the specification; and deliver a written report to the government.
4. System Inspection: Observe HVAC control system in shutdown condition. Check dampers and valves for proper normal positions. Document positions for the performance verification test report.

F. Sequences of operation

1. ERV (Energy Recovery Ventilator): The ERV shall be on continuously when in occupied mode and shall be turned off when the building is unoccupied.
2. Heat Pump Systems: The fan coil units shall run continuously while the building is in occupied mode. The air temperature shall modulate to reach the indoor air temperature. The fan coil unit shall communicate with the outdoor heat pump unit to deliver the appropriate temperature air when there is a call for heating or cooling. When the setpoint is reached, the heat pump shall turn off and the fan coil shall run to circulate ventilation air in the building.
3. Electric Unit Heaters: The electric unit heater shall have an associated thermostat and will modulate the space temperature based on the thermostat setpoint. The unit shall turn off when the space temperature is reached.

23 30 00 HVAC Air Distribution

A. Submittals: See Paragraph "F. Technical Submittals Required".

B. Quality Assurance

1. Protect metallic materials against corrosion. Provide rust-inhibiting treatment and standard finish for the equipment enclosures. Do not use aluminum in contact with earth and where connected to

dissimilar metal. Protect aluminum by approved fittings, barrier material, or treatment. Provide hot-dip galvanized ferrous parts such as anchors, bolts, braces, boxes, bodies, clamps, fittings, guards, nuts, pins, rods, shims, thimbles, washers, and miscellaneous parts not of corrosion-resistant steel or nonferrous materials in accordance with ASTM A123/A123M for exterior locations and cadmium-plated in conformance with ASTM B766 for interior locations.

2. Submit detail drawings showing equipment layout, including assembly and installation details and electrical connection diagrams; ductwork layout showing the location of all supports and hangers, typical hanger details, gauge reinforcement, reinforcement spacing rigidity classification, and static pressure and seal classifications. Include any information required to demonstrate that the system has been coordinated and functions properly as a unit on the drawings and shows equipment relationship to other parts of the work, including clearances required for operation and maintenance.

3. Protect stored equipment at the jobsite from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Additionally, cap or plug all pipes until installed.

C. Products

1. Anchor Bolts: Provide anchor bolts for equipment placed on concrete equipment pads or on concrete slabs. Bolts to be of the size and number recommended by the equipment manufacturer and located by means of suitable templates.

2. Painting: Paint equipment units in accordance with approved equipment manufacturer's standards unless specified otherwise. Field retouch only if approved.

3. Duct Systems: Provide metal ductwork construction, including all fittings and components, that complies with SMACNA 1966, as supplemented and modified by this specification. Provide radius type elbows with a centerline radius of 1.5 times the width or diameter of the duct where space permits. Otherwise, elbows having a minimum radius equal to the width or diameter of the duct or square elbows with factory fabricated turning vanes are allowed. Provide ductwork that meets the requirements of seal class c. Fabricate outdoor air intake ducts and plenums with watertight soldered or brazed joints and seams.

4. Metallic Flexible Duct: Provide duct that conforms to UL 181 and NFPA 90A with factory-applied insulation, vapor barrier, and end connections. Provide flexible round duct length that does not exceed 5 feet. Secure connections by applying adhesive for 2 inches over rigid duct, apply flexible duct 2 inches over rigid duct, apply metal clamp, and provide minimum of three no. 8 sheet metal screws through clamp and rigid duct. Provide inner duct core that is insulated with mineral fiber blanket type flexible insulation, minimum of 1 inch thick. Provide insulation covered on exterior with manufacturer's standard fire-retardant vapor barrier jacket for flexible round duct.

5. Duct Access Doors: Provide hinged access doors conforming to SMACNA 1966 in ductwork and plenums where indicated and at all air flow measuring primaries, automatic dampers, fire dampers, coils, thermostats, and other apparatus requiring service and inspection in the duct system.

6. Manual Balancing Dampers: Furnish manual balancing dampers with accessible operating mechanisms. Use chromium plated operators (with all exposed edges rounded) in finished portions of the building. Provide manual volume control dampers that are operated by locking-type quadrant operators. Install dampers which are 2 gauges heavier than the duct in which installed.
7. Diffusers: Provide diffuser types indicated. Furnish ceiling mounted units with anti-smudge devices, unless the diffuser unit minimizes ceiling smudging through design features. Provide diffusers with air deflectors of the type indicated. For connecting the duct to diffuser, provide duct collar that is airtight and does not interfere with volume controller.
8. Louvers: Provide louvers for installation in exterior walls that are associated with the air supply and distribution system as specified
9. Fan Coil Units: Provide base units that include galvanized coil casing, coil assembly drain pan valve and piping package, air filter, fans, motor, fan drive, motor switch, an enclosure for cabinet models and casing for concealed models, leveling devices integral with the unit for vertical type units, and sound power levels as indicated.
10. Energy Recovery Ventilator: Provide energy recovery ventilator unit that is factory-fabricated for indoor installation, consisting of a flat plate crossflow heat exchanger, cooling coil, supply air fan and motor and exhaust air fan and motor. The casing must be 20-gauge g90, galvanized steel, double wall construction with one inch insulation. Provide fibrous desiccant crossflow type heat exchanger core capable of easy removal from the unit.

D. Execution

1. Install materials and equipment in accordance with the requirements of the contract drawings and approved manufacturer's installation instructions.
2. Install access panels for concealed valves, vents, controls, dampers, and items requiring inspection or maintenance of sufficient size, and locate them so that the concealed items are easily serviced and maintained or completely removed and replaced.
3. Install pre-insulated flexible duct in accordance with the latest printed instructions of the manufacturer to ensure a vapor tight joint. Provide hangers, when required to suspend the duct, of the type recommended by the duct manufacturer and set at the intervals recommended.
4. Install according to SMACNA 1966 unless otherwise indicated. Install duct supports for sheet metal ductwork according to SMACNA 1966, unless otherwise specified. Attach supports only to structural framing members and concrete slabs.

23 81 00 Decentralized Unitary HVAC Equipment

A. Submittals: See Paragraph "F. Technical Submittals Required".

1. Submit drawings consisting of: equipment layouts which identify assembly and installation details, wiring diagrams which identify each component individually and interconnected or

interlocked relationships between components, automatic temperature control diagrams and control sequences, installation details which includes the amount of factory set superheat and corresponding refrigerant pressure/temperature, equipment schedules.

2. Protect stored items from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Properly protect and care for all material both before and during installation.
3. Provide equipment with the manufacturer's standard warranty.

C. Products

1. Ozone depleting substances: unitary air conditioning equipment must not use cfc-based refrigerants. Refrigerant may be an approved alternative refrigerant in accordance with EPA's significant new alternative policy (snap) listing.
2. Air-source unitary heat pumps: provide air source unitary heat pumps that comply with ANSI /AHRI 210/240. Provide units with assembled refrigerant circuit or circuits split system having remote outdoor section separate from indoor section. Provide unitary heat pumps that bear the energy star label.
3. Casing: Construct the casing of zinc coated, heavy-gage (14-gage minimum) galvanized steel. Surfaces in contact with the airstream must comply with requirements in ASHRAE 62.1.
4. Compressors: Provide direct-drive, variable speed type compressors with centrifugal type oil pumps. Motor must be suction gas cooled. Use internal overloads and crankcase heaters with all compressors.
5. Refrigerant Circuit: A minimum of two circuits is required. Provide each refrigerant circuit with independent fixed orifice or thermostatic expansion devices, service pressure ports, and refrigerant line filter driers factory installed as standard. An area must be provided for replacement with suction line driers.
6. Evaporator and Condenser Coils: Provide internally finned, DN 10 (NPS 3/8) copper tubes mechanically bonded to a configured aluminum plate fin. Leak test the evaporator coil and condenser coil at the factory to 200 psig and pressure test to 400 psig. All dual compressor units must have intermingled evaporator coils. Provide sloped condensate drain pans.
7. Outdoor Fans: Direct driven, statically and dynamically balanced, draw-through in the vertical discharge position. The fan motors must be permanently lubricated and have built-in thermal overload protection.
8. Indoor Fans: Provide forward-curved, centrifugal, v-belt driven fan with adjustable motor sheaves and adjustable idler-arm assembly for quick-adjustment of fan belts and motor sheaves. Thermally protect motors. Provide oversized motors for high static application.
9. Defrost Controls: Provide a time initiated, temperature terminated defrost system shipped with a setting of 70-minute cycle, and a choice of 50 or 90-minute cycle.

10. Unit electrical: Provide single point unit power connection. Locate the unit control box within the unit that contains controls for compressor, reversing valve and fan motor operation and must have a 50 VA 24-volt control circuit transformer and a terminal block for low voltage field wiring connections. Wire high pressure, low temperature, and low-pressure safety switches through a latching lockout circuit to hold the conditioner off until it is reset electrically by interrupting the power supply to the conditioner. All safety switches must be normally closed, opening upon fault detection.

11. Operating Controls: Provide unit with factory supplied DDC control system. Low voltage, adjustable room thermostat to control heating and cooling in sequence with delay between stages, compressor and supply fan to maintain temperature setting. Include system selector switch (off-heat-auto-cool).

12. Unit DDC Controller: Unit controller must include input, output and self-contained programming as needed for complete control of unit. Temperature control system interface: points must be available from the unit controller for service access and display or control. The wall mounted space temperature sensor must include occupied and unoccupied set point control, push button unoccupied override, space temperature offset and space temperature indication.

13. Refrigerants: Refrigerant must be one of the fluorocarbon gases. Refrigerants must have number designations and safety classifications in accordance with ASHRAE 15 & 34. Refrigerants must meet the requirements of AHRI 700 as a minimum. Provide a complete refrigerant charge for the installed system as recommended by the manufacturer.

D. Execution

1. Perform work in accordance with the manufacturer's published diagrams, recommendations, and equipment warranty requirements.

2. Provide refrigeration equipment conforming to ASHRAE 15 & 34. Provide necessary supports for all equipment, appurtenances, and pipe as required, including frames or supports for compressors, pumps, cooling towers, condensers, and similar items. Isolate compressors from the building structure.

3. Split-system refrigerant piping systems must be tested and charged. Packaged refrigerant systems which are factory charged must be checked for refrigerant and oil capacity to verify proper refrigerant levels in accordance with manufacturer's recommendations. Individual reports must be submitted for the refrigerant system tests including the following: the date the tests were performed, a list of equipment used, with calibration certifications, initial test summaries, repairs /adjustments performed, final test results.

4. If a refrigerant leak is discovered after the system has been charged, the leaking portion of the system must immediately be isolated from the remainder of the system and the refrigerant pumped into the system receiver or other suitable container. Under no circumstances must the refrigerant be discharged into the atmosphere.

5. Contractor's Responsibility: Take steps at all times during the installation and testing of the refrigeration system, to prevent the release of refrigerants into the atmosphere. The steps must include, but not be limited to, procedures which will minimize the release of refrigerants to the atmosphere and the use of refrigerant recovery devices to remove refrigerant from the system and store the refrigerant for reuse or reclaim. At no time must more than 3 ounces of refrigerant be released to the atmosphere in any one occurrence. Any system leaks within the first year must be repaired in accordance with the requirements herein at no cost to the government including material, labor, and refrigerant if the leak is the result of defective equipment, material, or installation.

6. Before each refrigeration system is accepted, conduct tests to demonstrate the general operating characteristics of all equipment by a registered professional engineer or an approved manufacturer's start-up representative experienced in system start-up and testing. Tests must cover a period of not less than 48 hours for each system and must demonstrate that the entire system is functioning in accordance with the drawings and specifications. Make corrections and adjustments, as necessary, tests must be re-conducted to demonstrate that the entire system is functioning as specified. Prior to acceptance, install and tighten service valve seal caps and blanks over gauge points. Replace any refrigerant lost during the system startup. If tests do not demonstrate satisfactory system performance, correct deficiencies and retest the system.

2. ELECTRICAL REQUIREMENTS

A. Submittals: See paragraph "F". "Technical Submittals Required".

B. . Quality Insurance: Inspect materials upon receipt prior to installation. Any communications or specialty subcontracting approved by the KO should undergo rigorous assurance and include a revised quality control plan.

C. C. Products: Materials and equipment will, as a minimum, meet requirements of UL, where UL standards are established for those items, and requirements of NFPA 70 for all materials, equipment, and devices.

1. Conduit and Fittings

a. Rigid Metallic Conduit: Rigid, Threaded Zinc-Coated Steel Conduit: ANSI C80.1, UL 6.

b. Electrical, Zinc-Coated Steel Metallic Tubing (EMT): UL 797, ANSIC80.3.

c. Liquid-Tight Flexible Metal Conduit, Steel: UL 360, limited to 6 feet in areas where not accessible or below a raised floor installation.

2. Fittings for Metal Conduit, EMT, and Flexible Metal Conduit: UL 514B. Ferrous Fittings: cadmium- or zinc-coated in accordance with UL514B.

3. Fittings for Rigid Metal Conduit: Threaded type. Split couplings are unacceptable.

4. Fittings for EMT: Die Cast or steel compression type.

5. Wires and Cables: Provide wires and cables in accordance with applicable requirements of NFPA 70 and UL for type of insulation, jacket, and conductor specified or indicated. Do not use wires and cables manufactured more than 24 months prior to date of delivery to site.

6. Cabinets, Junction Boxes, and Pull Boxes: UL 50; volume greater than 100 cubic inches, NEMA Type 1 enclosure; sheet steel, hot-dip, zinc-coated. Where exposed to wet, damp, or corrosive environments, NEMA Type 3R.

7. Conductors:

a. Conductor sizes and capacities shown are based on copper, unless indicated otherwise.

b. Conductors No. 10 AWG and larger diameter: stranded.

c. Conductors No. 12 AWG and smaller diameter: solid.

d. Conductors for remote control, alarm, and signal circuits, classes 1, 2, and 3: stranded unless specifically indicated otherwise.

e. All conductors: copper.

f. Minimum Conductor Sizes: Provide minimum conductor size in accordance with the following:

i. Branch circuits: No. 12 AWG.

ii. Class 1 remote-control and signal circuits: No. 14 AWG.

iii. Class 2 low-energy, remote-control and signal circuits: No. 16 AWG.

iv. Class 3 low-energy, remote-control, alarm and signal circuits: No. 22 AWG.

8. Color Coding: Provide color coding for service, feeder, branch, control, and signaling circuit conductors.

a. Provide color coding of ground and neutral conductors as follows:

i. Grounding conductors: Green.

ii. Neutral conductors: White.

iii. Exception, where neutrals of more than one system are installed in same raceway or box, other neutrals color coding: white with a different colored (not green) stripe for each.

9. Provide color coding of ungrounded conductors in different voltage systems as follows:

208/120 volt, three-phase

i. Phase A - black

ii. Phase B - red

iii. Phase C - blue

iv. 120/240 volt, single-phase: Black and red.

10. Insulation: Unless specified or indicated otherwise by NFPA 70, provide power and lighting wires rated for 600-volts, Type THWN/THHN conforming to UL83, except that grounding wire may be type TW conforming to UL 83; remote-control and signal circuits: Type TW or TF, conforming to UL 83. Where equipment or devices require 90-degree Centigrade (C) conductors, provide only conductors with 90-degree C insulation or better.

11. Bonding Conductors: ASTM B1, solid bare copper wire for sizes No. 8 AWG and smaller diameter. ASTM B8, Class B, stranded bare copper wire for sizes No. 6 AWG and larger diameter.

12. Splices and Termination Components: UL 486A-486B for wire connectors and UL 510 for insulating tapes. Connectors for No. 10 AWG and smaller diameter wires: insulated, pressure-type in accordance with UL 486A-486B or UL 486C (twist-on splicing connector). Provide solderless terminal lugs on stranded conductors.

13. Disconnect Switches: NEMA KS 1. Provide heavy duty-type switches where indicated, where switches are rated higher than 240 volts, and for double-throw switches. Provide horsepower rated switches serving as the motor-disconnect means. Provide switches in NEMA 3R, enclosure per NEMA ICS 6.

14. Multipole Breakers: Provide common trip-type with single operating handle. Design breaker such that overload in one pole automatically causes all poles to open. Maintain phase sequence throughout each panel so that any three adjacent breaker poles are connected to Phase A, B, and C respectively.

15. Manual Motor Starters (Motor Rated Switches):

a. Single pole designed for surface mounting with overload protection and pilot lights.

b. Pilot Lights: Provide yoke-mounted, seven element LED cluster light module.

c. Color: in accordance with NEMA ICS 2.

16. Panelboards:

a. Provide new directories for existing panels modified by this project as indicated.

b. Circuit Breakers: UL 489, thermal magnetic type having a minimum short-circuit current rating equal to the short-circuit current rating of the panelboard in which the circuit breaker will be

mounted. Breaker terminals: UL listed as suitable for type of conductor provided. Series rated circuit breakers and plug-in circuit breakers that do not use a retaining bolt are unacceptable.

17. Lockout Requirements: Provide circuit breakers, disconnecting means, and other devices that are electrical energy-isolating capable of being locked out for machines and other equipment to prevent unexpected startup or release of stored energy in accordance with 29 CFR 1910.147, NFPA 70E, and 29 CFR 1910.303. Comply with mechanical requirements for mechanical isolation of machines and other equipment.

18. Nameplates and Signs: Provide field fabricated nameplates in accordance with the following:

- a. ASTM D709.
- b. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device as specified or as indicated on the drawings.
- c. Each nameplate inscription: identify the function and, when applicable, the position.
- d. Nameplates: melamine plastic, 0.125 inch thick, white with black center core.
- e. Surface: matte finish. Corners: square. Accurately align lettering and engrave into the core.
- f. Minimum size of nameplates: one by 2.5 inches.
- g. Lettering size and style: a minimum of 0.25-inch-high normal block style.

19. Firestopping Materials: Provide firestopping materials, supplied from a single domestic manufacturer, consisting of commercially manufactured, asbestos-free, nontoxic products FM APP GUIDE approved, or UL listed, for use with applicable construction and penetrating items, complying with the following minimum requirements:

- a. Fire Hazard Classification: Material shall have a flame spread of 25 or less, and a smoke developed rating of 50 or less, when tested in accordance with ASTM E84 or UL 723. Material shall be an approved firestopping material as listed in UL Fire Resistance or by a nationally recognized testing laboratory.
- b. Toxicity: Material shall be nontoxic and carcinogen free to humans at all stages of application or during fire conditions and shall not contain hazardous chemicals or require harmful chemicals to clean material or equipment.
- c. Fire Resistance Rating: Firestop systems shall be UL Fire Resistance listed or FM APP GUIDE approved with "F" rating at least equal to fire-rating of fire wall or floor in which penetrated openings are to be protected.
- i. Through Penetrations: Firestopping materials for through-penetrations shall provide "F", "T" and "L" fire resistance ratings in accordance with ASTM E814 or UL 1479.

d. Material Certification: Submit certificates attesting that firestopping material complies with the specified requirements. For all intumescent firestop materials used in through penetration systems, the manufacturer shall provide certification of compliance with UL 1479.

D. Execution:

1. Installation: Electrical installations, including weatherproof and hazardous locations and ducts, plenums and other air-handling spaces: conform to requirements of NFPA 70 and to requirements specified herein.

2. Wiring Methods: Provide insulated conductors installed in rigid steel conduit or EMT, except where specifically indicated or specified otherwise or required by NFPA 70 to be installed otherwise. Grounding conductor: separate from electrical system neutral conductor. Provide insulated green equipment grounding conductor for circuit(s) installed in conduit and raceways. Minimum conduit size: 1/2 inch in diameter for low voltage lighting and power circuits. Firestop conduit which penetrates fire-rated walls, fire-rated partitions, or fire-rated floors as specified in this section.

3. Pull Wire: Install pull wires in empty conduits. Pull wire: plastic with a minimum of 200-pound force tensile strength. Leave minimum 36 inches of slack at each end of pull wire.

4. Conduit Installation: Unless indicated otherwise, conceal conduit under floor slabs and within finished walls, ceilings, and floors. Keep conduit minimum 6 inches away from parallel runs of flues and steam or hot water pipes. Install conduit parallel with or at right angles to ceilings, walls, and structural members where they are located above accessible ceilings and where conduit will be visible after completion of project.

5. Restrictions Applicable to EMT:

A. Do not install underground.

B. Do not encase in concrete, mortar, grout, or other cementitious materials.

C. Do not use in areas subject to physical damage including but not limited to equipment rooms where moving or replacing equipment could physically damage the EMT.

D. Do not use in hazardous areas.

E. Do not use outdoors.

F. Do not use in fire pump rooms.

G. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

6. Restrictions Applicable to Flexible Conduit: Use only as specified in paragraph FLEXIBLE CONNECTIONS. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

7. Conduit Through Floor Slabs: Where conduits rise through floor slabs, do not allow curved portion of bends to be visible above finished slab. Where conduit rises through slab-on grade, seal all electrical penetrations to address radon mitigation and prevent infiltration of air, insects, and vermin.

8. Conduit Support: Support conduit by pipe straps, wall brackets, threaded rod conduit hangers, or ceiling trapeze. Plastic cable ties are not acceptable. Fasten by wood screws to wood; by toggle bolts on hollow masonry units; by concrete inserts or expansion bolts on concrete or brick; and by machine screws, welded threaded studs, or spring-tension clamps on steel work. Threaded C-clamps may be used on rigid steel conduit only. Do not weld conduits or pipe straps to steel structures. Do not exceed one-fourth proof test load for load applied to fasteners. Provide vibration resistant and shock-resistant fasteners attached to concrete ceiling. Do not cut main reinforcing bars for any holes cut to depth of more than 1 1/2 inches in reinforced concrete beams or to depth of more than 3/4 inch in concrete joints. Fill unused holes. In partitions of light steel construction, use sheet metal screws. In suspended-ceiling construction, run conduit above ceiling. Do not support conduit by ceiling support system. Conduit and box systems: supported independently of both (a) tie wires supporting ceiling grid system, and (b) ceiling grid system into which ceiling panels are placed. Do not share supporting means between electrical raceways and mechanical piping or ducts. Identify independent conduit support in both fire and non-fire rated assemblies per NFPA 70. Coordinate installation with above-ceiling mechanical systems to assure maximum accessibility to all systems. Spring-steel fasteners may be used for lighting branch circuit conduit supports in suspended ceilings in dry locations. Where conduit crosses building expansion joints, provide suitable expansion fitting that maintains conduit electrical continuity by bonding jumpers or other means. For conduits greater than 2 1/2 inches inside diameter, provide supports to resist forces of 0.5 times the equipment weight in any direction and 1.5 times the equipment weight in the downward direction.

9. Directional Changes in Conduit Runs: Make changes in direction of runs with symmetrical bends or cast-metal fittings. Make field-made bends and offsets with hickey or conduit-bending machine. Do not install crushed or deformed conduits. Avoid trapped conduits. Prevent plaster, dirt, or trash from lodging in conduits, boxes, fittings, and equipment during construction. Free clogged conduits of obstructions.

10. Locknuts and Bushings: Fasten conduits to sheet metal boxes and cabinets with two locknuts where required by NFPA 70, where insulated bushings are used, and where bushings cannot be brought into firm contact with the box; otherwise, use at least minimum single locknut and bushing. Provide locknuts with sharp edges for digging into wall of metal enclosures. Install bushings on ends of conduits and provide insulating type where required by NFPA 70.

11. Flexible Connections: Provide flexible steel conduit between 3 and 6 feet in length for equipment subject to vibration, noise transmission, or movement; and for motors. Install flexible

conduit to allow 20 percent slack. Minimum flexible steel conduit size: 1/2 inch diameter. Provide liquid tight flexible conduit in wet and damp locations for equipment subject to vibration, noise transmission, movement or motors. Provide separate ground conductor across flexible connections. Plastic cable ties are not acceptable as a support method.

12. Boxes, Outlets, and Supports: Provide boxes in wiring and raceway systems wherever required for pulling of wires, making connections, and mounting of devices or fixtures. Boxes for metallic raceways: cast-metal, hub-type when located in wet locations, when surface mounted on outside of exterior surfaces, when surface mounted on interior walls exposed up to 7 feet above floors and walkways, and when specifically indicated. Boxes in other locations: sheet steel. Provide each box with volume required by NFPA 70 for number of conductors enclosed in box. Provide gaskets for cast-metal boxes installed in wet locations and boxes installed flush with outside of exterior surfaces. Fasten boxes and supports with wood screws on wood, with bolts and expansion shields on concrete or brick, with toggle bolts on hollow masonry units, and with machine screws or welded studs on steel. In open overhead spaces, cast boxes threaded to raceways need not be separately supported except where they are used for fixture support; support sheet metal boxes directly from building structure or by bar hangers. Where bar hangers are used, attach bar to raceways on opposite sides of box, and support raceway with approved-type fastener maximum 24 inches from box. When penetrating reinforced concrete members, avoid cutting reinforcing steel.

13. Boxes:

a. Boxes for use with raceway systems: minimum 1 1/2 inches deep, except where shallower boxes required by structural conditions are approved. Boxes for other than lighting fixture outlets: minimum 4 inches square, except that 4 by 2-inch boxes may be used where only one raceway enters outlet.

14. Pull Boxes:

a. Construct of at least minimum size required by NFPA 70 of code-gauge aluminum or galvanized sheet steel, except where cast-metal boxes are required in locations specified herein. Provide boxes with screw-fastened covers. Where several feeders pass through common pull box, tag feeders to indicate clearly electrical characteristics, circuit number, and panel designation.

15. Mounting Heights: Mount disconnecting switches so height of center of grip of the operating handle of the switch or circuit breaker at its highest position is maximum 79 inches above floor or working platform or as allowed in Section 404.8 per NFPA 70. Mount other devices as indicated.

16. Conductor Identification: Provide conductor identification within each enclosure where tap, splice, or termination is made. For conductors No. 6 AWG and smaller diameter, provide color coding by factory-applied color-impregnated insulation. For conductors No. 4 AWG and larger, provide color coding by plastic-coated, self-sticking markers; colored nylon cable ties and plates; or heat shrink-type sleeves. Identify control circuit terminations in accordance with manufacturer's recommendations.

17. Marking Strips

18. Provide white or other light-colored plastic marking strips, fastened by screws to each terminal block, for wire designations.

19. Use permanent ink for the wire numbers

20. Provide reversible marking strips to permit marking both sides or provide two marking strips with each block.

21. Size marking strips to accommodate the two sets of wire numbers.

22. Assign a device designation in accordance with NEMA ICS 1 to each device to which a connection is made. Mark each device terminal to which a connection is made with a distinct terminal marking corresponding to the wire designation used on the Contractor's schematic and connection diagrams.

23. The wire (terminal point) designations used on the Contractor's wiring diagrams and printed on terminal block marking strips may be according to the Contractor's standard practice; however, provide additional wire and cable designations for identification of remote (external) circuits for the Government's wire designations.

24. Prints of the marking strips drawings submitted for approval will be so marked and returned to the Contractor for addition of the designations to the terminal strips and tracings, along with any rearrangement of points required.

a. Splices: Make splices in accessible locations. Make splices in conductors No. 10 AWG and smaller diameter with insulated, pressure-type connector. Make splices in conductors No. 8 AWG and larger diameter with solderless connector and cover with insulation material equivalent to conductor insulation.

b. Electrical Penetrations: Seal openings around electrical penetrations through fire resistance-rated walls, partitions, floors, or ceilings in accordance with the paragraph Firestopping Materials.

25. Grounding and Bonding: Provide in accordance with NFPA 70. Ground exposed, non-current-carrying metallic parts of electrical equipment, metallic raceway systems, grounding conductor in metallic raceways, and neutral conductor of wiring systems.

26. Equipment Connections: Provide power wiring and connections to motors and equipment. Except as otherwise specifically noted or specified, automatic control wiring, control devices, and protective devices within the control circuitry are not included in this section of the specifications and are provided under the section specifying the associated equipment.

27. Repair of Existing Work: Perform repair of existing work, demolition, and modification of existing electrical distribution systems as follows:

28. Workmanship:

29. Lay out work in advance. Exercise care where cutting, channeling, chasing, or drilling of floors, walls, partitions, ceilings, or other surfaces is necessary for proper installation, support, or anchorage of conduit, raceways, or other electrical work. Repair damage to buildings, piping, and equipment using skilled craftsmen of trades involved.

30. Existing Concealed Wiring to be Removed:

a. Disconnect existing concealed wiring to be removed from its source. Remove conductors; cut conduit flush with floor, underside of floor, and through walls; and seal openings.

31. Removal of Existing Electrical Distribution System:

a. Removal of existing electrical distribution system equipment includes equipment's associated wiring, including conductors, cables, exposed conduit, surface metal raceways, boxes, and fittings, back to equipment's power source as indicated.

32. Continuation of Service: Maintain continuity of existing circuits of equipment to remain. Maintain existing circuits of equipment energized. Restore circuits wiring and power which are to remain but were disturbed during demolition back to original condition.

E. Field Fabricated Nameplate Mounting: Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets. Provide nameplate on all equipment in access-controlled spaces and areas.

F. Field Quality Control: Furnish test equipment and personnel and submit written copies of test results. Give TPOC 5 working days' notice prior to each test. Where applicable, test electrical equipment in accordance with NETA ATS.

1. Devices Subject to Manual Operation:

a. Operate each device subject to manual operation at least five times, demonstrating satisfactory operation each time.

2. 600-Volt Wiring Test:

a. Test wiring rated 600 volt and less to verify that no short circuits or accidental grounds exist. Perform insulation resistance tests on wiring No. 6 AWG and larger diameter using instrument which applies voltage of 1,000 volts DC for 600 volt rated wiring and 500 volts DC for 300 volt rated wiring per NETA ATS to provide direct reading of resistance. All existing wiring to be reused must also be tested.

G. Delivery, Handling and Storage

As appropriate, materials shall be delivered to the project site in the manufacturer's original packaging with the brand and item identification reference clearly marked. Components shall be stored in a dry location that is adequately ventilated, free from dust, water, or other contaminants, and which is easily accessible for inspection and handling.

H. Material Warranties

The Contractor shall note that a Warranty of Construction is required for this project for a period of 1 year from the date of final acceptance of the work, in accordance with the Contract Clauses. In addition, manufacturer's standard performance guarantees or warranties that extend beyond a 1-year period shall be provided to the Government, as appropriate.

I. Coordination

Liaison with the U.S. Army Corps of Engineers, New England District, by the Contractor shall be maintained for the duration of the project by communication with the TPOC's Representative assigned to this project. All Contractor project related questions, comments, clarifications, etc. shall be directed to the TPOC's Representative for action.

J. . References

AIR-CONDITIONING, HEATING, AND REFRIGERATION INSTITUTE (AHRI)

AHRI 700 (2016) Specifications for Fluorocarbon Refrigerants

AIR MOVEMENT AND CONTROL ASSOCIATION (AMCA)

AMCA 500-D (2018) Laboratory Methods of Testing Dampers for Rating

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI/AHRI 210/240 (2008; Add 1 2011; Add 2 2012) Performance Rating of Unitary Air-Conditioning & Air-Source Heat Pump Equipment

ANSI A10.44 (2020) Control Of Energy Sources (Lockout/Tagout) For Construction And Demolition Operations

ANSI Z21.22/CSA 4. 4 (2015; R 2020) Relief Valves for Hot Water Supply Systems

ANSI Z244.1 (2016) Control of Hazardous Energy: Lockout

ANSI Z359.2 (2023) Fall Protection Program Requirements

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 15 & 34 (2013) ASHRAE Standard 34-2016 Safety Standard for Refrigeration Systems /ASHRAE Standard 34-2016 Designation and Safety Classification of Refrigerants-

ASHRAE Standard 34-2016

ASHRAE 62.1 (2022) Ventilation for Acceptable Indoor Air Quality

ASHRAE 90.1 IP 9 (2019) Energy Standard for Buildings Except Low-Rise Residential Buildings [(2018; Addenda A-B 2021; Addenda C-K 2023; Addenda L 2024) Energy- Efficient Design of Low-Rise Residential Buildings

ASHRAE HVAC APP IP HDBK (2023) HVAC Applications Handbook, I-P Edition

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME A112,14.1 (2003; R 2017; R 2022) Backwater Valves

ASME A112.19.2/CSA B45.1 (2018) Plumbing Supply Fittings

ASME B16.1 (2020) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250

ASME B16.22 (2021) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings

ASME B16.5 (2020) Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard

ASME B16.50 (2021) Wrought Copper and Copper Alloy Braze-Joint Pressure Fittings

ASME B31.3 (2022; Errata 2023) Process Piping

ASME B40.100 (2022) Pressure Gauges and Gauge Attachments

ASME BPVC SEC VIII DI (2019) BPVC Section VIII-Rules for Construction of Pressure Vessels Division 1

ASSOCIATED AIR BALANCE COUNCIL (AABC)

AABC MN-1 (2002; 6th ed) National Standards for Total System Balance

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M (2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM B1 (2013) Standard Specification for Hard-Drawn Copper Wire

ASTM B8 (2023) Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft

ASTM B32 (2020) Standard Specification for Solder Metal

ASTM B584 (2022) Standard Specification for Copper Alloy Sand Castings for General Applications

ASTM B766 (2023) Standard Specification for Electrodeposited Coatings of Cadmium

ASTM B813 (2024) Standard Specification for Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube

ASTM B88 (2022) Standard Specification for Seamless Copper Water Tube

ASTM C1290 (2016; R 2021) Standard Specification for Flexible Fibrous Glass Blanket Insulation Used to Externally Insulate HVAC Ducts

ASTM C1710 (2011) Standard Guide for Installation of Flexible Closed Cell Preformed Insulation in Tube and Sheet Form

ASTM C534/C534M (2023) Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form

ASTM C553 (2013; R 2019) Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications

ASTM C795 (2008; R 2023) Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel

ASTM D709 (2017) Standard Specification for Laminated Thermosetting Materials

ASTM E1 (2014) Standard Specification for ASTM Liquid-in-Glass Thermometers

ASTM E84 (2024) Standard Test Method for Surface Burning Characteristics of Building Materials

ASTM E814 (2024) Standard Test Method for Fire Tests of Penetration Firestop Systems

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8 (2019) Specification for Filler Metals for Brazing and Braze Welding

AWS A5.8/A5.8M (2019) Specification for Filler Metals for Brazing and Braze Welding

AWS B2.2/B2.2M (2016) Specification for Brazing Procedure and Performance Qualification

AWS WHB-2.9 (2004) Welding Handbook; Volume 2, Welding Processes, Part 1

COPPER DEVELOPMENT ASSOCIATION (CDA)

CDA A4015 (2016; 14/17) Copper Tube Handbook

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS (2025) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

MANUFACTURING STANDARDIZATION SOCIETY (MSS)

MSS SP-110 (2010) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends

MSS SP-110 (2010) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends

SP-58 (2010) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends

MSS SP-58 (2018) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation

MSS SP-80 (2019) Bronze Gate, Globe, Angle and Check Valves

MSS SP-80 (2019) Bronze Gate, Globe, Angle and Check Valves

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI C80.1 (2020) American National Standard for Electrical Rigid Steel Conduit (ERSC)

ANSI C80.3 (2020) American National Standard for Electrical Metallic Tubing (EMT)

NEMA ICS 1 (2022) Standard for Industrial Control and Systems: General Requirements

NEMA ICS 2 (2000; R 2020) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V

NEMA ICS 6 (1993; R 2016) Industrial Control and Systems: Enclosures

NEMA KS 1 (2013) Enclosed and Miscellaneous Distribution Equipment Switches (600 V Maximum)

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

NEBB Procedural Standards (2015) Procedural Standards for TAB (Testing, Adjusting and Balancing) Environmental Systems

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2023; ERTA 1 2024; TIA 24-1) National Electrical Code

NFPA 90A (2024) Standard for the Installation of Air Conditioning and Ventilating Systems

NFPA 70E (2024) Standard for Electrical Safety in the Workplace

NFPA 241 (2022), Standard for Safeguarding Construction, Alteration, and Demolition Operations

NFPA 780 (2023) Standard for the Installation of Lightning Protection Systems

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1780 (2023) HVAC Systems - Testing, Adjusting and Balancing, 3rd Edition

SMACNA 1966 (2020) HVAC Duct Construction Standards Metal and Flexible, 4th Edition

SMACNA 1966 (2020) HVAC Duct Construction Standards Metal and Flexible, 4th Edition

UL SOLUTIONS (UL)

UL 6 - (2022) UL Standard for Safety Electrical Rigid Metal Conduit-Steel

UL 50 - (2024) UL Standard for Safety Enclosures for Electrical Equipment, Non-Environmental Considerations

UL 83 (2017; Reprint Mar 2020) UL Standard for Safety Thermoplastic-Insulated Wires and Cables

UL 181 (2013; Reprint Dec 2021) UL Standard for Safety Factory-Made Air Ducts and Air Connectors

UL 360 (2013; Reprint Jan 2024) UL Standard for Safety Liquid-Tight Flexible Metal Conduit

UL 486A-486B (2025) UL Standard for Safety Wire Connectors

UL 486C (2023; Reprint Feb 2025) UL Standard for Safety Splicing Wire Connectors

UL 489 (2025) UL Standard for Safety Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures

UL 514B (2012; Reprint Mar 2024) UL Standard for Safety Conduit, Tubing and Cable Fittings

UL 723 (2023) UL Standard for Safety Test for Surface Burning Characteristics of Building Materials

UL 797 (2007; Reprint Apr 2023) UL Standard for Safety Electrical Metallic Tubing -- Steel

UL 1479 (2015; Reprint Apr 2024) Fire Tests of Through-Penetration Firestops

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2024) Safety and Occupational Health (SOH) Requirements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.120 Hazardous Waste Operations and Emergency Response

29 CFR 1910.147 The Control of Hazardous Energy (Lock Out/Tag Out)

*** END OF NARRATIVE ***

Requirements

HVAC System Repairs, Buffumville Lake, Charlton, MA

0001

Product Service Code : Y1QA

Section E - Inspection and Acceptance

FAR Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
52.246-12	Inspection of Construction.	1996-08		

Section F - Deliveries or Performance

0001	Delivery Schedule From date of lead time event to completion of performance 180 Calendar Days Date of Notice to Proceed Receipt Quantity 1 Job Address and POC Place of Performance DoDAAC: 961309 CountryCode: USA CORPS OF ENGINEERS NEW ENGLAND DIST BUFFUMVILLE LAKE DAM, 48 OLD OXFORD RD NEW ENGLAND DIV CHARLTON, MA 01507-1418 UNITED STATES NICOLE C. GILES, DELIVER_TO_EMP_ID_NO
------	---

Section G - Contract Administration Data

DFARS Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
252.232-7003	Electronic Submission of Payment Requests and Receiving Reports.	2018-12		
252.236-7000	Modification Proposals--Price Breakdown.	1991-12		

DFARS Clauses Incorporated by Full Text

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
252.232-7006	Wide Area WorkFlow Payment Instructions.	2023-01		

WIDE AREA WORKFLOW PAYMENT INSTRUCTIONS (JAN 2023)

(a) Definitions. As used in this clause-

"Department of Defense Activity Address Code (DoDAAC)" is a six position code that uniquely identifies a unit, activity, or organization.

"Document type" means the type of payment request or receiving report available for creation in Wide Area WorkFlow (WAWF).

"Local processing office (LPO)" is the office responsible for payment certification when

payment certification is done external to the entitlement system.

"Payment request" and "receiving report" are defined in the clause at 252.232-7003, Electronic Submission of Payment Requests and Receiving Reports.

(b) Electronic invoicing. The WAWF system provides the method to electronically process vendor payment requests and receiving reports, as authorized by Defense Federal Acquisition Regulation Supplement (DFARS) 252.232-7003, Electronic Submission of Payment Requests and Receiving Reports.

(c) WAWF access. To access WAWF, the Contractor shall-

(1) Have a designated electronic business point of contact in the System for Award Management at <https://www.sam.gov>; and

(2) Be registered to use WAWF at <https://wawf.eb.mil/> following the step-by-step procedures for self-registration available at this web site.

(d) WAWF training. The Contractor should follow the training instructions of the WAWF Web-Based Training Course and use the Practice Training Site before submitting payment requests through WAWF. Both can be accessed by selecting the "Web Based Training" link on the WAWF home page at <https://wawf.eb.mil/>

(e) WAWF methods of document submission. Document submissions may be via web entry, Electronic Data Interchange, or File Transfer Protocol.

(f) WAWF payment instructions. The Contractor shall use the following information when submitting payment requests and receiving reports in WAWF for this contract or task or delivery order:

(1) Document type. The Contractor shall submit payment requests using the following document type(s):

(i) For cost-type line items, including labor-hour or time-and-materials, submit a cost voucher.

(ii) For fixed price line items-

(A) That require shipment of a deliverable, submit the invoice and receiving report specified by the Contracting Officer.

(Contracting Officer: Insert applicable invoice and receiving report document type(s) for fixed price line items that require shipment of a deliverable.)

(B) For services that do not require shipment of a deliverable, submit either the Invoice 2in1, which meets the requirements for the invoice and receiving report, or the applicable invoice and receiving report, as specified by the Contracting Officer.

(Contracting Officer: Insert either "Invoice 2in1" or the applicable invoice and receiving report document type(s) for fixed price line items for services.)

(iii) For customary progress payments based on costs incurred, submit a progress payment request.

(iv) For performance based payments, submit a performance based payment request.

(v) For commercial financing, submit a commercial financing request.

(2)) Fast Pay requests are only permitted when Federal Acquisition Regulation (FAR) 52.213-1 is included in the contract.

[Note: The Contractor may use a WAWF "combo" document type to create some combinations of invoice and receiving report in one step.]

(3) Document routing. The Contractor shall use the information in the Routing Data Table below only to fill in applicable fields in WAWF when creating payment requests and receiving reports in the system.

Routing Data Table*

Field Name in WAWF	Data to be entered in WAWF
Pay Official DoDAAC	_____
Issue By DoDAAC	_____
Admin DoDAAC	_____
Inspect By DoDAAC	_____

Ship To Code _____
Ship From Code _____
Mark For Code _____
Service Approver (DoDAAC) _____
Service Acceptor (DoDAAC) _____
Accept at Other DoDAAC _____
LPO DoDAAC _____
DCAA Auditor DoDAAC _____
Other DoDAAC(s) _____

(*Contracting Officer: Insert applicable DoDAAC information. If multiple ship to/acceptance locations apply, insert "See Schedule" or "Not applicable.")

(**Contracting Officer: If the contract provides for progress payments or performance-based payments, insert the DoDAAC for the contract administration office assigned the functions under FAR 42.302(a)(13).)

(4) Payment request. The Contractor shall ensure a payment request includes documentation appropriate to the type of payment request in accordance with the payment clause, contract financing clause, or Federal Acquisition Regulation 52.216-7, Allowable Cost and Payment, as applicable.

(5) Receiving report. The Contractor shall ensure a receiving report meets the requirements of DFARS Appendix F.

(g) WAWF point of contact.

(1) The Contractor may obtain clarification regarding invoicing in WAWF from the following contracting activity's WAWF point of contact.

(Contracting Officer: Insert applicable information or "Not applicable.")

(2) Contact the WAWF helpdesk at 866-618-5988, if assistance is needed.

(End of clause)

Section H - Special Contract Requirements

SECURITY REQUIREMENTS:

General security requirements and guidance: The security requirements described below apply to all contract personnel (including employees of the prime Contractor ("Contractor") and all subcontractor employees) supporting the performance requirements of this contract. The Contractor is responsible for compliance with these security requirements. Questions regarding security matters shall be addressed to the designated Government representative (eg., Contracting Officer Representative (COR), Requiring Activity (RA) representative, or Contracting Officer (if a COR or other RA representative is not appointed)). Contract personnel are critical to the overall security and safety of US Army Corps of Engineers (USACE) installations, facilities and activities, and security awareness training contributes to those efforts. The Department of Defense (DoD) and Army security training requirements specified below, if applicable, are performance requirements; all applicable contract personnel shall complete initial training within 30 days of contract award or the date new contract personnel begin performance on the contract. Within five business days from the completion of training, the Contractor shall provide written documentation (e.g., email or memorandum) to the Government representative. The documentation shall include the names of contract personnel trained and which training they completed; the Contractor shall maintain training records as part of their contract files and be prepared to provide copies of training certificates to the Government representative. Contractor personnel and vehicles are subject to search when entering federal installations. Additionally, all contract personnel shall comply with Force Protection Condition (FPCON) measures, Random Antiterrorism Measures (commonly referred to as "RAMs"), and Health Protection Condition (HPCON) measures. The Contractor is responsible for meeting performance requirements during elevated FPCON and/or HPCON levels in accordance with applicable RA plans and procedures -this includes identifying mission essential and non-mission essential personnel. In addition to the changes otherwise authorized by the changes clauses of this contract, should FPCON or HPCON levels at any individual facility or installation change, the Government may implement security changes that affect contract personnel. The Contractor shall ensure all contract personnel are aware of their security responsibilities, including any site-specific requirements identified in local policies or procedures.

Suspicious Activity Reporting training (e.g. iWATCH, CorpsWatch, or See Something, Say Something): All contract personnel shall receive initial and annual refresher training from the RA representative on the local suspicious activity reporting program. This locally developed training provides contract personnel with general information on suspicious behavior, and guidance on reporting suspicious activity to the project manager, security representative or law enforcement entity.

Pre-screen candidates using E-Verify Program: Contractors shall comply with the requirements set forth in FAR clause 52.222-54 Employment Eligibility Verification and FAR Subpart 22.18 in using the E-Verify Program at (<https://www.e-verify.gov/>) (website subject to change) to meet the contract employment eligibility requirements. Contractors are encouraged to cooperate with Federal and State agencies responsible for enforcing labor requirements to include eligibility for employment under United States immigration laws in accordance with FAR 22.102-1(i). An initial list of verified/eligible candidates shall be provided to the COR no later than three business days

after the initial contract award. When contracts are with individuals, the individuals will be required to complete a Form I-9, Employment Eligibility Verification, and submit it to the Contracting Officer to become part of the official contract file.

WAGE DETERMINATIONS:

The Wage Determination for this project can be found at:

<https://sam.gov/wage-determination/MA20260013/0>

Wage Determination No.: MA20260013

Modification No.: 0

Revised Date: 02 January 2026

*** END OF NARRATIVE ***

Section I - Contract Clauses

UAI 5152.249-9000 Basis for Settlement of Proposals

Actual costs will be used to determine equipment costs for a settlement proposal submitted on the total cost basis under Federal Acquisition Regulation (FAR) 49.206-2(b). In evaluating a termination settlement proposal using total cost basis, the following principles will be applied to determine allowable equipment costs.

(a) Actual costs for each piece of equipment, or groups of similar serial or series equipment, need not be available in the contractor's accounting records to determine total actual equipment costs.

(b) If equipment costs have been allocated to a contract using predetermined rates, those charges will be adjusted to actual costs.

(c) Recorded job costs adjusted for unallowable expenses will be used to determine equipment operating expenses.

(d) Ownership costs (depreciation) will be determined using the contractor's depreciation schedule (subject to the provisions of Federal Acquisition Regulation (FAR) 31.205-11).

(e) License, taxes, storage and insurance costs are normally recovered as an indirect expense and unless the contractor charges these costs directly to contracts, they will be recovered through the indirect expense rate.

(End of Clause)

52.211-10 Commencement, Prosecution, and Completion of Work.

The Contractor shall be required to (a) commence work under this contract within 14 calendar days after the date the Contractor receives the notice to proceed, (b) prosecute the work diligently, and (c) complete the entire work ready for use not later than 180 calendar days from notice to proceed.

* The time stated for completion shall include final cleanup of the premises.

(End of clause)

52.236-27 Site Visit (Construction) Alternate I (Feb 1995).

(a) The clauses at 52.236-2, Differing Site Conditions, and 52.236-3, Site Investigations and Conditions Affecting the Work, will be included in any contract awarded as a result of this solicitation. Accordingly, offerors or quoters are urged and expected to inspect the site where the work will be performed.

(b) An organized site visit has been scheduled for-

May 20, 2026 at 9:00 AM Eastern

(c) Participants will meet at-

Buffumville Lake Project Office, 48 Old Oxford Road, Charlton, MA

(End of Provision)

MAGNITUDE OF PROJECT

The estimated cost of the work is between \$100,000 and \$250,000.

*** END OF NARRATIVE ***

FAR Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
52.203-19	Prohibition on Requiring Certain Internal Confidentiality Agreements or Statements.	2017-01		
52.204-9	Personal Identity Verification of Contractor Personnel.	2011-01		
52.204-10	Reporting Executive Compensation and First-Tier Subcontract Awards. (Deviation 2026-O0038)	2026-02		
52.204-13	System for Award Management-Maintenance. (Deviation 2026-O0038)	2026-02		
52.204-19	Incorporation by Reference of Representations and	2014-12		

Certifications.

52.209-6	Protecting the Government's Interest When Subcontracting With Contractors Debarred, Suspended, Proposed for Debarment, or Voluntarily Excluded. (Deviation 2026-O0038)	2026-02
52.209-10	Prohibition on Contracting With Inverted Domestic Corporations. (Deviation 2026-O0038)	2026-02
52.219-6	Notice of Total Small Business Set-Aside. (Deviation 2026-O0038)	2026-02
52.222-3	Convict Labor. (Deviation 2026-O0038)	2026-02
52.222-6	Construction Wage Rate Requirements. (Deviation 2026-O0038)	2026-02
52.222-7	Withholding of Funds. (Deviation 2026-O0038)	2026-02
52.222-8	Payrolls and Basic Records. (Deviation 2026-O0038)	2026-02
52.222-9	Apprentices and Trainees. (Deviation 2026-O0038)	2026-02
52.222-10	Compliance with Copeland Act Requirements. (Deviation 2026-O0038)	2026-02
52.222-11	Subcontracts (Labor Standards). (Deviation 2026-O0038)	2026-02

52.222-12	Contract Termination-Debarment.	2014-05
52.222-13	Compliance with Construction Wage Rate Requirements and Related Regulations.	2014-05
52.222-14	Disputes Concerning Labor Standards. (Deviation 2026-O0038)	2026-02
52.222-15	Certification of Eligibility.	2014-05
52.222-35	Equal Opportunity for Veterans. (Deviation 2026-O0038)	2026-02
52.222-36	Equal Opportunity for Workers with Disabilities. (Deviation 2026-O0038)	2026-02
52.222-37	Employment Reports on Veterans. (Deviation 2026-O0038)	2026-02
52.222-50	Combating Trafficking in Persons. (Deviation 2026-O0038)	2026-02
52.222-54	Employment Eligibility Verification. (Deviation 2026-O0038)	2026-02
52.222-55	Minimum Wages for Contractor Workers Under Executive Order 14026. (Deviation 2026-O0038)	2026-02
52.222-62	Paid Sick Leave Under Executive Order 13706. (Deviation 2026-O0038)	2026-02
52.222-90	Addressing DEI Discrimination	2026-04

by Federal Contractors.
(Deviation 2026-O0038)

52.223-2	Reporting of Biobased Products Under Service and Construction Contracts. (Deviation 2026-O0038)	2026-02		
52.223-23	Sustainable Products. (Deviation 2026-O0038)	2026-02		
52.226-8	Encouraging Contractor Policies to Ban Text Messaging While Driving.	2024-05		
52.228-2	Additional Bond Security.	1997-10		
52.228-11	Pledges of Assets (DEVIATION 2020-O0016)	2021-02	Deviation 2020-O0016	2020-04
52.228-12	Prospective Subcontractor Requests for Bonds.	2022-12		
52.228-14	Irrevocable Letter of Credit.	2014-11		
52.228-15	Performance and Payment Bonds-Construction.	2020-06		
52.232-23	Assignment of Claims.	2014-05		
52.232-27	Prompt Payment for Construction Contracts.	2017-01		
52.232-33	Payment by Electronic Funds Transfer-System for Award Management.	2018-10		
52.232-40	Providing Accelerated Payments to Small Business	2023-03		

Subcontractors.

52.233-3	Protest after Award. (Deviation 2026-O0038)	2026-02
52.233-4	Applicable Law for Breach of Contract Claim. (Deviation 2026-O0038)	2026-02
52.236-2	Differing Site Conditions. (Deviation 2026-O0038)	2026-02
52.236-3	Site Investigation and Conditions Affecting the Work. (Deviation 2026-O0038)	2026-02
52.236-5	Material and Workmanship. (Deviation 2026-O0038)	2026-02
52.236-6	Superintendence by the Contractor. (Deviation 2026-O0038)	2026-02
52.236-7	Permits and Responsibilities. (Deviation 2026-O0038)	2026-02
52.236-8	Other Contracts. (Deviation 2026-O0038)	2026-02
52.236-9	Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements. (Deviation 2026-O0038)	2026-02
52.236-10	Operations and Storage Areas. (Deviation 2026-O0038)	2026-02
52.236-11	Use and Possession Prior to Completion. (Deviation 2026-O0038)	2026-02

52.236-12	Cleaning Up. (Deviation 2026-O0038)	2026-02
52.236-13	Accident Prevention. (Deviation 2026-O0038)	2026-02
52.236-14	Availability and Use of Utility Services. (Deviation 2026-O0038)	2026-02
52.236-21	Specifications and Drawings for Construction. (Deviation 2026-O0038)	2026-02
52.240-91	Security Prohibitions and Exclusions. (Deviation 2026-O0038)	2026-02
52.242-14	Suspension of Work.	1984-04
52.243-5	Changes and Changed Conditions. (Deviation 2026-O0038)	2026-02
52.244-6	Subcontracts for Commercial Products and Commercial Services. (Deviation 2026-O0038)	2026-04
52.246-21	Warranty of Construction.	1994-03
52.249-1	Termination for Convenience of the Government (Fixed-Price) (Short Form).	1984-04
52.249-10	Default (Fixed-Price Construction).	1984-04

DFARS Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
252.203-7000	Requirements Relating to Compensation of Former DoD Officials.	2011-09		
252.203-7002	Requirement to Inform Employees of Whistleblower Rights.	2022-12		
252.204-7003	Control of Government Personnel Work Product.	1992-04		
252.204-7004	Antiterrorism Awareness Training for Contractors.	2023-01		
252.204-7012	Safeguarding Covered Defense Information and Cyber Incident Reporting. (DEVIATION 2024-O0013 REVISION 1)	2024-05	Deviation 2024-O0013	2024-05
252.204-7018	Prohibition on the Acquisition of Covered Defense Telecommunications Equipment or Services.	2023-01		
252.204-7020	NIST SP 800-171 DoD Assessment Requirements.	2023-11		
252.209-7004	Subcontracting with Firms that are Owned or Controlled by the Government of a Country that is a State Sponsor of Terrorism.	2019-05		
252.223-7006	Prohibition on Storage, Treatment, and Disposal of Toxic or Hazardous Materials.	2014-09		

252.223-7008	Prohibition of Hexavalent Chromium.	2023-01		
252.225-7012	Preference for Certain Domestic Commodities.	2022-04		
252.225-7048	Export-Controlled Items.	2013-06		
252.225-7056	Prohibition Regarding Business Operations with the Maduro Regime.	2023-01		
252.225-7060	Prohibition on Certain Procurements from the Xinjiang Uyghur Autonomous Region.	2023-06		
252.232-7004	DoD Progress Payment Rates (DEVIATION 2020-O0010)	2014-10	Deviation 2020- O0010	2020-03
252.232-7010	Levies on Contract Payments.	2006-12		
252.237-7010	Prohibition on Interrogation of Detainees by Contractor Personnel.	2023-01		
252.243-7001	Pricing of Contract Modifications.	1991-12		
252.244-7999	Subcontracts for Commercial Products or Commercial Services. (DEVIATION 2026-O0015)	2026-02	Deviation 2026- O0015	2026-01
252.247-7023	Transportation of Supplies by Sea.	2024-10		

FAR Clauses Incorporated by Full Text

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
--------	-------	----------------	---------------------	--------------------------

52.213-4	Terms and Conditions-Simplified Acquisitions (Noncommercial). (Deviation 2026-O0038)	2026-02		
----------	---	---------	--	--

Terms and Conditions-Simplified Acquisitions (Noncommercial) (Feb 2026) (Deviation 2026-O0038)

(a) DELETED

(b) *Excusable delays.* The Contractor shall be liable for default unless nonperformance is caused by an occurrence beyond the reasonable control of the Contractor and without its fault or negligence. Examples of occurrences include acts of God or the public enemy, acts of the Government in either its sovereign or contractual capacity, fires, floods, epidemics, quarantine restrictions, strikes, unusually severe weather, and delays of common carriers. When an excusable delay occurs, the Contractor shall-

(1) Notify the Contracting Officer in writing as soon as possible;

(2) Remedy the delay as quickly as possible; and

(3) Notify the Contracting Officer when the occurrence is over.

(c) DELETED

(d) DELETED

(e) DELETED

(End of clause)

52.219-28	Postaward Small Business Program Rerepresentation. (Deviation 2026-O0038)	2026-02		
-----------	--	---------	--	--

Postaward Small Business Program Rerepresentation (Feb 2026) (Deviation 2026-O0038)

(a) *Definitions.* As used in this clause-

Long-term contract means a contract of more than five years in duration, including options. However, the term does not include contracts that exceed five years in duration because the period of performance has been extended for a cumulative period not to exceed six months under the clause at 52.217-8, Option to Extend Services, or other appropriate authority.

Small business concern-

(1) Means a concern, including its affiliates, that is independently owned and operated, not dominant in its field of operation, and qualified as a small business under the criteria in 13 CFR part 121 and the size standard in paragraph (c) of this clause.

(2) *Affiliates*, as used in this definition, means business concerns, one of whom directly or indirectly controls or has the power to control the others, or a third party or parties control or have the power to control the others. In determining whether affiliation exists, consideration is given to all appropriate factors including common ownership, common management, and contractual relationships. SBA determines affiliation based on the factors set forth at 13 CFR 121.103.

(b) If the Contractor represented that it was a small business concern, a small disadvantaged business concern, or a joint venture that was any of the small business concerns identified in 19.000(a)(3) prior to award of this contract, the Contractor shall rerepresent its size and socioeconomic status according to paragraph (e) of this clause or, if applicable, paragraph (g) of this clause, upon occurrence of any of the following:

(1) Within 30 days after execution of a novation agreement or within 30 days after modification of the contract to include this clause, if the novation agreement was executed prior to inclusion of this clause in the contract.

(2) Within 30 days after a merger or acquisition that does not require a novation or within 30 days after modification of the contract to include this clause, if the merger or acquisition occurred prior to inclusion of this clause in the contract.

(3) For long-term contracts-

(i) Within 60 to 120 days prior to the end of the fifth year of the contract; and

(ii) Within 60 to 120 days prior to the date specified in the contract for exercising any option thereafter.

(c) The Contractor shall rerepresent its size status in accordance with the size standard in effect at the time of this rerepresentation that corresponds to the North American Industry Classification System (NAICS) code(s) assigned to this contract. The small business size standard corresponding to this NAICS code(s) can be found at <https://www.sba.gov/document/support-table-size-standards>.

(d) The small business size standard for a Contractor providing an end item that it does not manufacture, process, or produce itself, for a contract other than a construction or service

contract, is 500 employees, or 150 employees for information technology value-added resellers under NAICS code 541519, if the acquisition-

(1) Was set aside for small business and has a value above the simplified acquisition threshold;

(2) Used the HUBZone price evaluation preference regardless of dollar value, unless the Contractor waived the price evaluation preference; or

(3) Was an 8(a), HUBZone, service-disabled veteran-owned, economically disadvantaged women-owned, or women-owned small business set-aside or sole-source award regardless of dollar value.

(e) Except as provided in paragraph (g) of this clause, the Contractor shall make the representation(s) required by paragraph (b) of this clause by validating or updating all its representations in the Representations and Certifications section of the System for Award Management (SAM) and its other data in SAM, as necessary, to ensure that they reflect the Contractor's current status. The Contractor shall notify the contracting officer in writing within the timeframes specified in paragraph (b) of this clause, that the data have been validated or updated, and provide the date of the validation or update.

(f) If the Contractor represented that it was other than a small business concern prior to award of this contract, the Contractor may, but is not required to, take the actions required by paragraphs (e) or (g) of this clause.

(g) If the Contractor does not have representations and certifications in SAM, or does not have a representation in SAM for the NAICS code applicable to this contract, the Contractor is required to complete the following rerepresentation and submit it to the contracting office, along with the contract number and the date on which the rerepresentation was completed:

(1) The Contractor represents that it is, is not a small business concern under 238220 NAICS Code assigned to W912WJ26PXXXX contract number.

(2) *[Complete only if the Contractor represented itself as a small business concern in paragraph (g)(1) of this clause.]* The Contractor represents that it is, is not, a small disadvantaged business concern as defined in 13 CFR 124.1001.

(3) *Women-owned small business (WOSB) joint venture eligible under the WOSB Program.* The Contractor represents that it is, is not a joint venture that complies with the requirements of 13 CFR 127.506(a) through (c). [____ The Contractor shall enter the name and unique entity identifier of each party to the joint venture: ____.]

(4) *Economically disadvantaged women-owned small business (EDWOSB) joint venture.* The Contractor represents that it is, is not a joint venture that complies with the requirements of 13 CFR 127.506(a) through (c). [____ The Contractor shall enter the name and unique entity identifier of each party to the joint venture: ____ .]

(5) *Service-disabled veteran-owned small business (SDVOSB) joint venture eligible under the SDVOSB Program.* The Contractor represents that it is, is not an SDVOSB joint venture eligible under the SDVOSB Program that complies with the requirements of 13 CFR 128.402. [____] The Contractor shall enter the name and unique entity identifier of each party to the joint venture: ____.]

(6) *HUBZone joint venture eligible under the HUBZone Program.* [*Complete only if the offeror is a HUBZone small business concern.*] The offeror represents, as part of its offer, that It is, is not a HUBZone joint venture that complies with the requirements of 13 CFR 126.616(a) through (c). [____] The Contractor shall enter the name and unique entity identifier of each party to the joint venture: .] Each HUBZone small business concern participating in the HUBZone joint venture must be certified as a HUBZone concern. [____] Contractor to sign and date and insert authorized signer's name and title.]

(End of clause)

52.223-9	Estimate of Percentage of Recovered Material Content for EPA-Designated Items.	2008-05
----------	--	---------

Estimate of Percentage of Recovered Material Content for EPA-Designated Items (May 2008)

(a) *Definitions.* As used in this clause-

Postconsumer material means a material or finished product that has served its intended use and has been discarded for disposal or recovery, having completed its life as a consumer item. Postconsumer material is a part of the broader category of "recovered material."

"Recovered material" means waste materials and by-products recovered or diverted from solid waste, but the term does not include those materials and by-products generated from, and commonly reused within, an original manufacturing process.

(b) The Contractor, on completion of this contract, shall-

(1) Estimate the percentage of the total recovered material content for EPA-designated item(s) delivered and/or used in contract performance, including, if applicable, the percentage of post-consumer material content; and

(2) Submit this estimate to the Technical Point of Contact.

(End of clause)

52.225-9 Buy American-Construction 2026-02
Materials. (Deviation 2026-
O0038)

Buy American-Construction Materials (Feb 2026) (Deviation 2026-O0038)

(a) *Definitions.* As used in this clause-

Commercially available off-the-shelf (COTS) item-

(1) Means any item of supply (including construction material) that is-

(i) A commercial product (as defined in paragraph (1) of the definition of "commercial product" at Federal Acquisition Regulation (FAR) 2.101);

(ii) Sold in substantial quantities in the commercial marketplace; and

(iii) Offered to the Government, under a contract or subcontract at any tier, without modification, in the same form in which it is sold in the commercial marketplace; and

(2) Does not include bulk cargo, as defined in 46 U.S.C. 40102(4), such as agricultural products and petroleum products.

"Construction material" means an article, material, or supply brought to the construction site by the Contractor or a subcontractor for incorporation into the building or work. The term also includes an item brought to the site preassembled from articles, materials, or supplies. However, emergency life safety systems, such as emergency lighting, fire alarm, and audio evacuation systems, that are discrete systems incorporated into a public building or work and that are produced as complete systems, are evaluated as a single and distinct construction material regardless of when or how the individual parts or components of those systems are delivered to the construction site. Materials purchased directly by the Government are supplies, not construction material.

Cost of components means-

(1) For components purchased by the Contractor, the acquisition cost, including transportation costs to the place of incorporation into the construction material (whether or not such costs are paid to a domestic firm), and any applicable duty (whether or not a duty-free entry certificate is issued); or

(2) For components manufactured by the Contractor, all costs associated with the manufacture of the component, including transportation costs as described in paragraph (1) of this definition, plus allocable overhead costs, but excluding profit. Cost of components does not include any costs associated with the manufacture of the construction material.

Critical component means a component that is mined, produced, or manufactured in the United States and deemed critical to the U.S. supply chain. The list of critical components is at FAR 25.105.

Critical item means a domestic construction material or domestic end product that is deemed critical to U.S. supply chain resiliency. The list of critical items is at FAR 25.105.

Domestic construction material means-

(1) For construction material that does not consist wholly or predominantly of iron or steel or a combination of both-

(i) An unmanufactured construction material mined or produced in the United States; or

(ii) A construction material manufactured in the United States, if-

(A) The cost of its components mined, produced, or manufactured in the United States exceeds 60 percent of the cost of all its components, except that the percentage will be 65 percent for items delivered in calendar years 2024 through 2028 and 75 percent for items delivered starting in calendar year 2029. Components of foreign origin of the same class or kind for which nonavailability determinations have been made are treated as domestic. Components of unknown origin are treated as foreign; or

(B) The construction material is a COTS item; or

(2) For construction material that consists wholly or predominantly of iron or steel or a combination of both, a construction material manufactured in the United States if the cost of foreign iron and steel constitutes less than 5 percent of the cost of all components used in such construction material. The cost of foreign iron and steel includes but is not limited to the cost of foreign iron or steel mill products (such as bar, billet, slab, wire, plate, or sheet), castings, or forgings utilized in the manufacture of the construction material and a good faith estimate of the cost of all foreign iron or steel components excluding COTS fasteners. Iron or steel components of unknown origin are treated as foreign. If the construction material contains multiple components, the cost of all the materials used in such construction material is calculated in accordance with the definition of "cost of components".

Fastener means a hardware device that mechanically joins or affixes two or more objects together. Examples of fasteners are nuts, bolts, pins, rivets, nails, clips, and screws.

Foreign construction material means a construction material other than a domestic construction material.

Foreign iron and steel means iron or steel products not produced in the United States. Produced in the United States means that all manufacturing processes of the iron or steel must take place in the United States, from the initial melting stage through the application of coatings,

except metallurgical processes involving refinement of steel additives. The origin of the elements of the iron or steel is not relevant to the determination of whether it is domestic or foreign.

Predominantly of iron or steel or a combination of both means that the cost of the iron and steel content exceeds 50 percent of the total cost of all its components. The cost of iron and steel is the cost of the iron or steel mill products (such as bar, billet, slab, wire, plate, or sheet), castings, or forgings utilized in the manufacture of the product and a good faith estimate of the cost of iron or steel components excluding COTS fasteners.

Steel means an alloy that includes at least 50 percent iron, between 0.02 and 2 percent carbon, and may include other elements.

"United States" means the 50 States, the District of Columbia, and outlying areas.

(b) Domestic preference.

(1) This clause implements 41 U.S.C. chapter 83, Buy American, by providing a preference for domestic construction material. In accordance with 41 U.S.C. 1907, the domestic content test of the Buy American statute is waived for construction material that is a COTS item, except that for construction material that consists wholly or predominantly of iron or steel or a combination of both, the domestic content test is applied only to the iron and steel content of the construction materials, excluding COTS fasteners. The Contractor shall use only domestic construction material in performing this contract, except as provided in paragraphs (b)(2) and (b)(3) of this clause.

(2) This requirement does not apply to information technology that is a commercial product or to the construction materials or components listed by the Government as follows:

Heat Pumps - Determination of COTS items

(3) The Contracting Officer may add other foreign construction material to the list in paragraph (b)(2) of this clause if the Government determines that-

(i) The cost of domestic construction material would be unreasonable.

(A) *For domestic construction material that is not a critical item or does not contain critical components.*

(1) The cost of a particular domestic construction material subject to the requirements of the Buy American statute is unreasonable when the cost of such material exceeds the cost of foreign material by more than 20 percent;

(2) For construction material that is not a COTS item and does not consist wholly or predominantly of iron or steel or a combination of both, if the cost of a particular domestic construction material is determined to be unreasonable or there is no domestic offer received, and the low offer is for foreign construction material that is manufactured in the United States

and does not exceed 55 percent domestic content, the Contracting Officer will treat the lowest offer of foreign construction material that exceeds 55 percent domestic content as a domestic offer and determine whether the cost of that offer is unreasonable by applying the evaluation factor listed in paragraph (b)(3)(i)(A)(1) of this clause.

(3) The procedures in paragraph (b)(3)(i)(A)(2) of this clause will no longer apply as of January 1, 2030.

(B) For domestic construction material that is a critical item or contains critical components.

(1) The cost of a particular domestic construction material that is a critical item or contains critical components, subject to the requirements of the Buy American statute, is unreasonable when the cost of such material exceeds the cost of foreign material by more than 20 percent plus the additional preference factor identified for the critical item or construction material containing critical components listed at FAR 25.105.

(2) For construction material that does not consist wholly or predominantly of iron or steel or a combination of both, if the cost of a particular domestic construction material is determined to be unreasonable or there is no domestic offer received, and the low offer is for foreign construction material that does not exceed 55 percent domestic content, the Contracting Officer will treat the lowest foreign offer of construction material that is manufactured in the United States and exceeds 55 percent domestic content as a domestic offer, and determine whether the cost of that offer is unreasonable by applying the evaluation factor listed in paragraph (b)(3)(i)(B)(1) of this clause.

(3) The procedures in paragraph (b)(3)(i)(B)(2) of this clause will no longer apply as of January 1, 2030.

(ii) The application of the restriction of the Buy American statute to a particular construction material would be impracticable or inconsistent with the public interest; or

(iii) The construction material is not mined, produced, or manufactured in the United States in sufficient and reasonably available commercial quantities of a satisfactory quality.

(c) Request for determination of inapplicability of the Buy American statute.

(1)

(i) Any Contractor request to use foreign construction material in accordance with paragraph (b)(3) of this clause shall include adequate information for Government evaluation of the request, including-

(A) A description of the foreign and domestic construction materials;

(B) Unit of measure;

(C) Quantity;

(D) Price;

(E) Time of delivery or availability;

(F) Location of the construction project;

(G) Name and address of the proposed supplier; and

(H) A detailed justification of the reason for use of foreign construction materials cited in accordance with paragraph (b)(3) of this clause.

(ii) A request based on unreasonable cost shall include a reasonable survey of the market and a completed price comparison table in the format in paragraph (d) of this clause.

(iii) The price of construction material shall include all delivery costs to the construction site and any applicable duty (whether or not a duty-free certificate may be issued).

(iv) Any Contractor request for a determination submitted after contract award shall explain why the Contractor could not reasonably foresee the need for such determination and could not have requested the determination before contract award. If the Contractor does not submit a satisfactory explanation, the Contracting Officer need not make a determination.

(2) If the Government determines after contract award that an exception to the Buy American statute applies and the Contracting Officer and the Contractor negotiate adequate consideration, the Contracting Officer will modify the contract to allow use of the foreign construction material. However, when the basis for the exception is the unreasonable price of a domestic construction material, adequate consideration is not less than the differential established in paragraph (b)(3)(i) of this clause.

(3) Unless the Government determines that an exception to the Buy American statute applies, use of foreign construction material is noncompliant with the Buy American statute or Balance of Payments Program.

(d) *Data*. To permit evaluation of requests under paragraph (c) of this clause based on unreasonable cost, the Contractor shall include the following information and any applicable supporting data based on the survey of suppliers:

Foreign and Domestic Construction Materials Price Comparison			
Construction material description	Unit of measure	Quantity	Price (dollars)*
Item 1:			

Foreign construction material.	_____	_____	_____
Domestic construction material.	_____	_____	_____
Item 2:			
Foreign construction material.		_____	_____
Domestic construction material.	_____	_____	_____
<i>[* Include all delivery costs to the construction site and any applicable duty (whether or not a duty-free entry certificate is issued)].</i> <i>[List name, address, telephone number, and contact for suppliers surveyed. Attach copy of response; if oral, attach summary.]</i> <i>[Include other applicable supporting information.]</i>			

(End of clause)

52.232-5 Payments under Fixed-Price 2014-05
Construction Contracts.

Payments under Fixed-Price Construction Contracts (May 2014)

(a) Payment of price. The Government shall pay the Contractor the contract price as provided in this contract.

(b) Progress payments. The Government shall make progress payments monthly as the work proceeds, or at more frequent intervals as determined by the Contracting Officer, on estimates of work accomplished which meets the standards of quality established under the contract, as approved by the Contracting Officer.

(1) The Contractor's request for progress payments shall include the following substantiation:

(i) An itemization of the amounts requested, related to the various elements of work required by the contract covered by the payment requested.

(ii) A listing of the amount included for work performed by each subcontractor under the contract.

(iii) A listing of the total amount of each subcontract under the contract.

(iv) A listing of the amounts previously paid to each such subcontractor under the contract.

(v) Additional supporting data in a form and detail required by the Contracting Officer.

(2) In the preparation of estimates, the Contracting Officer may authorize material delivered on the site and preparatory work done to be taken into consideration. Material delivered to the Contractor at locations other than the site also may be taken into consideration if-

(i) Consideration is specifically authorized by this contract; and

(ii) The Contractor furnishes satisfactory evidence that it has acquired title to such material and that the material will be used to perform this contract.

(c) Contractor certification. Along with each request for progress payments, the Contractor shall furnish the following certification, or payment shall not be made: (However, if the Contractor elects to delete paragraph (c)(4) from the certification, the certification is still acceptable.)

I hereby certify, to the best of my knowledge and belief, that-

(1) The amounts requested are only for performance in accordance with the specifications, terms, and conditions of the contract;

(2) All payments due to subcontractors and suppliers from previous payments received under the contract have been made, and timely payments will be made from the proceeds of the payment covered by this certification, in accordance with subcontract agreements and the requirements of Chapter 39 of Title 31, United States Code;

(3) This request for progress payments does not include any amounts which the prime contractor intends to withhold or retain from a subcontractor or supplier in accordance with the terms and conditions of the subcontract; and

(4) This certification is not to be construed as final acceptance of a subcontractor's performance.

____ (Name)

____ (Title)

____ (Date)

(d) Refund of unearned amounts. If the Contractor, after making a certified request for progress payments, discovers that a portion or all of such request constitutes a payment for performance by the Contractor that fails to conform to the specifications, terms, and conditions of this contract (hereinafter referred to as the "unearned amount"), the Contractor shall-

(1) Notify the Contracting Officer of such performance deficiency; and

(2) Be obligated to pay the Government an amount (computed by the Contracting Officer in the manner provided in paragraph (j) of this clause) equal to interest on the unearned amount from the 8th day after the date of receipt of the unearned amount until-

(i) The date the Contractor notifies the Contracting Officer that the performance deficiency has been corrected; or

(ii) The date the Contractor reduces the amount of any subsequent certified request for progress payments by an amount equal to the unearned amount.

(e) Retainage. If the Contracting Officer finds that satisfactory progress was achieved during any period for which a progress payment is to be made, the Contracting Officer shall authorize payment to be made in full. However, if satisfactory progress has not been made, the Contracting Officer may retain a maximum of 10 percent of the amount of the payment until satisfactory progress is achieved. When the work is substantially complete, the Contracting

Officer may retain from previously withheld funds and future progress payments that amount the Contracting Officer considers adequate for protection of the Government and shall release to the Contractor all the remaining withheld funds. Also, on completion and acceptance of each separate building, public work, or other division of the contract, for which the price is stated separately in the contract, payment shall be made for the completed work without retention of a percentage.

(f) Title, liability, and reservation of rights. All material and work covered by progress payments made shall, at the time of payment, become the sole property of the Government, but this shall not be construed as-

(1) Relieving the Contractor from the sole responsibility for all material and work upon which payments have been made or the restoration of any damaged work; or

(2) Waiving the right of the Government to require the fulfillment of all of the terms of the contract.

(g) Reimbursement for bond premiums. In making these progress payments, the Government shall, upon request, reimburse the Contractor for the amount of premiums paid for performance and payment bonds (including coinsurance and reinsurance agreements, when applicable) after the Contractor has furnished evidence of full payment to the surety. The retainage provisions in paragraph (e) of this clause shall not apply to that portion of progress payments attributable to bond premiums.

(h) Final payment. The Government shall pay the amount due the Contractor under this contract after-

(1) Completion and acceptance of all work;

(2) Presentation of a properly executed voucher; and

(3) Presentation of release of all claims against the Government arising by virtue of this contract, other than claims, in stated amounts, that the Contractor has specifically excepted from the operation of the release. A release may also be required of the assignee if the Contractor's claim to amounts payable under this contract has been assigned under the Assignment of Claims Act of 1940 (31 U.S.C.3727 and 41 U.S.C. 6305).

(i) Limitation because of undefinitized work. Notwithstanding any provision of this contract, progress payments shall not exceed 80 percent on work accomplished on undefinitized contract

actions. A "contract action" is any action resulting in a contract, as defined in FAR subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes.

(j) Interest computation on unearned amounts. In accordance with 31 U.S.C. 3903(c)(1), the amount payable under paragraph (d)(2) of this clause shall be-

(1) Computed at the rate of average bond equivalent rates of 91-day Treasury bills auctioned at the most recent auction of such bills prior to the date the Contractor receives the unearned amount; and

(2) Deducted from the next available payment to the Contractor.

(End of clause)

52.252-2	Clauses Incorporated by Reference.	1998-02
----------	---------------------------------------	---------

Clauses Incorporated By Reference (Feb 1998)

This contract incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of a clause may be accessed electronically at this/these address(es):

<https://www.acquisition.gov/>

(End of clause)

52.252-6	Authorized Deviations in Clauses.	2020-11
----------	-----------------------------------	---------

Authorized Deviations in Clauses (Nov 2020)

(a) The use in this solicitation or contract of any Federal Acquisition Regulation (48 CFR Chapter 1) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the date of the clause.

(b) The use in this solicitation or contract of any DFARS (48 CFR Chapter 2) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the name of the regulation.

(End of clause)

DFARS Clauses Incorporated by Full Text

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
252.236-7001	Contract Drawings and Specifications.	2000-08		

CONTRACT DRAWINGS AND SPECIFICATIONS (AUG 2000)

(a) The Government will provide to the Contractor, without charge, one set of contract drawings and specifications, except publications incorporated into the technical provisions by reference, in electronic or paper media as chosen by the Contracting Officer.

(b) The Contractor shall-

- (1) Check all drawings furnished immediately upon receipt;
- (2) Compare all drawings and verify the figures before laying out the work;
- (3) Promptly notify the Contracting Officer of any discrepancies;

(4) Be responsible for any errors that might have been avoided by complying with this paragraph (b); and

- (5) Reproduce and print contract drawings and specifications as needed.

(c) In general--

(1) Large-scale drawings shall govern small-scale drawings; and

(2) The Contractor shall follow figures marked on drawings in preference to scale measurements.

(d) Omissions from the drawings or specifications or the misdescription of details of work that are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.

(e) The work shall conform to the specifications and the contract drawings identified on the following index of drawings:

Title	File	Drawing No.
<u>Attachments Photos</u> <u>26QA095</u>	<u>Photos 1-18</u>	_____
<u>Attachments Drawings</u> <u>26QA095</u>	<u>Pages 1-8</u>	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

(End of clause)

Section K - Representations, Certification, & Other Statements

FAR Provisions Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
52.223-1	Biobased Product Certification. (Deviation 2026-O0038)	2026-02		
52.223-4	Recovered Material Certification.	2008-05		

DFARS Provisions Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
252.203-7005	Representation Relating to Compensation of Former DoD Officials.	2022-09		
252.204-7008	Compliance with Safeguarding Covered Defense Information Controls.	2016-10		
252.225-7055	Representation Regarding Business Operations with the Maduro Regime.	2022-05		
252.225-7059	Prohibition on Certain Procurements from the Xinjiang Uyghur Autonomous Region-Representation.	2023-06		

DFARS Provisions Incorporated by Full Text

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
252.204-7017	Prohibition on the Acquisition of Covered Defense Telecommunications Equipment or Services-Representation.	2021-05		

PROHIBITION ON THE ACQUISITION OF COVERED DEFENSE TELECOMMUNICATIONS EQUIPMENT OR SERVICES-REPRESENTATION (MAY 2021)

The Offeror is not required to complete the representation in this provision if the Offeror has represented in the provision at 252.204-7016, Covered Defense Telecommunications Equipment or Services-Representation, that it "does not provide covered defense telecommunications equipment or services as a part of its offered products or services to the Government in the performance of any contract, subcontract, or other contractual instrument."

(a) Definitions. "Covered defense telecommunications equipment or services," "covered mission," "critical technology," and "substantial or essential component," as used in this provision, have the meanings given in the 252.204-7018 clause, Prohibition on the Acquisition of Covered Defense Telecommunications Equipment or Services, of this solicitation.

(b) Prohibition. Section 1656 of the National Defense Authorization Act for Fiscal Year 2018 (Pub. L. 115-91) prohibits agencies from procuring or obtaining, or extending or renewing a contract to procure or obtain, any equipment, system, or service to carry out covered missions that uses covered defense telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system.

(c) Procedures. The Offeror shall review the list of excluded parties in the System for Award Management (SAM) at <https://www.sam.gov> for entities that are excluded when providing any equipment, system, or service to carry out covered missions that uses covered defense telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system, unless a waiver is granted.

(d) Representation. If in its annual representations and certifications in SAM the Offeror has represented in paragraph (c) of the provision at 252.204-7016, Covered Defense Telecommunications Equipment or Services-Representation, that it "does" provide covered defense telecommunications equipment or services as a part of its offered products or services to the Government in the performance of any contract, subcontract, or other contractual instrument, then the Offeror shall complete the following additional representation:

The Offeror represents that it ☐ will ☐ will not provide covered defense telecommunications equipment or services as a part of its offered products or services to DoD in the performance of any award resulting from this solicitation.

(e) Disclosures. If the Offeror has represented in paragraph (d) of this provision that it "will provide covered defense telecommunications equipment or services," the Offeror shall provide the following information as part of the offer:

(1) A description of all covered defense telecommunications equipment and services offered (include brand or manufacturer; product, such as model number, original equipment manufacturer (OEM) number, manufacturer part number, or wholesaler number; and item description, as applicable).

(2) An explanation of the proposed use of covered defense telecommunications equipment and services and any factors relevant to determining if such use would be permissible under the prohibition referenced in paragraph (b) of this provision.

(3) For services, the entity providing the covered defense telecommunications services (include entity name, unique entity identifier, and Commercial and Government Entity (CAGE) code, if known).

(4) For equipment, the entity that produced or provided the covered defense telecommunications equipment (include entity name, unique entity identifier, CAGE code, and whether the entity was the OEM or a distributor, if known).

(End of provision)

Section L - Instructions, Conditions, & Notices to Offerors or Quoters

INSTRUCTIONS TO VENDORS:

VENDORS SUBMITTING A QUOTE IN RESPONSE TO A SOLICITATION ARE RESPONSIBLE FOR ADHERING TO ALL INSTRUCTIONS AND TERMS AND CONDITIONS INCLUDED IN THE SOLICITATION. FAILURE TO DO SO MAY RESULT IN QUOTES BEING DEEMED NON-RESPONSIVE

INFORMATION:

1. This is a Request for Quotations (RFQ) in accordance with Revolutionary Federal Acquisition Regulation Overhaul (RFO) Part 13.
2. The Government may perform a comparative evaluation (comparing quotations to each other) to select the contractor that is best suited and provides the best value, considering the evaluation factors in this solicitation.
3. Evaluation factors will be technical, price, and past performance. Failure to provide sufficient documentation for Government evaluation for these factors with quote submission shall result in a quote being deemed non-responsive.
4. All responsible sources may submit a quote which, if timely received, must be considered by the Agency.
5. The Government may request that a vendor respond to a Quote Verification after the solicitation closes, but prior to award. The vendor shall respond in sufficient detail to all questions or statements no later than the response date and time listed in the correspondence. Failure to do so may result in quotes being deemed non-responsive and removed from consideration. The Government is under no obligation to provide extensions for responses.

QUESTIONS REGARDING SOLICITATIONS:

1. Questions regarding the solicitation shall be directed to the Contract Specialist:
 - a. Name: Alicia N. LaCrosse
 - b. Phone: 978-318-8902
 - c. Email: Alicia.N.LaCrosse@usace.army.mil
2. Technical Points of Contact shall not provide responses to interested vendors.
3. Please direct questions to the Contract Specialist. Any information received at the site visit which conflicts with this solicitation should be brought to the attention of the Contract Specialist. The solicitation and resulting contract shall be the governing document in all cases.

QUOTE SUBMISSION:

1. Quotes shall be submitted via email to the Contract Specialist listed above no later than the closing date and time identified in the solicitation or subsequent amendments.
2. The Government is under no obligation to consider any quote received after the solicitation closing date or time.
3. Interested vendors shall submit signed copies of all material amendments (SF30) with their quotes. Failure to do so will result in quotes being deemed non-responsive and removed from consideration.

BID SCHEDULES:

1. If a Bid Schedule is included in the solicitation, vendors shall complete the bid schedule in its entirety (all tasks, all years).
2. Vendors shall enter \$0.00 on Bid Schedules in which items are Not Separately Priced. Blank entries will not be considered and will result in quotes being deemed non-responsive.
3. Failure to complete the Bid Schedule in its entirety and return same with a quote will result in quotes being deemed non-responsive.
4. When Bid Schedules or Contract Line Item Numbers (CLINs) require unit pricing and total amounts, unit pricing shall govern in case of discrepancy between unit prices and total amounts.

SITE VISITS:

1. SITE VISITS ARE HIGHLY RECOMMENDED PRIOR TO PROVIDING A QUOTE.
2. If date(s)/time(s) for site visits are included in the solicitation, then interested vendors will be permitted to visit the site during those dates/times. No other dates/times will be permitted for site visits.
3. If no dates/times for site visits are included in the solicitation, then interested vendors shall contact the Technical Point of Contact as identified in the solicitation to schedule a site visit.
4. No site visits will be permitted AFTER a solicitation closes.

BONDING:

1. In accordance with FAR 28.101-1(a), the Contractor will NOT be required to provide a Bid Guarantee.
2. In accordance with FAR 28.102-2(b), the Contractor will be required to provide the following payment protections for all construction contracts at or above \$150,000.00.

- (i) Payment Bond or
- (ii) Irrevocable Letter of Credit and
- (iii) Performance Bond

A Payment Bond or Irrevocable Letter of Credit is the SELECTED payment protection for the Government. The penal amount of bond shall be 100% of the original contract price. If the contract price increases, the Government will require an increase in the penal sum of the existing bond. This bond shall be submitted to the Contracting Officer within 10 days after receipt of award.

A Performance Bond shall be required if the total price of the quote is \$150,000.00 or above. The penal amount of the Performance Bond shall be 100% of the original contract price. If the contract price increases, the Government will require an increase in the penal sum of the existing bond. This bond shall also be submitted to the Contracting Officer within 10 days after receipt of award.

3. In accordance with FAR Part 28.102-2(c), the Contractor will be required to provide one of the following payment protections for all construction contracts \$35,000.00 or above, but not exceeding \$150,000.00.

- (i) Payment bond or
- (ii) Irrevocable letter of credit

A Payment Bond or Irrevocable Letter of Credit is the SELECTED payment protection for the Government. The penal amount of bond shall be 100% of the original contract price. If the contract price increases, the Government will require an increase in the penal sum of the existing bond. This bond shall be submitted to the Contracting Officer within 10 days after receipt of award.

****No Payment Protections Required for construction contracts less than \$35,000****

4. Prior to award, the Government may request that the Contractor provide a Letter of Bond Ability issued by a Surety that is listed on US Treasury Circular 570 (<https://www.fiscal.treasury.gov/surety-bonds/list-certified-companies.html>).

Letter of Bond Ability shall be issued to the Contractor and shall state that the Contractor is pre-qualified for bonding, include the single and aggregate bond limits that the bond company will support, and provide contact information of the bond agent or attorney-in-fact.

Failure to provide a Letter of Bond Ability as required will result in the Contractor's quote being deemed non-responsive.

QUOTATION INSTRUCTIONS:

1. If subcontractor will be used for this work, please provide company name and contact information: _____

2. In accordance with FAR Part 52.204-7(b)(1) Contractors must be registered in the System for Award Management (SAM) database (www.SAM.gov) to submit a quote. Registered is considered when a SAM registration is marked "Active".

3. Representations and Certifications are to be completed in www.sam.gov.

NOTE: SAM.gov registration takes approximately 3 weeks (Unique Entity Identified (UEI) 1-2 business days; CAGE code validation up to 10 business days; IRS validation and overall submission 7-10 business days). It is the contractor's responsibility to track SAM.gov registration and follow-up with required tasks.

4. Provide business Unique Entity Identifier (UEI): _____

5. Provide business CAGE code: _____

*** END OF NARRATIVE ***

FAR Provisions Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
52.203-18	Prohibition on Contracting with Entities that Require Certain Internal Confidentiality Agreements or Statements-Representation.	2017-01		
52.204-7	System for Award Management-Registration. (Deviation 2026-O0038)	2026-02		
52.222-5	Construction Wage Rate Requirements-Secondary Site of the Work. (Deviation 2026-O0038)	2026-02		

DFARS Provisions Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
252.204-7019	Notice of NIST SP 800-171 DoD Assessment Requirements.	2023-11		
252.204-7024	Notice on the Use of the Supplier Performance Risk System.	2023-03		

FAR Provisions Incorporated by Full Text

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
52.252-1	Solicitation Provisions Incorporated by Reference.	1998-02		

Solicitation Provisions Incorporated by Reference (Feb 1998)

This solicitation incorporates one or more solicitation provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. The offeror is cautioned that the listed provisions may include blocks that must be completed by the offeror and submitted with its quotation or offer. In lieu of submitting the full text of those provisions, the offeror may identify the provision by paragraph identifier and provide the appropriate information with its quotation or offer. Also, the full text of a solicitation provision may be accessed electronically at this/these address(es):

<https://www.acquisition.gov/>

(End of provision)

52.252-5	Authorized Deviations in Provisions.	2020-11		
----------	--------------------------------------	---------	--	--

Authorized Deviations in Provisions (Nov 2020)

(a) The use in this solicitation of any Federal Acquisition Regulation (48 CFR Chapter 1) provision with an authorized deviation is indicated by the addition of "(DEVIATION)" after the date of the provision.

(b) The use in this solicitation of any DFARS (48 CFR Chapter 2) provision with an authorized deviation is indicated by the addition of "(DEVIATION)" after the name of the regulation.

(End of provision)

Section M - Evaluation Factors for Award

Evaluation--Noncommercial Acquisitions under Revolutionary Federal Acquisition Regulation Overhaul (RFO) Part 13

1. Addendum. The Government may perform a comparative evaluation (comparing quotes to each other) to select the contractor that is best suited and can perform work at a fair and reasonable price, considering the evaluation factors in this solicitation.

a. Potential vendors are notified that the evaluation factors shall be technical, price, and past performance.

b. By submission of its quote, the vendor agrees to comply with all solicitation requirements, including terms and conditions, representations and certifications, and technical requirements, in addition to those identified as evaluation factors.

2. Evaluation factors. The Government will award a Purchase Order resulting from this solicitation to the responsible vendor whose quotation conforms to the solicitation and is most advantageous to the Government, price and other factors considered. The following factors will be used to evaluate quotes:

a. Technical

b. Price

c. Past Performance

3. Options (if applicable). The Government will evaluate quotes for award purposes by adding the total price for all options to the total price for the basic requirement. The Government may determine that a quote is unacceptable if the option prices are significantly unbalanced. The evaluation of options does not obligate the Government to exercise the option(s).

4. Evaluation process.

a. Step 1 - Evaluate all quotes for responsiveness and reject quotes not considered responsive.

b. Step 2 - The Government may perform a comparative evaluation of all quotes deemed responsive.

c. Step 3 - Contracting Officer will follow award process.

A. Action/Step-1 (Responsiveness).

i. Initially, the Government will verify the quote is signed, via SF18, blocks 14-16, and signed copies of all material amendments have been submitted. If the SF18 is signed and signed copies of material amendments have been included, the evaluation will continue. If the SF18 blocks 14-16

are not completed, and/or material amendments not signed and returned, the quote will be determined non-responsive, and quote will be eliminated from any further evaluation.

ii. Government will then verify vendor's quote has fully provided all requirements stated above in Section L. If the quote schedule is not completed, the quote will be determined non-responsive, and quote will be eliminated from any further evaluation.

iii. Government will then verify quoter's Technical factors information requested in the Solicitation Survey is fully provided. Per solicitation requirements, if the survey included with the solicitation documents is not completed, the quote will be determined non-responsive, and quote will be eliminated from any further evaluation.

iv. If quoter is found to be responsive from information provided the evaluation will continue to the next Action/Step (Review Technical Factors Information).

B. Action/Step 2 (Review Technical Factors Information).

i. Government will review key personnel, subcontractor teaming arrangements, documents, and certifications as they relate to the solicitation. Subcontractor teaming arrangements shall be considered a confirmation from a subcontractor that they agree to perform the work required by the solicitation in conjunction with the prime contractor.

C. Action/Step-3 (Price Evaluation).

i. The Government shall rank all responsive quotes from the lowest price to the highest price received, including any options if applicable.

ii. Only firm fixed price quotes will be evaluated. A quote using a sliding price scale or subject to escalation based on any contingency will not be accepted and will be considered non-conforming to this solicitation.

iii. A quoter's pricing will be determined by multiplying any quantities identified in the pricing schedule by the proposed unit price for each task or line item to confirm the extended amount for each. The price evaluation will document reasonableness and affordability of the total evaluated price.

D. Action /Step 4 (Past Performance).

i. The Government shall review the recent and relevant past performance as listed in the survey. Recent contracts are those within the past three years. "Relevant" means the performance being considered must have a logical connection to the work described in the solicitation. Normally, relevance would include such aspects as the product or service similarity, product or service complexity, contract type, and magnitude. Magnitude is important because it will define not only the scope but project similarity to this requirement.

- ii. Vendors whose System for Award Management (SAM) registration includes a Responsibility /Qualification record due to termination for cause or default, or administrative agreement, may be determined unacceptable and quote will be eliminated from any further evaluation.
- iii. Only past performance of the prime contractor shall be considered. Past performance of subcontractors shall not be considered unless a teaming arrangement is submitted in response to the Request for Quotation.
- iv. Quoter's shall insert proposed unit and extended totals for each task or line item as required. Any quote that fails to cite a price for each item or fails to make an entry that indicates service will not be provided for an Item will be rejected as non-conforming to this solicitation. Quotes that fail to price all items or indicate that the amount is \$0 or Not Separately Priced (NSP) will be rejected as nonconforming to this solicitation.
- v. After final price ranking is complete the Contracting Officer will continue to the next Action/Step (Award Process).

E. Action/Step-4 (Award Process).

- i. The Contracting Officer may conduct a comparative evaluation of all responsive quotes. A Purchase Order will be awarded to the vendor that submitted a responsive quote with acceptable past performance that includes fair and reasonable pricing, and who is considered technically capable of performing the work as required by the solicitation.
- ii. Quoters are cautioned to submit sufficient information for evaluation. Communication conducted to resolve minor or clerical errors would not constitute discussions and the contracting officer reserves the right to award a contract without the opportunity for quote revisions.
- iii. The Government intends to award a contract without discussions with respective quoters. The Government, however, reserves the right to conduct discussions if deemed in its best interest.

*** END OF NARRATIVE ***

FAR Provisions Incorporated by Reference

Number	Title	Effective Date	Alternate Deviation	Variation Effective Date
52.225-10	Notice of Buy American Requirement-Construction Materials.	2014-05		

