



United States Department of the Interior
NATIONAL PARK SERVICE
DENVER SERVICE CENTER
CONTRACTING SERVICES
1 DENVER FEDERAL CENTER, BUILDING 50
P.O. BOX 25287
DENVER, COLORADO 80225-0287

File Code: B01
Synopsis Pre-Solicitation Notice
D5217 (DSC-CS)
VICK 209252/310725/324137
140P2025R0092

Date: June 26, 2025

To: General Public via SAM.gov

From: National Park Service (NPS), Denver Service Center (DSC), Contracting Services (CS) Division

Subject: Pre-Solicitation Notice (PSN) – Request for Proposal (RFP) 140P2025R0092

Reference: VICK 209252 Stabilize Mint Spring Bayou & VICK 310725/324137 Stabilize Terraces & Graves

This pre-solicitation announcement is to advise the Industry that NPS DSC intends on issuing an RFP Solicitation for the Construction Services described below, in support of the above referenced project requirement at Vicksburg National Military Park in Vicksburg, Mississippi.

This PSN is not a formal Solicitation in itself, but rather a Synopsis of forthcoming RFP 140P2025R0092. Specific instructions on submitting your proposal will be contained in the solicitation documents to be issued on or after August/September of 2025.

General Project Description and Scope:

This project is located at Vicksburg National Military Park in Vicksburg, Mississippi. Work to be performed under this Construction Services project requirement includes:

Stabilize Terraces and Graves (VICK 310725/324137):

This project will provide for stabilization of terraces to protect the resource and mitigate the potential for injuries with the construction of approximately 272 linear feet of soldier pile and lagging retaining wall with an earthen buttress for slope stabilization to repair landslide at the National Cemetery and restore a section of Given Hill Road. Principal features of the work include mobilization and demobilization, clearing and grubbing, demolition of existing drainage features, fencing and existing pavement, site grading, excavation, select fills, asphalt paving, concrete paved ditches, retrofit of an existing drain inlet installing drainage structures and HDPE storm drain piping, soldier pile and lagging retaining wall including the setting of H-Piles, installation of permanent ground anchors and wood lagging, two-stage french drain and underdrain construction, new turf establishment, stormwater pollution prevention, temporary erosion control items, and environmental protection. Archaeological and cultural investigations will be conducted to monitor any ground disturbance and construction activities deemed necessary to protect archaeological resources.

Efforts between the National Park Service, US Geological Survey, Southeast Archaeology Center and the US Army Corp of Engineers' Eastern Research and Development Center have determined that immediate short term stabilization efforts are needed to protect not only the cultural resources, which include remains of Civil War soldiers, but also protect anyone who may attempt to enter the site as it now is in an unsafe condition and susceptible to further deterioration.

Stabilize Mint Spring Bayou (VICK 209252):

The current stabilization scope for the Mint Spring Bayou project includes construction of a slope stabilization system consisting of high-capacity strand anchors with reinforced concrete anchor plates and placing reinforced granular fill in front of the anchor benches to stabilize the slope adjacent to the Mint Spring Bayou. In addition to the stabilization work proposed at the Mint Spring Bayou and due to continuous deterioration of the soils including the landslides at the National Cemetery, the project also considers the stabilization of the area (gap)

between the southwest corner of the cemetery and Mint Spring Bayou project. The project consists of mobilization of construction crew, associated site work including minor clearing, erosion control measures and installing the wall drainage system per the site plans and specifications. Archaeological and cultural investigations will be conducted to monitor any ground disturbance and construction activities deemed necessary to protect archaeological resources.

The unique conditions that exist within the valley of Mint Spring Bayou have caused the bluff on which the National Cemetery is situated to slough off and erode. The southern brick wall around the cemetery and many other culturally sensitive components have already collapsed and fallen into Mint Spring. A project completed in 2011 consisted of the installation of two soil nail walls with shotcrete facing. At the base of the lower nail wall, the soil has become unstable and is sliding to the south causing movement of the Mint Spring Bayou bank. Continued erosion and sliding of the soil at the base of the nail walls may eventually cause undercutting of the walls and eventual failure of the original project. The ongoing slide north of Mint Spring Bayou has forced the creek against the south bank, which in turn is causing the south bank to be undercut. As a result of this undercutting, a significant number of trees from the south bank have fallen across the creek. The collapsing soil above the creek on the south side shows signs of progressive failure over time. Unless the creek channel is stabilized, the south bank and slope above will continue to fail and could force the closure of the tour road through the cemetery and would leave no alternative route.

North American Industry Classification System (NAICS) Code for this requirement is: 237990 - Other Heavy and Civil Engineering Construction

Set-Aside: *Small Business - Set-Aside*

Size Standard: \$46.0 Million.

Product Service Code (PSC): Y1LB - Construction of Highways, Roads, Streets, Bridges, And Railways

Magnitude of Construction: More than \$15,000,000.

Anticipated Period of Performance: 548 calendar-days from Notice to Proceed (NTP).

Contract-Type Vehicle: Firm-Fixed-Price (FFP)

Bonding: Bid, Performance and Payment Bonds will be required.

Additional Information: RFP 140P2025R0092 will be issued electronically via the System for Award Management website (<https://sam.gov>). Specific instructions on submitting Proposals will be contained in the formal Solicitation documents, which is anticipated to be issued in August/September of 2025. Documents will be made available for download purposes in Microsoft Word, Microsoft Excel, Adobe PDF, and/or HTML formats; Specifications available in Adobe PDF; and Drawings available in Adobe PDF. Paper Copies of the referenced documents will not be made available.

Prospective offerors desiring to conduct business with the NPS DSC are required to have an active registration in the Systems for Awards Management (SAM) at www.sam.gov, and required to have a UEI number in order to conduct business with the Federal Government. The SAM.gov website has a "Contract Opportunities" area and "Watchlist" option, where you can add your company's interest. Registering provides the opportunity to receive notifications, which is a tool of convenience only; and does not serve as a guarantee of notification. Interested Parties are required to visit the SAM.gov website periodically to check for Amendments and other changes to the Synopsis or Solicitation documents.

This is currently an unfunded requirement, with a high expectation that funding will be available. When and if funds become available a Contract will be awarded at that time.

The NPS DSC anticipates a Pre-Proposal Conference and Site Visit, after issuance of the formal RFP Solicitation and prior to the Proposal Due Date.

Federal Acquisition Regulations (FAR) Procedures: FAR Part 15 – "Contracting by Negotiation," and FAR Part 36 – "Construction and Architect-Engineer Contracts," in conjunction with FAR 6.203 and FAR 19.502-2. Award shall be made to the responsible Offeror whose offer conforms to requirements and represents the Best Value to the Government, considering Technical, Past Performance, and Price factors. Evaluation of interested firms will be based on the following in the Solicitation:

Trade-off: The basis of award will utilize the best value continuum – Trade-off process in accordance with FAR 15.101-1 to result in an award to the responsible Offeror pursuant to FAR 9.1.

NPS DSC CS Division Point-of-Contact:

Contracting Officer, Carlos Garcia – carlos_garcia@nps.gov