

Simplified Acquisition Procedures
Green Roofs Maintenance

0100000 – General Information		
Spec Item	Title	Description
1	General Information	
1.1	Outline of Services	Except where otherwise stated, the Contractor shall furnish all labor, supervision, management, tools, materials, equipment, facilities, transportation, incidental engineering, and other items necessary to provide the services outlined below and described in this Performance Work Statement (PWS) at Norfolk Naval Base, Norfolk Virginia. This procurement is a Recurring Price Contract. The intention of this specification is to provide ongoing maintenance for two green roofs on the Norfolk naval station at buildings A-50 and LP-50. The two green roofs were installed by different contractors and the requirements to maintain the two roofs are similar. Both roofs shall be maintained in accordance with the slightly more stringent maintenance requirement.
1.2	Acquisition of Additional Work	The Government reserves the right to acquire additional services at additional locations, within the scope of the annexes and areas included in Spec Item 1.1 Outline of Services, in addition to the services and locations identified in the requirements of this contract. Additional services will be incorporated into the contract in accordance with the CHANGES clause, SECTION I or ordered under the non-recurring work provisions of the contract. Items of work not covered by this contract but within the general intent are considered in the scope of this contract.
1.3	Background Information	Norfolk Naval Station, NSA Norfolk and HR IPT Norfolk, Virginia There are 13 major piers from Pier 1 on the south end to Pier 14 on the north end of the base. (There is not a Pier 13). There are also several minor piers for port services vessels. Tied up to the piers are a wide range of Navy and Military Sealift Command ships including submarines, destroyers, frigates, cruisers, underway replenishment ships, amphibious ships, and aircraft carriers. Ships from foreign navies also make Norfolk a port of call.
1.4	Project Location	The work shall be performed at Norfolk Naval Station, Norfolk, Virginia, (Buildings A-50 and LP-50)
1.5	Navy PBSA Approach	The Navy's approach to performance-based service acquisition (PBSA) includes four component parts, which are 1) performance outcomes, 2) measurable standards, 3) consideration of incentives, and 4) performance assessment plan.
1.6	Verification of Workload and Conditions	All facilities, systems, and assets identified in this contract shall be accepted by the Contractor in "AS-IS" condition. The Contractor is fully responsible for all work up to and including the limits of liabilities specified. As prescribed in FAR 52.237-1, offerors' or quoters are urged and expected to inspect the site where services are to be performed and to satisfy themselves regarding all general and local conditions that may affect the cost of contract performance, to the extent that the information is reasonably obtainable. In no event shall failure to inspect the site constitute grounds for a claim after contract award.

Simplified Acquisition Procedures
Green Roofs Maintenance

0100000 – General Information		
Spec Item	Title	Description
1.7	Contractor's Knowledge	The Navy expects to receive insightful management from its contractors. This management shall include the knowledge, skills, authority and willingness to use contractor resources to find better ways of serving Navy clients' strategic and operational goals and objectives. The Navy's use of performance-based objectives evidences this principle. Although performance work statements will typically contain several levels of performance assessment, the Navy wants its contractors to exercise maximum discretion within bounds of prudent risk management to adjust processes and resources needed to reach specified objectives at the highest performance level.
1.8	Technical Proposal Certification	The Contractor warrants that its proposal including, but not limited to, proposed approaches, staffing, methodology, or work plans, will meet the performance objectives and standards set forth in this contract during execution thereof. The Contractor is not excused from meeting such performance objectives and standards in the event such proposal proves inadequate as conceived or executed to meet such performance objectives and standards. The Contractor understands that it bears all of the cost and performance risk associated with adopting acceptable additional (and/or alternative) means or methods of meeting the performance objectives and standards. .

0200000 - Management and Administration		
Spec Item	Title	Description
2	Management and Administration	
2.1	General Information	
2.1.1	Government Regular Working Hours	The Government's regular working hours are from 0700-1600, five days per week, Monday through Friday, except observed Federal holidays. Exceptions to the regular hours of operation are detailed in subsequent sections of this PWS. The performance of other work requirements shall be accomplished within the Government's regular working hours unless the specific work requirement specified herein necessitates otherwise. Any other work outside Government regular working hours must be authorized by the KO prior to commencement of work.
2.1.1.1	Observed Federal Holidays	The Government observes the following holidays: New Year's Day, Martin Luther King Jr.'s Birthday, President's Day, Memorial Day, Juneteenth, Independence Day, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day, and Christmas Day.
2.1.1.2	Restriction to Contractor Working Hours	If the Contractor wishes to work outside of the Government's regular working hours for the Contractor's convenience, the Contractor shall submit a written Request to Work Outside Government's Regular Working Hours.
2.2	Wage Determinations	Will be provided by the contract specialist.
2.3	General Administrative Requirements	
2.3.1	Commencement, Prosecution and Completion of Work	The contract shall be for a period of twelve months or less commencing 15 days after notice of award. The Government has the option to extend the term of the contract in accordance with OPTION TO EXTEND THE TERM OF THE CONTRACT – SERVICE (Fac) 5252.217-9301 clause section1. In the option periods the Government will adjust the prices, as required, based on new Department of Labor Wage Determinations.

Simplified Acquisition Procedures
Green Roofs Maintenance

0200000 - Management and Administration		
Spec Item	Title	Description
2.3.1.1	Required Conferences and Meetings	The Contractor shall attend administrative and coordination meetings.
2.3.1.2	Permits and Licenses	The Contractor shall obtain all required permits, licenses, and authorizations to perform work under this contract and comply with all the applicable Federal, state and local laws and regulations.
2.3.2	Insurance	With in 15 days after award of this contract, the Contractor shall submit a Certificate of Insurance as evidence of the existence of the following insurance coverage in amounts not less than the amounts specified below in accordance with the FAR Clause 52.228-5, INSURANCE – WORK ON A GOVERNMENT INSTALLATION. This insurance must be maintained during the performance period.
2.3.2.1	Certificate of Insurance	The Certificate of Insurance shall provide for at least 30 calendar days written notice to the KO by the insurance company prior to cancellation or material change in policy coverage. Other requirements and information are contained in the aforementioned insurance clause.
2.3.2.2	Minimum Insurance Amounts	The Contractor shall procure and maintain, during the entire period of performance under this contract, the following minimum insurance coverage: Comprehensive General Liability: \$500,000 per occurrence Automobile Liability: \$200,000 per person, \$500,000 per occurrence, \$20,000 per occurrence for property damage Workmen's Compensation: As required by Federal and state worker's compensation and occupational disease statutes Employer's Liability coverage: \$100,000, except in states where worker's compensation may not be written by private carriers Other as required by state law.
2.3.3	Protection of Government Property	During execution of the work, the Contractor shall protect Government property. The Contractor shall return areas damaged as a result of Contractor negligence under this contract to their original condition at no cost to the Government.
2.3.4	Directives, Instructions, and References	The Contractor shall comply with the most current version of directives, instructions, and references including versions published during the term of the contract.
2.3.5	Forms	All forms referenced in this Specification will be provided as needed after the award e.g. accident reporting, and damage reporting.
2.4	Government-Furnished Items	NONE
2.4.1	Government-Furnished Property (GFP)	NONE
2.4.2	Government-Furnished Facilities	NONE
2.4.3	Government-Furnished Vehicles and Equipment	NONE

Simplified Acquisition Procedures
Green Roofs Maintenance

0200000 - Management and Administration		
Spec Item	Title	Description
2.4.4	Government-Furnished Utilities	The Government will make available water and electricity at existing outlets, required for the work to be performed under the contract. The Contractor shall provide and maintain, at its expense, the necessary service lines from the existing Government outlets to the work site. Provide and maintain backflow prevention devices on connections to domestic water lines and electrical transformer provisions on connections to electric lines. Meet all Federal, State, local, and installation codes and regulations for backflow prevention devices and electrical transformer provisions. Services required by the Contractor, for which there are no available Government outlets, shall be provided by the Contractor at no cost to the Government.
2.5	Contractor-Furnished Items	Except for items identified as Government Furnished, the Contractor shall provide all equipment, materials, parts, supplies, components, and facilities to perform the requirements of this contract. The KO may inspect Contractor-furnished items for adequacy and compliance with contract requirements. Inadequate or unsafe items shall be removed and replaced by the Contractor at no cost to the Government. Materials containing asbestos, lead, and polychlorinated biphenyls (PCBs) shall not be brought onsite. Energy efficient tools and equipment shall be used when available. KO may at any time require Samples, Safety Data Sheets (SDS) or Manufacturer's Data Cut Sheets of Materials used in this contract.
2.6	Quality Management System (QMS)	The Contractor shall establish and maintain a complete QMS program in accordance with the provisions specified herein. The Contractor's QMS program shall provide an effective and efficient means of identifying and correcting problems throughout the entire scope of operations. The Contractor's QMS program shall address: • Accurate documentation of work processes, procedures, and output measures. • A systematic procedure for assessing compliance with performance objectives and standards. • Accurate documentation of quality inspections and surveillance conducted throughout the execution of work. • Assessment-driven corrective actions and process adjustments as appropriate in a timely manner.
2.6.1	Quality Management (QM) Plan	The Contractor shall develop and submit a QM Plan per Section F. The QM Plan shall describe the QMS methodology and approaches used under this contract. The Contractor's QM Plan shall include, at a minimum, the following: • Policy and objectives of Quality Management System (QMS) • Quality organization ○ List of personnel ○ Responsibilities & lines of authority ○ Training and qualifications • Approach to assuring quality of services provided and conformance with performance objectives and standards • Methods and procedures for effective planning, operation and control of processes and performance of work • Procedures for inspection and surveillance of services to include all contractual requirements. ○ Scheduling and performance of inspection and surveillance

Simplified Acquisition Procedures
Green Roofs Maintenance

0200000 - Management and Administration		
Spec Item	Title	Description
		○ Measurement, data collection and analysis ○ Corrective action, preventive action, and continuous improvement ○ Oversight of subcontracted work • Documentation and records management • Communication with government (customers)>>
2.6.2	Quality Inspection and Surveillance	The Contractor shall establish and maintain an inspection and surveillance system in accordance with the FAR Clause 52.246-4, INSPECTION OF SERVICES – FIXED PRICE, to ensure that the work performed conforms to the contract requirements. The Contractor shall document and maintain a file of all scheduled and performed inspections and surveillances, inspection and surveillance results, and dates and details of corrective and preventive actions. The quality inspection and surveillance file shall be the property of the Government and made available during the Government's regular working hours. The file shall be submitted to the COR after completion/termination of the contract.
2.7	Security Requirements	The Contractor shall comply with all Federal, state, and local security statutes, regulations, and requirements. The Contractor shall become acquainted with and comply with all Government regulations as posted, or as requested by the KO when required to enter a Government site. The Contractor shall ensure that all security/entrance clearances are obtained. The Contractor shall ensure that Contractor personnel do not present a risk to security. By entering the installation, Contractor personnel are subject to installation, state, local and federal regulations and laws, including but not limited to debarment and criminal prosecution.
2.7.1	Employee Listing	The Contractor shall maintain and provide to KO upon request a current listing of employees. The list shall include employees' name, social security number, and level of security clearance. No employee or representative of the Contractor will be admitted to the site of work unless satisfactory proof of citizenship is furnished, or, if an alien, legal residency within the United States is confirmed.
2.7.2	Vehicles	The company name shall be displayed on each of the Contractor's vehicles in a manner and size that is clearly visible. All vehicles shall display a valid state license plate that complies with the State Vehicle Code. Vehicles shall meet all other requirements of the State Vehicle Code, such as safety standards, and shall carry proof of insurance and state registration, if applicable.
2.7.3	Passes and Badges	All Contractor employees shall obtain the required employee and vehicle passes. The Contractor employees must be able to obtain Common Access Cards (CAC) in accordance with security requirements. Each employee shall wear the Government issued badge over the front of the outer clothing. When an employee leaves the Contractor's service, the employee's Passes and Badges shall be confiscated by the Contractor immediately and returned within 10 calendar days.
2.7.4	Access to Installation	All Contractor personnel shall obtain access to the installation through enrollment and registration into the Defense Biometric Identification System (DBIDS). The Contractor shall provide the KO with the name of their designated Service Contractor Administrator (SCA) for enrollment in DBIDS. Once enrolled, the Contractor must provide the DBIDS Registrar with an approved employee list and then direct their employees to register into DBIDS.

Simplified Acquisition Procedures
Green Roofs Maintenance

0200000 - Management and Administration		
Spec Item	Title	Description
2.7.5	Access to Buildings	The Contractor shall monitor and control access into restricted areas under their responsibility, allowing only those individuals who have been properly cleared into restricted areas or other controlled access areas. The Contractor shall comply with security requirements, plus those imposed by the installation Commander at all times. Personnel with access to restricted areas shall have the appropriate screening and shall wear special badges authorizing access for those areas. Contractor personnel shall not enter restricted or controlled areas or installation facilities unless specifically authorized in performance of their duties. The Contractor shall secure all buildings and facilities entered during non-duty hours and will secure all building and facilities under the Contractor's cognizance at the end of each workday or shift period.
2.7.6	Access Arrangements	The Contractor shall make all arrangements through the appropriate office necessary to obtain access to buildings, facilities and other work areas, and when necessary, arrange for them to be opened and closed by the controlling authority. The Government may issue keys to the Contractor. The Contractor shall use due diligence and be responsible for compromised security systems to include replacement costs that result from its action or inaction>
2.7.7	Security Clearances	The Contractor shall obtain all required corporate and personnel Security Clearances prior to commencement of work. The Contractor shall ensure that a list of all personnel with Security Clearances is maintained current, including clearances that are pending
2.8	Contractor Safety Program	The Contractor shall develop and implement a Safety Program detailing how the Contractor plans, staffs, performs, and controls all safety practices while delivering best value services to the Government without any accidents or mishaps. The Contractor's safety program shall comply with all safety standards identified in the U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, UFC 3-560-01 Operation and Maintenance Electrical Safety, and Public Law 91-596, Occupational Safety and Health Act. Any reference to "USACE" facilities, property, or equipment specified in EM 385-1-1 should be interpreted as Government facilities, property, and equipment.
2.8.1	Accident Prevention Plan (APP)	The Contractor shall develop and implement a site Accident Prevention Plan (APP). The APP shall be prepared by the Contractor's SSO and shall be followed by all Contractor employees, subcontractors, and vendors at each service site. "The APP shall follow the abbreviated format and include, as a minimum, elements addressed in paragraph 3.k. of Appendix A of EM 385-1-1. Within fifteen days after award, the Contractor shall submit an APP to the KO for acceptance. The Contractor shall review, update, and submit revisions to the APP whenever a change in work conditions, hazards, or activities occur. The Contractor shall not commence work until the APP has been accepted and no activity shall be started on site until the applicable AHAs and compliance plans have been accepted. Once accepted by the Contracting Officer, the APP and attachments will be enforced as part of the contract. Disregarding the provisions of this contract

Simplified Acquisition Procedures
Green Roofs Maintenance

0200000 - Management and Administration		
Spec Item	Title	Description
		or the accepted APP will be cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified.
2.8.2	Activity Hazard Analysis (AHA)	The Contractor shall prepare Activity Hazard Analyses (AHAs) for all applicable common recurring work activities performed under this contract. AHAs for recurring work shall be submitted with the APP and shall be updated as work activities or conditions change and additional AHAs prepared as new work activities are required. AHAs for non-recurring and one-time (e.g., non-recurring work task orders) work occurrences shall be submitted at least two working days prior to start of work. Specifically: • For contract modifications to recurring work requirements where changes are germane to the original contract, the Contractor shall revise applicable AHAs within 15 calendar days after modification is signed. • For contracts with non-recurring work ELINs, the Contractor shall submit an AHA on non-recurring work task orders, with the associated proposal, whenever the service environment or required task is different from the recurring work priced services. • For construction (including renovation or alteration) task orders placed on the non-recurring work portion of contract, the Contractor shall submit a separate AHA for each task order with the associated proposal. The Contractor shall follow the Risk Management Process for the development of Activity Hazard Analysis (AHA) in accordance with paragraph 01.A.14 and Appendix A of EM 385-1-1. A formatted outline of an AHA is provided in Figure 1-2 of EM 385-1-1. During the performance of services, the SSHO shall periodically review the AHA at each service site and for each sub-annex to assess the effectiveness of the Contractor's overall APP. If changes to the AHAs are required, such changes shall be submitted to the KO for review and acceptance.
2.8.3	Accident and Damage Reporting	The Contractor shall notify the Contracting Officer as soon as practical, but no more than four hours after any accident meeting the definition of Recordable Injuries or Illnesses or High Visibility Accidents, property damage equal to or greater than \$2,000, or any Weight Handling Equipment (WHE) accident. Notification shall also be provided for any mishap occurring in any of the following high hazard areas: electrical (to include Arc Flash, electrical shock, etc.); uncontrolled release of hazardous energy (includes electrical and non-electrical); weight or load handling equipment (LHE) or rigging; fall-from-height (any level other than same surface); and underwater diving. These mishaps shall be investigated in depth to identify all causes and to recommend hazard control measures. Within notification include Contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (to include type of equipment used, PPE used, etc.). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted.

Simplified Acquisition Procedures
Green Roofs Maintenance

0200000 - Management and Administration		
Spec Item	Title	Description
		The Contractor shall conduct an accident investigation for recordable injuries and illnesses, for accidents requiring Medical Treatment, property damage accidents resulting in at least \$20,000 in damages, and near misses as defined in EM 385-1-1, to establish the root cause(s) of the accident. The Contractor shall complete the applicable NAVFAC Contractor Incident Reporting System (CIRS), and electronically submit via the NAVFAC Enterprise Safety Applications Management System (ESAMS).
2.8.3.1	Accident Reporting and Notification Criteria	The following criteria and definitions apply to the accident reporting requirements specified above: Recordable Injuries or Illnesses. Any work-related injury or illness that results in: 1) Death, regardless of the time between the injury and death, or the length of the illness. 2) Days away from work (any time lost after day of injury/illness onset). 3) Restricted work. 4) Transfer to another job. 5) Medical treatment is beyond first aid. 6) Loss of consciousness; or 7) A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (1) through (6) above. High Visibility Accident. Any mishap which may generate publicity or high visibility. Medical Treatment. Treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even through provided by a physician or registered personnel.
2.8.4	Fire Protection	The Contractor shall know where fire alarms are located and how to activate them. The Contractor shall handle and store all combustible supplies, materials, waste and trash in a manner that prevents fire or hazards to persons, facilities, and materials.
2.8.5	Government Safety Inspections	The Government may inspect the Contractor's workspace for OSHA and Safety violations. Abatement of violations will be the responsibility of the Contractor as determined by the Contracting Officer. The Contractor shall assist inspectors from the Safety Office and federal or state OSHA offices if a complaint is filed. The Contractor shall pay promptly any fines levied by federal or state OSHA offices.
2.8.6	Safety Certification	No work that requires certification shall start without a valid and approved certification.
2.8.7	Emergency Medical Treatment	Contractors will arrange for their own emergency medical treatment. The Government has no responsibility to provide emergency medical treatment.
2.9	Environmental Protection	The Contractor shall comply with all applicable Federal, state, and local laws, regulations, and executive orders, and with base-wide instructions, standards, and permit requirements.

Simplified Acquisition Procedures
Green Roofs Maintenance

0200000 - Management and Administration		
Spec Item	Title	Description
2.9.1	Non-Regulated Waste Disposal	The Contractor shall dispose all wastes in accordance with all applicable Federal, state, and local laws, regulations, and executive orders, and with base-wide instructions, standards, and permit requirements. Disposal of all non-regulated debris and rubbish resulting from the work under this contract shall comply with the federal regulations in 40 CFR Part 258 (Subtitle D of RCRA), or equivalent state regulations and be disposed of at appropriate off installation waste handling facilities.
2.9.2	Protection of Endangered and Threatened Species (Flora and Fauna)	The Contractor shall not disturb endangered and threatened species and their habitat. The Contractor shall carefully protect in-place and report immediately to the KO endangered and threatened species discovered in the course of work. The Contractor shall stop work in the immediate area of the discovery until directed by the KO to resume work.

3	Recurring Work	The contractor shall establish and conduct a maintenance program to sustain the vegetative roof located on buildings A-50 and LP-50. Vegetative roofs shall be maintained to meet the manufacturers' care and maintenance requirements. Vegetative roofs shall always have sufficient maintenance and care applied to support proper growth of the vegetative cover to provide proper protection of the roof surface. Contractor at minimum shall be certified to maintain these roofs. The contractor is responsible for repairs up to and including \$250.00. All repairs discovered, for which the estimated cost is over, will be immediately reported to the Contracting Officer along with a detailed estimate of the repair needed. Within 15 days after the award, the contractor shall provide all work schedules to the contracting officer.
3.1	Warranted Roofs	Each green roof has an extended roof warrantee, due to the installation of a green roof. The Contractor is responsible for performing all green roof maintenance items as required in order to prevent voiding the Original Equipment Manufacturers (OEM) warranty on the roof membrane. Should the Contractor fail to perform, and the OEM warrantee is voided as a result of the Contractors actions or inactions, it shall be the Contractors responsibility to cover the remaining term of the roof warrantee at the Contractor expense. In that case repair or replacement of the roof membrane would then be at the Contractors sole expense. Equipment, components, and parts, other than that installed under the contract, shall not be removed or replaced or deficiencies corrected while still under warranty of the manufacturer or the installer without prior approval of the Contracting Officer. All defects in material or workmanship, defective parts, or improper installation and adjustments found by the Contractor shall be reported to the Contracting Officer so that necessary action may be taken. The Contractor shall be knowledgeable of the equipment, parts, and components that are covered by warranty and the duration of such warranties. The Contracting Officer will furnish available warranty information to the Contractor.
3.2	OEM Technical Specification A-50	Basic Maintenance Plan for Roof meadow Green Roof Roof meadows 7135 Germantown Ave.2nd Floor Philadelphia, PA, 19119 Office 1-215-247-8784

Simplified Acquisition Procedures
Green Roofs Maintenance

		Fax 1-215-247-8784 MelissaMuroff [mmuroff@roofmeadow.com] 3-inch un-irrigated Type II Naval Facilities Engineering Command Building A-50, Norfolk, VA The contractor must contact OEM above and submit their qualifications for acceptance as an OEM approved contractor or apply for the training needed to become a Roof meadows approved contractor.
3.2.1	Requirements to maintain OEM warranty after two-year establishment period	The green roof must be maintained by a service provider accepted by OEM. Green roof maintenance Contractor must demonstrate compliance with OEM Maintenance Plan.
3.2.2	Watering	The plants selected for this project are drought tolerant. In fact, growing conditions for These plants will be optimum when they are exposed to episodes of media desiccation. By keeping the surface of the media dry, it will also be easier to minimize the germination of weed seeds. The media is intended to optimize the use of applied rainfall. Following the establishment of the cover, further irrigation is discouraged. However, in conditions of sustained drought, hand watering may be undertaken at the discretion of the service provider. Frequent watering will be detrimental to the vegetated cover and shall be avoided.
3.2.3	Fertilization	Regular fertilization of the green roof is as recommended by OEM. Soil tests shall be conducted each year in the fall to assess plant nutritional requirements. Laboratory reports should be copied to the Contracting Officer. Ideal total soluble nitrogen (nitrate plus ammonium) levels, using the saturated paste methodology, for These plantings fall in the range of 1.5 to 5 ppm. Do not fertilize if soil test shows total soluble nitrogen levels exceeding 5 ppm. The nutrient applications shall be made in early spring or fall. Over-fertilization can seriously disturb the green roof.
3.2.4	Gardening	Two documented maintenance visits each year are required for compliance with the OEM Maintenance Plan – one during early June and again during late September when conditions are conducive to weed germination and establishment. Thorough weed removal at these times is required. Patches of bare media shall be covered by distributing cuttings taken from adjacent plants or by separating and transplanting healthy plants. Sedum cuttings should be at least one inch long and should preferably include some ‘air roots.’ Cuttings will set best in the early spring and late fall, but can be planted at any time except when the temperature is below freezing. A light dusting of compost may accelerate growth. Indications of a system upset shall be reported to the Contracting Officer and the OEM within 30 days of the previous maintenance visit. Examples of upsets include a) large bare spots, b) colonization of the green roof by annual grass, moss or weeds, c) high mortality rates for one or more plant species, d) loss of media to wind scour, or e) perennially moist or spongy areas. Weeding should be by hand pruning or, as appropriate, hand weeding. Immature extensive green roofs are particularly vulnerable to colonization by annual grass, especially crabgrass. A pre-emergent crabgrass treatment may be advised. Under no circumstance shall the following proscribed activities be undertaken: Digging or use of pointed or sharpened tools (i.e., trowels, shovels, spades, weeders,

Simplified Acquisition Procedures
Green Roofs Maintenance

		hand cultivators, etc.)
		Use of lawn staples or stakes for any purpose, including the tethering of tarps or erosion mats Mowing or scything If there is any concern that damage has been done to the underlying waterproof system as result of maintenance activities, report the nature of the event to the Contracting Officer and the OEM within 24 hours.
3.2.5	Drainage	As part of each maintenance visit, the drain outlets (scuppers) shall be inspected to make certain that they are free from clogging or obstructions. Correct any problems and report them to The Contracting Officer and the OEM. Evidence of periodic pooling of water following rainfall events or of surface runoff across the surface of the cover shall be immediately reported.
3.2.6	Traffic, Winter Maintenance, and Waterproofing	This roof is not designed for pedestrian access. Foot traffic associated with maintenance activities shall be kept to a minimum. All plant varieties in the cover system are winter hardy. No special requirements apply to winter protection. During each maintenance visit, examine exposed components of the waterproofing system, including flashings and counter-flashings. Report any damage or deterioration within three (3) days of the maintenance visit to the KO and to the NAVFAC Facilities Maintenance Services.
3.2.7	Documentation	Each maintenance visit shall be documented using Maintenance Report forms provided by The Contracting Officer. Completing the Maintenance Report includes a) inventorying the plant, b) photographing the green roof, (c) describing maintenance activities, including any corrective measures, d) assessing the condition of the plants, and e) inspecting any exposed portions of the waterproofing system for damage or irregularities. A copy of each Maintenance Report shall be sent to the Contracting Officer, NAVFAC Facilities Maintenance Services, and the OEM.
3.2.8	Metal Components and Vegetated Roof Accessories	Vegetated roof systems incorporate specialized sheet metal components designed to allow water flow while retaining the growing medium and vegetation. In general, pay careful attention to the condition of the metal including rust, wind deformation and joint integrity. Note any resulting stressed roof areas. Flow-through Gravel Stops. Inspect the perforated face of the edge system to ensure that the holes are not clogged by soil, roots, or debris. Separator Components. Inspect the joints of the separator metal to ensure that the joint covers are intact. If necessary, temporarily remove pavers or ballast to inspect the outside face of the metal separator component. Remove soil and debris that may collect at the bottom of the separator due to "wash out" from the drainage media.
3.3	OEM Technical Specification LP-50	CARE AND MAINTENANCE Sip last Para green Vegetated Roof Systems Please contact Sip last at 1-800-922-8800 and ask for Vegetated Roof Systems Technical Support.
3.3.1	Maintenance requirements	Maintain green roof system in accordance with all the requirements 3.2.1 through 3.2.8 above and any additional OEM requirements.
3.3.2	Procedures for Reporting Leaks	All leaks through a sip last guaranteed membrane Shall be reported immediately to the Contracting Officer, NAVFAC Facilities Maintenance Services, the original roofing contractor and to sip last. When such notifications are made verbally, they should be confirmed in writing as soon as possible. An inspection will be made either by the original roofing contractor or by sip last to determine both the source of the problem and the responsibility for it.