

Project Name: WA FLAP JEFFER 134309(2), Two Trout Creek Culvert Replacement

WA FLAP JEFFER 134309(2), Two Trout Creek Culvert Replacement
Jefferson County, Washington State

This work consists of constructing an Aquatic Organism Passage (AOP) Culvert at Oil City Road MP 0.5 to replace a failing culvert that blocks fish passage in a tributary to the Hoh River

Project Location: This project is located approximately 16 Miles South of Forks city, Jefferson County, Washington State.

Project Length: 0.1 Miles

Estimated Price Range: Between \$2,000,000 and \$5,000,000

Tentative Solicitation Date: Fall/Winter 2025

Tentative Fixed Completion Date: Winter 2026

DESCRIPTION OF WORK in US CUSTOMARY UNITS
USING FP-24 SPECS

	One Schedule Sch Name
DIVISION 150 – Project Requirements	
152 Construction Survey & Staking (yes/no)	Yes
153 Contractor Quality Control and Assurance (yes/no)	Yes
154 Contractor Sampling & Testing (yes/no)	Yes
155 Schedules for Construction Contracts (<i>construction schedules</i>) (yes/no)	Yes
157 Soil Erosion Control (<i>Silt Fence</i>)	1200 LNFT
157 Soil Erosion Control (<i>Fiber Roll</i>)	2,600 LNFT
157 Soil Erosion Control, Check Dam (<i>Fiber Roll</i>)	12 EACH
DIVISION 200 – Earthwork	
201 Clearing & Grubbing	1,000 SQYD
204 Roadway Excavation	1,770 CUYD
207 Stabilization Geotextile	2,200 SQYD
DIVISION 250 – Slope Reinforcement and Retaining Walls	

251 Riprap, Class 4	70 CUYD
	One Schedule Sch Name
251 Riprap Ditch, Class 1	550 LNFT
30201-2000 Roadway Aggregate, Method 2	650 CUYD
DIVISION 600 – Incidental Construction	
602 Reinforced Concrete Box Culvert (18' Span, 12' Rise)	52 LNFT
617 Guardrail System G4, Type 4, Class B Steel Post	200 LNFT
617 Terminal System, Type MGS Tangent	4 EACH
622 Rental Equipment (yes/no)	No
623 General Labor (yes/no)	No
625 Turf Establishment	900 SQYD
626 Plants	LPSM
635 Temporary Traffic Control – <u>Portable Changeable Message Signs</u>	1 EACH
635 Temporary Traffic Control – <u>Construction Sign</u>	4 EACH
647 Environmental Design, Root Wad	14 EACH
647 Environmental Design, Streambed Material	340 CUYD