

US Department of Agriculture (USDA)



Statement of Work

Contents

Project 3

General Information 3

 1.0 Scope of Work..... 3

 2.0 Background 3

Contractor Requirements 3

 3.0 Technical Requirements / Tasks..... 3

 4.0 Government Furnished 4

 5.0 Deliverables / Schedule..... 4

 6.0 Travel 4

 7.0 Contractor’s Key Personnel..... 4

 8.0 Security Requirements..... 4

 9.0 Data Rights 4

 10.0 Section 508 – Electronic and Information Technology Standards 4

Attachment 4

Project

0414 NEW SUPP FLATBED - 7151

General Information

1.0 Scope of Work

The requested bed will be for a 2026 Ford F-550 EXT Cab, 4x4, Diesel, Dual Rear Wheels, Cab & Chassis configuration with a Cab to Chassis length of 84". (Government Provided)

2.0 Background

The Forest Service Engineering Road Crew requires a heavy-duty vehicle to support field operations. The 2026 Ford F550 has been selected for its durability and capability to meet operational needs in rugged environments. This flatbed will facilitate their ability to transport large equipment, construction materials, and tools efficiently to remote job sites, ensuring timely completion of road maintenance and improvement projects.

Contractor Requirements

3.0 Technical Requirements / Tasks

The desired bed will be a steel hybrid design that combines low profile Utility Bed-type side-mounted compartments on a flatbed configuration to allow for a "gooseneck" trailer to be attached. Black in color is acceptable.

Alternative locations and layout of compartment, cabinets/toolboxes will be considered if they meet the overall storage space requirements and meet the water resistant needs.

Fuel Filler location - Must function as designed by Ford, at the designed height off the ground to facilitate fast fuel filling from a standard gas station pump. An empty tank should be refilled without repeatedly tripping the nozzle shutoff due to fuel backing up in the filler tube prematurely.

Compartments/Cabinets/Toolboxes - The compartments must be designed to be water resistant. Use of Weather Trim Seals, Rain Channels and adjustable tension handles are desired.

Auxiliary Fuel Tank (Government Provided)- The bed will be required to provide room to house an auxiliary 2-compartment tank, overall minimum of 90 gallon capacity, located in the front center of the bed, directly behind the headache rack. The tank will include plugged bung holes for draining and a standard threaded port V1to attach a pump to each compartment. Approximate tank dimensions: 47.5" L x 31" W x 24.38" H or 47.38" L x 31" W x 24.19" H

Electrical - All lights will be "weatherproof" to rain and water splashing from the road. All wiring will be waterproof with exposed wiring protected from rocks. Any location the wiring passes through the metal structure, the hole will be grommited to prevent chaffing of wires. The trailer wiring harness will provide dual outlets, one at each location, to provide hookup for either a gooseneck or a tow behind trailers.

No used parts are authorized.

Front Boxes - 2 side located boxes mounted at the front of the bed. One on the driver's side and one on the passenger side. Access provided by waterproof doors (preferred) or lids. Desired both have, no less than, 4 swing-out or sliding trays.

Dimensions would need be approximately 28" x 36" x 15" deep.

Middle Boxes - 2 side located boxes mounted in behind the front boxes identified above. One on the driver's side and one on the passenger side. Access provided by waterproof doors (preferred) or lids. Desired both have, no less than, 4 swing-out or sliding trays. Approximate dimensions of the middle boxes would be 27" x26" x 15" deep.

Long over-the-rear-wheel well boxes - 2 side located, long horizontal boxes, one on the driver's side and one on the passenger side, each mounted directly behind the Middle Boxes. Access provided by waterproof doors (preferred) or lids. No trays are desired in these compartments. One of these boxes should have dimensions, of approximately 70" x 15" x 10" and the other could be shorter at approximately 63" x 15" x 10".

Behind the Wheel Box - 2 side located boxes mounted behind the rear wheel wells and under the long boxes mentioned above, One on the driver's side and one on the passenger side Access provided by waterproof doors (preferred) or lids. Approximate dimensions of the rear boxes would be 6"x16"x15".

Specifications - Spare Tire Location & Mount

The Operator will mount the spare, at the location that best suits their needs.

4.0 Government Furnished

None

5.0 Deliverables / Schedule

The Seller shall have the service utility bed installed on or before 60 days after award of the contract, or after the vehicle is delivered at the Sawtooth National Forest, whichever comes first. Vehicle is currently ordered but not yet delivered to Sawtooth National Forest. POC will coordinate delivery of vehicle after it has been received.

Seller shall give the Forest Service at least 72 hours' notice as to when the new truck utility bed is to be installed. The person to contact about the delivery date is Cody Wilber at 208-277-4274.

6.0 Travel

Sawtooth National Forest will be responsible for delivering truck to vendor for bed installation within **250 road miles of 370 American Ave, Jerome, Idaho 83338**. Vendor will have to tow agency provided vehicle to and from beyond those 250 road miles of this forest location.

7.0 Contractor's Key Personnel

NONE

8.0 Security Requirements

NONE

9.0 Data Rights

NONE

10.0 Section 508 – Electronic and Information Technology Standards

NONE

Attachment