

STATEMENT OF WORK (SOW)

Fire Pump Repair – BOSTON Easton Building

1. Project Overview

This project involves the repair of existing Fire Pump gasket in the basement of Easton Building located at 15 State Street, Boston MA. The scope includes a minor rebuild/repair of Allis Chalmer fire pump. Perform open lid inspection on the interior components of the fire pump and perform a laser shaft alignment.

2. Scope of Work

The contractor shall provide all labor, materials, equipment, and supervision necessary to perform the following:

2.1 Demolition and Removal

- Isolate the motor from the controller and lock out /tag out Isolate pump from system (Alarms by others).
- Set up and rig pump casing lid off pump.
- Remove rotating assembly from pump.
- Remove old packing and clean up and inspect shaft sleeves Inspect impeller and shoulder/lantern rings Install rotating assembly into pump.

2.2 Installation

- Re-pack pump and re-install pump casing lid with new gasket Replace glands, gland bolts, nuts and washers Inspect inboard and outboard bearings.
- Clean stuffing box area and clear packing box drain lines Perform laser shaft alignment.
- Run pump and adjust packing.
- Return pump to service.

2.3 Testing and Commissioning

*Include Fire Department Detail as required ***

*Include BFD required Fire pump flow test done off hours ***

- Boston Fire Department (BFD) requires a fire watch while work is being performed (staffing detail as required by BFD)
- Fire pump flow test as required.

2.4 Training

- Provide basic training to on-site staff for operation and troubleshooting of the new control system.
-

3. Deliverables

- Removal of all obsolete components.
 - Installation of new components.
 - Documentation, including as-built drawings, wiring diagrams, and O&M manuals.
 - Warranty information for all installed equipment (minimum 1-year parts and labor).
-

4. Period of Performance

Work shall be completed within [14] calendar days from the Notice to Proceed (NTP).

5. Work Hours

All work shall occur during regular business hours unless otherwise approved.

6. Codes and Standards

All work shall comply with:

- Boston Fire Department
-

7. Safety and Protection

Contractor shall implement appropriate safety measures and ensure the protection of building occupants and property during all phases of work.

8. Budget & Funding

- Any cost overruns must be pre-approved by the Contracting Officer.
-

9. Point of Contact

Larry Seaboyer
Supervisory Facility Operations Specialist
National Park Service Interior Region 1

15 State Street
Boston, MA 02109-3572

617-223-5023 (o)
978-427-5388 (c)
laurence_seaboyer@nps.gov

10. Attachments (If Applicable)

- NONE
-

End of Statement of Work