

Enclosure 3

APPENDIX B - Statement of Work

ANL Site Emergency Generator & Automatic Transfer Switch (ATS) Service Contract

May 4, 2026

1.0 Background

The ANL campus relies on a collection of 35 emergency standby generators and 56 automatic transfer switches (ATS) to provide critical backup power to essential facilities.

Due to the critical role these systems play, it is imperative that they remain in optimal working condition at all times. Unexpected failures or downtime can create significant operational risks, including loss of power to critical infrastructure, safety hazards, and potential disruption of campus activities. To mitigate these risks, a formal service contract is required to provide routine preventative maintenance, system testing, and immediate service response to equipment failures.

Establishing a service contract ensures that qualified technicians are available to respond rapidly to generator or ATS issues as quickly as possible.

2.0 Scope

The objective is to create an emergency generator & ATS service contract to replace the expiring 31-60076 contract. This contract is to provide preventative maintenance, system testing, and immediate service response to equipment failures on an as needed basis.

Current generator & ATS equipment lists to be attached to contract request requisition. We reserve the right to add equipment as necessary to accommodate changes to the ANL site.

3.0 Performance

This vendor must be a full-service commercial service provider with the capability to perform all required maintenance & repair services for the major brands listed in this contract. All services shall be performed by the vendor's in-house qualified service technicians. Subcontracting of any core services is not permitted. This requirement ensures consistency, accountability, and technical competence across all the repair & maintenance services that the ANL campus requires.

The vendor shall include, as part of their technical proposal, a list of at least five client accounts they currently service that are most compatible in size and scope to Argonne. Please include a summary of the equipment brands & sizes serviced under these contracts to demonstrate your capability to successfully support a broad range of generator & ATS OEM's.

Major brands that contractor shall be fully capable of servicing in-house

- | | |
|------------------|----------------|
| - Cummins | - Asco |
| - Kohler | - Zenith |
| - Caterpillar | - Russelectric |
| - Marathon | - ONAN |
| - Detroit Diesel | - Generac |



Core Services that contractor shall be fully capable of performing in-house

- Full-service commercial generator preventative maintenance & repairs
- Full-service ATS repairs
- Generator load bank testing service
- Paralleling switchgear repair service

The vendor shall have the ability to procure original (OEM) replacement parts (if available) for all the brands listed earlier in this section. The vendor shall also have the ability to access & troubleshoot with the proprietary software required to service these brands.

The vendor shall maintain a primary service facility within 75 miles of the ANL campus. This proximity is required to ensure timely access to technical support, parts, service personnel, and equipment enabling the fastest possible response time for our service requests.

Due to the critical nature of our emergency backup power systems, we require an onsite response time of 4 hours or less for any critical service request involving a system outage.

The vendor must have an in-house technical support & engineering (Including Mechanical & Electrical engineers) to support their local field service team. The vendor shall include the details of their internal technical & engineering support teams in their technical bid. Technical expertise, qualifications, and experience should be included.

The vendor shall have a workforce of at least 30+ generator service technicians. At least 20 shall be considered journeyman level. Technicians shall be Electrical Generator Systems Association (EGSA) certified (or equivalent) to ensure they have the highest level of technical ability. Maintaining a sufficiently large and skilled technician pool is essential to ensuring timely response to emergency service requests. This staffing level helps minimize downtime and ensures that our critical power systems receive prompt and qualified attention. The vendor shall include the details of their technician workforce size, experience level (ex. Journeyman, apprentice, etc.), and technical training background description (EGSA or equivalent, OEM certifications, etc.)

The vendor must own & properly maintain their own load bank testing equipment. The vendor shall have the necessary load bank equipment needed to test up to 2MW. Detailed specifications of this equipment, along with the vendor's maintenance standard, shall be included in the technical part of their bid submission. All load bank testing equipment will be subject to Argonne inspection and approval prior to use on-site.

4.0 Requirements

All site visitors representing vendor must be US citizens with acceptable forms of identification (Real ID, Passport).

Required Training

- Annual Argonne Contractor Safety Orientation (CSO) Training
- NFPA 70E Training
 - o Current & within the last three years
 - o Full day NFPA 70E Training must have been completed originally, but refresher type training is acceptable to maintain the 3-year requirement
 - o Vendor must provide their own arc flash PPE. All PPE will be subject to ANL inspection before use
- Lock-out Tag-out Training
 - o Current & within last three years

- Building Specific Training (example nuclear facility required training, GERT, and be willing to apply for ANL issued dosimeter if required to access nuclear facility)
- OSHA 10 Training for listed ESH Rep & at least one on-site technician

5.0 Period of Performance

ONE (1) Base Year Contract, starting July 7, 2026, with TWO (2) Option Years, expiring on July 6, 2029.

6.0 Argonne Technical Representative Responsibilities

- Coordinate site access with necessary gate passes
- Coordinate scheduling and building access with proper staff i.e. (Foremen, Building Managers, Facilities, and Engineers).
- Provide Argonne Contractor Safety Orientation training materials