



eProjects No: 1747833

Executable Scope

Extend 35KV Circuit From Navy South Substation to SA Substation

At the

NSA Hampton Roads Norfolk, Norfolk, Virginia

PREPARED BY:

NAVFAC MID-ATLANTIC
Public Works Department Norfolk
Facilities Engineering and Acquisition Division
Norfolk, VA 23511

Submitted By: Frances Peppers

PPROVED BY:

Lead Discipline Branch Manager: C. Jeff Morton, P.E.
Project Mgmt & Engineering Director: Jim Smith, R.A.

For FEC for Commander, NAVFAC:

Date: 7-30-25



Extend 35kV Ckt from Navy South Substation to SA Substation Executable Scope

eProjects No.: 1747833

eProjects Work Order No: 1747833
Maximo SR Number: 21999490
Location: NSA HR, Norfolk, VA
Project Title: Extend 35kV Ckt from Navy South Sub to SA Sub

Customer: CNIC
Project POC: Janice Fishburn janice.d.fishburn.civ@us.navy.mil 757-341-1627
Funding POC: Jason Etheridge jason.a.etheridge2.civ@us.navy.mil 757-836-4099

Scope By: Electrical / DM Frances Peppers frances.peppers1.ctr@navy.mil 757-341-0640
Project Manager (PM) C. Jeff Morton, P.E. calvin.j.morton2.civ@us.navy.mil 757-341-0639

Date: July 23, 2025

1. Points of Contact:

FEAD Contracting Officer: Natalie Augsburger natalie.g.augsburger.civ@us.navy.mil 757-341-0555
FEAD Contracts Specialist in Charge: TBD
Construction Manager (CM): TBD
Engineering Technician (ET): TBD
Facility Maintenance Specialist (FMS): Doug Hintz douglas.p.hintz.civ@us.navy.mil 757-836-1913

2. General Description:

Contractor must provide supervision, labor, material, and equipment required to perform all work for the following project: Extend 35kV Circuit from Navy South Ckt #5 to Switch 232. Refer to section 7 "Project Overview and Work Requirements" for additional information.

All work must be performed in accordance with, but not limited to the following:

- Standard industry practices.
- Applicable local, state, federal codes, laws, and regulations.
- The Unified Facilities Criteria.

3. Location:

The work is located at substation Navy South Switching Station (CEP-51) Naval Station Norfolk, Virginia and Switch 232, NSA Hampton Roads, Norfolk, Virginia, approximately as indicated. The exact location will be shown by the Contracting Officer. Refer to attachment 8.1 Location map of Naval Station Norfolk and NSA Hampton Roads, Norfolk.

Extend 35kV Ckt from Navy South Substation to SA Substation Executable Scope

eProjects No.: 1747833

4. Special Scheduling Requirements / Work Procedures:

- 4.1 Utility Services will be in accordance with the procedures in FAR 41.202.
- 4.2 The work must be performed during regular Government working hours. Regular working hours must consist of an 8-1/2 hour period established by the Contracting Officer, Monday through Friday, excluding Government holidays.
- 4.3 The Contractor will be working around an existing substations. Do not enter the substation without prior approval of the Contracting Officer and NAVFAC MIDLANT UEM.
- 4.4 Damage caused by construction operations must be repaired, patched and/or replaced to match adjacent areas to the satisfaction of the Contracting Officer at no additional cost to the Government.
- 4.5 Permission to interrupt any Activity roads, railroads, or utility service must be requested in writing a minimum of 15 calendar days prior to the desired date of interruption.

5. Safety:

- 5.1 All work must be conducted in a safe manner and must comply with all requirements of the U.S. Army Corps of Engineers Safety Health Requirements Manual EM-385-1-1.
- 5.2 Contractor must submit an Accident Prevent Plan (APP), and Activity Hazard Analysis (AHA) for approval by the Contracting Officer. Submit the APP and AHA to the Contracting Officer 15 calendar days prior to the pre-construction conference for acceptance.

6. Submittals:

- 6.1 The Contractor must submit the following documents required for government approval, prior to the start of any construction activities:
 - Shop Drawings
 - Manufacturer's Product Data
 - Test Reports
 - Certificates
 - Manufacturer's Warranties
 - Work Schedule
 - Equipment List
 - Site Plan for Construction Laydown Area
 - Additional submittals as required for the project
- 6.2 The Contractor must submit all required data together for the following sections:
 - 26 08 00 APPARATUS INSPECTIN AND TESTING
 - 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION

Extend 35kV Ckt from Navy South Substation to SA Substation Executable Scope

eProjects No.: 1747833

7. Project Overview and Work Requirements:

7.1 Project Overview:

- a. This project will extend a 34.5kV underground circuit from Navy South Switching Station circuit #5 (NS-5) to existing Switch #232, way 1. This underground circuit will replace NS-15 overhead circuit as the primary 34.5kV line for the SA Substation. The NS-15 overhead circuit will then provide redundancy for the SA Substation.
- b. This project provide Electrical Manhole Inspection Report (EMIR) that will document the existing conditions of all 29 manholes in the project. Refer to Attachment 8.2 Electrical Manhole Inspection Report Requirements and Sample Report and Attachment 8.3 Electrical Manhole Layouts.

7.2 Demolition – Work Requirements

- a. Demolish circuit NS-5 from Navy South Switching Station from existing circuit breaker to electrical manhole (EMH) #3803 to EMH #3804 to EMH #3805 to EMH #3746 to EMH #3745 to EMH #3744 to EMH #3743A. Refer Attachment 8.4 Extend 35kV Circuit Electrical Site Plans.

7.3 New Work – Work Requirements

- a. Provide 3-1/C #750kcmil 35kV EPR & 1#4/0, 600V Cu ground from existing circuit breaker #5 in Navy South Switching Station to Switch 232 way 1 through the existing underground ductbank system from EMH #3803 to EMH #3408B in accordance with Attachment 8.5 UFGS SECTION 26 08 00 APPARATUS INSPECTION AND TESTING and Attachment 8.6 UFGS SECTION 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.
- b. Provide cable tags on all circuits in manholes in accordance with paragraph 2.11 entitled "CABLE TAGS IN MANHOLES" in Attachment 8.6 UFGS SECTION 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.

- 7.4 The Contactor must dispose of all existing demolished / removed material off base and must completely clean up the job site daily at the end of each workday.

8. Attachments:

- 8.1 Location map of Naval Station Norfolk and NSA Hampton Roads
- 8.2 Electrical Manhole Inspection Report Requirements and Sample Report
- 8.3 Electrical Manhole Layouts
- 8.4 Extend 35kV Circuit Electrical Site Plans Drawings
- 8.5 UFGS SECTION 26 08 00 APPARATUS INSPECTION AND TESTING
- 8.6 UFGS SECTION 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION