

ADDENDUM NO. ADDM-01

National Park Service – Interior Regions 3, 4 5
Facilities, Planning and Infrastructure
601 Riverfront Drive
Omaha, NE 68102

to the
Bidding Documents

for

7 May 2026

THEODORE ROOSEVELT NATIONAL PARK – NORTH UNIT ZONE 1 BOUNDARY FENCE
REPLACEMENT – PHASE 1

PMIS No. 314720

NOTICE TO BIDDERS: The Specifications and Drawings for the above referenced project are hereby amended as follows:

DRAWINGS

ITEM NO. G-1 SHEET L2.1 DETAIL 5 – TYPICAL IN-LINE FENCE INSTALLATION

- a. ADD the following note and photographic images to the detail:

‘SECURE WOVEN WIRE ROLLS TO 3/8” INCH AIRLINE CABLE IN BETWEEN IN-LINE POSTS AT 1/3 AND 2/3 SPACING BETWEEN POST TO POST DIMENSION. PROVIDE A MINIMUM OF ONE SECURE TIE OF WOVEN WIRE TO AIRLINE CABLE AT THE MIDPOINT OF SPAN BETWEEN POSTS OF H-BRACE OR OTHER STRUCTURES TO PROVIDE SUFFICIENT TAUGHTNESS OF THE WOVEN WIRE FENCING.

PROVIDE 12-GAUGE WIRE TIES CENTERED ON A VERTICAL WOVEN WIRE STRAND AND WRAP A MINIMUM OF 3 ROTATIONS AROUND THE AIRLINE CABLE EACH DIRECTION FROM CENTER AS DEMONSTRATED IN THESE REPRESENTATIVE IMAGES:





END OF ADDENDUM