

Statement of Requirement (SOR)

Repair of John Deere 544H Loader

For: 733d Civil Engineer Squadron Location: Fort Eustis, VA 23604

Period of Performance: 30 Days After Receipt of All Materials

1.0 Purpose

The purpose of this contract is to procure required parts and perform repairs necessary to restore a John Deere 544H Loader to full operational capability for the 733d Civil Engineer Squadron at Fort Eustis, Virginia.

2.0 Scope

The contractor shall provide all labor, materials, tools, equipment, transportation, and supervision necessary to procure parts, deliver materials to Fort Eustis, and perform repairs on the John Deere 544H Loader. Work includes replacement of major assemblies, hydraulic components, bushings, pins, seals, and associated hardware, as well as line-boring, cylinder resealing, and structural component replacement.

All work shall be completed within 30 days after all materials have been delivered to the Government.

3.0 Applicable Documents

- John Deere 544H Loader technical manuals and OEM specifications
- OSHA standards for heavy equipment maintenance
- Fort Eustis installation access and safety requirements
- Environmental and hazardous waste handling regulations

4.0 Requirements

4.1 Parts Procurement

The contractor shall procure all parts required to complete the repairs. Parts include, but are not limited to:

- 4-in-1 bucket
- 544H coupler
- 544H boom
- Bushings, seals, washers, and pins
- Hydraulic cylinder and hydraulic fluid
- Components required for bucket cylinder reseal
- Components required for Z-bar and bucket link repair

- Miscellaneous shop supplies and environmental handling materials
- Hauling services for materials and equipment

All parts shall be new, OEM, or OEM-equivalent and compatible with the John Deere 544H Loader.

4.2 Transportation and Hauling

The contractor shall transport all procured materials to Fort Eustis to complete repairs on-site.

4.3 Repair Tasks

The contractor shall perform the following repairs:

- Remove and install the bucket and boom frame
- Line-bore top frame holes
- Remove old bushings and press in new bushings
- Replace Z-bar bushings and bent bucket link
- Reseal bucket cylinder
- Replace broken boom cylinder
- Perform all associated mechanical adjustments and alignments

All repairs shall meet OEM specifications.

4.4 Contractor Coordination Requirements

The contractor shall:

- Provide estimated delivery dates for all materials within 5 business days of contract award
- Notify the Government of any delays or backorders
- Coordinate all site access and repair scheduling with the Government point of contact
- Provide weekly status updates until project completion

4.5 Government Responsibilities

The Government will:

- Provide access to the John Deere 544H Loader
- Provide a safe work area on the installation
- Provide a Government point of contact for coordination
- Review and approve material delivery timelines and repair schedule

5.0 Performance Standards

Task	Performance Standard	Acceptable Quality Level (AQL)
Parts procurement	All required parts delivered and verified as OEM/OEM-equivalent	100% accuracy
Repairs	All repairs meet OEM specifications and restore full functionality	Zero defects
Schedule compliance	All work completed within 30 days after receipt of materials	100% on-time completion
Communication	Provide an initial update on material delivery timelines within seven business days of award and promptly report any changes or delays thereafter.	No more than one missed update

6.0 Quality Assurance Surveillance

The Government will evaluate contractor performance through:

- Inspection of delivered materials
- On-site observation of repair activities
- Final operational testing of the loader
- Verification that all documentation is complete and accurate

The Government reserves the right to inspect any phase of the work.

7.0 Deliverables

- All procured parts delivered to Fort Eustis
- Completed repairs restoring full operational capability
- Documentation package including:
 - Repair completion report
 - Operational test results
 - Warranty information for parts and labor

8.0 Security and Access Requirements

The contractor shall comply with all Fort Eustis access control procedures. All personnel must possess valid identification and meet installation vetting requirements.

9.0 Safety Requirements

The contractor shall comply with OSHA regulations, installation safety policies, and all environmental handling and disposal requirements. Hazardous materials shall be managed in accordance with federal, state, and installation regulations.

10.0 Period of Performance

The contractor shall complete all repairs within 30 calendar days after all materials have been delivered to the Government.