

Attachment 1 – Specifications

Specifications for:
Roofing Materials
For Delivery to
Hawaii Volcanoes National Park
1 Crater Rim drive HNP HI,96718

OVERVIEW

Hawai'i Volcanoes National Park (HAVO) intends to purchase commercially available metal roofing materials. HAVO requires these materials to perform roofing replacement on park facilities exposed to high moisture and corrosive volcanic/geothermal conditions. The materials must meet strict durability and corrosion-resistance requirements to ensure long-term asset protection and compliance with NPS facility standards.

All components must be compatible with each other and designed for installation in high-wind and corrosive environments. Color and finish must match specified requirements for visual consistency within park facilities.

A. MINIMUM SALIENT CHARACTERISTICS or GENERALLY ACCEPTABLE SPECIFICATIONS

Note: All products must meet the requirements set forth by the BUY AMERICAN ACT.

Contractor shall provide the minimum requirements metal corrugated roofing panels in pattern 7 in 24-gauge, Ridge caps in 21-inch 24-gauge and in forest green color in low gloss, Flash band 12-inch (Protecto brand or equivalent), 2-inch roofing screws, HPM metal roof color in forest green and low gloss sheen.

Overview of Required Items

Item	Item Quantity	Item Description
Roofing panels	70	Zinc/Aluminum. 25-ft in length and 36-inches in width. HPM forest green color
Ridge caps flashing	12	Zinc/Aluminum. 21-inches in width and 10-ft in length. HPM forest green color
Flashing Band	15	12-inches in width and 50-ft in length. Sliver on the outside and black adhesive tape on the bottom side
Edge seal	2	2-quart cans
Screws	3000	2-inch in length, width ¼-inch head, and forest green in color

Roofing Panels.

Quantity: 70

Summary Description: Metal panels

- Metal Type: Zinc/Aluminum.
- 24-gauge pattern 7 corrugated 25-ft length and 36-inches width.
- Color in HPM dura coat forest green.

Ridge Cap flashing

Quantity: 12

Attachment 1 – Specifications

Summary Description: Metal ridge caps

- Metal Type: Zinc/Aluminum.
- 24-gauge 21-inch width and 10-ft length.
- HPM Dura coat forest green in color.

Flashing Band

Quantity: 15

Summary Description: Rubberized membrane

- 12-inch width and 50-ft length. Sliver on the outside and black adhesive tape on the bottom side.
- Protecto brand or equivalent.

Edge seal

Quantity: 2

Summary Description: Metal edge sealer

- Watertight seals to prevent rust and corrosion.

Roofing screws

Quantity: 3,000

Summary Description: Metal screws

- Metal Type: Stainless Steel.
- 2-inch length, width 1/4-inch head.
- HPM dura coat forest green in color.

Safety Features

- No Required safety terms.

Warranty

- No Required warranty terms.

B. OTHER REQUIREMENTS

No other specified requirements.

C. GOVERNMENT FURNISHED PROPERTY OR SERVICES

D. DELIVERY INFORMATION

Delivery Location

- Hawaii Volcanoes National Park 1 Crater Rim Drive HNP, HI 96718
- Items to be delivered to the HAVO rain shed.

Delivery Logistics

- A park-operated forklift will NOT be available for unloading. The Contractor is responsible for providing all necessary equipment to offload delivered items. The Contractor must ensure that all personnel operating equipment for delivery are appropriately licensed and qualified, as applicable.

Attachment 1 – Specifications

Delivery Term

- The Contractor shall contact the COR within 7 calendar days after contract award to coordinate delivery logistics, including exact delivery dates, locations, and any special site access requirements.
- Delivery shall be made Monday through Thursday between the hours of 6:00 AM HDT to 4:00 PM HDT.

Special Inspections / Invasive Species Inspection

- See the accompanying *HAVO Invasive Species SOPs*. All Contractor vehicles, to include subcontractor vehicles, shall be inspected for invasive species prior to entering the park. Inspections shall be coordinated with the NPS representative(s) identified by the *HAVO Invasive Species SOPs* no later than 7 days prior to the intended delivery date. Invasive species inspections may take approximately 1 hour to perform. If the delivery shipment is found to be contaminated with pests, to include little fire ants (LFAs), the shipment will be rejected. If rejected, the shipment must then be treated at the vendor's expense prior to the rescheduling of a reinspection. If no pests are found, then the material will be accepted.

E. INSPECTION AND ACCEPTANCE

Inspection

- The Contracting Officer's Representative will inspect the delivered items at the time of delivery.

Acceptance

- The Government reserves the right to reject all items that do not adhere to these specifications. Any item identified through timely inspection that does not conform to these specifications may be rejected by the Government. The Contractor shall replace all non-conforming items at no cost to the Government. The Government reserves the right to seek consideration from the Contractor for failures to satisfy the requirements established by these specifications.
- The Government reserves the right to reject defective items identified through timely inspection. Defects in materials and workmanship include, but are not limited to weld cracks, paint flaking, bubbling, fading, corrosion, and other deficiencies that may require rework or redress.

F. PAYMENT

Payment Made through the Invoice Processing Platform (IPP)

- See the IPP clause within the solicitation or contract award for payment guidance.
- Prior to submitting an invoice to IPP, all invoices shall be submitted to the Contracting Officer's Representative or Park Point of Contact for review and, if acceptable, approval.