

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE		PAGE 1 OF 4 PAGES		
2. AMENDMENT/MODIFICATION NUMBER 0001		3. EFFECTIVE DATE 04/28/2026		4. REQUISITION/PURCHASE REQUISITION NUMBER		5. PROJECT NUMBER (If applicable)	
6. ISSUED BY NPS, PWR - LAKE MABO 601 Nevada Way Boulder City NV 89005-2426				7. ADMINISTERED BY (If other than Item 6) CODE			
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)				9A. AMENDMENT OF SOLICITATION NUMBER (X) 140P8126Q0020			
				9B. DATED (SEE ITEM 11) (X) 04/28/2026			
				10A. MODIFICATION OF CONTRACT/ORDER NUMBER			
				10B. DATED (SEE ITEM 13)			
CODE		FACILITY CODE					

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

See continuation page

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) Bradley Metler	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

Previous edition unusable

NAME OF OFFEROR OR CONTRACTOR

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	Amendment #1 addresses vendor questions. No extension to the closing date. Period of Performance: 07/01/2026 to 12/28/2026				

Amendment #1 addresses vendor questions. Answers are in **ORANGE**, below.

Q1. WET WELL DIMENSIONS AND SURFACE AREA

Please provide the interior dimensions (diameter or length x width, and depth) and total surface area to be coated for each of the three wet wells (Temple Bar, Katherine Landing Main, and Katherine Landing Back Bay).

A1: KL Main LS has a diameter of 105 inches with a depth of 180 inches, Back bay dia. 80" and depth of 126", Temple Bar dia. 75", depth of 213"

Q2. SEWAGE FLOW RATES FOR BYPASS PUMPING

Can NPS provide expected average and peak sewage flow rates (gpm) for each of the three lift stations so that bypass pumping equipment can be sized appropriately?

A2: Historic flow rate maximums for Temple Bar= 7,000 gpd, Katherine Main= 15,129 gpd, KL Back bay= 1,700 gpd

Q3. TEMPLE BAR LINER REMOVAL AND SUBSTRATE CONDITION

For the Temple Bar wet well, can NPS provide the approximate square footage of failing fiberglass liner that must be removed, along with the estimated condition and depth of any spalling or structural damage to the underlying concrete substrate? Has any prior condition assessment, inspection report, or as-built drawing been completed that can be shared with offerors?

A3: Unknown, Operators can see the failing liner from the hatch on top of the wet well. No further inspection has been conducted.

Q4. SURFACE PREPARATION STANDARD AND COATING THICKNESS

What is the required minimum dry film thickness (DFT) for the protective coating, and is surface preparation specified to a particular NACE or SSPC standard (e.g., SSPC-SP 6, SSPC-SP 10) with a defined blast profile?

A4: Surface must be cleaned of all grease , oil, rust, scale and other contaminants in accordance with ICRI Technical Guidelines No. 03732. 200 mils thickness per coat, additional coats may be needed in certain instances.

Q5. BYPASS ROUTING DISTANCE AND DISCHARGE TIE-IN POINTS

What is the approximate distance and elevation change for the bypass routing (Back Bay to Main at Katherine Landing, and Main lift to the sewage lagoons via force main at both sites)? Are there existing force main connection points or manholes that the contractor can tie into for bypass discharge, or must the contractor provide all temporary piping?

A5: No existing tie in points on force main. Depending on tech approach to project the distances can vary. The force main should be able to be tied in to within a 100' radius at all locations.