

PERFORMANCE WORK STATEMENT
FOR
Emergency Power and Switchgear
Automation Controls Repair
FOR
USSTRATCOM/J020
20 APRIL 2026

PERFORMANCE WORK STATEMENT (PWS)
For
Emergency Power and Switchgear Automation Controls Repair

1.0 INTRODUCTION

1.1.1 Background: The electric power sources to United States Strategic Command (USSTRATCOM) must operate as a never-fail utility. Commercial Power loss is inevitable due to weather, manmade disasters, and natural disasters. The Commercial Power grid is a target of United States adversaries. Emergency Power Generator systems and Electrical Switchgear must continuously perform at the highest possible level of operational resiliency.

1.1.2 Description of Services: The contractor shall provide all personnel, equipment, supplies, transportation, tools, materials, supervision, and other items and non-personal services necessary to perform Emergency Power and Switchgear Automation Controls Repair as defined in this PWS except for those items specified as services. The contractor shall perform to the standards in this contract.

1.1.3 Objectives: This project will improve the Building 1000 (B1000) Switchgear through three main efforts: updating the control programming, repairing identified issues in the control wiring configuration, replacing equipment that has reached end of life.

2.0 SCOPE/TECHNICAL REQUIREMENTS: The contractor shall accomplish the following upgrades, repairs, and/or replacements to the Emergency Power Generator Systems and Electrical Switchgear Systems located within B1000.

2.1 Upgrades/Repairs/Replacements

2.1.1 Program capability to manually via Human Machine Interface (HMI) initiate NB0A & SB0B electrical busses separation from commercial power for a closed transition to generator power.

2.1.2 Program capability to manually via HMI simultaneously separate Global Operations Center (GOC) from commercial power sources at SU1C & SU2C breakers

2.1.3 Program should enable ability to use emergency generator test automation in situations when Mission Support bus ties are closed and only one commercial source is in use.

2.1.4 Program capability to manually manage minimum generators required to meet load demand without N+1 programming limitation

2.1.5 Program capability to use load banks in conjunction with live load generator testing.

2.1.6 Install input devices, output devices, and control switches as needed to enable stated logic capabilities, manual modes, and automatic modes.

2.1.7 Establish and limit Electric and Power System controls access to 55 CES specified personnel via HMI.

2.1.8 Establish and limit Electric and Power System view access to USSTRATCOM specified personnel via HMI.

2.1.9 Replace/Upgrade Master A and Master B existing Programmable Logic Controllers (PLC) with latest hardware

2.1.10 Repair power to Primary I/O PLC and Secondary I/O PLC so that modules have separate fuses

2.1.11 Perform and document on-site systems field tests of new integrated logic for proper Power Plant and Electrical Switchgear function and controls operations. (CDRL A001)

2.1.12 Correct local/remote indication light. Verify Local/Remote annunciation and correct if necessary. Potential change to match switch legend, "Manual/Automatic."

2.2 Documentation, Commissioning, and Training

2.2.1 Develop, document, and provide system restoration software/hardware/licenses and recovery implementation methods needed to back up and restore the power controls system. (CDRL A002)

2.2.2 Update and test the switchgear's PLC programming to define the system's response to concurrent failure scenarios, and based on the final code, develop a comprehensive Sequence of Operations (SOO) document and a supporting Failure Modes and Effects Analysis (FMEA) report detailing all normal, abnormal, and failure modes. (CDRL A001)

2.2.3 Perform commissioning tests on all upgrades, repairs, and replacements to demonstrate successful implementation of intended sequence of operations as well as the successful retention of previous system settings that provided automatic system recovery from simultaneous unforeseen total commercial power grid loss. (CDRL A003)

2.2.4 Perform training to on-site maintenance personnel integrated with commissioning activities as well as upon completion of successful implementation to include a video disk (as security allows) for Operations, Maintenance, and Facilities Engineering personnel. Training will clarify "red button" operation and troubleshooting. Areas contained within Sensitive Compartmented Information Facility (SCIF) will not have video recordings required. (CDRL A004)

2.3 Special Qualifications:

2.3.1 The contractor is responsible for ensuring all contractor employees working on USSTRATCOM systems are certified by the OEM for the system they are working on.

3.0 GENERAL INFORMATION

This is a non-personnel services contract to provide Emergency Power and Switchgear Automation Controls Repair. The Government shall not exercise any supervision or control over the contract service providers performing the services herein. Such contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government.

3.1 Period of Performance: The period of performance shall be 6 months.

3.2 Place of Performance: The work under this contract will be performed at Contractor and Government Facilities within B1000.

3.3 Recognized Holidays: The Government will have limited manning on the following holidays. The contractor shall correlate a work schedule with the Contracting Officer Representative (COR) prior to one of the holidays listed below.

New Year's Day	Labor Day
Martin Luther King Jr.'s Birthday	Columbus Day
President's Day	Veteran's Day
Memorial Day	Thanksgiving Day
Juneteenth	Christmas Day
Independence Day	

3.4 Hours of Operation: Upon award, the contractor will coordinate a work schedule with the COR. Building and specific location access may be limited during Federal holidays or when the Government facility is closed due to local or national emergencies, administrative closings, or similar

Government directed facility closings. The Contractor shall at all times maintain an adequate workforce for the performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons. When hiring personnel, the Contractor shall keep in mind that the stability and continuity of the workforce are essential.

4.0 CONTRACT REQUIREMENTS

4.1 Quality Control Plan (QCP): The contractor shall develop and maintain an effective quality control program to ensure services are performed in accordance with this PWS. The contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The contractor's quality control program is the means by which the work complies with the requirements of the contract. The QCP shall be submitted with contractor proposal and shall be incorporated into the resulting contract. Any subsequent changes to the QCP shall be submitted to the Contracting Officer and COR within 5 working days. After acceptance of the quality control plan the contractor shall receive the contracting officer's acceptance in writing of any proposed change to his QCP.

4.2 Quality Assurance: The government shall evaluate the contractor's performance under this contract in accordance with the Quality Assurance Surveillance Plan. This plan is primarily focused on what the Government must do to ensure that the contractor has performed in accordance with the performance standards. It defines how the performance standards will be applied, the frequency of surveillance, and the minimum acceptable defect rate(s).

4.3 Meetings

4.3.1 Post Award Conference: The Contractor agrees to attend (virtually or in person) any post award conference convened by the contracting activity or contract administration office in accordance with Federal Acquisition Regulation Subpart 42.5.

4.3.2 Periodic Progress Meetings: During the biweekly meetings, the contractor will provide a slide deck to review progress and apprise the Government of concerns/minor problems, if any, being experienced. The slide deck shall be sent to the COR 2 days prior to the meeting. Appropriate action shall be taken to resolve outstanding issues. These meetings shall be at no additional cost to the government. If a significant problem is identified that will prohibit the continuation of work, the COR shall be immediately notified by email.

4.4 Key Personnel: The following personnel are considered key personnel by the government: PLC Programmer and Project Manager. The contractor shall provide a project manager who shall be responsible for the performance of the work. The name of this person and an alternate who shall act for the contractor when the project manager is absent shall be designated in writing to the CO and COR. The project manager or alternate shall have full authority to act for the contractor on all project matters relating to daily operation of this contract. The Project manager or alternate shall be reachable via phone or email between 8:00am to 4:30pm Central Time; Monday through Friday except Federal holidays or when the government facility is closed for administrative reasons. Qualifications for all PLC Programmers are listed below:

- All PLC programmers shall be certified by the OEM to work on the systems at USSTRATCOM.

4.5 Contractor Travel: Tasks in support of this PWS may be performed at the contractor identified facility as allowable and at USSTRATCOM, Offutt AFB. Any contractor travel to USSTRATCOM shall be authorized travel expenses consistent with the substantive provisions of the Joint Travel Regulation (JTR) and the limitation of funds specified in this contract. All travel requires Government prior approval/authorization and notification to the COR. Contractor travel is a government populated value CLIN and will be funded at the SLIN level and only be billable when travel is approved.

4.6 Other Direct Costs (ODCs): The contractor is responsible for providing all their own tools,

diagnostic equipment, and incidental materials (such as small connectors, fasteners, etc.) needed to perform the work.

The ODC CLIN will be a Government populated value and will be funded as approved. For the major replacement (exceeding \$300) of the hardware and/or software for the control system, the process will be as follows:

- The contractor shall identify the required components and provide the Government a quote for review and approval.
- The Government shall provide written approval before the contractor purchases these items.
- The contractor shall invoice for the actual documented cost of the approved items.

4.8 Deliverables

The following deliverables will be required from the Contract:

CDRL	Name	Required	PWS Ref.
A001	System Operations and Failure Analysis Documentation	A comprehensive Sequence of Operations (SOO) document, supported by a Failure Modes and Effects Analysis (FMEA), that is a direct reflection of the final, tested PLC programming. This document shall detail the system's response to all normal, abnormal, and concurrent failure modes.	2.2.2, 2.1.11
A002	System restoration software/hardware/license and recovery implantation methods report	Submit to the Government for review and acceptance within 20 business days of completion. The COR shall review the report and request any updates with 20 days of receiving the completed report from the contractor.	2.2.1
A003	Commissioning Testing Logs	Logs shall include documentation that commissioning testing has been performed and was successful for all systems in support of this PWS. The logs shall be provided within 15 days of testing completion.	2.2.3
A004	Video Disk for Operations, Maintenance, and Facilities Engineering	Video shall be provided within 30 days of systems completion.	2.2.4
A005	Periodic Progress Meeting Slides	The slide deck shall be sent to the COR 2 days prior to the meeting.	4.3.2

5.0 SERVICES SUMMARY (SS)

The SS is a list of Performance Objectives and Performance Thresholds that will be regularly verified by Government personnel. Each Performance Objective represents a significant task as identified in the PWS by the Government at the time of contract award. The Performance Threshold represents the minimum acceptable level of performance. The Performance Objectives and Performance Thresholds represent only the significant tasks of this PWS and do not excuse the Contractor from the performance of other responsibilities identified in this PWS. Performance Objectives will be monitored regularly by Government CORs.

PERFORMANCE OBJECTIVE	PWS PARAGRAPH REFERENCE	PERFORMANCE THRESHOLD
Closed Transfer Capability	2.1.1	Operator is able to initiate closed transfer to generators for full building.
GOC Power Transfer Capability	2.1.2	GOC can separate from commercial power as described in 1.4.1.2

Generator Testing while on single commercial source	2.1.3	Operator is able to initiate a closed transfer generator test while main switchgears are tied together.
Generator Quantity Control	2.1.4	Operator is able to manually set minimum generators required.
Load Bank in conjunction with generator testing	2.1.5	Operator is able to utilize currently installed load bank in conjunction with a building load generator test.
Install input and output devices and control switches as required	2.1.6	Contractor has installed all devices and switches required to implement programming changes.
HMI Access Controls Established	2.1.7, 2.1.8	Contractor has implemented access control for designated personnel as specified in 2.1.7 and 2.1.8
Replacing Legacy master PLC's	2.1.9	Contractor has replaced existing legacy master PLC's with latest hardware
Separate Primary and Secondary PLC I/O Power	2.1.10	Primary and Secondary PLC I/O power is separate
Perform and document on-site system testing for updated system logic	2.1.11	Contractor shall submit for approval, and perform on site system testing to ensure updates are functioning as intended
Correct Annunciation Display Panels	2.1.12	Contractor shall ensure that annunciation display panels are correctly displaying system status
System Documentation and Restoral	2.2.1, 2.2.2	Contractor shall provide a full set of documents covering all facets of system configuration and operation to include steps required to restore the system, and failure mode analysis.
Commissioning Testing	2.2.3	Contractor shall test all upgrades to ensure successful function and ensure that system automation is working as intended.
On Site Training	2.2.4	Contractor shall perform on site training for all key government personnel.
Staffing	4.4	No defect in or complaint in availability of contract manager as specified in Key Personnel section.

6.0 SECURITY

6.1 Physical Security: The contractor shall be responsible for safeguarding all government equipment, information and property provided for contractor use. At the close of each work period, government facilities, equipment, and materials shall be secured.

6.2 Key Control: The Contractor shall establish and implement methods of making sure all keys/key cards issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. NOTE: All references to keys include key cards. No keys issued to the Contractor by the Government shall be duplicated. The Contractor shall develop procedures covering key control that shall be included in the Quality Control Plan. Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas. The Contractor shall immediately report any occurrences of lost or duplicate keys/key cards to the Contracting Officer.

6.2.1 In the event keys, other than master keys, are lost or duplicated, the Contractor shall, upon direction of the Contracting Officers Representative, re-key or replace the affected lock or locks; however, the Government, at its option, may replace the affected lock or locks or perform re-keying. When the replacement of locks or re-keying is performed by the Government, the total cost of re-keying or the replacement of the lock or locks shall be deducted from the monthly payment due the Contractor. In the event a master key is lost or duplicated, all locks and keys for that system shall be replaced by the Government and the total cost deducted from the monthly payment due the Contractor.

6.2.2 The Contractor shall prohibit the use of Government issued keys/key cards by any persons other than the Contractor's employees assigned to this requirement. The Contractor shall prohibit the opening of locked areas by Contractor employees to permit entrance of persons other than Contractor employees engaged in the performance of assigned work in those areas, or personnel authorized entrance by the Contracting Officer.

6.3 Lock Combinations: The Contractor shall establish and implement methods of ensuring that all lock combinations are not revealed to unauthorized persons. The Contractor shall ensure that lock combinations are changed when personnel having access to the combinations no longer have a need to know such combinations. These procedures shall be included in the Contractor's Quality Control Plan.

6.4 Pass and Identification: An Air Force Common Access Card (CAC) shall be required for all employees. A security background check shall be required to obtain a CAC, and this process takes approximately two weeks. The Contractor shall ensure the pass and identification items required for contract performance are obtained and renewed (as required) for employees and non-Government owned vehicles. If only a temporary ID is required, the COR will work with the contractor to obtain access via the security office.