

U.S. Coast Guard Station New Orleans



Door Repairs Project Scope of Work

**201 Metairie-Hammond Hwy
Metairie, LA 70005**

Primary POC:

MKC Dayton Loyola, EPO

Cell- (808) 937- 3840

Dayton.a.loyola@uscg.mil

Alternate POC:

MK1 Robbie Johnson, AEPO

Office- (504) 329 3595

Cell- (910) 308 4668

Robbie.h.johnson@uscg.mil

Background:

Station New Orleans has 37 doors that are damaged. This has caused a significant physical security deficiency, health and sanitation compliance, placing higher demand on the Station's ageing HVAC system causing condensation, and negatively impacting overall habitability and crew morale

SUMMARY OF WORK**PART 1 GENERAL****1.1. GENERAL DESCRIPTION****1.1.1. General Work Requirements**

Furnish all labor, tools, equipment, and materials for the installation of associated hardware, as well as affect repairs to 37 doors to include but not limited to: hinges, handles, locks, cypher locks, closures, and miscellaneous hardware.

- A. Contractor shall provide and install all new, unused parts and material only.
- B. Contractor shall provide replacement of associated parts, material, hardware, etc.
- C. Contractor Shall provide all materials associated with the completion of this project.
- D. This summary is not all inclusive and delineates only those work items deemed as major to the contract. Ancillary work items necessary to attain the completed project shall be included in the contract as inherent to the work.

1.1.2. SPECIFIC WORK REQUIREMENTS**A. Qualifications**

- (1) The installation shall be performed by a licensed and insured contractor.
- (2) The installation shall comply with current federal, state, and local laws, regulations, and building codes.
- (3) All contractors, sub-contractors, representatives, etc. working on site must be US Citizens or possess a federal work visa, and are required to provide a government issued photo identification Prior to gaining access to the work site.

B. Additional Performance Requirements

- (1) Contractor is required to complete a site visit prior to submitting a bid.
- (2) Contractor shall be responsible to dispose of all old materials replaced during the execution of work
- (3) All doors must operate as designed and close and latch automatically upon completion of the project.
- (4) All associated parts, materials, and equipment shall be new and unused.
- (5) All supplied materials must be made in America.

1.1.3. SPECIAL WORK REQUIREMENTS

- A. Comply with all hot work requirements of the local Coast Guard unit.
- B. Coordinate all staging and laydown areas with the Coast Guard Station New Orleans POC prior to commencing any work.
- C. Comply with all OSHA and industry safety standards.

1.2. TEMPORARY FACILITIES OR UTILITIES

None Required

1.3. PROJECT PERFORMANCE PERIOD

- A. The total contract performance period shall include not only the time needed to complete the base bid and approved option items, but also includes the time needed to submit, review, and approve all material submittals, and complete all project record (closeout) documents. After work begins at the site, perform the work continuously during normal working hours and show daily progress until all work is complete.
- B. The total contract performance period is 120 calendar days.

1.4. LOCATION

All work is located at:
U.S. Coast Guard Station New Orleans
201 Metairie- Hammond Hwy
Metairie, Louisiana, 70005

Arrangements for visiting the site may be made by contacting:

Senior Chief Robert Zaabel, MKCS, EPO

Email: Robert.w.zaabel@uscg.mil

Telephone: (504) 428-8002

1.5. DRAWINGS ACCOMPANYING SPECIFICATION

There are no drawings accompanying this specification.

1.6. WORK HOURS

1.6.1. Normal Working Hours

A. Perform all work at the site from Monday through Friday from 7:00am to 4:00 pm, unless otherwise approved. The contractor shall plan a schedule to minimize disruptions to building operations.

B. Performing work beyond the listed working hours is at the discretion of the local Coast Guard unit point of contact and the contractor must gain prior approval.

1.7. SPECIFIC ENVIRONMENTAL REQUIREMENTS

All removed items, trash, debris, etc. must be disposed of IAW federal, state, and local laws, and regulations.

1.8. SAFETY PROGRAM

1.8.1. General

The Contractor is wholly responsible for work site safety. Implement a safety program that protects the lives and health of personnel in the construction area, prevents damage to property and avoids work interruptions. Provide appropriate safety measures including but not limited to barricades, signs and signal lights as well as complying with the requirements of all applicable federal, State and local safety laws, rules and regulations.

1.9. AVAILABILITY OF UTILITY SERVICES

A. Reasonable amounts of the following utilities will be made available to the Contractor without charge.

(1) Electricity

(2) Potable Water

(3) Access to toilet facilities

B. The Contractor shall pay all costs incurred in connecting, converting, and transferring the utilities for the work. The contractor shall be responsible for making connections including providing back flow preventers, transformers and for disconnection.

1.10. UTILITY OUTAGES

Identify the utility, reason for interruption, proposed time of interruption, and duration of interruption. Do not interrupt utilities until authorized by the Contracting Officer's Representative (COR).

1.11. CONTRACTOR USE OF PREMISES

The work shall be performed on a Coast Guard operational military installation. Contractor shall become familiar with and obey station fire, traffic, and security regulations. Personnel shall not stray from the immediate area of work or direct avenues of ingress and egress unless authorized in advance by the COR. Provide temporary covers on excavations that remain open overnight.

1.12. CLEANUP

The Contractor shall keep the work area, including the laydown and storage area, free from accumulations of waste materials on a daily basis and comply with all federal, state, and local regulations pertaining to the storage, transport, and disposal of wastes. The Contractor shall not use Coast Guard waste disposal facilities including garbage cans, trash piles, or dumpsters.

1.13. ENVIRONMENTAL

1.13.1. Protection of the Environment

The Contractor shall comply with all applicable federal, state, and local laws and regulations for the protection of the environment, including but not limited to the Endangered Species Act (ESA), Bald and Golden Eagle Protection Act (BGEPA), the Migratory Bird Treaty Act (MBTA), National Historic Preservation Act (NHPA), the Resource Conservation and Recovery Act (RCRA), and Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA).

1.13.2. Generated Waste

A. Any waste generated because of the project shall either be recycled or be disposed of in accordance with RCRA requirements.

B. Any hazardous waste shall be manifested off site with the Coast Guard unit listed as the Generator and signatory. Any hazardous waste shall be analyzed, characterized, stored, and disposed of in accordance with RCRA and all applicable federal, state, and local laws and ordinances.

C. Hazardous waste shall be properly transported and delivered to an appropriate facility. The Contractor shall submit for COR approval the proposed disposal facility, qualifications of the transporters, and the draft hazardous waste manifest.

1.15. DISPOSITION OF MATERIALS

A. All materials including construction debris and equipment shall be removed from Government property. The Government will not be responsible for the condition or loss of, or damage to, such property after notice to proceed. Materials and equipment shall not be viewed by prospective purchasers or sold on the site.

B. The Contractor shall submit the disposal receipt from the landfill within 10 working days of disposal as applicable.

1.16. STORM PROTECTION

The Contractor shall take every practicable precaution to minimize danger from storms to personnel, the work, and to adjacent property. Precautions shall include, but not be limited to, closing all opening, removing all loose materials, tools, and equipment from exposed locations, and removing or securing scaffolding and other temporary work.

1.17. RECEIPT OF MATERIALS

The Contractor is responsible to receive all equipment, materials, and supplies.

1.18. DELIVERY AND STORAGE

The Contractor is responsible for the proper transport and storage of all equipment and materials.

1.19. SECURITY

- A. Submit a list of the names of all personnel working on the project site prior to the preconstruction conference for approval. The roster shall be submitted via email, and at a minimum, include the first name, last name, job description, and company of employment.
- B. Immediately submit a new list upon a change in on-site project personnel. Refer to the paragraph titled, Special Notice Prior Notification, for notification requirements. Only personnel on the approved list are allowed onto the project site.
- C. All approved personnel shall carry a valid, Government-issued photo identification while on Government property in conformance with the Real ID Act of 2005. Non-compliant personnel shall be escorted off Government property.

1.20. FINAL INSPECTION AND ACCEPTANCE

Electronically submit a written request for final acceptance to the Coast Guard.

1.21. WARRANTIES

Endorse all warranties or guarantees to the Government. A standard one-year warranty shall be provided for all labor and materials associated with this project

1.22. TRAINING

The Contractor shall provide training to unit personnel in the operation of the equipment. The Operation and Maintenance Manuals shall be approved and provided to the unit prior to the training.