



**DEPARTMENT OF THE AIR FORCE
HEADQUARTERS 628TH AIR BASE WING (AMC)
JOINT BASE CHARLESTON SC**

Statement of Work

Replace Standpipes, Bases, & Guardrails at Bldg 509 Sewer Lift Station

Joint Base Charleston Air Base

South Carolina

18 February 2026 - **Revision 1, 06 May 2026**

Statement of Work: The project consists of providing all plant, labor, material parts, and equipment necessary to replace standpipes, bases, and guide rails on the sewer lift station at building 509 on Joint Base Charleston Air Base, South Carolina. The project requirements include, but are not limited to the following major items of work:

Sewer Lift station Contractor Requirements:

- Set-up to perform OSHA Permitted Confined Space Entry (CSE).
- Plug manhole and install contractor-provided bypass pump.
- Pull pump #1 and perform CSE to remove #1 guide rail, standpipe and base.
- Set new base, new standpipe, and new guide rail using new guide rail brackets.
- Repeat process for other bases, standpipes, and guide rails on the other 3 existing pumps.
- Once installed, all components will be tested for functionality to ensure normal operations.

Water and Fuel Shop (CE) Requirements:

- Following OSHA safety standards, disconnect power to pumps and control panel. Lock out and tag out pumps at the panel.
- After all equipment has been installed and in coordination with contractor for timing, all locks will be removed, and power will be turned back on.

Required Warranty Period:

All products and materials used under this project requirement shall be warranted against defective workmanship and material failure for a period of one year from the completion date.

Products:

All products and materials shall be installed in accordance with the manufacturer's technical instructions and specifications. All excess material and products shall be turned over to the government.

Applicable Instructions:

Work areas around project site will be occupied by the using activity during the course of work. Caution must be taken to ensure all safety work practices are adhered to while construction work requirements are performed at the facility work site.

Caution must be taken in all work areas of the site to avoid physical or cosmetic damage to existing government property. Any damage to government property resulting from construction procedures shall be the responsibility of the contractor.

Special Instructions:

Project site shall be kept clean and orderly daily.

Work methods and practices shall be accomplished in a safe manner abiding by work safety and base safety standards. Work site is subject to OSHA inspections.

Work site areas shall be returned to existing conditions at completion of work requirements.

D. ENVIRONMENTAL: The contractor shall comply with all applicable requirements stated in the Toxic Substances Control Act of 2016. All materials used in the performance of this contract shall be applied in strict accordance with manufacturer's printed label instructions and all applicable standards. The use of Class I ozone depleting substances, asbestos containing materials, and lead paints are strictly prohibited.

E. SAFETY: The contractor shall comply with all OSHA safety regulations during the performance of this delivery order. Install and maintain barricades and barriers as needed. Lay down areas are to be as designated by the Contracting Officer. Work methods and practices shall be accomplished in a safe manner complying with work safety and base safety standards.