



DEFENSE LOGISTICS AGENCY
AVIATION AT OKLAHOMA CITY
3001 STAFF DRIVE, SUITE 2B95
TINKER AIR FORCE BASE, OKLAHOMA 73145-3015

13 June 2025

MEMORANDUM FOR: Parker-Hannifin Corporation

FROM: DLA Aviation - AOBA
3001 Staff Dr., 2B95
Tinker AFB, OK 73145

SUBJECT: Letter Solicitation SPRTA1-25-Q-0394

This solicitation is issued to acquire the supplies identified below. Please provide your best price and delivery quote for the part number based on the quantity listed. This correspondence constitutes a letter solicitation as this item is intended to be ordered as a firm fixed price contract against Basic Ordering Agreement SPE4A1-22-G-0007.

CLIN	P/N	NSN	Noun	Quantity
0001	63038-08	6115-01-121-3632HY	HYDRAULIC MOTOR-GEN	3 EA

Required Quantity: 3 each

IUID APPLIES: DFARS 252.211.7003

FMS REQUIREMENT

Inspection: Origin

Acceptance: Origin

TAC: DFMS

Inspection/Acceptance Report: Receiving Report Required.

Quality Assurance: Standard Inspection, FAR 52.246-2,-3,-4,-5 or -6 as applicable to contract

Buy American Act/balance of Payments Program

Requested Delivery: 3 each On or Before 27 FEB 2026

Ship to:

DSR004

Please provide a quote no later than 4:00 PM CST on 14 July 2025. Please forward your quote and direct all questions to Scott Rountree at scott.rountree.1@us.af.mil.

Sincerely,

//SIGNED//

Scott Rountree

Contracting Officer

Attachments

Packaging Requirements

Special Packaging Instructions

Transportation Data

IUID Report

IUID Engineering Order

PACKAGING REQUIREMENTS																		
PURCHASE INSTRUMENT NUMBER: FD20302501780-00												VERSION: 1						
MIL-STD 129 REVISION: R												MIL-STD 2073-1 REVISION: E						
THE FOLLOWING STATEMENT IS IN COMPLIANCE WITH THE UNITED NATIONS-IMPLEMENTED RESTRICTIONS ON WOOD PACKAGING MATERIAL (WPM). THIS REQUIREMENT IS SPECIFICALLY CONCERNED WITH INVASIVE SPECIES SUCH AS THE PINWOOD NEMATODE. WPM IS DEFINED AS WOOD PALLETS, SKIDS, LOAD BOARDS, PALLET COLLARS, WOODEN BOXES, REELS, DUNNAGE, CRATES, FRAMES, AND CLEATS. THE STATEMENT BELOW CITES THE REQUIREMENTS IN DETAIL AND COVERS LUMBER FOR BUILDING CONTAINERS AND PALLETS USED FOR DELIVERIES RESULTING IN SHIPMENTS WORLDWIDE (DIRECT, OR THROUGH AIR LOGISTICS CENTERS (ALC), CONTAINER CONSOLIDATION POINTS (CCP), OR OTHER BASES). WOODEN LUMBER, WOODEN PALLET AND PACKAGING/CONTAINER STATEMENT: ALL WOODEN LUMBER, WOODEN PALLET'S, AND WOODEN CONTAINERS PRODUCED ENTIRELY OR IN PART OF WOOD PACKING MATERIAL (WPM) SHALL BE CONSTRUCTED FROM DEBARKED WOOD IN ADDITION TO THE APPLICATION OF HEAT-TREATED (HT) MATERIAL (HT TO 56 DEGREES CENTIGRADE OR 133 DEGREES FAHRENHEIT FOR 30 MINUTES). CERTIFICATION/MARKING IS REQUIRED BY AN ACCREDITED AGENCY RECOGNIZED BY THE AMERICAN LUMBER STANDARDS COMMITTEE (ALSC). FOR REFERENCE DOCUMENTATION, SEE LATEST REVISION OF "INTERNATIONAL STANDARDS FOR PHYTOSANITARY MEASURES" (ISPM)NO.15), "REGULATION OF WOOD PACKAGING MATERIAL IN INTERNATIONAL TRADE."																		
PACRN:		PACKAGING REQUIREMENT:						PRESERVATION LEVEL:		PACKAGING LEVEL:		SPI:		SPI REV:		SPI DATE:		
AAA		MIL-STD-2073-1 / SPI						MIL		B		F011213632		A		87282 - 09 OCT 1987		
ITEM(S): 6115011213632HY																		
CODED DATA:																		
QUP		ICQ	PRES METH	CD	PRES MTL	WRAP MTL	CUSH DUNN	CT	UNIT CONT	INT CONT	UCL	SPEC MKG	UNIT PACK WEIGHT	UNIT PACK LENGTH	UNIT PACK WIDTH	UNIT PACK DEPTH	UNIT PACK CUBE	OPI
ADDITIONAL PACKAGING AND CONTAINER MARKING REQUIREMENTS:																		
SUPPLEMENTAL PACKAGING INSTRUCTION TEXT:																		
VENDOR PACKAGING INSTRUCTIONS: Military Packaging and Marking Items shall be packaged in accordance with MIL-STD-2073-1, Standard Practice for Military Packaging. Shipping and storage markings shall be in accordance with MIL-STD-129, Standard Practice for Military Marking. Shipping Container Marking Shipping containers shall be marked meeting the following criteria: (a) MIL-STD-129, Standard Practice for Military Marking. (b) Additional marking and/or bar coding requirements exceeding those of MIL-STD-129 (e.g., unit serial numbers, original equipment manufacturers (OEM) name, or OEM model number, as specified on the AFMC Form 158.																		
ORGANIZATION / OFFICE SYMBOL:		PACKAGING SPECIALIST:				PHONE NUMBER:				SIGNATURE:				DATE:				
406 SCMS / GULAA		Davis, Richard R				405-371-9037 / 582-5972				//SIGNED//Davis, Richard R				25108 - 18 APR 2025				

SPECIAL PACKAGING INSTRUCTION			CODE ID	SPI NO. (TPO)
			98749	01-121-3632
			SHEET 1 OF 2	
PART OR DRAWING NO. 63038-08	NATIONAL STOCK NO. 61 1 5 01 121 3632 UH	CURRENT REV 87282	ILL LUCY LEE CHK C. SCUDERI ENGR AUTH	
ITEM NOMENCLATURE HYDRAULIC GENERATOR		ORIGINAL DATE 84010		
PRESERVATION IAW MIL-P-116 LEVEL A METHOD I I b LEVEL B METHOD I I b LEVEL C METHOD I I I OMIT P/N(s) 8, 9 & 1 0 CLEANING DRYING PRESERVATIVE FLUSH PORTS W/MIL-H-6083 MARKING IAW MIL-STD-129 SPECIAL MARKING: A) SPI NO. 01-121-3632 (OPPOSITE ID MARKING) B) REUSABLE CONTAINER - DO NOT DESTROY C) METHOD I I (WHEN REQUIRED) D) UP ARROWS (ON BOTH CONTAINERS) CLOSURE TAPE METHOD V IAW APPENDIX OF PPP-B-636			PACKING AS SPECIFIED BELOW AND BILL OF MATERIALS LEVEL SPEC STYLE TYPE CL VAR GR A B PPP-B-636 RSC CF WR SW W5c C LEVEL A LEVEL B LEVEL C GROSS CU FT 2.3 GROSS WT LBS 39 DESIGN FRAGILITY G. 110+ G. G. LENGTH WIDTH DEPTH CTNR I.D. 1 3 IN. 1 3 IN. 21 IN. CTNR O.D. 1 3-1/4 IN. 1 3-1/4 IN. 21-1/2 IN. ITEM DIM 15-1/2 IN. 8-3/8 IN. 7-3/4 IN. ITEM WT LBS 30-1/2	
REVISIONS				
LTR	DESCRIPTION	DATE	ILL	APRVD
A	DELETED ALT FIP PACK	87282		RCS
10	1	HUMIDITY INDICATOR		MS20003
9	40	DESICCANT UNITS		MI L-D-3464 TYPE I
8	1	BARRIER	70 X 38	MI L-B-1 31 CLASS 1
7	1	INTERIOR CONTAINER	1 2 X 1 2 X 20	PPP-B-636 RSC CF DOM SW 175
6	1	TOP & BOTTOM PAD	1 2 X 1 2 X 9/1 6	PPP-F-320 TW
5	2	SLEEVE, UPPER & LOWER	47-1/2 X 9-5/8 X 9/1 6	PPP-F-320 TW
4	2	BOLT, CC W/N&W	2-1/4 X 1/4	FF-B-584 (SEE NOTE 4)
3	1	BASE	1 2 X 1 2 X 1/2	NN-P-530 (SEE DETAIL)
2	1	WRAP	37 X 28	MI L-B-1 21 GRADE A (SEE NOTE 1)
1	1	EXTERIOR CONTAINER		(SEE PACKING DATA)
PART NO.	QTY REQD	NOMENCLATURE OR DESCRIPTION	SIZE	MATERIAL SPECIFICATION

SPECIAL PACKAGING INSTRUCTION

(CONTINUATION SHEET)

CODE ID
98749



SPI NO. (TPO)
01-121-3632

ITEM NOMENCLATURE
HYDRAULIC GENERATOR

SHEET 2 OF 2

NOTES:

1. P/N 2 MAY BE SUBSTITUTED IF IT MEETS THE REQUIREMENTS OF MIL-P-116 AND PROVIDES EQUAL PROTECTION AT NO INCREASED COST.
2.  INDICATES DIRECTION OF FLUTES.
3. CAP PORTS IAW MIL-C-5501.
4. BOLT ITEM TO BASE; USE ITEM TO LOCATE BOLT HOLES ON BASE.
5. UP ARROWS MUST BE ON BOTH CONTAINERS OR THE PRESERVATIVE FLUID WILL LEAK OUT IF ITEM IS PLACED ON ITS SIDE. ITEM MUST REMAIN UPRIGHT.



TRANSPORTATION DATA FOR SOLICITATIONS		PURCHASE INSTRUMENT NUMBER: FD20302501780-00		DATE INITIATED: 18 APR 2025	
COMMODITY: See Continuation		STOCK NUMBER: See Continuation			
F.O.B. TERMS RECOMMENDED AS BEST SUITED FOR THIS PROCUREMENT					
☒ ORIGIN		☐ DESTINATION		☐ OTHER <i>(Specify)</i>	
		☐ DATA / FIRST ARTICLE F.O.B. DESTINATION			
TRANSPORTATION PROVISIONS / CLAUSES				FAR CITATION	
F.O.B. Origin				52.247-29	
Clearance and Documentation Requirements				52.247-52	
Freight Classification Description				52.247-53	
Contact DCMA Transportation Contact DCMA Transportation on ALL "DCMA Administered" contracts prior to shipment for shipping instructions using the DCMA Shipment Instruction Request (SIR) eTool System, at http://www.dema.mil < http://www.dema.mil > for ALL FOB: Origin, Foreign Military Sales (FMS), and FOB: Destination OCONUS/Export movements to obtain the appropriate DOD regulatory clearances, shipping documentation and instructions from your cognizant DCMA Transportation Office. If you are new to DCMA, and do not already have a SIR eTool account, you will first need to request an account via DCMA External Web Access Management (EWAM) application which can be accessed at http://www.dema.mil . If you need additional assistance, email DCMA Transportation Group at: Transportation.Division@dema.mil . Do not move any freight to a water or aerial port prior to contacting DCMA or it will become frustrated. Failure to contact the responsible DCMA may result in vendor incurring additional expenditures.				Vendor Transportation Instructions	
TACRN: AAA					
TRANSPORTATION FUNDS INFORMATION:					
Purchase Instrument Line LOA: 9711X8242.0002 4FX LC5W CKDFSR 000000 00000 001000 503000 F03000 FSR: 090407 PSR: 062570					
First Destination Transportation Account Code: DFMS					
Miscellaneous Obligation / Reimbursement Document:					
Second Destination Transportation Account Code:					
FMS LOA: 9711X8242.0002 4FX LC5W CKDFSR 000000 00000 0					
Additional Funding Information:					
ITEM / SHIP TO(s):					
NSN / Pseudo NSN: 6115011213632HY Purchase Instrument Line Item Number: 0001 Ship to (DoDAAC / MAPAC): DSR004 Mark For: DSRA00 Ship To (Address): WPOD: APOD: BBP / CCP: RIC: Ship To (Remarks): TAC: DFMS			Requisition Number: DSRA5V50190046 Supplemental Address: DA4KDF FMS Case: KDF		
EVALUATION OF PORT BID OR PROPOSAL:					
SOLICITATION DATA NOTES:					
OTHER TRANSPORTATION DATA:					
NAME	ORGANIZATION / OFFICE SYMBOL	COMMERCIAL / DSN PHONE	SIGNATURE	DATE	
Hogan, Darrick D	406 SCMS / GULAA	478-327-3489 / 497-3489	//SIGNED//Hogan, Darrick D	18 APR 2025	

ITEM UNIQUE IDENTIFICATION (IUID) CHECKLIST	
I. IUID DETAILS: DFARS 252.211.7003	
SECTION (c) (1) (ii) APPLIES TO THE FOLLOWING:	
ITEM REQUIRING IUID MARKING	
NSN 6115011213632HY	VERSION NUMBER 2
NOUN HYDRAULIC MOTOR-GEN	
INITIATOR Elden, Mark E	ORGANIZATION CODE / OFFICE SYMBOL 422 SCMS / GUEA
COMMERCIAL PHONE 405-582-5340	DSN PHONE 852-5340
CAGE / REFERENCE NUMBER	
MARKING IS TO BE PERFORMED IN ACCORDANCE WITH THE LATEST VERSION OF MIL-STD-130	
MARKING GUIDANCE Contractor Determined Location and Method	ENGINEERING DRAWING / ECP / ECO NUMBER
MARKING TYPE	MARKING METHOD
DESCRIPTION / LOCATION	
REMARKS	
ATTACHMENT(S)	
II. EMBEDDED ITEMS	
SECTION (c) (1) (iii) APPLIES TO THE FOLLOWING:	
NSN	NOUN
CAGE / REFERENCE NUMBER	
ITEM IS AN EMBEDDED ITEM FOR NSN / PSEUDO NSN: 6115011213632HY	
MARKING GUIDANCE	ENGINEERING DRAWING / ECP / ECO NUMBER
MARKING TYPE	MARKING METHOD
DESCRIPTION / LOCATION	
REMARKS	
ATTACHMENT(S)	

ENGINEERING ORDER						1. ENGINEERING ORDER NO. 2011C1186-T				
						DATE: 2010-09-17		PAGE 1 OF 3 PAGES		
2. DWG TITLE MOTOR-GENERATOR, HYDRAULIC EMERGENCY ELECTRICAL POWER				3. DWG CAGE CODE 93835		4. DWG NO. 63038-08				
5. NEXT ASSY N/A		6. USED ON F-15 Aircraft		7. OPR CAGE CODE 98748		DWG SIZE	DWG SHEET(S)	LATEST DWG REV LTR		
8. TYPE OF ENGINEERING ORDER		9. REASONS FOR CHANGE		11. DOCUMENTS AFFECTED (TO/TCTO/SPEC/OTHER) 9H23-4-3 9H23-4-4		14. CORROSION CONT. MON.		SYMBOL	DATE	
☒	ADVANCE CHANGE		ERROR CORRECTION			15. NDI		SYMBOL	DATE	
	DEVIATION AUTHORIZED		DESIGN CHANGE							
	CHANGE NOTICE		DRAWING CLARIFICATION							
	INFORMATION	☒	UPDATE DRAWING	12. EO PREPARED/REQUESTED BY Adolfo Cortez Jr		SYMBOL 422 SCMS	DATE 20110922	16.	SYMBOL	DATE
10. DISPOSITION OF SPARES		9. OTHER COMMENTS		CORTEZ.ADOLFO.JR.1384345812		PHONE (405) 734-8273	17. DWG CHANGED BY			
	REWORK	This EO adds Item Unique Identification (IUID) requirements to the drawing DRC Contract		13. ENGINEERING APPROVAL		SYMBOL 422 SCMS	DATE 27 SEP 2011	18. CHANGE CHECKED BY	SYMBOL	DATE
	MODIFY			JIMENEZ.JOSE.A.1231036500 OSE.A.1231036500		PHONE 405/734-8274	19. EO/DWG RELEASED BY JIMENEZ.JOSE.A.1231036500		SYMBOL GUEA	DATE 9-27-11
	SCRAP					Digitally signed by JIMENEZ.JOSE.A.1231036500 DN: cn=US, o=U.S. Government, ou=DoD, ou=PKI, ou=USAF, cn=JIMENEZ.JOSE.A.1231036500 Date: 2011.09.27 09:10:31 -0500				
	REPLACE					Digitally signed by JIMENEZ.JOSE.A.1231036500 DN: cn=US, o=U.S. Government, ou=DoD, ou=PKI, ou=USAF, cn=JIMENEZ.JOSE.A.1231036500 Date: 2011.09.27 09:10:42 -0500				
20. DESCRIPTION OF CHANGES/REMARKS										
- As of the date of this EO (17 Sept 2010), no copy of this drawing exists in JEDMICS. - F-15 Aircraft Emergency Electrical Power Hydraulic Motor-Generator (PN 63038-08) shall be marked with a Unique Item Identifier (UII). (REF: MIL-STD-130) - If no UID label is present, fabricate new UID label (200733803-33) to attach to the end item (PN 63038-08). - New UID label will be located on the end item as shown in sketch/photo on page 2, AF form 3926. (UID Label P/N 200945085-013A is an acceptable alternate part)										

ENGINEERING ORDER

(Continuation Sheet)

1. ENGINEERING ORDER NO.
2011C1186-T

DATE: 2010-09-17

PAGE 2 OF 3 PAGES

2. DWG TITLE

MOTOR-GENERATOR, HYDRAULIC EMERGENCY ELECTRICAL


3. DWG CAGE CODE

93835

4. DWG NO.

63038-08

5. DESCRIPTION OF CHANGES/REMARKS



ENGINEERING ORDER - PARTS LIST CHANGES

1. ENGINEERING ORDER NO.
2011C1186-T

DATE: 2010-09-17

PAGE 3 OF 3 PAGES

2. DWG TITLE

MOTOR-GENERATOR, HYDRAULIC EMERGENCY ELECTRICAL POWER

| 3. DWG CAGE CODE

93835

4. DWG NO.

63038-08

PARTS LIST CHANGE

[illegible]