



PERFORMANCE WORK STATEMENT (PWS)
for
AIRCRAFT FUEL & GROUND FUEL SUPPORT SERVICES
and
FUEL STORAGE AND DISTRIBUTION
under
SOLICITATION SPE603-26-R-0528
at
NAVAL AIR STATION KINGSVILLE

Dated: April 10, 2026

TABLE OF CONTENTS

C-1.0 Requirements and Deliverables	3
C-1.1 Responsibilities.....	3
C-1.2 Facilities	3
C-1.3 Detailed Plans.....	3
C-1.4 Contract Turnover.....	7
C-1.5 Quality Monitoring and Evaluation.....	7
C-1.6 Staffing.....	7
C-1.7 Key Personnel.....	8
C-1.8 Service Personnel	10
C-1.9 Correspondence and Visits	12
C-1.10 Information and Records Management.....	12
C-2.0 Performance Requirements	12
C-2.1 Fuel Operations.....	12
C-2.2. Bulk Storage Operations	14
C-2.3 Internal Transfers.....	14
C-2.4 Ground Fuels.....	15
C-2.5 Recyclable and Recoverable Fuels	15
C-2.6 Product Inventory and Accountability	15
C-2.7 Product Quality Surveillance.....	15
C-2.8 Maintenance	16
C-2.9 Training	24
C-2.10 Safety.....	25
C-2.11 Environmental.....	26
C-2.12 Security	27
C-2.13 Incidental Equipment.....	28
C-2.14 Use of Navy Facilities.....	29
C-2.15 Air Show Fueling Services	29
C-3.0 Contractor Furnished Equipment	29
C-3.1 Vehicles and Equipment.....	29
C-3.2 Records	32
C-3.3 Disposition of Property.....	32
C-3.4 Property Storage	32
C-3.5 Equipment Inspection	32
C-3.6 Other Contractor Provided Equipment and Supplies	33
Appendix A: Facility Specific Information.....	35
Appendix B: Definitions, Acronyms, and Abbreviations.....	41
Appendix C: Reference Documents	45
Appendix D: Common Access Card (CAC) Requirements	48

C-1.0 Requirements and Deliverables

C-1.1 Responsibilities: This Performance Work Statement (PWS) is established to identify reasonable and realistic Operational (needed) Missions, relevant and applicable, to stakeholders Non-Agency Functional Requirements. DLA Energy substantiated, an official justification during the budgetary approval process. This was conducted, during the validation of stakeholder requirements, associated with operational mission workloads. Based on the validation conducted, the PWS does not have inherently Military or Civil Service functions or redundancies of services. The PWS was developed and must be executed in accordance with DoDM 4140.25, DoDI 5000.74 and DLAM 5000.74. The contractor must be responsible, to ensure, any newly discovered, requested, and/or communicated operational workloads, beyond the scope-of-work(s), described in the contract or PWS, are immediately communicated to the Contracting Officer. Any out-of-scope workloads must not be performed by contractor without the prior, official approval from the Contracting Officer. The contractor must only execute the management, operation, maintenance, repair, product quality surveillance, inventory/accounting controls, security, safety, and environmental protection of the assets, properties and performance duties as identified in the PWS. The contractor must utilize best industry directives, regulations, and instructions, in accordance with Department of Defense (DoD), Federal, Navy, State, and Local References and Laws identified in Appendix C, along with the references listed within each individual subject reference. If a situation occurs where a conflict between two or more set of references exists, the overarching Directive or Law must take order of precedence. Any unresolved issues and nonconcurrences between Office of Secretary Defense (OSD) and Department of Defense (DoD) Component Heads or between two or more DoD Component Heads, or Agencies, must be addressed to the DLA Energy, Contracting Officer in accordance with DoDI 5025.01.

C-1.2 Facilities: Naval Air Station (NAS) Kingsville aviation bulk fuel storage compound is a compact system consisting of three (3) 20,000-barrel aboveground fuel storage tanks and the components to receive fuel by commercial tank truck, and supply product to the mobile refuelers at the fill stands. The fuel storage compound, building 5722 houses the fuel laboratory, office and training space, and pump house controls. East across Forrestal Street is the fill stand, refueler truck parking, maintenance area, and the administrative compound. A two lane fill stand dispenses product to the refuelers kept in the adjacent parking area. The Fuel Dispatch Center, driver's ready room, and a small office are located in Bldg. 4777. NAS Kingsville is home to Training Air Wing TWO, comprised of aviation units VT-21 and VT- 22 (T-45 Goshawk) that train Navy and Marine Corps Jet/Strike aviators for the Fleet.

C-1.2.1 NALF Orange Grove, On-station: The fuel facility at NALF Orange Grove is a compact system consisting of three (3) 25,000 gallon Cut and Cover fuel storage tanks, a covered fill stand/parking area, and receipt headers. The system is supplied by tank trucks via a receipt header. NALF Orange Grove also has a portable pantograph for hot refueling aircraft via the mobile refueling vehicle

C-1.3 Detailed Plans: The contractor must submit all detailed plans listed below to the Contracting Officer (KO) for review and acceptance no later than 60 days prior to the start of the contract performance period and ensure that required plans are accepted and approved by DLA Energy 30 days prior to start of the contract performance period. The contractor must ensure, the twelve detailed plans specify the identical proposed approach stipulated in their Proposal. DLA Energy reserves the right to request changes or modifications to any detailed plans at any time throughout the contract performance period. The plans are considered dynamic documents and must be updated as required throughout the contract period. Updates will be provided to the Contracting Officer Representative (COR) and KO for review. The KO must provide final approval, as to any changes. These plans must be used by the COR and Quality Assurance Evaluator (QAE) for monitoring and assessing contract performance, along with the Quality Assurance Surveillance Plan (QASP).

C-1.3.1 Contract Compliance Plan: The contractor must be responsible for ensuring compliance with contract performance requirements indicated in the PWS. A monitoring system must be used by the contractor to measure performance on a continuous basis throughout the contract performance period and any contract option periods. The Contract Compliance Plan (CCP) must include performance requirements for all the services, specific tasks listed, and the contractor's own performance-based plans. General performance criteria must include the contractor's ability to provide continuous support capabilities as specified in the PWS, by record keeping, reporting procedures pertaining to administrative requirements, facility operations, upkeep of facilities, and grounds. The CCP must include time specific checklists for evaluation of all operational requirements. The CCP must address procedures for corrective actions including the resolution of any Contract Discrepancy Report (CDR) generated by the KO/COR. The CCP must be made available for KO/COR review upon request at any time during the contract performance period.

C-1.3.2 Product Quality Surveillance Plan: The contractor must provide a comprehensive plan to ensure that products placed in the care of the contractor are properly handled, remain on-specification, and are ready for issue. The plan must include policy and procedure regarding product sampling, visual examination of samples, and the submission of samples needing further analysis to the regional fuel laboratory. In addition, the plan must outline the documentation of samples, test results, reports, records keeping applicability, and actions to be taken in case of unacceptable test results. The plan must fully outline contractor responsibilities for quality surveillance under this contract.

C-1.3.3 Maintenance Plan: The contractor must provide a detailed maintenance plan for assigned facilities, equipment, and system components. The Maintenance Plan must clearly outline the process of planning, programming, accomplishing, documenting, reporting all maintenance actions, by including the use of a contractor-furnished computerized maintenance management system (CMMS) to track maintenance for components and facilities at assigned locations, in compliance with all American Petroleum Institute (API) Standards, National Fire Protection Association (NFPA) Codes, National Electric Codes, Unified Facility Criteria (UFC), Environmental Protection Agency (EPA) Laws, Department of Defense (DoD), Federal, State, and Local requirements throughout the life of the contract. The Maintenance Plan must identify a contractor-furnished computerized maintenance management system (CMMS) at each management team location. This contract site must have a web- link capability to communicate collectively (with each other software locations), operate independent at each location, and provide real time reporting of maintenance discrepancies, by sending automated emails to COR's, QAE's, and **(when applicable)** other stakeholders. The CMMS must have the capability to assign two system licenses, for one COR and one QAE's (read only authorization roles). This is required, to ensure (both) command and control locations have capabilities to address any maintenance concerns. These CMMS read only roles must be used by the COR's and QAE's for monitoring and assessing contract performance, maintenance accomplish ratio's, analytical maintenance data calls, and used in conjunction with the QASP. The plan will be continuously reviewed over the course of the contract and any need for changes, must be communicated to the contractor through the KO (IAW C-1.3), as all final changes must be approved by the KO. The complete Maintenance Plan will include a copy of all maintenance action forms signed by the maintainers and managers, along with applicable reports to be generated by the CMMS.

C-1.3.4 Operations and Staffing Plan: The contractor's plan must contain a comprehensive and detailed matrix that outlines all manning aspects, to include sub-contracting, and requirements regarding the management and labor force to undertake the required tasks. The plan must include a detailed organization chart showing the number of key and service employees identified by job classification, wage determination, full or part time equivalent status, a brief description of the tasks to be performed, and

the duty description of the employee that will perform the task described for a typical seven-day workweek must be included. The quantified manning approach must be concise in meeting PWS, Appendix A, workloads. Additionally, an operational matrix defining how the proposed staffing of full-time and part-time equivalents must meet the workload requirements for a typical seven-day workweek, and higher known tempo of operations must also be included. The contractor must include the above-mentioned information as a part of the contractor's proposal submission in response to the underlying solicitation for this contract and ensure that both (Operations and Staffing) matrix(s) and plans. Operating and Staffing hours are detailed in Appendix A. The Staffing Plan must be submitted with the Contractor's proposal and submitted for approval any time the contractor makes changes to staffing levels or positions.

C-1.3.5 Environmental Protection Plan: The contractor must submit a comprehensive and detailed plan outlining policy, procedures, and safeguards necessary to protect the environment. The contractor's plan must be site specific, cover all areas, facilities, equipment, duties, and tasks for which the contractor is responsible, establish mishap reporting procedures as required below, and elaborate on issues that may be unique to the activity. CNIC appoints shore Navy On-Scene Coordinator (NOSC) and provides policy guidance for planning, coordination, and reporting incidents on shore and offshore within 12 nautical miles of land. The contractor must not be assigned any NOSC duties, at any Naval Installation. The plan must comply with all applicable DoD, Federal, Navy, State, and Local References and Laws identified in Appendix C.

C-1.3.6 Equipment Provisioning Plan: The contractor must identify and include the types and quantities of vehicles, major equipment items, powered grounds maintenance equipment (unless subcontracted), computer systems, and office machines necessary to support the locations under this contract proposal. Upgrading or modifying equipment to meet specific on station public over-the-road requirements, licensing or obtaining permits for equipment and personnel, and the adherence to insurance requirements must be the responsibility of the contractor. Vehicles and major equipment items, powered grounds maintenance equipment, must be in an up-to-date maintenance, and operational condition to withstand the entire contract period. All vehicles and equipment must meet the performance requirements of the latest versions of: National Fire Protection Agency (NFPA) 407, Standards for Aircraft Fuel Servicing, Department of Transportation (DOT) 406, National Fire Protection Agency (NFPA) 385 Standard for Tank Vehicles for Flammable and Combustible Liquids, ATA Spec 103 Standards for Jet Fuel Quality Control at Airports, and other Federal Policies/Laws as applicable. Information relevant to equipment capabilities such as and not limited to manufacture date, mileage/hours, make, and model along with the maintenance plan for assigned vehicles and equipment, must identify each piece, and will be utilized in determining operational abilities. Contractor equipment must be on site and available at the start of the performance period. Should the contractor be required to lease equipment due to long lead times or unexpected delays with procuring equipment it will do so at contractor expense to ensure there is no disruption of service. Any proposed vehicle fleet and equipment must meet the performance requirements and specifications as stated in this PWS. The contractor must include the above-mentioned information as a part of the contractor's Equipment Provisioning Plan.

C-1.3.7 Contract Contingency Plan: The contractor plan must outline detailed procedures and processes, to ensure there are no significant interruptions. The plan must provide specifics regarding labor issues as may result from potential strike actions, military contingency, war time, and emergent staffing requirement, (including subcontracting where required), and the replacement of equipment. The contractor must be responsible for repairing or replacing inoperable equipment or obtaining additional equipment and labor required to carry out day-to-day and contingency operations. The plan must include contingencies for major/minor breakdowns or unavailability of contractor-furnished equipment such as vehicles, major equipment items, powered grounds maintenance equipment (unless subcontracted), computer systems, and office machines, necessary to support the locations under this contract proposal. The contingency plan must detail fluctuating quantities of equipment, such as one

refueler out of service, two refuelers out of service, three to four or more, and a resolution for each situation without any interruption of customer service. Contractor must note the availability of Incidental Equipment (as further defined in C-2.13 and Appendix A), which includes Navy-owned personal equipment, such as truck operated mobile pantographs, lab equipment, and any equipment categorized as “personal” equipment, which are considered incidental to the fuel facilities and made available for contractor’s use in the performance of the contractor’s service obligations and PWS workloads, and which remain the responsibility of the Navy to purchase/replace, as needed, in support of the locations identified under this contract. The contractor must perform operator level maintenance, which includes, without limitation, the lubrication of machinery and replacement of filters and small parts, by utilizing hand tools, and excludes any system level maintenance. All parts and materials must be purchased by the Navy (Operation and Maintenance, Navy (O&M, N)), in accordance with NAVSO P-1000.

C-1.3.8 Security Plan: The contractor must provide a detailed plan and identify their responsibilities for maintaining the security of incidental facilities, including contingency procedures for power outages, inoperative automated equipment, data processing, and computer systems, as well as any contractor furnished equipment, tools, and materials. The plan must outline policy, guidance, and procedures regarding facility access controls, visitor logs, lock and key controls, random patrols of fuel management facilities and pipelines, Automated Data Processing (ADP) security, and other minimal force protection measures. The contractor is not authorized or responsible to provide installation escort services in accordance with OPNAVINST 5530.14, Navy Physical Security.

C-1.3.9 Inventory Control and Accountability Plan: A detailed plan must be written to ensure contractor compliance with the inventory, accounting, and reporting requirements of DoDM 4140.25, DoD Management of Bulk Petroleum Products, Natural Gas and Coal, and DLA Energy and Navy instructions, DLA Energy P-7 Policy, regulations, and other policies as applicable

C-1.3.10 Safety Plan: The contractor must provide a detailed plan outlining procedure necessary to maintain safety in accordance with applicable DoD, Federal, Navy, State, and Local References and Laws identified in Appendix C. This plan must include industrial hygiene, confined space entry, disaster preparedness, fire prevention and protection, hazardous waste operations, emergency response, safety and health standards, Safety Data Sheets, accident/incident reporting, and safety procedures during general fuel handling operations. The plan must identify, the responsible individual that will monitor the safety program and maintain records.

C-1.3.11 Training Plan: The contractor must provide a comprehensive plan outlining training and objectives. The plan must list course and subject titles of materials to be used, a brief description of the subject, identify training sources, establish the frequency of training, and detail the method of monitoring plan compliance, and record keeping. Training required by applicable DoD, Federal, Navy, State, and Local References and Laws identified in Appendix C.

C-1.3.12 Fuel Safety Plan: The contractor must provide a detailed plan outlining the fuel systems applicable to the contracted locations, product handling characteristic and the policy, procedures, and actions necessary to maintain a safe working environment. The plan, a compendium of references, laws, and regulations applicable to the products stored and handled, Safety Data Sheets, and guidelines regarding the safe handling of such products must be maintained and updated over the course of the contract.

C-1.4 Contract Turnover: During the ten working days prior to the start of contract performance, the outgoing contractor must permit the incoming contractor access to the applicable fuel facilities to observe their operation. During this ten-day period, the incoming contractor must receive assistance from the outgoing contractor, DLA Energy representatives, and the COR to accomplish a joint facilities turnover inspection, to include product testing, inventory of product, and audit of property. The outgoing contractor must also provide the incoming contractor with all relevant information concerning the facility and its operation, including maintenance records, and engineering documentation. The incoming contractor must protect and not disclose any proprietary information of the outgoing contractor discovered during the turnover period. The outgoing contractor must have all contractor furnished equipment (CFE) removed from the installation 30 calendar days after the termination or expiration of their contract date.

C-1.5 Quality Monitoring and Evaluation: DLA Energy will utilize a Quality Assurance Surveillance Plan (QASP) to monitor and evaluate the contractor's performance throughout the contract performance period. DLA Energy may also perform customer satisfaction surveys, which may be used as part of the assessment of contractor's performance. The CMMS read only roles must be used by the COR's and QAE's for monitoring and assessing contract performance, maintenance accomplish ratio's, analytical maintenance data calls, and used in conjunction with the QASP. The COR can manage the frequency of surveys to address contract compliance concerns, based on trend analysis.

C-1.6 Staffing: The contractor must provide sufficient staffing to accomplish identified functions and tasks to include simultaneous operations that are identified in Appendix A. Staffing full-time employee(s) must consist of a minimum ratio of one, for each listed function/primary position, as identified in C-1.7 through C-1.7.6, C-1.8 through C-1.8.7, and Appendix A. These primary positions must be staffed with as many full-time employees, as may be required, based on the manning/working hours of operations, the workload requirements, simultaneous operational requirements, and as identified in Appendix A and Table 1. There is no provision for augmentation or overtime. One full-time employee must be equivalent to 2080 annual hours, and one part-time employee(s) must be equal to 1040 annual hours. The contractor's staffing must be flexible and fully capable of meeting identified demands of hot and cold aircraft fuel services (to include transient aircraft), ground fuel services, bulk fuel storage, fuel offloading (extended offloading), internal transfer operations, quality surveillance, general management, and administrative functions based on current, projected, and historical workload demands as identified in Appendix A. In addition, contractor's staffing must be able to support multiple aircraft servicing via mobile refuelers to provide hot and cold refueling services.

C-1.6.1 Workload: The contractor must plan to provide simultaneous operations as defined within the periods established in Appendix A. Based on historic information, control center notifications, and coupled with current flight schedules, aircraft/squadron deployments, exercise, and training schedules provided in accordance with NAVAIR 00-80T-124 by Air Operations (Air Plan), the contractor must be fully responsible for adjusting (increasing and decreasing) levels of services, along with providing personnel, and equipment to meet workload demands for day- to-day operations . The contractor is expected to exercise good judgement in the operation of their refueling equipment and personnel. In the event of a conflict between refueling/defueling operations, the Air Department, Duty Officer shall be contacted to provide a final decision between aircraft mission requirements for the Airfield. In the event there is a conflict between NAVAIR 00-80T-124 and local instructions, NAVAIR 00-80T-124 supersedes the local instruction. Unforeseen workloads such as the testing of fuels after normal laboratory duty hours or contingency support of any type are not quantified but are required to be supported.

C-1.6.1.1 Scheduled and Recurring Event: Once the installation is notified of an event, the installation will provide the contractor documented information outlining anticipated dates, number(s) and types of aircraft, number(s) of anticipated sorties, and historical information regarding aviation and ground fuel requirements in order to support known, scheduled, and recurring event, annual large force exercises, tactical training, and competition events, or air shows. The contractor must be given access to event planning meetings to meet missions. In concert, the contractor must fully document all services provided for all specified events. When the contractor is informed or becomes aware of scheduled or unscheduled events which are out-of-scope of this current PWS, the contractor must immediately inform the KO, to avoid unauthorized commitments. Any decisions made between the contractor and any other parties, leading to the provision of services by the contractor, without the official authorization of the KO, are made at the contractor's expense.

Note: Monthly Surge-Flight Operations are scheduled to include four (4) weekend flight operations per month, occurring on either Saturday(s) or Sunday(s) (but not both) to make-up for lost flying hours.

C-1.6.2 Knowledge and Skills: The contractor must ensure that personnel assigned to identified tasks have the requisite knowledge and skills to meet the performance standards for those tasks and comply with applicable DoD, Federal, Navy, State, and Local References and Laws identified in Appendix C. All employees must be able to read and understand English (be literate) to the extent they can understand and follow oral instructions/directions, read, and understand instructions, directives, regulations, operating procedures, detailed written orders, and training materials, and be capable of writing in English to compose required detailed reports. All employees must be capable of performing basic numeric operations (addition, subtraction, multiplication, and division) and the use of numbers as they relate to ledgers, logs, forms, meters, gauges, and measuring devices such as tapes, thermometers, hydrometers, and other instruments as may be used during the receipt, handling, inventory, and issue of petroleum products.

C-1.6.3 Employment Standards: All employees or persons who may be hired to represent, perform on behalf of, or work under the management of the contractor must comply with all DoD, Federal, Navy, State, and Local References and Laws identified in Appendix C, regarding employment at, and entry to Naval Facilities. The contractor must ensure that they meet the requirements of employment and conform to the rules regarding, but not necessarily limited to, security, clearance, identification policy, vehicle registration and operation of a POV on station, medical assistance, the use of the exchange, and military facilities, and other local rules, guidance, or prohibitions that may apply to their entrance to and activity or employment on station.

C-1.7 Key Personnel: The Corporate Executive Officer, Terminal Manager and Assistant Terminal Manager are mandatory key personnel, and must have the required education, training, background/experience, and skills necessary to make fiscal and management decisions, direct personnel, and collaborate solutions with individuals, at different levels of corporate management, civil service representatives, and/or military personnel for this contract. The contractor staffing roster information must be incorporated into the monthly Common Access Card (CAC) Log.

C-1.7.1 Corporate Executive Officer(CEO): To assure continuity between the contracted location, activity, and corporate office, the contractor must employ an executive who, for the duration of the contract, can make fiscal, management, and administrative decisions concerning this contract. CEO must have a complete understanding of the terms and conditions of this contract and should be knowledgeable of the management, operation, and maintenance of fixed and mobile fuel systems and bulk fuel storage facilities equivalent to the extent outline herein.

C-1.7.2 Terminal Manager (TM): The TM must have experience relevant to the facilities, contractor provided equipment, in bulk fuel storage and distribution systems, the maintenance and upkeep of barge pier facility, mobile (aviation and ground) fuel servicing equipment, direct aviation fuel servicing equipment, quality surveillance of aviation and ground fuel products, aviation and ground fuel inventory, accounting, and administration. Practical experience in the basic design and layout of petroleum facilities, component makeup and flow characteristics of storage piping systems, and the ability to read and understand basic drawings, blueprints, and system specifications. DLA Energy Policy P-32 provides training requirements and procedures for the TM. The TM must comply with DLA Energy Policy P-32 and complete all training requirements established therein. This training is funded by DLA Energy. TM must have extensive knowledge of Automated Fuel Handling Equipment (AFHE), **(if system is installed)**, and be capable to collaborate scheduled movements of fuel. Temporary replacements for this position are required to have the same qualifications listed above. Other than those administrative duties commonly associated with and carried out by an individual in a management position, the TM must not have collateral duties. Likewise, a non-TM, hired primary position cannot perform a TM primary position, as a collateral duty.

C-1.7.2.1 Supervisory Experience: The TM must have three years of experience in petroleum storage and distribution operations, airfield petroleum services, and fuel systems maintenance within three years immediately prior to the contract start date or the individual's hiring date. That experience must have been specialized supervisory training with emphasis in equipment inspection, operation, maintenance, inventory management, and environmental compliance. The contractor must not be assigned any NOSC duties, at any Naval Installation. In addition, the TM's will complete required underground and aboveground storage tank Operator Training and Spill Response Training.

C-1.7.3 Assistant Terminal Manager (ATM): The ATM must have a minimum of two years of commercial or military experience in the fuel petroleum and terminal operations, bulk storage and distribution services and operations, petroleum equipment/systems maintenance, laboratory and/or environmental compliance prior to the performance start date or individual's hiring date. The individual must have a minimal two years of specialized experience in the following positions: Accountant, Dispatcher/Computer Operator (DCO), Lead fuel distribution system operator (FDSO),. After the individual hiring date, they must attend Joint Responsible Officer and Fuels Terminal Manager Course at the first available course date. This management position may have collateral duties such as: Fuel Distribution System Operator, Driver/System Operator, Laboratory Technician to supplement the day-to-day workforce. However, the ATM may not act as the Dispatcher/Computer Operator, Fuel Distribution Systems Mechanic (FDSM), and Accountant. The contractor ATM who is elevated to the Terminal Manager position, short or long term, must not have any collateral duties.

C-1.7.3.1 Supervisory Experience: The ATM must have a minimum supervisory experience equivalent to that outlined in Section C-1.7.2.1, with an emphasis in equipment inspection, operation, maintenance, inventory management, and environmental compliance.

C-1.7.3.2 Availability: Either the TM or ATM must be locally available for oversight 24 hours, 7 days a week.

C-1.7.4 Replacement of Key Personnel: In the event it becomes necessary to replace any key personnel, the contractor must immediately notify both KO and COR, as to the final workday or termination date of the outgoing person. A plan outlining specific dates/time frames for the replacement of the key person must be provided to the KO and COR. Key personnel are salary base positions and proposed replacement must have qualifications that are equal to or greater than the qualifications of the person being replaced.

C-1.7.5 Resumes: Resumes must be submitted to DLA Energy, for key personnel, immediately, and prior to Performance Period (start of contract). The resumes will be reviewed and assessed based on job description vacancy and required standards. A replacement candidate's resume must be submitted for review and assessment prior to assuming duties. Key personnel are salary base positions and proposed replacement must have resumes which meet qualifications that are equal to or greater than the qualifications of the person being replaced.

C-1.8 Service Personnel: The United States Department of Labor is responsible for the administration of federal laws governing occupational safety and health, wage and hour standards, unemployment benefits, reemployment services, and occasionally, economic statistics. The contractor service personnel, primary job description is listed in the PWS, must remain mandatory, and required to be identified in contractor proposals. In the event there is no wage determination listing for a class of service, for any service personnel, the contractor must submit a request to conform to a specific salary category, to the DLA Energy, KO with the contractor initial offer.

C-1.8.1 Dispatcher/Computer Operator (DCO): The Fuels Dispatcher must possess sufficient skills to effectively operate the dispatch system and Business System Management-Enterprise (BSM-E)/Enterprise Business System (EBS). He/she must also be familiar with the use of Microsoft standard office products such as Word and Excel to ensure that daily fuel operations are conducted in an effective and efficient manner. In addition, dispatchers must be knowledgeable of radio communications, instructions/regulations pertaining to fueling and defueling of military and civilian aircraft, and military forms used to document aircraft fuel servicing. He/she must demonstrate familiarity with the layout of the base and outlying fields as well as the airfield and aircraft parking areas and restrictions applicable to servicing aircraft within those areas. Individuals acting as dispatchers must be capable of communicating in English, both orally and in writing. Except for those administrative and accounting duties outlined within this PWS, dispatchers must not have collateral duties. The Dispatcher must be familiar with the Facilities Response Plan (FRP).

C-1.8.2 Accounting Clerk's III(AC-III): The AC's-III must be fully knowledgeable of manual and automated fuel management, inventory, and accounting systems. Possess sufficient skills to effectively operate Business Systems Modernization-Enterprise(BSM-E)/Enterprise Business System (EBS), Fuel Manager Defense (FMD), Automated Fuel Service Station (AFSS) module, Energy Enterprise Business Portal (EEBP), Wide Area Workflow (WAWF), Power Track, Electronic Point of Sale (EPoS), and any other applicable to the processing of fuel management, inventory, and accounting data. The AC-III must be efficient in computer skills to use client/server applications in a Microsoft Windows environment, including Microsoft Office products such as Word, Excel, and PowerPoint; other commercial off the shelf applications, utilities; and custom software in such a manner that daily fuel transactions are recorded accurately. Skills must include the use of the real time information systems, the manipulation of data within the Fuel Manager Data system and the related fuel management modules and status systems. Those skills must include the ability to logon; shutdown; initiate modems; manipulate files and resolve technical issues and problems required to maintain a fully functional file, records, and reporting system; send and receive email; and to use web browsers to send and receive information in accordance with DLA Business System Modernization Interim Policy and Procedural Guidance for the receipt, handling, issue, inventory, and accounting of petroleum products. Additionally, the TM must ensure that a fully trained alternate/back-up accountant will process transactions when the primary accountant is not available for duty to ensure compliance with DoDM 4140.25, Segregation of Duties. Temporary replacements for this position are required to have the same qualifications listed above. Other than those administrative duties commonly associated with and carried out by an individual in an AC's-III primary position, the AC's-III must not have collateral duties. Likewise, a non- AC's-III, hired primary position cannot perform an AC's- III primary position, as a collateral duty.

C-1.8.3 Truck Driver, Tractor-Trailer's (TD-TT's): The TD-TT's must be qualified to perform fuel servicing operations (refuel/defuel) by mobile fuel servicing equipment/trucks, truck operated mobile pantograph, hose sets or carts, and fixed direct fuel servicing systems (hydrants). A TD-TT's must perform deadman operations and may be trained to perform other duties, such as hot refueling fire watch, nozzle operator, or refueling director tasks, within a pit operation. Drivers must be trained in the appropriate use of radio procedures. TD-TT's must pass a contractor administered base and flightline familiarization test; and additional mandatory installation flightline courses, which can include but not limited as the: Airfield Operators Course, practical equipment/facility competency tests, and must be certified, by the contractor, as qualified, and the individual's training record updated prior to the unsupervised operation of any fuel, and defueling servicing equipment. The contractor must recertify personnel annually or as required. TD- TT's must be familiar with safety regulations applicable to aviation and ground fuel servicing operations on and around the airfield and supported activities. Unless specifically directed by the KO, the contractor is not responsible for the staffing of the fire watch, nozzle operator, or refueling director positions. The squadron or organizational unit receiving fuel services must remain responsible for providing required staffing, other than deadman operator. Temporary replacements for this position are required to have the same qualifications listed above.

C-1.8.4 Fuel Distribution System Operator's (FDSO's): The FDSO's must have practical experience in operation of bulk fuel distribution systems. The FDSO's must be able to perform receipt, issue, storage, spill cleanup, preventative maintenance scheduling, hazardous waste, and petroleum quality surveillance operations. Temporary replacements for this position are required to have the same qualifications listed above.

C-1.8.5 Laboratory Technician's (LT's): The LTs must have a minimum of one-year experience in the use of common fuel sampling equipment, aviation, and ground fuel sampling procedures, and conducting laboratory tests of petroleum products commensurate with the level of analysis required to be performed at the assigned locations. Personnel performing these duties must be properly trained in accordance with applicable regulations and assigned to perform the full spectrum of quality surveillance sampling and testing. These duties may be required to include weekend and holiday fuel support. Temporary replacements for this position are required to have the same qualifications listed above. Other than those administrative duties commonly associated with and carried out by an individual in a LT primary position, the LT must not have collateral duties. Likewise, a non-LT, hired primary position cannot perform a LT primary position, as a collateral duty.

C-1.8.6 Replacement of Service Personnel: In the event it becomes necessary to replace any service personnel, the contractor must immediately notify both the KO, and COR, as to the final workday or termination date of the outgoing person. A plan outlining specific dates/time frames for the replacement of the service person must be provided to the KO and COR. Service personnel are wage determination positions and proposed replacement must have qualifications that are equal to or greater than the qualifications of the person being replaced.

C-1.8.7 License, Special License, Skills, Training, and other Certifications: All drivers and operators must be licensed in accordance with the vehicle operating laws, regulations, and code for the state in which they will operate and must be/remain in compliance with all such requirements for the duration of their employment under this contract. The contractor must ensure that drivers required to operate vehicles and equipment on public roads are licensed for the class of vehicle to be operated on such public roads. The State of Texas mandates that all personnel who will operate fuel-servicing vehicles on or off station must hold a current and valid Commercial Drivers License (CDL) with Hazardous Endorsement. Specific fuel operation tasks may require other special skills, training, or certifications. Personnel will be required to maintain other skills, training, or certification for the

operation of heavy equipment on and off base. The contractor must evaluate task requirements and provide enough qualified personnel to complete tasks in accordance with all applicable DoD, Federal, Navy, State and Local References and Laws identified in Appendix C and as set forth by the Department of Transportation

C-1.9 Correspondence and Visits: The contractor must notify the COR of all visits or notice of intent to visit contract management, its employees, or the contracted facilities by any federal, state, local representative, base (military) office/agency, union representative, or contract corporate officers. Except for that considered to be company or proprietary correspondences. The contractor must establish and maintain a visitor's log showing name of all visitors, date of visit, time of visit, organization, and reason for the visit.

C-1.10 Information and Records Management: Documents held or generated by the contractor must be open and readily available for inspection, review, and audit for the duration of the contract and any subsequent and contiguous contract periods. The contractor must submit reports to the appropriate agency in compliance with DoD, Federal, and State requirements. In addition, special reports may be requested for audits, inspections, reviews, and research. Should proprietary company, or non-DoD maintenance, and accounting systems be installed by the contractor, the contractor must provide continuous secure web access or access to a secure workstation. Upon termination of the contract, all records except personnel files, training records, contractor-furnished equipment records, and proprietary company management records must be turned over to DLA Energy.

C-2.0 Performance Requirements

C-2.1 Fuel Operations: The contractor must receive, maintain, store, sample, test, internally transfer, and issue petroleum products throughout NAS Kingsville and any outlying fields, by utilizing infrastructure property, incidental equipment, and contractor-furnished equipment. The contractor must be responsible for all fuel-servicing operations and safeguarding facilities, equipment, and fuel products under its control during normal and adverse conditions.

C-2.1.1. Dispatch Control Center: Requests for all fuel services must be taken by and processed by the Dispatcher/Computer Operator, at the fuel dispatch center. Based on the specific request, equipment and personnel must be dispatched and controlled as needed to satisfy the request received. All requests for fuel services must be recorded, monitored, and historically kept, by using Business Systems Modernization-Enterprise (BSM-E), Enterprise Business System (EBS), Fuel Manager Defense (FMD), Automated Fuel Service Station (AFSS) module, Energy Enterprise Business Portal (EEBP), Wide Area Work Flow (WAWF), Electronic Point of Sale (EPoS) and NAVAIR 00-80T-109 template or similar form, appropriate software, and business systems. The dispatchers must ensure all documents are legible and accurate, must generate required reports, and ready all documents and pass down logs for submission to the fuel accounting office by 0800 Monday through Friday. Weekend/holiday documents must be submitted the next duty day following the weekend or holiday. The contractor must advise the COR of any circumstance that may result in the inability to perform the required services in a timely manner. The control center must be staffed by contractor personnel during hours of operation as required in Appendix A.

C-2.1.2 Fuel Servicing: The contractor must issue, defuel, and provide off-station fuel services to aircraft and support equipment by mobile fuel servicing vehicles and portable/mobile pantograph systems. Aircraft fuel services must comply with Naval Air (NAVAIR) 00-80T-109, Aircraft Refueling Naval Air Training and Operating Procedures Standardization (NATOPS) Manual, NAVAIR 00-80T-124, Airfield Operations Manual, and all other applicable military, federal, and

commercial policies regarding the performance of aircraft fuel servicing operations. Since off-station fuel services will require movement of mobile fuel servicing vehicles and transportation of JAA between installations and possibly onto public roads, such vehicles must comply with all applicable federal, state, and local rules and regulations regarding the operation of vehicles on highways and public roadways. It is the responsibility of the contractor to identify situations where the contractor believes applicable guidance conflicts. If a situation occurs, where a conflict between two or more set of references exists, the overarching Directive or Law must take order of precedence. The contractor must immediately inform the KO, to avoid unauthorized commitments, and eliminate out-of-scope contractual concerns.

C-2.1.3 Performance of Services: The contractor must provide refueling and defueling services as identified in Appendix A. The request for service must result in the dispatch and arrival of a truck/operator to the location identified by the requesting activity within the established priority in the Airfield Operations Manual. If an individual request for service encompasses multiple aircraft and simultaneous refueling operations of such aircraft, then truck/operator must provide simultaneous refueling. If simultaneous refueling is not requested, then the truck/operator should respond to subsequent aircraft in the priority provided by the requesting activities. Truck/operator must not service aircraft to which they are not directed without approval by the dispatch center. The contractor's performance is measured from time of request received at the dispatch center to time of arrival to requesting activity location and the same for individual request encompassing multiple aircraft. If an activity submits a complaint, circumstances must be annotated by the dispatch center, in the remarks section of the contractor dispatch control log. The COR must evaluate each complaint and identify all contributing facts which may or may not have contributed to mission failure, on a case-by-case basis. If any personnel action or lack of action caused unacceptable performance, the delay is not valid, and the contractor is responsible to notify the COR. If the complaint is deemed valid and resulted in a mission failure, the COR must notify the KO.

C-2.1.3.1 Mobile Fuel Servicing Equipment: The contractor must provide the fuel servicing equipment in sufficient numbers to undertake the workload. The contractor must fully maintain all furnished trucks, tractors, equipment fuel tanks, refueling/defueling systems, and components ready for dispatch condition. Equipment inspections and product sampling/testing, periodic Type "C" product analysis, must be completed and documented prior to the initial dispatch of the equipment for the duty day.

C-2.1.3.2 Portable Pantograph (Hot) Refueling: The Contractor must provide sufficient staffing to simultaneously operate two mobile hot refueling pantographs at NAS Kingsville within the operating hours that are identified in Appendix A and must be requested 24 hours in advance. As Required (AR) services for Saturday or Sundays must be requested 24 hours in advance to the contractor. The contractor at NALF Orange Grove, must provide the sufficient staffing for hot refueling services as identified in Appendix A. In all cases, the Contractor assigned truck deadman control operator must remain in control of all hot and cold refueling operations. Mobile hot refueling is defined as the use of mobile refueling vehicles in conjunction with the use of a mobile pantograph system, or additional ancillary components (hoses, nozzles, etc...) to refuel aircraft while engines are running.

C-2.1.3.3 After Hours Notification: The contractor must establish an after-hours notification mechanism: a means of being contacted in the event emergent services or workforce augmentation is required without prior coordination/notification. Aircraft fueling services and emergency requests, impacting missions, required outside of the normal hours of operation, without prior coordination/notification, must be met within two (2) hours, as measured from the time the contractor is notified until the operator is in position to perform the service required. The contractor must meet these requirements for after-hours service. All after hours support must be contractor's responsibility under the Monthly Usage Charge CLIN without increased cost.

C-2.1.3.4 Off Station Operations: If required, aviation and ground fuel deliveries over public roads to

off station locations must be accomplished using equipment that is configured and licensed/permitted for use on public roads. All Federal, State inspections, licensing or permits, and insurance requirements for the equipment used, must be the responsibility of the contractor. Furthermore, the contractor must ensure that cargo quantities and vehicle weights are adjusted to meet all Federal, State, and highway laws, regulations, and codes for traveling over public roads.

C-2.1.3.5 On Station Operations: Any Naval Facility/Area of Operation (AoO) or locations that is identified in Appendix A, that requires staffing, besides emergency functions.

C-2.1.3.6 Jet Fuel Services Data: The Squadrons and Aircraft Assigned Table found in Appendix A, is a breakdown of squadrons/aircraft currently assigned to the airfield and provides a local picture of the services required on a day-to-day basis. The contractor must keep this table, as well as the home station aircraft database in FMD, current. Transient aircraft ranging from trainer, fighter series, to the larger military transport requiring multiple truck services are possible.

C-2.2. Bulk Storage Operations: Bulk Storage operations are defined as the receipt, storage, handling, inter-terminal product movement, and issue of capitalized bulk fuel products at Navy-owned facilities via all modes of conveyance (tank truck, internal pipeline transfers, and bulk loading). The contractor must be responsible and capable of performing bulk fuel operations, system inspections, operator maintenance, quality surveillance, inventory accountability, and safeguarding fuel supplies under its control during normal and adverse conditions, 24 hours a day, seven days a week, year-round. Bulk operations require a dedicated Operational Dispatcher, capable of receiving fueling request from customers; scheduling shipments, deliveries, and receipts; making scheduling changes; and creating daily schedules of fuel operations. During all product movement evolutions, there must be a person in charge. The contractor must oversee and coordinate all ongoing, scheduled, or unplanned operations. All assignments and control of qualified personnel will be handled by the contractor to ensure compliance with approved standards and operating procedures.

C-2.2.1 Bulk Output: Products are transferred by different modes of conveyance (tanker trucks, internal pipeline transfers, and bulk loading). The contractor will operate a network of piping systems, and fuel fill stand. Bulk storage systems must be kept in the ready-to-pump (issue) mode to supply product on demand.

C-2.2.2 Bulk Tanks: The Bulk Storage system consists of three (3) 840,000-gallon jet fuel tanks at NAS Kingville and three (3) 25,000-gallon cut and cover jet fuel tanks at NALF Orange Grove with all related components, receipt headers, and fill stand area. See Appendix A, Incidental Facilities, for a detailed breakdown of these facilities. The contractor must utilize contractor-furnished equipment to deliver fuel to airfield mission customers, home station, and transient aircraft.

C-2.2.3 Receipts of Fuel: The contractor must be responsible for receipt of all bulk fuel products, for the fuel facility. All receipt operations must incorporate the procedures outlined in NATOPS 00-80T-109 paragraph 12.13.3. Product is received by commercial tank truck (outside vendor) as per contractor requested of deliveries.

C-2.3 Internal Transfers: Internal transfers may be necessary to consolidate product inventories, accommodate tank or pipeline repairs. All transfers must be monitored at both the issue and receipt point, for the duration of the transfer operation. The contractor must be responsible for all coordinated gauging, measurement, reconciliation, and documentation actions relevant to all transfer operations.

C-2.3.1 Transfers to Refuelers: The truck fill stand is a driver-operated, supply on demand or self-service system used to fill refuelers. Documentation relevant to refueler top offs, the disposition of those documents must be compiled, and controlled in a manner as to ensure compliance with DoD Policy

C-2.3.2 Truck Stands: There are three (3) fill stands which are utilized for filling F-24 trucks and four (4) offloading stands throughout NAS Kingsville and outlying fields. There are (3) jet fuel offload stands at facility 5722 and two (2) jet fuel fill stands at facility 4777 at NAS Kingsville, TX. There is one (1) jet offload stand and one (1) jet fuel fill stands at facility 14 at NALF Orange Grove.

C-2.4 Ground Fuels: The contractor must be responsible for performing all ground fuel delivery operations and safeguarding fuel supplies under its control during normal and adverse conditions.

C-2.4.1 Equipment: The contractor must furnish and maintain ground fuel servicing equipment necessary to undertake identified workloads and include specifications for the proposed equipment in their proposal. The contractor must fully maintain all equipment and components in a safe, serviceable, and ready for dispatch condition. Equipment inspections must be completed and documented on the vehicle inspection form of each equipment prior to the initial use of the equipment for the duty day. All Federal, state, and local inspections, permits, licensing and insurance requirements for the truck(s) used on public roads, are the responsibility of the contractor and must be included under the MUCG, at no additional cost to DLA Energy.

C-2.4.2 Delivery: Fuel products must be delivered to authorized activities listed in Appendix A. Unscheduled requests must be accomplished within the time limits mutually agreed upon by the requesting activity and dispatch center.

C-2.5 Recyclable and Recoverable Fuels: The contractor must be responsible for recycling and recovery of aviation and ground fuels within the identified fuel facilities in Appendix A. This includes, but not limited to, quality surveillance samples, facility maintenance, and tank bottoms. The contractor must be responsible for coordinating with the COR for disposition of all recoverable and recyclable fuel stocks in accordance with DLA Policies and Instructions. All products classified as non-reclaimable are collected and disposed of by the Installation.

C-2.6 Product Inventory and Accountability: The contractor must be responsible for the inventory management and accounting of petroleum products held within the facilities, equipment, tanks, and vehicles under contractor control. The contractor must provide accurate inventories of all DLA Energy Capitalized Stocks in accordance with DoDM 4140.25, applicable DLA Energy Policies and Instructions, and all clauses/provisions of this contract. The contractor must be responsible for updating the automated accounting system and providing information to DLA Energy and COR on current inventory levels in accordance with DLA Energy P-3, Document/Data Control and Retention. The COR must be informed immediately of any discrepancy in inventory or fuel shortages, based on customer requests. All product receipts, issues, shipments, or transfers must be properly documented and auditable.

C-2.6.1 Electronic Point of Sale, QR (Quick Response) Code Management: The contractor must utilize Electronic Point of Sale (EPOS) devices (pedestal and/or mobile) provided by DLA Energy as Incidental Property/Equipment to capture and report sales from the GOCO. The contractor must contact the DLA Policy and System Sustainment Branch at EPoSFunctionalSupport@dla.mil to coordinate the installation on the GOCO.

C-2.7 Product Quality Surveillance: The contractor must be responsible for maintaining the quality of the Capitalized Stocks in accordance with MIL-STD-3004-1, Department of Defense Standard Practice, and Quality Assurance/Surveillance for Fuels, Lubricants and Related Products; NAVAIR 00-80T-109, Aircraft Refueling NATOPS Manual; and the contractor developed Product Quality Surveillance Plan.

C-2.7.1 Quality Determination: No petroleum products, include Lubricating Oils, must be received, or issued without first determining and confirming conformance with product quality requirements. Products must be issued on a first-in, first-out basis unless otherwise specified or directed by DLA Energy. Non-conforming product must be reported to the COR immediately. Anytime product is received into a tank, the

tank's contents must be suspended from issue pending quality conformance sampling and testing. The contractor must ensure that certificates of quality conformance (test reports) are maintained on file for all on-hand fuel stocks, to include Regional Test Results.

C-2.7.2 Laboratory Operation: The contractor must operate and maintain Type "C", incidental petroleum laboratory test equipment. Calibration of laboratory test equipment, replacement of standards, and material necessary for daily operations must be provided by the contractor, as consumables. Only qualified and trained personnel must perform tests and related laboratory operations. The contractor must provide and maintain a bench stock of all consumable and expendable material necessary for the sustainment of laboratory operations. Parts and materials required to repair, renovate, or restore to operational conditions any laboratory equipment, remains the responsibility of the Navy-Owned, incidental equipment custodian. The contractor must perform operator level maintenance, small replacement of parts, by utilizing hand tools. All parts and materials must be purchased by Navy (Operation and Maintenance, Navy (O&M, N)), in accordance with NAVSO P-1000.

C-2.7.3 Sampling: The contractor must be capable of sampling in accordance with MIL-STD-3004-1, and NAVAIR 00-80T-109 and provide "C" level testing 24 hours a day and 365 days a year. Type C testing must be done on site. The contractor must transport capitalized petroleum and lubrication oil samples owned by DLA Energy that require B Level Testing or additional testing in accordance with any state, federal laws, or regulations that apply to the location. Prior coordination of 48-hours with the DLA Energy, Quality Assurance Representative (QAR) is required, before the B Level sample(s) are taken, to determine if a commercial or military laboratory is to be utilized. Contractor must ensure sample tags are affixed to the sample container. The contractor must immediately report any delays to the COR for resolution. The contractor must take all required samples.

C-2.7.4 Housekeeping: Fuel laboratory facilities and equipment must be maintained to the degree of cleanliness and order commensurate with a "quality surveillance" program. Fuel samples and chemicals must be properly labeled and stored in the appropriate hazardous storage lockers, glassware washed, dried, and stored, and laboratory hardware stored to present an orderly appearance

C-2.8 Maintenance: The fuel contractor must be responsible for the normal, continuous operations, maintenance, and real time reporting of discrepancies applicable to all petroleum systems, facilities, and equipment. Petroleum system means an underground or aboveground fuel storage tank, associated fuel piping, pump house, loading and unloading station, hydrant fuel system and associated hydrant outlets and pantographs, oil water separator, ancillary equipment and appurtenances, electrical power and controls, lighting, emergency generators, refueler truck parking, fire protection system, and containment system, if any. The contractor must manage, coordinate, oversee, and report as required, to ensure all required inspections, services, maintenance and repairs of all facilities, incidental equipment and real property associated with this contract are performed in compliance with all Navy Operations and Maintenance Manual for Maintenance of Petroleum Systems, Department of Defense (DoD), DoDM 4140.25-Chapter 8, MIL-STD-161 Identification Methods for Bulk Petroleum Products Systems Including Hydrocarbon Missile Fuels, State, Local, Federal, American Petroleum Institute (API), and Unified Forces Criteria (UFC) requirements throughout the life of the contract. This includes monitoring all maintenance being performed by DoD Agencies or other agency contractors, to track maintenance progress, in a timely manner, scheduled based on periodic maintenance requirements, coordinated with COR and relevant offices, from cradle to grave, and recorded in the maintenance database. The contractor must report immediately any maintenance deficiencies, scheduled coordination, parts/material orders, delays, and conflicts to the COR and KO for assistance and resolution. Any equipment categorized as Navy-Owned/Furnished, known as "personal" equipment, is considered incidental equipment to the performance of the contractor and PWS

workloads, must remain the responsibility of the Navy, to support the locations identified under this contract. The contractor must perform operator level maintenance, including small replacement of parts, by utilizing hand tools. All parts and materials must be purchased by the Navy (Operation and Maintenance, Navy (O&M, N)), in accordance with NAVSO P-1000.

C-2.8.1. Operator Maintenance Requirements: The contractor must ensure all operator level recurring maintenance checks and services for fuel facilities and related fuel handling equipment are scheduled and accomplished, in accordance with PWS C-2.8. These operator level recurring maintenance checks and services are recommended by the manufacturer or in accordance with commercially accepted practices, as well as the effort required to keep a facility, a piece of equipment or system functioning. The refueling contractor must provide all staffing, materials and equipment not otherwise specified by any source to accomplish the required recurring maintenance tasks. The refueling contractor must ensure that all costs associated for operator maintenance must be included in the Monthly Usage Charge CLIN, regardless of frequency or periodic time required by UFC 3-460-03.

C-2.8.2 System Maintenance (SM): SM is performed by base facility maintenance technicians, base operating service contracts, or recurring maintenance contractors. The DLA Energy, Sustainment, Restoration, and Modernization (SRM), Recurring Maintenance and Minor Repair (RM/MR) Program will provide a contractor to perform system maintenance tasks in accordance with UFC 3-460-03 and DoDM 4140.25-Chapter 8. Periodic time of inspections, testing of system components, and maintenance of associated fuel fixed facilities, should generally occur on a quarterly basis. However, the refueling contractor under this PWS, must track and document corrective and preventive system maintenance tasks, from cradle to grave, relevant towards system maintenance records for fuel components, in the CMMS. If any recurring maintenance tasks are not performed as required or sufficiently met by the RM/MR contractor, the refueling contractor must document the discrepancies in the CMMS, report the problem to the COR, and DLA Energy KO.

C-2.8.2.1 System Maintenance Requirements: Recurring maintenance tasks are defined as recurring, periodic and scheduled maintenance requirements that are on a fixed schedule as dictated in UFC 3-460-03; Manufacturer Recommendations; Federal, State, Code of Regulation, and American Petroleum Institute (API) Requirements. The RM/MR contractor is responsible for the inspection, maintenance, and services of DLA Energy Capitalized petroleum facilities. The maintenance and services of the facilities must be completed to ensure the systems meets all Department of Defense, State, Local, Federal and Unified Forces Criteria (UFC) requirements; throughout the period of performance and all maintenance actions will be recorded as described in paragraph C-2.8.4. If any recurring maintenance requirements are not being performed as required or sufficiently met by the RM/MR contractor, the refueling contractor, must document the discrepancies in the CMMS, report the problem to the COR, and DLA Energy KO.

C-2.8.3 Repairs: The RM/MR contractor must take immediate action to assess corrective, minor, and emergency repair situations. This must be performed on all fuel fixed facilities, identified in the Navy, Real Property Record, and Coded (D-33) Facilities, for maintenance responsibilities (only). All deficiencies identified by the refueling contractor, that require repair work, out-of-scope of refueling contractor workloads, must be documented in the CMMS, and submitted to the COR, to be performed by the RM/MR contractor. The refueling contractor must monitor, track, and document all repairs performed by the RM/MR contractor and collect all documents relevant to the repairs performed, related to the completion of these maintenance actions, in the CMMS. If repairs are not performed in a timely manner, the contractor must report, and document all delays in the CMMS. The refueling contractor must notify the COR and DLA Energy, KO for assistance and immediate resolution.

C-2.8.3.1 Naval Facilities Engineering Command (NAVFAC), Maintenance Support: NAVFAC, Public

Works Department (PWD) provides support to military, civil service, and tenant commands for the maintenance of assigned fuel facilities and infrastructures. The PWD is supported in this effort by Building Manager (BM) who are assigned by the military, civil service, and tenant commands, to act as the local liaison for the maintenance and repair of those assigned fuel facilities. The Building Manager (BM) or Building Manager Alternate (BMA) is the on-site assigned representative to fuel facilities in this contract. BM's and BMAs are responsible for the upkeep and maintenance, by coordinating with local respective NAVFAC Facilities Operation Specialists (FOS), on projects, health, and safety inspections, and identify, document, and report deficiencies in the material condition of facilities to include fire and safety discrepancies. The BMA acts in the absence of the BM and must stay current on all issues affecting their assigned fuel facilities. The COR has the responsibility to oversee this effort and ensure that the BM or BMA are performing their duties to maintain fuel facilities, and existing facility components in their customary state of operating efficiency, or to restore a real property fixed facility, system, or component to such a condition that may be effectively used for its designated functional purpose, in accordance with 10 U.S.C Section 2811, OPNAVINST 11010.20. Facility costs are funded by DLA Energy, SRM, based on real property maintenance code (D-33). However, facility costs to support new mission changes are typically borne by the command that creates the requirement, until the item is budgeted for the upcoming fiscal year. Any command is authorized to fund PWD to perform approved facility repairs or improvements, which have not been funded or remain unfunded. This avenue is available to the COR, as another alternative, in meeting maintenance and repair requirements, and missions.

C-2.8.3.2 Centralized Managed Programs (CMP): American Petroleum Institute (API), inspections that fall under Centrally Managed Programs (CMP) and in accordance with DoDM 4140.25 are scheduled and managed by DLA Energy and are at no cost to the contractor. Should DLA Energy have another contractor perform work under a CMP, SRM, or any other contract or program, the contractor chosen to perform the work will have primacy over any maintenance/repair/inspection conflict and/or overlap at any DLA Energy Capitalized petroleum facility. Therefore, the contractor performing work under the subject contract must allow the CMP, SRM, or other contractor to perform the required maintenance, repair and inspection work at the designated facility when instructed by the KO. However, the refueling contractor must track and document CMP tasks, from cradle to grave, relevant towards fixed fuel facilities, in the CMMS. If any CMP tasks are not being performed as required or sufficiently, the refueling contractor must report the problem to the COR and DLA Energy KO for assistance and immediate resolution.

C-2.8.3.3 Sub-Contractor Personnel: Efforts performed to utilize sub-contractors, including acquisition, on site management, coordination of multiple teams, specialized inspection efforts, and/or quality control must be the responsibility of the contractor. Any sub-contract provider employees working at the terminal to accomplish maintenance and repair at any time other than the normal hours of operation must be under the observation of an employee of the contractor who is familiar with the system/subsystem undergoing maintenance and repair. Costs associated with this must be included in the Monthly Use Charge CLIN. Contractor must ensure that sub-contractor employees are certified and receive a safety briefing prior to start work. Certified is defined as having met the official industry standard requirements that are needed to do the type of work required, to include official proof of required training and certification.

C-2.8.4 Maintenance Records: Maintenance, repairs, inspections, calibrations, certifications, and test findings must be electronically and manually recorded and maintained for all fixed facilities. The contractor is required to keep all maintenance records using a CMMS. The contractor must develop and maintain an electronic database on deficiencies and problem areas needing corrective work. Record keeping includes all

noted deficiencies found and work performed at the fuel facility, even if performed by another organization, agency, or contractor. All information obtained must be inputted into the CMMS and used to schedule the required maintenance as appropriate. Records must be maintained for the duration of the contract and turned over to DLA Energy at completion of the contract. In addition, the COR and QAE must have access (read only), to the contractor developed database. The contractor will track all maintenance and repair expenditures using real property numbers associated with fixed facilities, coded D-33 (only).

C-2.8.5 Buildings and Structures: The contractor must ensure that all buildings, structures, and facilities used by or under contractor control are kept clean, sanitary, and in an orderly manner. The contractor must sweep, mop, and wax floors, wash windows, and walls of occupied buildings or office spaces to present a clean, sanitary, and orderly appearance. Food storage and preparation areas must be maintained in an orderly and sanitary condition. Clothing locker and change areas must be kept orderly and clothing hung or kept in lockers. Areas immediately around buildings for which the contractor is responsible must be kept free of debris. The contractor must not allow fire hazards, such as oily rags, loose paper, and trash to accumulate in or around buildings, structures, facilities, and areas used, occupied, or controlled by the contractor. The contractor must reset circuit breakers and switches, furnish, and replace burned out standard and fluorescent lights, and plunge sinks and toilets to keep them serviceable. The requirement for other building/structure maintenance, from electric, carpentry, and other skilled trade work, out-of-scope of the contractor, must be documented in the CMMS and forwarded to the COR. The contractor must not alter any structure or allow it to be altered without explicit written approval by DLA Energy, SRM processes. Maintenance of fire alarm systems is provided by the base, public works. Maintenance of eyewash stations if plumbed are the responsibility of the base and if portable the responsibility of the contractor. The contractor is responsible to test the eyewash stations and emergency showers. The maintenance of all HVAC systems is the responsibility of the base, public works. The contractor must notify the COR, to ensure the above-mentioned offices perform their required maintenance in a timely manner. The contractor must report delays to the COR and DLA Energy KO.

C-2.8.6 Pest and Rodent Control: The contractor is not responsible for Pest and Rodent Controls. All facilities must remain the responsibility of the base operating support services within the base, public works. Requests for services must be forwarded to the COR. The use of insecticides and rodenticides by the contractor must meet DoD, Federal, Navy, State, and Local criteria requirements, throughout all periods of performance.

C-2.8.7 Designated Areas: The contractor must establish a smoking policy that prohibits smoking in other than installation- designated areas. The contractor must provide signs to be posted at the entrance to work areas that read, "NO SMOKING EXCEPT IN DESIGNATED AREAS." The contractor must also designate a smoking area and provide signs that read, "DESIGNATED SMOKING AREA." The contractor's smoking policy, designated smoking areas, and signs will comply with DoD, Federal, Navy, State, Local Laws, and Regulations.

C-2.8.8 Trash Removal: The contractor must be responsible for the pick-up of all trash and debris within and around fuel areas under its control and must dispose of all such trash and debris in local containers or dumpsters. The Navy Base Operating Support contract must dispose of the trash and debris placed within the containers or dumpsters. Under no circumstances must the contractor permit or allow accumulated trash to be burned or disposed of within the terminal. The contractor must participate in and support any recycling base programs.

C-2.8.9 Grounds: Grounds maintenance, grass cutting, tree and shrub pruning, and general vegetation control must be provided by the contractor. Services must include, but are not limited to maintaining lawns, beds, curbs, driveways, sidewalks, buildings, keeping all areas clear of sediment build-up, and controlling the amount of standing water to minimize mosquito breeding. All grass within 20' feet of structures, tanks,

pits, pipelines, field grass, slopes, hills, swales, ditches, and fire hydrants, must be maintained and must not exceed "4" inches in height at any given time. All vegetation within contractor-controlled areas, on/under fence lines, and in the security zone outside the fence line of the bulk storage, refueler-parking area, must be maintained with the prescribed limits. Bulk vegetation and waste accumulated during mowing, removal, and control operations must be disposed of by the contractor. Remove all vegetation and silt within the berms and throughout the terminal drainage ditch system. Ensure unimpeded pedestrian and vehicular traffic. The use of fungicides by the contractor is prohibited. These services must be executed with contractor-furnished equipment, and the contractor must include all cost; including manpower, tools, equipment, expendable parts/materials needed to perform these ground maintenance services under this contract. The contractor must ensure their approach to meeting these requirements is clearly defined in their proposal and covered under the MUCG.

C-2.8.10 Other Facilities, Equipment, and Utilities: The contractor must continuously monitor other relevant facilities, equipment, and utilities, identified as storm drains, exterior lighting, potable water systems, sewage systems, security lighting, exterior building lights, fences, to include signs and markings, gates and automatic gate openers; roads, paved surfaces, curbing, and sidewalks within contracted fuel management areas; fire hydrants, AFFF systems, exterior water systems, power poles, lines and transformers, high-voltage lines and exterior telephones within fuel management areas. Noted malfunctions, discrepancies, or an obvious need for maintenance must be documented in the CMMS, reported to the COR, and DLA Energy KO.

C-2.8.10.1 Fences and Gates: The contractor must inspect all fences, to include signs, markings, barbed wire, gates, and automatic gate openers of fuels management compounds. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.10.2 Roads and Paved Surfaces: All roads, paved surfaces, curbing, and sidewalks within contracted fuel management areas must be monitored continuously. Damage, defects, anything beyond the need for minor repairs must be documented in the CMMS and reported to the COR.

C-2.8.10.3 Road Maintenance: The contractor must be responsible for removing snow and ice from roads and sidewalks, moving gravel from paved roadways, and keep all roads free of debris. The Navy Building Manager must coordinate road repair, relevant to materials such as crush and run and cold patch materials for pothole repairs. The contractor must document any deficiencies in the CMMS and report them to the COR.

C-2.8.10.4 Area Lighting: The contractor must inspect exterior lighting, security lighting, and exterior building lights on a continuous basis. The contractor must document any deficiencies in the CMMS and reported to the COR. The Navy Building Manager must coordinate repairs to streetlights.

C-2.8.11 Storage Tanks: The contractor must visually inspect the exterior of all storage tanks, to include small connected or freestanding residual product collection tanks. Along with tank components, the contractor must visually examine the various samples taken from the tanks in accordance with the Operations and Maintenance Manual. All inspections and visual examinations must be documented in the CMMS and corrective action within scope of PWS (operator maintenance) must be accomplished. The contractor is responsible for keeping the tank exterior clean, free of mold, dirt, and rust. The contractor must pressure wash, remove corrosion, apply corrosion inhibitor, and spot paint as needed. Maintenance requirements such as the need for exterior corrosion control and painting of tank(s) and tank inspection/cleaning as may be indicated by the visual examination of drawn samples must be recorded on the appropriate inspection documents, CMMS, reported to the COR, and DLA Energy KO.

C-2.8.12 Tank Maintenance: API 653 Interior and Exterior Inspections, remain within the DLA Energy, Centrally Managed Programs (CMP), in accordance with DoDM 4140.25. These inspections and repairs are

scheduled and managed by DLA Energy at no cost to the contractor. Upon notification of a cleaning or repair project, the contractor must, to the extent possible, use installed system-pumping equipment to empty/ready all selected tanks for cleaning and inspection. The removal and disposal of remaining tank bottoms must be the responsibility of the CMP contractor cleaning and gas freeing the subject tank. On completion of tank cleaning or repairs by the CMP contractor, the Navy Building Manager must document a joint ENV, API 653 Contractor, and NAVFAC Engineer internal or external tank/system inspection to ensure all tanks and system components have been returned to a ready state and can be returned to service, by accepting the project as completed; before the refueling contractor is allowed to operate the tank. The contractor must document in the CMMS and upload all relevant documents associated with the subject tank.

C-2.8.13 Berms, Canals, and Containment Systems: The contractor must ensure that all tank berms, drainage canal, primary and secondary containment systems are kept clean, free of vegetation, the accumulations of other debris that may hamper proper system drainage and to protect the buried berm liner. Ground liners for tanks (**if applicable**) must be kept free of silt and the gravel borders around the tanks, drop inlets, and access roads to the tanks must be maintained vegetation free. Canals must be maintained free of vegetation, debris, and contain no more than two (2) inches of silt that would hamper the flow of water and block drains. Canals must require cleaning with mechanical equipment more than once a year to maintain proper drainage of the area. Debris and silt generated from canal cleanings must be removed and disposed of per environmental regulations at Navy designated sites. Drain valves must be inspected, actuated in accordance with preventive maintenance schedule, and secured in a closed position when not in use. The contractor must clean all moats, keep them free of accumulations of sand, dirt, debris, and vegetation. The direct discharge of any liquid from any berm/containment system must comply with all Spill Prevention Control and Countermeasures (SPCC) plans and National Pollution Discharge Elimination System (NPDES) permitted in 40 CFR 112.8, and as applicable. The contractor must maintain a clear, concise log as to the dates and time berms are drained, observed conditions of the water drained, and who performed the drain operation. Drain valves, devices, and outlets must be kept in the closed position and locked, except as required to physically clean and drain berm areas. Keys must be controlled as outlined in local lock and key control security instructions. The contractor must procure, maintain, and utilized contractor furnished equipment in maintaining berms, canals, and containment systems.

C-2.8.14 Gauges (Pressure, Differential, and Vacuum): The contractor must inspect gauges continuously, as part of the operations and maintenance requirements. The contractor must document in the CMMS, the removal, calibration, or arrange to have calibrations performed by an agent certified for such work, and replace all such gauges required, by UFC 3-460-03. Calibration tags must be affixed to each gauge to document completion date. The RMMR Program must execute, majority of these responsibilities applicable to UFC 3-460-03 (System Maintenance). Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.15 Pressure/Thermal Relief Valves: The contractor must continuously monitor all installed pressure/thermal relief valves as part of its facility inspection program, operations, and maintenance requirements. All deficiencies must be documented in the CMMS and reported to the COR immediately. All pressure relief valves must be maintained in the open position, in accordance with Operational Procedures.

C-2.8.16 Pipelines: The contractor must continuously monitor piping and pipeline systems, to include all valves and expansion joints, by keeping the pipeline unearthed and exterior clean, free of mold, dirt, and rust. The contractor must pressure wash, remove corrosion, apply corrosion inhibitor, and spot paint exposed portions of the pipeline, as needed to control, and prevent the spread of corrosion. DLA Energy must be responsible for pipeline replacement and major repairs; however, the contractor must be responsible for maintenance, inspections, testing, and incidental tasks, the manipulation of valves to isolate a line or the operation of system pumps to pressurize or evacuate lines. The Navy Building Manager must document a joint ENV, API 570 Contractor, and NAVFAC Engineer, observation of pressurizing the affected pipelines

to ensure the integrity of the pipeline and repair areas. This must be accomplished by the Navy Building Manager, prior to returning the pipeline to service and before the refueling contractor is allowed to operate the pipeline. The contractor must document discrepancies in the CMMS and upload all relevant documents associated with the subject pipeline repairs and inspections.

C-2.8.17 Valve Pits: The contractor must keep all pipeline and component pits clean and free of debris, water, and fuel. The contractor must remove any water and/or fuel that may accumulate in pits and must periodically air pits to reduce/prevent corrosion. The pits vary in depth from 4 to 10 feet. Oily water can be removed from the valve pits using incidental vacuum trucks. Recovered oily water must be disposed of in accordance with environmental regulations. Prior to entry, all confined valve pit spaces must be certified safe for entry in accordance with 29 CFR 1910.146. In the event any pit appears to contain excessive fuel or fuel vapors, the contractor must inspect all pipeline connections (flanges), valves, and controls, to locate, correct the problem (within scope), document in the CMMS, and report to the COR. Appropriate confined space safety measures must be observed, always. Pits known to be less than watertight must be identified, marked, and monitored continuously. The Navy Building Manager must submit appropriate work requests for the repair, sealing, or possible replacement of such pits. The contractor must not exceed their scope of work of this contract, the discrepancy must be documented in the CMMS, and reported to the COR.

C-2.8.18 Oil/Water Separator System: The system consists of a series of regulated outfalls. The contractor must provide the labor, material, equipment, and vehicle resources to operate the oil/water separators and outfalls seven days per week or as required. Visually inspect, measure the contents of oil/water separators, and debris must be removed as required. Gauge readings and noted discrepancies must be documented in the CMMS and reported to the COR. Testing of the separators and outfalls; along with maintaining these systems is coordinated between the Navy Building Manager and PWC Environmental (Public Works).

C-2.8.19 Shower and Eyewash Stations: The contractor must inspect, test, and maintain shower and eyewash stations for proper function. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.20 Cathodic Protection System: Cathodic protection systems must be monitored (power on/off or damaged) by the contractor but maintained by Public Works via a DLA Energy, Centrally Managed Program. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.21 Corrosion Control and Painting: Painting must be required to preserve and protect equipment, pipes, tank roofs and stairways on fixed fuel facilities. When paint has chipped, loosened, or deteriorated allowing rust to form on surfaces. The contractor must perform corrosion control and painting (of those systems requiring painting) as part of preservation measures and document these tasks in the CMMS. Painting consists of removing dirt and corrosion, preparing the surface, applying primer/corrosion inhibitor, and repainting surfaces area and components, such as valves, strainer, motors, to protect surfaces from mold, bio growth, corrosion, and to preserve equipment appearances. The contractor must not paint over locator markings and identification plate, placed on pipelines as part of the API 570 inspection. The contractor must also apply color code bands and symbols as outlined in MIL-STD- 161, Identification Methods for Bulk Petroleum Products Systems, as required, to remain in compliance. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.21.1 Large Surfaces: The contractor will not be required to paint large horizontal/vertical surfaces such as buildings, entire tanks, or entire pipeline systems, but is required to protect surfaces from mold, bio growth, corrosion, and to preserve equipment. Components requiring more than 25% of its surface painted are not considered spot painting and are not included in the Monthly Usage Charge CLIN. However, the contractor must remain responsible for preventing any component from deteriorating beyond 24% of the

entire component. Painting of areas, which are more than 10ft above a stable footing surface, will not be required or covered under the Monthly Usage Charge CLIN of this contract; and, in such cases, the painting requirements must be documented in the CMMS and reported to the COR.

C-2.8.21.2 Materials Used: Paint and Primer used must be an epoxy based suitable for use on metal and exterior surfaces. Epoxy paint and primer must meet the standards of MIL-DTL-24441, Exterior Coating of Steel Structures, and must be matching or compatible with the existing paint scheme. Painting of surfaces must conform to UFGS Section 09 97 13.27 and UFC 3-460-03.

C-2.8.22 Pumps: The contractor must maintain all terminal pumps and electric motors in a serviceable condition by performing inspections, operator maintenance, checking for leaks, adjusting the packing, checking vibration, inspecting packing glands and gaskets, providing lubrication, tightening loose bolts, and adjusting valves. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.23 Valves and Valve Motor Operators: The contractor must inspect and maintain all types of valves. The contractor must perform operator maintenance, lubricate, and provide for frequent inspection and operation of each valve. Check operation of hand/off/auto switch; replace lights on valve motor operators. Adjusting torque settings and limit switches must be coordinated with the Navy Building Manager. All valves less than 2.5 inches must be monitored continuously. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.23.1 Tank Valves: The contractor must ensure that all applicable valves, such as, tank, terminal and/or booster pump house are in the closed position except when product is being received, issued, or transferred through a particular pipeline, manifold, or system, in compliance with Operations Manuals. All system valves must be aligned to allow for thermal expansion and pressure relief to prevent over pressurizing pipelines. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.24 High/Low Level Alarms and Control Valves: The contractor, in coordination with the Navy Building Manager, and AFHE Representative/Technician, must functionally test installed alarm systems. A systems status report must be forwarded to the COR on completion of testing. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.25 Automated Tank Gauge (ATG) System: The contractor must monitor ATG systems continuously. When used for custody transfers, ATG readings must be validated by manual gauging as directed by policy. A systems status report must be forwarded to the COR on completion of gauge validation/testing. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.26 Truck Fill Stands: Fill stands must be inspected on a continuous basis for leaks, faulty components, loose connections, and filters differential pressure readings, and electrical continuity. The contractor must perform operator maintenance that may include but is not necessarily limited to the replacing of ground wires, clamps, and plugs, inspecting seals and gaskets, and the cleaning of strainers, in compliance with UFC 3-460-03. The contractor must also accomplish corrosion control and spot painting of fill stand facilities. The contractor must ensure that the tank truck fill stands are clean and free of debris including bird droppings, and that the tank truck fill stand containment area is free of water and product residue. Fill stand containment valves must be always closed unless containment is being drained to product recovery tank. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.27 Overfill Protection: Must be monitored on a continuing basis. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.28 Fuel Meters: The contractor must monitor meters on a continuing basis. All positive

displacement, temperature- compensating meters must be calibrated by qualified personnel semiannually. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.29 Strainers and Basket Strainers: The contractor must inspect, clean, procure, and replace the strainers or basket strainers, when applicable, in accordance with UFC 3-460-03. The contractor must perform operator-level maintenance, small replacement of parts, by utilizing hand tools. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.30 Fuel Hoses: Fuel hoses normally detached after an operation must be drained, capped, and properly stored off the ground and protected from the elements after each use. Attached hoses, such as those at a fill stand, must be properly stored off the ground and protected to the maximum extent possible. All hoses must be inspected for cuts, abrasions, and general wear and tear IAW UFC 3-460-03. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.30.1 Pressure Testing Hoses: The Navy Building Manager must coordinate with the RMMR Representative to test refueling hoses annually at 1½ times the maximum allowable working pressure (MAWP) as defined in UFC 3-460-03. The RMMR Representative must mark the latest testing date and MAWP on the hose where it can be seen. Discrepancies must be documented in the CMMS and reported to the COR. Any hoses utilized with contractor furnished equipment must be pressure tested by the contractor.

C-2.8.31 Manifolds and Pipelines: The contractor must inspect manifolds and pipelines for leaks and general condition of equipment as part the daily inspection process. Manifolds, pits, slabs, and surrounding areas must be clean and free of debris, water, and vegetation. Discrepancies must be documented in the CMMS and reported to the COR.

C-2.8.32 Pressure Testing Pipelines and Loading Arms: The Navy Building Manager must coordinate pressure testing of all POL lines and the loading arms as required, in UFC 3-460-03. Over the water pipelines must be pressure tested annually, and intra-terminal pipelines must be pressure tested every five years. API 570 testing must be accomplished through DLA Energy, Centralized Management Program. The contractor must support the pressure testing as required; document pressure testing results in the CMMS, and discrepancies must be reported to the COR.

C-2.8.33 Fire Protection Systems: The contractor is responsible for the inspection, monitoring, and operation of the fire protection systems. The site consists of water pumps, pump houses, water lines, and hydrants. The Navy Building Manager must coordinate all fire alarm testing and routine water lines/hydrant flushing requirements with Naval Air Station Kingsville, Fire Department. Public Works Center (NAVFAC) is responsible for all repairs associated with the fire alarm systems at all locations listed within this contract. The Fire Departments at Naval Air Station Kingsville are responsible for the fire protection system monthly testing of alarms throughout the facilities/locations and may provide fire bottle inspections monthly. The contractor must monitor, document and report all observed discrepancies to the COR.

C-2.8.34 Fire Extinguisher Inspection: The contractor must inspect all fuel facility fire extinguishers as required by the regional fire prevention instruction. Contractor personnel must attend the class for fire extinguishers to perform the monthly inspections. However, this does not dissolve the Fire Department at Naval Air Station Kingsville overall accountability and responsibilities.

C-2.9 Training: The contractor must establish and maintain a training program that is acceptable and in compliance to DoD, DLA Energy, Navy, and station/base regulations. Contractor employees performing fuel duties must be company trained and certified. Company training requirements must not preclude Personnel

Qualification Standard (PQS) for Aviation Fuel Operations Ashore, NAVEDTRA 43288. Certification must include and not limited to initial employee indoctrination, fuel safety, environmental issues, and DoD Antiterrorism (AT) Standards Level I. Along with a written or oral examination, as well as direct observation of the employee performing the certified duties. Recorded training documents and certifications must be maintained, fully documented within everyone training record, and made available for assessment.

C-2.10 Safety: The contractor must maintain a comprehensive fuel safety program that complies with applicable DoD, Federal, Navy, State, and Local References and Laws identified in Appendix C. The contractor must appoint a responsible individual for collateral duties as a Safety Program Monitor, the primary point of contact regarding the contractor's safety program. All operators must adhere to operational safety rules, such as flightline vehicle operations, grounding and bonding, safety distance criteria, fire watch, lock out/tag out, hearing conservation, and any other safety guidelines, during the duration period of the contract. Discrepancies applicable to fuel facilities must be documented in the CMMS, and reported to the COR.

C-2.10.1 Accident/Incident Reporting: All duty related accidents and incidents, to include traffic violations involving contractor operated equipment, for which the contractor personnel are responsible or involved in must be reported to the COR immediately or, depending on the severity and circumstances, as soon as practicable. All accidents and incidents must be fully documented and a copy of all initial draft and final accident/incident reports forwarded to the COR within the next duty day.

C-2.10.2 Hearing Conservation: The contractor must ensure that a hearing conservation program is fully implemented required for those employees who are exposed to noise hazards as defined by 29 CFR 1910.95 Noise Exposure.

C-2.10.3 Occupational Safety and Health: The contractor must have an ongoing Health and Safety Program meeting the requirements of Occupational Safety and Health Administration (OSHA) regulation 29 CFR 1910.120, Hazardous Waste Operations and Emergency Response and 29 CFR 1910.146, Permit Required Confined Spaces.

C-2.10.4 Lock Out/Tag Out/Requirements for Mechanical Systems: The contractor must ensure the use of blind flanges when a component of a fueling system is removed or altered and left unattended. A closed valve upstream tagged or locked is not considered a positive shutoff and will not eliminate the requirement for the installation of blind flanges. Open-end pipe flanges or loosened flanges (unbolted except one or two bolts to hold valve or equipment in position) will not be allowed at any time. The contractor must be responsible when a component is removed, or the system is altered for installing the blind flanges to ensure that the integrity of the fueling system is retained.

C-2.10.5 Static Resistant Clothing: The contractor must not wear any clothing that generates static charges that could ignite fuel-air mixtures. The contractor must not wear any outer clothing, consisting of all wool, silk, or nylon materials, or blends of silk or nylon, during fuels maintenance or minor repair work. Wool stockings, wool glove inserts, woolen navy stocking caps and underwear of nylon, silk or polyester pose no significant hazard and are acceptable. The contractor must not put on or remove outer garments such as jackets and parkas while engaged in maintenance or minor repair work on petroleum systems and facilities to prevent the electrostatic interaction of the fabric fibers.

C-2.10.6 Electrical: Electrical currents are more dangerous than static charges because of the possibility of a continuous electrical spark, as opposed to the brief spark released by a static charge. The contractor must take precautions to observe and eliminate the hazard of electrical discharge. The contractor must ensure compliance with the requirements of the U.S. National Electrical Code (NEC) for hazardous locations. All temporary wiring will conform to National Fire Protection Association (NFPA) 70, NFPA 30, and NFPA

regulations. The contractor must submit a written report of any electric installation that does not meet requirements to the COR when the deficiencies are found. Corrective measures that are to be taken will be determined in a coordinated contractor, COR, and KO lead effort.

C-2.10.7 Inclement Weather: When electrical storms are within a 10-nautical mile radius, all refueling/defueling evolutions shall cease until the condition clears the 10-nautical mile radius, unless specified otherwise by applicable local directives. The dispatcher must continue to advise customer of weather conditions and receive calls for refueling/defueling services. The Fuels Management Data (FMD) base/log must be updated with remarks applicable to weather conditions, as the reason for any delays in services. The dispatcher must communicate with pending customers to reestablish refueling/defueling priorities after all clear is received by Air Operations (Tower). If a conflict between aircraft mission is identified, the Air Department Duty Officer must be informed to make the final determination on Mission Priorities.

C-2.11 Environmental: The contractor must be fully responsible for compliance with all DoD, Federal, Navy, State, and Local References and Laws identified in Appendix C, to include DoDI 4715.06 (Environmental Compliance in the United States), DoDI 4715.17 (Environmental Management Systems), and OPNAVINST 5090.1 (Environmental Readiness Program). The contractor must comply with all additions, changes, and revisions as may become effective during the contract period of performance, to include disposal of all hazardous material waste. The contractor's work must conform to all operational controls identified in the Environmental Management System (EMS), by monitoring, and measurement of required information, to address performance relative to the goals of EMS. Environmental permits and licenses required for the operation of fuel facilities will be obtained by and kept on file by the Navy. The contractor must be responsible for maintaining compliance required by the fuel facility permits and licenses. The contractor's performance must be in accordance with environmental plans that will be provided by the Navy. The contractor must modify standard operating procedures and work practices to ensure compliance with any new or revised permits, licenses, laws, or regulations. The contractor must ensure that all necessary actions are taken to prevent, control, and abate environmental incidents. If the contractor receives a Notice of Violation, they must immediately notify the COR and KO. Any discrepancies must be documented in the CMMS and reported to the COR.

C-2.11.1 Assignments: CNIC appoints shore Navy On-Scene Coordinator (NOSC) and provides policy guidance for planning, coordination, and reporting incidents on shore and offshore within 12 nautical miles of land. The contractor must not be assigned any NOSC duties, at any Naval Installation. The Spill Prevention Control and Countermeasures (SPCC) plan and/or the Facility Response Plan (FRP) or equivalent, may designate contract management/personnel to serve as Initial Point of Contact (IPOC) relevant to fuel facilities under the control of the contractor. The contractor must be capable of meeting the requirements and participate fully in all required spill exercises. In concert with the base environmental goals, the contractor must train personnel regarding all required duties relevant to the assigned tasks, Hazardous Waste Operations and Emergency Response (HAZWOPER), and Safe Transportation of Hazardous Materials and Under Ground Storage Tank Operator Training and Oil Pollution Act of 1990 (OPA 90), conducted annually, and all other systems for which it is responsible.

C-2.11.2 Spill Response: In the event of a spill, the contractor will follow the SPCC and FRP.

C-2.11.3 Spill Reporting: In accordance with DLA Energy Policy P-40 (Spill/Leak/Release/Reporting) the contractor must report all reportable spills and documentation requirements for any discharged, leaked, or

spilled Defense Working Capital Funds (DWCF) product. In addition, the contractor must also notify the KO and COR. The contractor must also provide to the KO and COR a simplified report of all spills involving the contractor, its personnel, equipment, and systems for which it is responsible. All reports must be immediate (same day) written (e-mail) accounts of the circumstances surrounding the spill, the estimated amount of the spill, and actions taken to remediate the spill.

C-2.11.4 Spill Response Supplies: The contractor must be responsible for the care and upkeep of all spill containment and clean up kits, supplies, and contractor-furnished equipment within occupied contractor-controlled facilities. Consumables must be replenished anytime the quantity on hand drops 10%. These consumable materials may include the following items, such as absorbent pads, sweeps and litter; rags; rubber gloves and boots; coveralls; squeegees; safety goggles; trash bags; brooms; and 55- gallon drums. The contractor must consolidate materials used for spill cleanups and coordinate with NAVFAC Environmental Services when arranging for the pickup and disposal of the solid waste materials. The spill response lockers are maintained and staged throughout the facilities (at various locations) and resupplied by contractor under the Monthly Usage Charge CLIN at no additional cost to DLA Energy.

C-2.11.5 Storm Water: In addition to spill response consumables and contractor-furnished equipment, the contractor must provide all labor, material, and dewatering equipment necessary to comply with the Storm Water Pollution Prevention Plan (SWPPP). The contractor's responsibilities must be primarily visual observations of storm water discharge and other actions to support the SWPPP.

C-2.11.6 Environmental Remediation Support: The contractor must provide the labor necessary to periodically pump out the oil from the holding tanks associated with the oil recovery wells and solar collection systems **(if applicable)**. Oil collection will be scheduled and coordinated with the remediation contractor and listed on the Daily Operation Schedule. The oil must be transported and discharged into the oil reclamation system.

C-2.11.7 CHRIMP: The contractor must comply with the local Consolidated Hazardous Regularization and Inventory Management Program (CHRIMP), a program that centrally manages hazardous materials from purchase to the return (turn in) of empty container, residual stocks, and time-controlled items. All materials used by the contractor and designated a hazardous material (HAZMAT) may be purchased from off station sources, stored, and used in accordance with acceptable environmental practices, but must be deposited of through the local CHRIMP control point.

C-2.12 Security: Under the guidelines of the most current OPNAVINST 5530.14, Navy Physical Security, the contractor must be responsible for implementing the administrative and physical security measures as required to protect incidental facilities, vehicles, equipment, materials, systems, and petroleum products, as well as contractor-owned equipment, tools, supplies, and vehicles. The contractor must provide all labor, vehicles, equipment, materials, and supplies necessary to manage and protect all the areas under its contractor control, to include during force protection measures. The contractor is not authorized or responsible to provide installation escort services, in accordance with OPNAVINST 5530.14, Navy Physical Security.

C-2.12.1 Facility Assessment: The contractor must perform and document end-of-day facility inspections to ensure all systems are secure to the extent of the physical barriers provided. During operating hours all fuel facilities must be randomly inspected. Facility security, physical barriers, and lighting discrepancies must be documented in the CMMS and reported to the COR.

C-2.12.2 ADP and Information Assurance: The contractor must comply with all ADP security measures and requirements for incidental computer systems. OPNAVINST 5239.1, United States Navy Cybersecurity

Program and Installation Command Regulations for information of cyber networks. The COR must ensure that contractor personnel are issued a Common Access Card (CAC) to gain access to fuel facilities and Navy Marine Corps Intranet (NMCI) computer network email account for the execution of PWS workloads, to include the applicability of EPoS Systems.

C-2.12.3 Identification Badges: Access to the terminals is controlled by Common Access Card (CAC) issued to each employee. Contractor employees must display applicable CAC's while on site. To receive an identification badge, contractor employees must complete and sign Sections I and II of the DD Form 1172-2. The contractor forwards the DD Form(s) 1172-2 to the COR. The COR must sponsor the contractor employee and submit the DD Form(s) 1172-2 to the Mission Partner Identity and Credential Access (MP ICAM). The contractor employee will receive an email via MP ICAM when his/her account has been approved. The email will notify the employee to obtain a government-issued CAC from the nearest Real-Time Automated Personnel Identification System (RAPIDS) office. Each contractor employee must obtain his/her issued CAC from the RAPIDS office. Upon receiving the CAC, the contract employee must submit a request for an email account, required to conduct business on military installation and electronic equipment. The contractor must account for all security identification badges issued to their employees. The COR must maintain and submit a CAC Log of all issued CAC's and COR Report to the KO; monthly.

C-2.12.4 Key Control: The contractor must account for all incidental keys and establish a control system to safeguard and prevent theft, loss, or use by unauthorized personnel. A Primary and Alternate Key Custodian with the responsibility for the issue, receipt, inventory, and securing of keys must be designated in writing and a copy of these designations must be provided to the COR. If, through negligence by the contractor, the Navy must replace or re-key locks, the contractor must reimburse the Navy for all expenses incurred. The contractor must not replace Navy locks without approval from the COR; once approved the contractor must provide copies of new keys to the COR. The contractor must only use keyed locks. The contractor must immediately notify the COR of any keys lost or stolen.

C-2.12.5 Heightened Security: The contractor must comply with Naval Regional Installation Policies to ensure mission accomplishment during heightened security postures at naval installations. Force Protection Conditions (FPCON) Bravo, Charlie, and Delta apply when an incident occurs, or intelligence is received indicating some form of terrorist action against personnel or facilities is imminent. To provide continuity of operations, the contractor must designate essential personnel, to provide continuity of operations.

C-2.12.6 Truck Access: Contractor personnel must adhere to truck access control measures being employed at the sites during Force Protection Conditions (FPCON). All trucks will be subject to inspections and/or searches. During FPCON Charlie and Delta postures, there will be limited access with commercial deliveries restricted to essential items only. The COR, civil service, or military representative(s) must provide escort services for trucks entering and exiting sites. The contractor is not responsible or authorized to escort other parties onto any military installation; in compliance with OPNAVINST 5530.14, Navy Physical Security.

C-2.13 Incidental Equipment: Incidental Equipment means certain items located at the fuel facilities which are made available to the contractor for use in the performance of the services required under this PWS. See Appendix A and follow instructions to receive the list of Incidental Equipment.

C-2.13.1 Joint Incidental Equipment Inventory: At contract turnover, the outgoing and incoming contractor, and the COR must conduct a joint inventory of all on-site furnished facilities, systems, equipment, supplies, and other incidental equipment. They must jointly validate the list of facilities, fuel systems, and incidental equipment to be utilized by the contractor for the contract performance period. An inventory listing must be signed by the TM and COR and provided to the KO.

C-2.13.2 Annual Inventory: The contractor must account for all properties, maintain records, and submit a

report of on-site property in the custody of the contractor annually on the anniversary date of the contract award. The report must be signed by the TM and COR not later than 30 days after the anniversary date of the contract award. The contractor's report must provide a complete inventory of on-site furnished property under its custody. The contractor must identify all property deleted and received since the preparation of the last inventory and provide copies of source documents.

C-2.13.3 Disposition of Incidental Equipment: The contractor must request disposition instructions from the COR for any property other than fuel products.

C-2.13.4 ATG Annual Inventory: The contractor must perform an annual assessment of automatic tank gauging equipment identified in Appendix A. This assessment must be furnished to the Contracting Officer and the Property Administrator in a format of the contractor's choosing but will, at a minimum, identify the asset number and/or serial number and attest to the presence and condition of subject equipment. A final assessment must be furnished upon contract completion or termination or as directed by the Contracting Officer.

C-2.14 Use of Navy Facilities: The contractor must not permit or authorize its personnel to store, repair, or care for personal property of contractor's personnel, such as boats, motor vehicles, recreational vehicles, trailers, and motorcycles on Navy property. Likewise, the contractor must not use or allow the use of Navy property, facilities, or buildings for the storage or repair of contractor-owned vehicles and equipment except as otherwise specified or provided for within the terms of this contract.

C-2.15 Air Show Fueling Services: This requirement is executed under established policy DoD Directive 5410.18 and NOT covered under CLIN 0001. The Air Station has the option to contract air show requirements exterior from DLA Energy contracted fuel services. The fuels contractor has the option to bid on such contract requirements and utilize contractor furnished equipment. Should the Air Station choose to utilize the DLA Energy contracted fuels services, requests for such services must be submitted to the DLA Energy Contracting Officer 30 days prior to the event start date. A proposal must be submitted by the contractor that includes staffing, equipment, and materials utilized beyond contracted requirements. The proposal will be negotiated with DLA Energy, Navy Petroleum Office (NPO), and requesting activity, in advance, through the Contracting Officer for payment via firm fixed price and contract modification. Given the air show dates and tasking, the contractor must, by whatever means deemed most cost-effective plan for and support all requirements. The contractor has the option of performing the services, utilizing rental/lease equipment, or subcontracting to another company. The Military Interdepartmental Purchase Request (MIPR) is the only method available and accepted for transferring funds for air show services. Before contractor is authorized to proceed, MIPR must be accepted by DLA Energy not less than seven days prior to air show services.

C-3.0 Contractor Furnished Equipment

C-3.1 Vehicles and Equipment: The contractor must provide aviation, ground, utility vehicles, and equipment in quantities and with specifications sufficient to meet the aircraft refueling/defueling and ground receipt/issues workload requirements, including surge demands. All vehicles and equipment must meet the performance requirements of the latest version of National Fire Protection Agency (NFPA) 407, Standards for Aircraft Fuel Servicing, Department of Transportation (DOT) 406, National Fire Protection Agency (NFPA) 385 Standard for Tank Vehicles for Flammable and Combustible Liquids, ATA Spec 103 Standards for Jet Fuel Quality Control at Airports, and other Federal Policies/Laws as applicable. The contractor must provide all necessary tools, instruments, devices, and parts required to operate and maintain vehicles and equipment. All vehicles and equipment must be maintained in fully serviceable condition by the contractor and must be fully capable of safely performing the tasks for which they are designed. The vehicles provided at contract start must not be replaced or removed from the base/station without written notification to and documented approval by the KO.

C-3.1.1 Condition of Vehicles and Equipment: Prime-movers, tractors and refuelers utilized in the performance of this contract must be capable of meeting the current standards listed in “PWS C-3.1 Vehicles and Equipment” and all other requirements outlined in the PWS for the duration of the basic and option contract performance periods. All refueling vehicles taken out of service for maintenance and repair must be reported to the COR. However, this does not relieve the contractor of their responsibilities in meeting fuel-servicing requirements within this PWS. The contractor must include in their technical proposal the make, model, manufacture date, capabilities relevant to this PWS, specifications, and maintenance/inspection records of contractor-furnished vehicles and equipment. The technical proposal must provide a quantified approach in meeting PWS workload requirements and a contingency plan for major/minor breakdowns or unavailability of contractor-furnished equipment such as vehicles and equipment that ensure no disruption of support or inability to meet the contract requirements. These contingency plans must include plans for varying quantities of unavailable equipment, such as one refueler out of service; two refuelers out of service; three to four or more. This information will be included for use in evaluating the contractor’s ability to perform as required for the duration of the contract. The contractor must ensure that all proposed refueling vehicles and equipment are in place at the start of the performance period.

C-3.1.2 Modification/Overhaul/Replacement of Vehicles and Equipment: The contractor furnished vehicles and equipment on site deemed undependable, unreliable, or incapable of meeting any specific requirement outlined in this PWS must be reported to the KO and must be repaired, modified, overhauled, upgraded, or replaced at no cost to DLA Energy. The contractor must bear all risks and expense associated with the maintenance, serviceability, licensing, permitting, operation, and use of the contractor furnished vehicles and equipment.

C-3.1.3 Vehicle Lighting: All Vehicles required to enter the runway, taxiway, and ramp area must conform to FAA Advisory Circular AC 150/5210-5C for vehicle lighting. Daytime running lights and headlights must be configured to be turned off by the operator.

C-3.1.4 Company Logo: Aviation, ground, utility vehicles and equipment doors must be marked with a permanently affixed company name or logo. Stenciled or spray-painted logos or magnetic placards must not be used.

C-3.1.5 Spill Remediation Kits: All contractor aviation, ground, and utility vehicles must be equipped with a spill clean- up/remediation kit that is protected from the elements but readily available to the vehicle operator. Sufficient spares must be provided so that in vehicle kits can be maintained at a 100 per cent level.

C-3.1.6 Overfill Protection Equipment (OPE): The contractor must provide aviation and ground equipment to meet DLA Energy Overfill Protection Maintenance Guide. Each mobile refueler placed in service must be equipped with overfill prevention, ground verification, and Truck Identification Module (TIM). The OPE must consist of an automatic electronic continuous self- checking system with dual level overfill prevention to include high and high-high liquid level sensing. The system must mirror that of DLA Energy managed OPE installed at the fuel facility and incorporate an anti-driveaway feature. The OPE system must have a pre-check feature to ensure the automatic high-level shutoff system is functioning properly. The high-level liquid sensor must be the primary method of shutdown at the fill stand. The high-high level liquid sensor must be the secondary method of shutdown on the truck to include defuel operations, both must cause the internal tank valve to close and sound an audible alarm.

C-3.1.7 Low Point Drain: All tanks must be configured with an internal self-closing stop-valve.

C-3.1.8 Recirculation and Defueling: All aviation fuel servicing vehicles must have recirculation and defueling capabilities.

C-3.1.9 Meters: Refuelers/de-fuelers must be equipped with positive displacement, temperature-compensating meters sized to the flow rates established. For dedicated de-fuelers, non-compensated, positive displacement meter(s) with a gallon register must be installed. The contractor must calibrate or have calibrated each meter by a certified agent semi-annually, after maintenance or servicing. The contractor must also inspect each temperature element semi-annually of meters equipped with temperature compensation feature. The contractor must mark each meter and compensator to indicate the date of calibration or inspection and must establish a system of records to validate calibration date markings.

C-3.1.10 Hoses: Unless otherwise specified, every refueler must be configured with over wing and under wing hoses compatible with the aircraft and safety requirements. Refer to NAVAIR 00-80T-109 for specified length requirement..

C-3.1.11 Hose Fittings: Nozzles, tubes, drum thieves, cut hard/soft hose, and any other apparatus required to connect to and defuel the equipment and facilities must be provided by the contractor.

C-3.1.12 Hose Storage: Hose reels must be provided for all hoses, automatic or manual.. Hoses must not be hung or draped over intermittent points attached to or protruding from the tank or frame. The hose storage arrangement must prevent sharp bends or kinks occurring, while hoses are stored.

C-3.1.13 Nozzle(s): Depending on the type aircraft requiring service, three types of nozzles may be used; single point nozzle, over-wing (gravity) nozzle, or the closed circuit refueling (CCR) nozzle.. Unless stated otherwise, refuelers shall normally be configured with a single point nozzle and overwing type nozzle.

C-3.1.14 Swivels and Hose Couplings: Except as noted throughout this specification, couplings/connections shall be of the permanent, threaded type.

C-3.1.15 Deadman Controls: Refuelers must be equipped with a handheld deadman control with a connecting hose/cable installed in such a manner that it can be stored on a reel or removed and stowed when not in use. The deadman control hose/cable, located/mounted at the unit control panel, must be of sufficient length that the operator can reach and monitor all controls.

C-3.1.16 Static Bonding Cables: A static bonding cable must be installed on a rewind reel with cable guide. The overall length of the static bonding cable must be 50 feet, or the length of the longest hose being used whichever is greater. The cable must be of stranded steel (galvanized or stainless) wire rope 3/32-inch in diameter coated with a petroleum-resistant plastic containing light sensitive dye. The cable must terminate with a heavy-duty clip.

C-3.1.17 Tires: Unless specific tire requirements are established by the Commanding Officer, 49 CFR, Chap III, Sub- Chap B, Part 393, Sub-Part G applies. Non-FOD tire may be mounted at the contractor's discretion; however, recaps and slicks are not authorized for use on the front wheels when operating off base.

C-3.1.18 Fenders and Mudguards: Fenders and mudguards must be installed over the wheels of the tractor to fully protect the cargo tank and pumping system. Such fenders/mudguards may be tractor or trailer mounted. Non-functional skirting and flashing are prohibited.

C-3.1.19 Spotlight: All aviation refuelers must be equipped with a cab-mounted spotlight (work light) that can be manipulated by the driver from within the truck cab.

C-3.1.20 Warning Light: All vehicles operating on or entering the airfield must be equipped with a yellow flashing light.

C-3.1.21 Relaxation Chamber: Aviation refuelers handling fuels products that do not contain a static dissipater additive, such as JP5; must incorporate the use of a relaxation chamber that increases

the residence time of the fuel downstream of the filter to at least 30 seconds, thereby allowing most of the charge to dissipate before the fuel arrives at the aircraft.


C-3.1.22 Pressure Regulation and Flow Control: Refueling systems must have separate and independent primary and secondary pressure control device. Hose End Pressure Regulator (HEPR) will be used as secondary control device.

C-3.1.23 Exterior Paint Color: Conform to the most current FAA Advisory Circular, 150/5210-5.

NOTE

Aviation fuel equipment previously purchased for use at Government Owned Contractor Operated (GOCO) facilities and Government Owned Government Operated (GOGO) facilities and painted yellow in accordance with Naval Facilities Engineering Command Publication NAVFAC P-300 may continue operation through maximum economic service life.

C-3.1.24 Vehicle Marking and Identification Numbers: Conform to the most current FAA Advisory Circular, 150/5210-5. Additionally, refueling equipment must be clearly marked with the appropriate NATO Code Number contained in a rectangle as well as the common U.S. military designation. For example, JP-5 refueling trucks must carry the following symbol as well the JP-5 designation:



Refuelers used as refuelers/de-fuelers must be marked with “JET FUEL/JP” since the fuel will, in most cases, be a mixture of JP- 4, JP-5, JP-8, F-24 and/or commercial jet fuels. No NATO Code Number is to be applied to such equipment.

C-3.2 Records: The contractor must keep maintenance records on all fuel servicing equipment provided containing a complete description of the truck, tractor, and fuel tank provided, and a copy of fuel tank certification and any applicable inspection documents. A complete maintenance history relevant to the contractor’s possession of the vehicle must be provided and available to the COR for the duration of the contract.

C-3.3 Disposition of Property: Contractor furnished equipment must be used solely in the performance of this contract. Vehicles and equipment that do not meet the performance requirements of this contract, excess equipment, or fire/safety hazard must be removed from the work site and replaced (**if applicable**), at the contractor’s expense (immediately).

C-3.4 Property Storage: The contractor must not store vehicles or equipment in excess of contract requirements on Navy property. Equipment deemed to be unacceptable for use within the terms of this contract, excess to contract requirements, and standby equipment must be removed from the base immediately. That property in place at termination of the contract must be removed from Navy property within turnover period.

C-3.5 Equipment Inspection: Prior to the contract start date or a date mutually agreed upon by all parties, the contractor must have all equipment, supplies, materials, and documents available on-site for physical inspection, count, and/or review by DLA Energy and the COR. The expense of making all such property available for inspection, to include the labor necessary to move, fill, operate, and adjust/repair

the equipment being inspected, must be borne by the contractor. An accurate vehicle identification list must be presented for inspection. Copies of documents and all required attachments must be provided to the KO and the Post-Award Inspection Team Leader on the first day of the equipment inspection. Should it become necessary for the team to physically re-inspect contractor provided equipment, supplies, or materials deemed unacceptable, they must be repaired, modified to meet specifications, or replaced at the contractor's expense and documented in the contract file.

C-3.6 Other Contractor Provided Equipment and Supplies: The contractor must provide the following equipment, supplies, materials, and services. In doing so, the contractor must adhere to all DoD, Federal, Navy, State, and Local laws, codes, and regulations applicable to the products and services provided and the purchase, transport, use, storage, and disposition of hazardous materials that may be required to fulfill the conditions of this contract.

C-3.6.1 Fuel Products used by Contractor: The Contractor must provide all fuel products necessary and required to operate all contractor-owned equipment used under this contract. The Contractor must also provide, if required, the necessary federal, state, and local environmentally approved storage tank, dispensing system, meter, and security devices, and must arrange to have those products delivered to the Contractor's site. The cost for these fuel products will be included in CLIN 0001.

C-3.6.2 Radios: The Contractor must provide radios for all required Contractor-owned vehicles and the fuel dispatch center. The Navy will provide communication devices for airfield operations.

C-3.6.2 Communication Services: The contractor must provide all services and equipment necessary to conduct company business.

C-3.6.3 Administrative Supplies and Equipment: Except for base-furnished forms and equipment, the contractor must provide all administrative supplies and equipment necessary to undertake the administrative and records keeping functions required by the contract. The contractor must not be given access to or use of Navy office equipment, not specifically provided under the terms of this contract.

C-3.6.4 Janitorial/Housekeeping Supplies, Equipment, and Services: At those locations for which the contractor is tasked to perform janitorial services, the contractor must provide all janitorial and housekeeping equipment and supplies, to include small trash/waste baskets, self-closing waste containers and basic personal cleanliness items and restroom supplies, necessary and required to maintain the cleanliness and sanitation of buildings and facilities. Janitorial services may be sub- contracted.

C-3.6.5 Tools: The contractor must provide all hand/power tools, test/measurement/calibration devices, and powered/non- powered equipment required and necessary to inspect, test, calibrate, maintain, and repair contractor-furnished vehicles and equipment. Sufficient tools must also be available for (operational, preventive, scheduled and corrective) maintenance of Navy facilities and equipment.

C-3.6.6 Spares for Contractor Furnished Equipment: The contractor must provide all spares, replacement parts, components, and repair services required to maintain and repair contractor-furnished vehicles and equipment.

C-3.6.7 Specifications/Standards: All parts, items, and materials furnished must meet or exceed DoD specifications/standards or equivalent commercial item standards.

C-3.6.8 Consumables and Expendables: With reference to contractor truck maintenance, equipment and facilities operated and maintained by the contractor, the contractor must provide and maintain a bench stock of all consumable and expendable material necessary for all operator maintenance and operations.

C-3.6.9 Replacement Filters: Filters for fixed facilities are provided in accordance with DLA Energy P-22, Procedures for Requisition, Funding Requests, or Reimbursement of Filter/Coalescer Elements. Contractor furnished refueling vehicle filters are the responsibility of the contractor and included in the Monthly Usage Charge.

C-3.6.10 Grounds Maintenance Equipment and Supplies: The contractor must furnish all powered and non-powered equipment required and necessary to maintain minor cleanup, grass and weed control around contractor-maintained buildings and facilities.

C-3.6.11 Computer Hardware and Software: Both computer hardware and software needed to generate company correspondence, reports, and business forms/documents or for training must be provided by the contractor.

C-3.6.12 Uniforms: All contractor personnel must wear a distinctive company uniform in performance of their duties. The contractor must provide seasonal uniforms. All shirts, coveralls, jackets, coats, and caps must be emblazoned with a readily identifiable company name or logo with the employee's nametag affixed.

C-3.6.13 Safety Equipment: Contractor personnel must wear personal protective equipment and safety equipment applicable to the task/duty being performed and as mandated by 29 CFR 1910.132. If applicable, other equipment such as fire-retardant overalls, safety harnesses and ropes, test equipment for the monitoring of oxygen deficient or explosive atmospheres in confined spaces and breathing apparatuses must be furnished by the contractor. Special safety equipment used in the performance of direct refueling operations by contractor personnel must be provided by the contractor.

Appendix A: Facility Specific Information

- 1. Staffing and Operation Hours:** The contractor must be responsible for providing the entire fuel support. The contractor staffing total must be covered under the MUCG. The contractor must provide sufficient staffing to meet manning hours, operating hours, primary positions, missions, function, and tasks applicable to workloads driven by simultaneous operations as indicated on Table 1, and 2. All full-time employee(s) must consist of a minimum ratio of one, for each listed primary position, as identified in C-1.7 through C-1.7.6, C-1.8 through C-1.8.10, and in this Appendix A. These primary positions must be staffed with as many Full-Time Employees as may be required based on manning/working hours as identified in the tables below. Contractor's staffing approach must consider any simultaneous operational requirements identified in this PWS. There is no provision for augmentation or overtime. One full-time employee must be equivalent to 2080 annual hours, and one part-time employee(s) must be equal to 1040 annual hours. The following table stipulates the typical days of the week and hours of operation for which the contractor must be responsible for providing support/services. The term "As Required" (AR) indicates that the required manning or support coverage is deemed as in scope operations, regardless of the fact, such manning/support coverage is outside the typical hours listed below and will be provided by contractor under the Monthly Usage Charge CLIN at no additional cost to DLA Energy. The customer(s) will provide schedules of applicable flights, exercises, deployments, and other scheduled events. However, the contractor must be ready and able to support any changes to such schedules and fueling operations, should fueling operations (including an increase in manning/support coverage on any weekday or weekend), or fluctuations in the daily start/stop times, such as hot pit or bulk receipts, at no additional cost to DLA Energy. The customer(s) must, at the earliest opportunity, provide the contractor notice of such changes. The table does not dictate or account for pre-operations equipment inspections, quality surveillance, or maintenance requirements, nor does it indicate the total count of staffing required. The contractor's staffing approach must consider its fueling service obligations, as well as the obligation to monitor and support other DLA Energy or Navy contractors as identified in the PWS.

1. Table 1: Staffing Hours/Hours of Operation:

NAS Kingsville Hours of Operation			
Function	Mon-Thur	Fri.	Sat/Sun/Holidays
Fuel Dispatch Center	0000-2400	0000-2400	A/R*
Aircraft Fuel Servicing Operations			
Truck "Cold" Refueling Operations	0000-2400	0000-2400	A/R*
Truck "Hot" Refueling Operations Pantograph 1&2 (Dual Hot Pits)	0830-2000**	0830-2000**	A/R*
Truck "Hot" Refueling Operations Pantograph 1 or 2 (Single Hot Pits)	2000-2230**	2000-2230**	A/R*
Ground Support Equipment	0700-1600	0700-1600	
Fuel Inventory and Accounting	0700-1600	0700-1600	
Bulk Storage Operations	0700-1600 (A/R*)	0700-1600 (A/R*)	
Fuel Laboratory/Quality Surveillance	0700-1600 (A/R*)	0700-1600 (A/R*)	A/R*

*As Required – see Appendix A and Appendix B definition.

** Only One (1) Pantograph (hot refueling) required after sunset

NALF Orange Grove Hours of Operation			
Function	Mon-Thur	Fri.	Sat/Sun/Holidays
Aircraft Fuel Servicing Operations			
Truck “Cold” Refueling Operations	0800 - 1700	0800 - 1700	A/R*
Truck “Hot” Refueling Operations Pantograph 1	0800 - 1700	0800 - 1700	A/R*

*As Required – see Appendix A and Appendix B definition.

Recognized holidays:

New Year’s Day: 1 January
 Martin Luther King’s Birthday: 3rd Monday in January
 President’s Day: 3rd Monday in February
 Memorial Day: Last Monday in May
 Juneteenth: 19 June
 Independence Day: 4 July
 Labor Day: 1st Monday in September
 Columbus Day: 2nd Monday in October
 Veterans Day: 11 November
 Thanksgiving Day: 4th Thursday in November
 Christmas Day: 25 December

NOTE (1): If the holiday falls on Saturday—the previous Friday must be observed as the holiday. If the holiday falls on Sunday—the next Monday shall be observed as the holiday.

NOTE (2): Fuels Operations must operate during normal or required extended hours of operation and on observed holidays unless authorized to close by the Wing/Base Commander or designee. If closed, standby personnel must be identified to Base Operations and Security Forces and be available to respond within 2 hrs.

Table 2-7: Site Specific Information**2. Storage:**

TANK	STORAGE	PRODUCT	TYPE
Orange Grove			
001	25,000 USG (595 BBLs)	F-24	Underground storage tank (UST)
002	25,000 USG (595 BBLs)	F-24	Underground storage tank (UST)
003	25,000 USG (595 BBLs)	F-24	Underground storage tank (UST)
Kingsville			
5723A	840,000 USG (20,000 BBL)	F-24	Aboveground Storage Tank (AST)
5723B	840,000 USG (20,000 BBL)	F-24	Aboveground Storage Tank (AST)
5723C	840,000 USG (20,000 BBL)	F-24	Aboveground Storage Tank (AST)

3. Throughput and Receipt: NAS Kingsville Projections

Years	Product	Annual Issue Gallons (GALs)	Annual Receipt Gallons (GALs)	Annual Defueling Gals	Issue Mode	Receipt Mode
2025	F-24 (JAA)	5,715,774	6,362,403	112,299	Refueler / Pantograph	Tanker Truck
2024	F-24 (JAA)	5,151,080	4,471,535	114,218	Refueler / Pantograph	Tanker Truck
2023	F-24 (JAA)	5,724,615	5,494,783	108,920	Refueler / Pantograph	Tanker Truck

NALF Orange Grove Projections

Years	Product	Annual Issue Gallons (GALs)	Annual Receipt Gallons (GALs)	Annual Defueling Gals	Issue Mode	Receipt Mode
2025	F-24 (JAA)	224,131	231,015	0	Refueler / Pantograph	Tanker Truck
2024	F-24 (JAA)	503,541	532,439	0	Refueler / Pantograph	Tanker Truck
2023	F-24 (JAA)	485,719	477,357	0	Refueler / Pantograph	Tanker Truck

4. Laboratory Samples:

Year	Product	Location	C-Test	Monthly Average
2025	F-24 (JAA)	Kingsville	3,575	297
		Orange Grove	870	73
2024	F-24 (JAA)	Kingsville	3,224	269
		Orange Grove	593	49
2023	F-24 (JAA)	Kingsville	3,086	257
		Orange Grove	421	35

5. Home Station Squadrons and Aircraft:

Squadron/Unit	Type Aircraft	Number Assigned	Max. Fuel Load	Average Refuel
VT-21 Redhows	T-45 Goshock	46	443	320
VT-22 Golden Eagles	T-45 Goshock	46	443	320
Transit Line	Various	None	Various	Various

6. Incidental Facilities:

Facility	Description	Qty
5723A	Bulk Storage Tank 101 20,000 BBL AST	1
5723B	Bulk Storage Tank 102 20,000 BBL AST	1
5723C	Bulk Storage Tank 103 20,000 BBL AST	1
T-104	Reclaimed Fuel Storage Tank (at 5722)	1
5726	Tanker Truck Offload Facility	3
5722OW	Oil Water Separator/Containment Basin	3
5722	POL Operations Building/Fuels Lab	1
5722GI	Emergency Generator Building 5722	1
5722B	POL Pedestrian Bridges (Access to Tanks) 5722	5
5724C	POL Security Fencing	1
5725D	POL Security Lighting	All
5722A	POL Sidewalk	All
5725B	POL Paved Roads	All
5725C	POL Unpaved Roads	All
5722	Pump and Filter Separator Shelter Facility	1
5725	Refueler Load Facility 4777 area	2
5725A	Canopy Refueler Load Facility 4777 area	1
4777	Contractor Operations Building	1
5727	Filter Separator Shelter 4777 area	1
4777OW	Oil Water Separator/Containment Basin	1
4777C	Refueler Maintenance facility and Canopy	1
5724A	Storage Building 4777 area	1
5724B	Storage Building 4777 area	1
T403	Reclaimed Fuel Storage Tank (at 4777)	1
4777B	Refueler Parking Area	1
200604	POL Above Ground Piping	All
0001 - 0003	Tank, 25,000 gallon, Horizontal Steel, underground storage tank (UST)	3

7. Incidental Facilities/Equipment:

Facility	Description	Quantity
	FMD Equipment:	
4777	Computer	2
4777	Monitors	2
4777	Printer	1
4777	APC Devise	2
	NMCI:	
4777	Computer	3
5722	Computer	2
Building 26	Stand Alone Computer Orange Grove	1
	Printer Orange Grove	1
	Laboratory Equipment:	
	Combined/Contaminated Fuels Detector(CCFD) 2 EA NASKV and NAS OG	4
	AEL Water Detector Back-up Tester	1
	B-2 FSII Test Kit 1 EA NASKV and NAS OG	2
	Flashpoint tester 1 EA NASKV and NAS OG	2
	Gammon Field Test Kit	0
	Conductivity Meter	2
	Calibrated Thermometers	2
	Dishwashers, NASKV	1
	Hydro-Light Water Test Kit (1) Each Location	2
	Hydro-Light Water Test Kit Back-up Units (COR Office)	2
	Water Detector Pad (1) Each Location Holders	2
	Water Detector Pad Back-up Units (COR Office) Holders	2
	Hydrometer (1) Each Location	2
	Pensky-Martin Flash Point Tester (Back-Up Unit Facility 5722)	1
Facility 15E	Kingsville Airfield – Navy Portable Pantograph	2
	Orange Grove Airfield – Navy Portable Pantograph	1

Base Operating Services:

<u>Fire Suppression Equipment:</u> Except for contractor-furnished extinguishers mounted on vehicles, all fire suppression equipment, such as, fire extinguishers or portable/installed fire suppression equipment will be provided and maintained by the Base Fire Department. The Base Fire Department will establish the quantity and type of fire suppression equipment on station within the Fuel Management facilities.
<u>Telephone Services:</u> The tenant and base communication office must provide on base telephone services, DSN, and on-station emergency lines, Area Network (LAN) connections, and equipment required and necessary to conduct official business, such as, BSM-E input.
<u>Utilities:</u> The tenant and base energy resources must provide electricity, natural gas/propane heating/power production fuels, water, and sewage services as required for the health and welfare of contract personnel that occupy facilities provided by the base.
<u>Refuse Collection:</u> The tenant and base supporting services must provide refuse collection. Refuse placed in refuse containers by the contractor must be limited to that generated at the contracted location in the performance of this contract.
<u>Grounds Maintenance:</u> The tenant and base supporting services must provide grounds maintenance, except for those grounds' maintenance tasks specified in the PWS. Ground maintenance inside the fuel facilities security fence line is performed by the contractor.
<u>Emergency Medical Service:</u> The tenant and base supporting services must provide the emergency medical service limited to first responder emergency medical services as available through the U.S. Navy Branch Medical Section.
<u>Postal/Mail Distribution:</u> The tenant and base supporting services must provide access to and postage for the United States Postal Service and United Parcel Service for official mail (mailing to a DoD agency) generated because of performance of this contract. The tenant and base supporting services must also provide on-installation distribution of mail. Correspondence (mail to) with the corporate office, vendors, financial institutions, and the like, as well as with employees, must be a contractor expense.
<u>Fuel Products:</u> Limited to those products stocked and issued on base, the contractor may utilize base fuel facilities to purchase fuel at established DLA Energy current standard price for their fuel servicing equipment, trucks, and tractors identified as fuel servicing equipment IAW FAR 51 and the terms of the contract. The contractor must first establish a Fuel Purchase Agreement (FPA) with DLA Energy to purchase petroleum products in accordance with DLA Energy I-3 "DEFENSE ENERGY SUPPORT CENTER FUEL PURCHASE AGREEMENT PROGRAM".
<u>Forms and Documents:</u> The Navy or DLA Energy will provide the necessary forms.
<u>Automated System Chips, Keys, and Cards:</u> DLA Energy will provide all hardware, software, and programmable chips, keys, and cards applicable to automated services stations/product dispensing systems.
<u>Safety Data Sheets (SDS):</u> The appropriate agency will provide SDS for products furnished.

Appendix B: Definitions, Acronyms, and Abbreviations

Accounting: The manipulation of inventory, receipt, and issue data to portray an accurate record of daily events regarding the purchase and sale of products, the adjustment of inventories, and the capture of information in the form of manual records and computer files.

AFHE: Automated Fuel Handling Equipment

AFHS: Automated Fuel Handling System

AFSS: Automated Fuel Service Station

ANSI: American National Standards Institute

API: American Petroleum Institute

AR: As Required. According to the need of providing fuel support for in-scope fueling requests outside the typical Manning and Operating Hours. The contractor must staff accordingly. This is a situational workload should the need arise and requires reasonable contractor planner scheduler coordination.

ASA: Anti-static Additive

ASME: American Society of Mechanical Engineers

ATM: Assistant Terminal Manager, the person assigned as the assistant to the TM and the acting Terminal Manager in the absence of the TM.

ATG: Automatic Tank Gauge

AST: Aboveground Storage Tank

ASTM: American Society for Testing and Materials

Barrel: A barrel is equal to 42 U.S. gallons.

BPH: Barrels per Hour

Biodiesel: Fuel comprised of 20 percent vegetable oils or animal fats blended with petroleum diesel as outlined in ASTM D7467.

CEO: Corporate Executive Officer, the person at the corporate level with the authority to make fiscal, management, and administrative decisions concerning the contract. He/she must have a complete understanding of the terms, conditions, and requirements of the contract and must be knowledgeable of fuel management and operations to the extent outline within the specific contract.

CDR: Contract Discrepancy Report

CFE: Contractor Furnished Equipment

CFR: Code of Federal Regulations

CLIN: Contract Line Item Number

CMMS: Computerized Maintenance Management System

CNRSE: Commander, Navy Region, Southeast

Collateral Duties: Additional duties, tasks, and work assigned to or undertaken by a person within the management structure, a person of a specific skill category, or one assigned to a specific function that infringe on one's commitment, ability, or availability to carry out his or her primary duties. The term does not however preclude management, skilled labor, or specifically assigned personnel from performing single event or short term tasks for which they are qualified, i.e., assist in the receipt of product, service at aircraft by truck, or other crucial tasks requiring immediate or emergent attention required to ensure mission success.

Contract Award Date: The date entered in block 20C, Date Signed, of the Standard Form 26, Award/Contract. This date may differ from the start/performance date. Note that elements of the solicitation/contract are linked to this date.

Contract Start Date: The contract start date, performance date, or first day of the performance period is the first day of the period cited in block 15 (A through F) of the Standard Form 26, Award/Contract. The start date and performance period may be adjusted by amendment to provide the contractor sufficient lead-time to ready equipment for the contract. In this respect, the award and start dates are linked dates in that one may drive actions of the other.

Contracting Officer (KO): The Contracting Officer is the only individual expressly authorized to enter, administer, change, and terminate contracts. Contracting Officers may bind the government only to the extent of the authority delegated to them through a warrant. The Contracting Officer is the only person authorized to appoint/designate CORs.

Contracting Officers Representative (COR): The local or on-site Navy technical specialist, military or civilian, designated by the Contracting Officer to inspect and accept or reject the supplies and services furnished under a specified contract.

Contractor (KTR): the individual, group of persons, company, group of companies, or corporation specifically named and contracted by/with DLA Energy to fulfill the terms of the specified contract document. The term "Contractor" as used herein refers to the company or corporation as a whole or any individual, manager or assistant, attendant, technician, operator, driver, dispatcher, or laborer who may be acting on behalf of the named Contractor.

DFAMS: Defense Fuel Automated Management System

DFSP: Defense Fuel Support Point

DiEGME: Diethylene Glycol Monomethyl Ether, a type of Fuel System Icing Inhibitor (FSII)

DLA-E: Defense Logistics Agency Energy

DOD: Department of Defense

DoW: Department of War

DODAAC: Department of Defense Activity Address Code (also see UIC)

DoT: Department of Transportation

DSN: Defense Switching Network (telephone communications system)

E85: Gasoline, Automotive (Fuel, Ethanol) composed of at least 85% ethanol

EBS: Enterprise Business System

EDP: Emergency Distribution Plan

EGME: Ethylene Glycol Monomethyl Ether, a type of Fuel System Icing Inhibitor (FSII)

EPA: Environmental Protection Agency

EPOS: Electronic Point of Sale

FA, Fuel Accountant: A person who is capable and cleared for computer related work within FMD, FES, and other systems as

may be applicable

FAR: Federal Acquisition Regulations

FES: Fuels Enterprise Server

FMD: Fuels Manager Defense

FSII: Fuel System Icing Inhibitor

FDSO: Fuel Distribution System Operator, a person whose primary skill and function is to operate (manipulate system components) and maintain bulk storage facilities at a preventative and operator maintenance level, perform operator level quality surveillance and inventory operations, and as may be required, document all such activities.

FMSR: Fuels Maintenance and Service Representative

Fuel Additives: Chemicals added to petroleum products to inhibit undesirable characteristics.

FOR: Fuel Oil Reclaimed

FRP: Facility Response Plan

GOCO: Government Owned Contractor Operated

iNFADS: internet Navy Facilities Asset Data Store

ISSA: Inter-Service Support Agreement

LT: Laboratory Technician, a person whose skills and function is to sample and test petroleum products, maintains the fuels laboratory, and document/report on quality surveillance issues.

MILCON: Military Construction

MPMS: Manual of Petroleum Measurements Standards

NATOPS: Naval Air Training and Operating Procedures Standardization

NAVFAC: Naval Facilities Engineering Command

NFPA: National Fire Protection Agency

NPDES: National Pollution Discharge Elimination System

NSN: National Stock Number

NOSC: Navy On-Scene Coordinator

Off Station: A generic term used to stipulate the areas outside the boundaries of a Naval Station, facility, support activity, Marine Corps Base, Air Station, or location not requesting routine manning on PWS.

OPA: Oil Pollution Act

OSHA: Occupational Safety and Health Administration

Operational Maintenance: As the term implies operational maintenance is performed by the operator and is the care and minor maintenance of equipment using procedures that do not require detailed technical knowledge of the equipment's or system's function and design. Maintenance that is regularly performed to preserve and maintain equipment, apparatus, or facilities in such condition that they may be effectively used for their intended purpose. This category of operational

maintenance normally consists of inspecting, cleaning, servicing, preserving, lubricating, and adjusting, as required. Such maintenance may also include minor parts replacement that does not require the person performing the work to have highly technical skills or to perform internal alignment. Operator maintenance is that work accomplished during routine inspections and during system use/operation. Operator maintenance may be, but is not necessarily limited to, work such as the replacement of ground wires, plugs, and clips, the replacement of O-rings and gaskets, the tightening of nuts, bolts, and screws to prevent leakage, or corrosion control and spot painting. Operator maintenance is normally limited to those actions taken by qualified system operators using common hand tools.

PA: Property Administrator

Performance of Services: A measurement of time, from the call for services is received by the Contractor Dispatch Center to the time the fuel servicing equipment or operator arrives at the aircraft, vehicle, facility, or equipment to be serviced. Note that there may be variances between scheduled, unscheduled, weekly, and week-end hours of operation towards the support for services

POS: Peacetime Operating Stock

POV: Privately Owned Vehicle

Preventive Maintenance (PM): Preventive maintenance is a program of recurrent periodic or cyclic scheduled work designed to preserve and maintain equipment, apparatus, or facilities in such condition that they may be effectively used for their intended purpose.

PSI: Pounds per Square Inch

PWC or D: Public Works Center or Department

PWS: Performance Work Statement

QASP: Quality Assurance Surveillance Plan

Recurring Maintenance: Maintenance inspections and services which are on a fixed schedule. This schedule will come from UFC 3-460-03, Manufacturer Recommendations, API Requirements, Federal, State, Local Law, Code or Regulation.

RMMR: Recurring Maintenance and Minor Repair

SDS: Safety Data Sheet

SOP: Standard Operating Procedure

SOW: Statement of Work

SPCC: Spill Prevention Control and Countermeasure Plan

SRM: Sustainment, Restoration and Modernization

System Maintenance (SM): SM is normally performed by trained personnel of base facility maintenance, facility operating contracts, or maintenance contracts for recurring maintenance and repair.

TM: Terminal Manager, the person assigned to manage the Fuel Services Contract activities at locations categorized as a Naval Air Station (NAS), Naval Air Facility (NAF), Naval Station (NS), Naval Base (NB), Naval Support Activity (NSA), Naval Amphibious Base (NAB), Navy Submarine Base (NSB), Marine Corps Air Station (MCAS), Marine Corps Base (MCB) and other small activities supporting various types of aircraft and small water borne craft.

UFC: Unified Facilities Criteria

USCG: United States Coast Guard

UST: Underground Storage Tank

Appendix C: Reference Documents

The following is a list of most recent references directly and indirectly cited within the PWS. It is not all-inclusive and does not cite local base/facility or command instructions. It is the responsibility of the contractor to ensure full compliance with all DoD, Federal, Navy, State, and Local References and Laws. On contract award, the contracted activity will provide a copy of applicable DoD, USN, and local instructions required under this contract. All other references, federal and state code, professional, association, and industry standards and guidelines must be provided by the contractor.

Reference	Title
29 CFR	Labor
29 CFR Part 1910	Occupational Safety and Health Standards
32 CFR Part 187	Environmental Effects Aboard of Major Department of Defense Actions
40 CFR 112	Oil Pollution Prevention
49 CFR 171	Hazardous Materials Regulations; General information, regulations, and definitions
49 CFR 172	Hazardous materials table, special provisions, hazardous materials communications, emergency response information, and training requirements
49 CFR 173	Shippers--general requirements for shipments and packaging
49 CFR 178.345	General design and construction requirements applicable to Specification DOT 406
49 CFR 178.346	Specification DOT 406; cargo tank motor vehicles
49 CFR 180	Continuing Qualification and Maintenance of Packaging
49 CFR 382	Controlled Substance and Alcohol Use and Testing
49 CFR 383	Commercial Driver's License Standards; Requirements/Penalties
49 CFR 387	Minimum Levels of Financial Responsibility for Motor Carriers
49 CFR 390	Federal Motor Carrier Safety Regulations; General
49 CFR 391	Qualification of Drivers
49 CFR 392	Driving of Commercial Motor Vehicles
49 CFR 393	Parts and Accessories Necessary for Safe Operation
49 CFR 395	Hours of Service for Drivers
49 CFR 396	Inspection, Repair and Maintenance
NFPA 385	Tank Vehicles for Flammable and Combustible Liquids
NFPA 407	Aircraft Fuel Servicing
EI Bulletin 1529	Aviation Fuel Hose
EI Specification 1581	Specifications and Qualifications Procedures for Aviation Jet Fuel Filter Separators
10 U.S.C.	United States Code, Title 10
Public Law 101-508	Pollution Prevention Act of 1990
DoDD 1100.04	Guidance for Manpower Management
DoDI 1100.22	Policy and Procedures for Determining Workforce Mix
DoDI 3020.41	Operational Contract Support (OCS) Outside the United States
DoDD 3020.49	Program Management for the Planning and Execution of Operational Contract Support
DoDM 4140.25	DoD Management of Bulk Petroleum Products, Natural Gas, and Coal
DoDI 4715.02	Regional Environmental Coordination

Reference	Title
DoDI 4715.17	Environmental Management Systems
DoDI 4150.07	DoD Pest Management Program
DoDI 4715.06	Environmental Compliance in the United States
DoDI 4165.03	DoD Real Property Categorization
DoDI 5000.64	Accountability and Management of DoD Equipment and Other Accountable Property
DoDI 1015.15	Establishment, Management, and Control of Non-Appropriated Fund Instrumentalities and Financial Management of Supporting Resources
DLA I & P	DLA Energy Instructions and Policy Notices
MIL-STD-3004	Quality Surveillance Handbook for Fuel, Lubricants and Related Products
NAVAIR 00-80T-109	Aircraft Refueling NATOPS Manual
NAVAIR 00-80T-124	Airfield Operation Manual
NAVFAC P-300	Management of Transportation Equipment
NAVFACINST 11013.40	Project Partnering on Facilities Construction Projects
NAVFAC Manual P-501	Condition Based Maintenance Management (CBMM) Manual
NAVFAC NFAS	Naval Facilities Acquisition Standards (NFAS)
NAVSO P-1000	Department of the Navy, Office of the Assistant Secretary of the Navy (Financial Management and Comptroller)
OPNAVINST 5450.339	Mission, Function, and Tasks of Commander, Navy Installation Command
OPNAVINST 5450.348	Mission, Function, and Tasks of Commander, Naval Facilities Engineering Systems Command (COMNAVFACSYSCOM)
OPNAVINST 5450.349	Mission, Functions, and Tasks of Commander, Naval Supply System Command (COMNAVSUPSYSCOM)
OPNAVINST 5440.77	Missions, Functions, and Tasks of United States Fleet Forces Command
OPNAVINST 11010.20	NAVFAC Facility Projects
OPNAVINST 5420.70	Mission, Functions and Tasks of the Board of Inspection and Survey (INSURV)
OPNAVINST 4790.2	The Navy Aviation Maintenance Program (NAMP)
OPNAVINST 4790.4	Maintenance and Material Management System Policy
OPNAVINST 11014.3	Facilities Maintenance Unit Identification Code Holder Responsibilities
OPNAVINST 4790.16	Condition Based Maintenance Plus Policy
OPNAVINST 4000.84	Support Agreements
OPNAVINST 4020.27	Capitalized Bulk Fuel Tank Management at Navy Installations
OPNAVINST 5530.14	Navy Physical Security and Law Enforcement Program
OPNAVINST 5090.1	Environmental Readiness Program
OPNAV Manual 5090.1	Environmental Readiness Program Manual
OPNAVINST 5100.23	Safety and Occupational Health Program
OPNAVINST 11010.40	Encroachment Management Program
OPNAVINST 6250.4	Navy Pest Management Programs
UFC 3-460-01	Design: Petroleum Fuel Facilities

Reference	Title
UFC 3-460-03	Operation & Maintenance: Maintenance of Petroleum Systems
DLA Energy Program Management SOP	Government Owned, Contractor Operated (GOCO) Maintenance and Repairs Standard Operating Procedures (SOP)
DLA Energy QASP	Quality Assurance Surveillance Plan

Appendix D: Common Access Card (CAC) Requirements

Performance under this contract must require all contractors to obtain a Common Access Card (CAC) with Public Key Infrastructure (PIV) Certificates to access DoD and DLA Energy Business Systems to perform required job functions within these applications. The contractor must complete and comply with the following steps to obtain, control, and turn-in Government-issued CACs, as well as establish procedures to always control and account for contractor CACs. This process is only for the issuance and accountability of CACs. Contractors may be required to provide additional forms and follow additional procedures for other forms of access and/or background/security checks depending on local site/installation requirements.

1. The Contractor has each employee requiring a CAC complete and sign Sections I and II of the DD Form 1172-2. The instructions for completing the DD Form 1172-2 are located at <https://www.cac.mil/Portals/53/Documents/1172-2-Instructions.pdf>
 - a) For Section II, Block 22 - If the Contractor employee signs and the DD Form 1172-2 it is then forwarded by the Contractor. This provides verification for the employee information. If the Contractor is submitting a DD Form 1172-2 for him/herself (e.g., the owner), with no higher authority above them for verification, then the signature in Block 22 must be notarized to verify identity.
2. The Contractor forwards the DD Form(s) 1172-2 via hand-carry, secure mail, or encrypted email to (NOTE: The Contractor may forward these forms individually or as a group):
 - a) The COR for the contract, if a COR was designated
 - b) The KO for the contract, if no COR was designated.
3. Each Contractor employee must verify his/her account information upon receipt of an email from the Government containing a username and password for the Mission Partner Identity Credential Access Management (MP ICAM) Portal.
4. Each Contractor employee will receive an email via MP ICAM when his/her account has been approved. The email will notify the employee to obtain a government-issued CAC from the nearest Real-Time Automated Personnel Identification System (RAPIDS) office. The email will also provide a link that identifies the locations of RAPIDS offices.
5. Each Contractor employee must obtain his/her issued CAC from the RAPIDS office within 90 days from CAC application approval email sent from MP ICAM.
6. The Contractor, within one (1) business day of issuance, provides written notice via email to the COR (or the KO, if no COR was designated) for each Contractor CAC issued identifying the Contractor employee's name, the date of issuance, and the date of expiration of the CAC. This notification may be made individually for each Contractor employee or together for a group of Contractor employees.
7. The Contractor establishes procedures to always control and account for Government-issued Contractor CACS, to include the following:
 - a) Ensure Contractor CACs issued for this contract are only used for the purpose of performing under this contract.

- b) Ensure Contractor CACs are secured in a manner that precludes unauthorized use and that recognizes the CAC is the property of the U.S. Government.
 - c) Ensure Contractor employees do not abuse or place holes in their CACs.
 - d) Ensure Contractor employees do not display their CACs in public.
8. If a Contractor CAC is lost or stolen:
- a) The Contractor employee must immediately notify the Contractor that the Contractor CAC has been lost or stolen.
 - b) The Contractor must immediately notify the COR (or the KO, if no COR was designated), detailing the circumstances regarding the lost or stolen Contractor CAC, as follows:
 - i) In person, followed within one (1) business day by a written notice via email, or
 - ii) In writing, via email, or
 - iii) By telephone, followed within one (1) business day by a written notice via email.
 - c) The Contractor must report the lost or stolen CAC card to the local DLA Police/host installation police, who will provide the Contractor with a police report. If there is no local DLA Police/host installation police, or no police report is provided, the Contractor must provide information to the COR/KO, as applicable, detailing the circumstances of how the CAC was lost or stolen. The COR/KO will provide a memorandum for the Contractor employee to support the issuance of new CAC.
 - d) The Contractor has the Contractor employee bring the report/memorandum to the nearest RAPIDS office. If the CAC can be reissued within 24 hours, bring the report/memorandum to the nearest CAC office for reissue. If the CAC cannot be reissued in 24 hours, follow the steps for a new CAC, beginning at Step 1.
9. If the expiration date for a Contractor CAC is prior to completion of the contract and the Contractor employee is to continue working under the contract and still requires a CAC, the Contractor:
- a) Notifies the COR as follows:
 - i) In person, followed within one (1) business day by a written notice via email, or
 - ii) In writing, via email, or
 - iii) By telephone, followed within one (1) business day by a written notice via email.
 - b) No less than two (2) weeks prior to the current CAC's expiration date, completes and complies with the steps above beginning with Step 2 for issuance of a new Contractor CAC for the employee.
 - c) Brings the expiring CAC to the RAPIDS office for turn-in and receives new CAC.
 - d) Notifies the COR once a new CAC has been issued.
10. The Contractor/Contractor employee turns in any found CACs immediately, via hand- carry, to the nearest Federal law enforcement office.
11. The Contractor immediately collects all Contractor CAC(s) from the Contractor employee(s) at:
- a) Contract completion or termination
 - b) Termination/Reassignment of an employee (this includes any reason the employee is no longer working for the Contractor under the contract or otherwise no longer requires a CAC)
12. The Contractor:
- a) For contract completion or termination – within one (1) business day after collecting the Contractor CAC(s), arranges for turn-in via one of the below methods:

13. If the COR/CO is co-located or near enough that in-person transfer of CACs can be arranged, the Contractor:
 - a) Arranges to meet the COR (or the KO, if no COR was designated) to turn-in the collected Contractor CAC(s).
 - b) Hand-carries all collected Contractor CACs for turn-in to meet the COR (or the KO, if no COR was designated).
 - c) Completes and signs the Government-Issued Contractor CAC Turn-In Receipt with the COR (or the KO, if no COR was designated). The Contractor is provided a copy of the receipt.
14. If in-person transfer of CAC cannot be arranged, the Contractor:
 - a) Sends, via certified mail, the CACs to the COR/KO. The Contractor includes in the package the Government-Issued Contractor CAC Turn-In Receipt, with signed acknowledgement of Contractor turn-in.
 - b) Notifies COR/KO that CACs have been sent via certified mail.
 - c) Receives a completed copy of the receipt from the COR/KO once the COR/KO has received the CACs.
 - d) For termination/reassignment of an employee:
15. Immediately notifies the COR (or the KO, if no COR was designated) that the employee is no longer working for the Contractor under the contract or otherwise no longer requires a CAC, as follows:
 - a) In person, followed within one (1) business day by a written notice via email, or
 - b) In writing, via email, or
 - c) By telephone, followed within one (1) business day by a written notice via email.
16. Follows the turn-in procedures above for contract completion or termination, as applicable.
 - a) If the contractor leaves the contract without turning in CAC card(s), the COR can put note on the CAC turn-in sheet.
 - b) RAPIDS office locations will NOT sign the CAC turn-in sheet for contractors. COR must retain copy of CAC turn-in sheet for audit purposes.
17. Contractor Reporting Requirements: The Contractor is required to submit, on a monthly basis, to the COR (or the KO, if no COR was designated) a report of all employees working on the contract who have been issued CAC cards and a verification of whether each listed employee still requires a CAC. The report must note where changes have occurred (additions or deletions) since the previous month. Contractor employees who already have a CAC related to another DLA or DoD contract must be included in the monthly report. The Contractor must note the issuing organization and the CAC expiration date. Contractor is still responsible for notifying the COR/KO when the individual is no longer working under the subject contract.
18. The above procedures have been established as a DLA security measure. Contractors are advised that failure to comply with any of the above requirements will be considered a violation of the terms and conditions of the contract and the KO may take action to remedy such violations. Specifically, failure to safeguard, follow these procedures, including reporting requirements, or turn-in CACs within the established timeframes may result in the following actions, which are in addition to other actions the KO may take under governing law and regulation and the terms and conditions of the contract:
 - a) Immediate work stoppage (issuance of a stop work order), not to be lifted until resolution of

- b) Disapproval of invoices and delay of payment
- c) Withholding of final payment (in accordance with FAR 52.204-9)
- d) Documentation of CAC Non-Compliance in the Contractor Performance Assessment Reporting System (CPARS)