

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

DESCRIPTION / SPECIFICATIONS / STATEMENT OF WORK

SPECIFICATIONS: Construction guidance used to fulfill this Simplified Acquisition of Base Engineering Requirements (SABER) contract shall adhere to the construction standards established by the specifications provided in the solicitation and meet the requirements of the Dyess Installation Facilities Standards (IFS).

STATEMENT OF WORK

- C 101. PROJECT DESCRIPTION
- C 102. CONTRACTOR MOBILIZATION & PERFORMANCE
- C 103. TECHNICAL SPECIFICATIONS
- C 104. REGULATIONS
- C 105. MATERIALS FOR DESIGN
- C 106. EQUIPMENT/SUPPLIES
- C 107. PRESERVING HISTORICAL AND ARCHAEOLOGICAL FINDS
- C C 108. STANDARD PRODUCTS
- C 109. PROJECT MANAGEMENT AND SUPERVISION
- C 110. APPLICATION OF WAGE RATES AND FRINGE BENEFITS
- C 111. SAFETY
- C 112. PARTNERING

GENERAL CONDITIONS

- C 201. LOCATION OF STAFF
- C 202. STAGING/STORAGE AREA
- C 203. PASS AND IDENTIFICATION ITEMS
- C 204. CONTRACTOR'S TELEPHONE
- C 205. EMPLOYEE STANDARDS
- C C 206. PROHIBITED ITEMS
- C 207. GOVERNMENT FURNISHED EQUIPMENT/MATERIALS
- C C 208. GOVERNMENT LIABILITY
- C 209. WORK
- C 210. AIRFIELD REQUIREMENTS
- C C 211. UTILITIES SERVICES
- C 212. SURVEY MARKERS

TASK ORDER PROCEDURES

- C 301. CONTRACT ADMINISTRATION
- C C 302. ORDERING PROCEDURES
- C 303. NON-PRICED WORK
- C 304. SABER PROJECT ESTIMATING
- C 305. PREPARATION OF PROGRESS SCHEDULES AND REPORTS
- C 306. MEETINGS AND CONFERENCES
- C 307. TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER
- C C 308. APPROVED EQUAL
- C 309. RECORD DRAWINGS
- C 310. DIFFERENCES IN DRAWINGS
- C 311. ACCEPTANCE
- C 312. CLOSEOUT OF TASK ORDER
- C 313. CONTRACTOR-FURNISHED EQUIPMENT DATA
- C 314. REQUEST FOR INFORMATION (RFI) PROCESS

Statement of Work – Attachment 1 - page 1 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

C 315. WITHHOLDING FOR DEFICIENT WORK

SUBMITTAL PROCEDURES

C 401. SUBMITTAL CLASSIFICATIONS
C 402. APPROVED SUBMITTALS
C 403. DISAPPROVED SUBMITTALS
C C 404. GENERAL
C 405. MATERIAL APPROVAL SUBMITTAL FORM (AF Form 3000)
C 406. CONTROL OF SUBMITTALS
C 407. GOVERNMENT APPROVED SUBMITTALS
C 408. MATERIAL USE SUBMITTAL

QUALITY CONTROL

C 501. REFERENCES
C 502. PAYMENT
C 503. GENERAL
C 504. QUALITY CONTROL PLAN
C 505. QUALITY CONTROL ORGANIZATION
C 506. SUBMITTALS
C 507. CONTROL
C 508. TESTS
C 509. COMPLETION INSPECTION
C 510. DOCUMENTATION
C 511. NOTIFICATION OF NONCOMPLIANCE

WORK IN CONTROLLED AREAS

C 601. GENERAL ENTRY PROCEDURES
C C 602. RESTRICTED AREA
PROCEDURES
C 603. FREE ZONE PROCEDURES
C 604. FLAME-PRODUCING DEVICES
C 605. EQUIPMENT STOCKPILES AND CONSTRUCTION DEBRIS
C 606. CONTRACTOR OPERATIONAL FACILITIES
C 607. MISCELLANEOUS
C 608. DRAINAGE
C 609. EMERGENCY OUTAGES
C 610. SECURITY FENCE WORK
C 611. SECURITY LIGHTING/ COMMUNICATION OUTAGES

ENVIRONMENTAL

C 701. ENVIRONMENTAL REFERENCES
C 702. HAZARDOUS MATERIAL SUBMITTAL REQUIREMENTS
C 703. HAZARDOUS WASTES DISPOSAL REQUIREMENTS
C 704. INSPECTION LIABILITY
C C 705. POLLUTION
ABATEMENT
C 706. POLICY FOR STORAGE OF HAZARDOUS MATERIALS ON CONSTRUCTION SITES
C 707. UNEXPECTED ASBESTOS ON CONSTRUCTION (RENOVATION/DEMO)
C 708. UNEXPECTED HAZARDOUS SUBSTANCES
C 709. DEMOLITION

Statement of Work – Attachment 1 - page 2 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

CYBERSECURITY AND NETWORK PROTECTION

**C 801. NETWORK AND INFORMATION SYSTEMS
SECURITY**

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

C 100. STATEMENT OF WORK

C 101. PROJECT DESCRIPTION: All work shall be in conformance with the requirements of the contract including, but not limited to, furnishing all materials, labor, plant, tools, equipment, transportation, supervision, management, and other services (including engineering/technical design support), items, and incidentals necessary for the successful completion of each issued delivery order. This contract is for a broad range of maintenance, repair, and minor construction on Dyess Air Force Base. The contract is a firm fixed price, Indefinite Delivery, Indefinite Quantity (IDIQ) for Simplified Acquisition of Base Engineer Requirements (SABER), consisting of the four major elements as follows:

- C 101.1. Detailed delivery orders specifications encompassing most aspects of Base Civil Engineer work
- C 101.2. Units of measure and corresponding prices for each of the specifications and delivery order
- C 101.3. General and Special Provisions
- C 101.4. No monetary amount shall be obligated by the award of the contract. Monetary amounts are obligated by the issuance of task orders only.

C 102. CONTRACTOR MOBILIZATION AND PERFORMANCE: Contractor shall be fully operational with 30 days of IDIQ award, capable of responding to request for proposal requirements and commencing work. Commencing of work shall be specified on each individual task order outlined in the Notice to Proceed issued by the Contracting Officer. Work shall be prosecuted diligently to ensure completion by the date specified in the contract.

- C 102.1. Post-Award Readiness: No later than thirty (30) calendar days after the award of the base contract, the Contractor shall be fully mobilized and ready to perform. This readiness is defined as having the necessary personnel, systems, and procedures in order to successfully prepare proposals and manage task orders.
- C 102.2. Commencement of Task Order Work: The official start date for work on any individual task order shall be the date specified in the Notice to Proceed (NTP) issued by the Contracting Officer for that order.
- C 102.3. Diligent Prosecution: The Contractor shall diligently prosecute the work to ensure completion within the period of performance specified in each individual task order.
- C 102.4. The Contractor shall schedule its demolition and new construction activities to ensure a continuous flow of work, minimizing the time that any facility or portion thereof is non-operational. To support this requirement, demolition shall not commence until the Contractor has submitted, and the Contracting Officer has accepted, evidence that all critical and long-lead-time materials required for the follow-on construction phase have been delivered to the site or are otherwise secured. The Government-approved project schedule shall reflect this coordinated sequencing. Any deviation from this plan requires the prior written approval of the Contracting Officer.

C 103. TECHNICAL SPECIFICATIONS: The SABER Technical Specifications shall adhere to the specifications provided in the solicitation (attachment 2) and meet the requirements of the Dyess AFB Installation Development and Design (ID2). These Technical Specifications shall furnish concise industrial and/or commercial standards for maintenance and repair of government facilities.

- C 103.1. The SABER Technical Specifications are numbered and organized by the Construction Specification Institute's (CSI's) Master Format 2020.

C 104. REGULATIONS:

- C 104.1. The Contractor shall comply with all applicable Federal, State, local and Air Force regulations, including supplements pertaining to safety, traffic control, and fire prevention.
- C 104.2. The work under the task orders shall be designed in accordance with the design and construction standards contained in National Fire Protection Code, National Electrical Code, Uniform Plumbing Code,

Statement of Work – Attachment 1 - page 4 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

Architectural Barriers Act; and other applicable Department of Defense and Air Force regulations, federal regulations, State of Texas regulations, manuals, engineering technical letters (ETL's), Unified Facilities Criteria (UFC), energy conservation criteria, Dyess's Technical Specifications and ID2.

C 104.3. The Contractor may view the most applicable Air Force and Corps of Engineer publications as well as some commercial product data information at the following site: <http://www.wbdg.org/> However, the Air Force will not furnish the Contractor reference materials, codes, regulations, or guide specifications. These may be acquired from the Government Printing Office or from other federal agencies.

C 104.4. The latest edition of the following Building Codes shall be used and maintained for all construction under this contract.

C 104.4.1. Engineering Technical Letters (ETL)

C 104.4.2. Unified Facilities Criteria (UFC)

C 104.4.3. Uniform Plumbing Code (UPC)

C 104.4.4. International Building Code (IBC)

C 104.4.5. International Existing Building Code

C 104.4.6. International Mechanical Code

C 104.4.7. International Plumbing Code

C 104.4.8. International Fire Code

C 104.4.9. International Energy Conservation Code

C 104.4.10. NFPA 101, Life Safety Code

C 104.4.11. NFPA 70, 2014 National Electrical Code

C 104.4.12. NESC National Electrical Safety Code

C 104.4.13. ACI 318, Building Code Requirements for Structural Concrete

C 104.4.14. Manual on Uniform Traffic Control Devices (MUTCD)

C 104.5. Should a conflict arise between project requirements, the Unified Facilities Criteria (UFC) shall take precedence. In all other conflicts, the most stringent requirement among the applicable codes, regulations, and specifications shall apply.

C 104.6. All designs performed under this contract shall consider employing green principles established by the Green Building Certificate Institute.

C 105. MATERIALS FOR DESIGN:

C 105.1. Drawings: The Government will furnish copies of available as-built drawings which are pertinent to the facility/area involved in the Statement of Work to the Contracting Officer who, in turn, will provide them to the Contractor.

C 105.1.1. The Government does not guarantee the accuracy or adequacy of the available as-built drawings. The Contractor shall verify, by field investigation, all conditions and information relevant to the project, including dimensions, utilities, prior to the issuance of each delivery order. This confirmation of accuracy shall enhance the quality of the task order's design. The Contractor shall advise the Contracting Officer, or his/her authorized representative, in writing of any discrepancies prior to submitting the proposal. Failure to verify the dimensions and locations shall be at the Contractor's risk and shall not relieve the Contractor from completing the work required by the contract at the price awarded by the Government.

C 105.1.2. Where exact locations are not given in the Statement of Work for the positioning of equipment, devices, and work, they shall be positioned to permit easy access for maintenance and for removal and replacement of component parts. The Contractor is responsible for the coordination and proper relation of the work with the existing surroundings.

C 106. EQUIPMENT/SUPPLIES: The Contractor shall be required to provide to the Government and to maintain the following equipment and programs at the Contractor's expense:

C 106.1. Electronic Format: All electronic correspondence of information outside of e-mail shall be done in Microsoft Word, Excel, Adobe PDF, or AutoCAD.

C 106.2 Publications: The Contractor shall provide the Government with the number of copies indicated below

Statement of Work – Attachment 1 - page 5 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

of the following publications, the latest edition, and any updates, for the life of the contract. If there is a conflict between these codes, regulations, and specifications, the most stringent requirements shall apply at all times. These publications shall be furnished to the Contracting Officer no later than 30 days after contract award.

<u>Copies</u>	<u>Publication</u>
1	Engineering Technical Letters (ETL)
1	Unified Facilities Criteria (UFC)
1	Uniform Plumbing Code (UPC)
1	International Plumbing Code (IPC)
1	International Mechanical Code
1	International Fire Code
1	International Energy Conservation Code
1	NFPA 101, Life Safety Code
1	NFPA 70, 2014 National Electrical Code
1	NESC National Electrical Safety Code
1	ACI 318, Building Code Requirements for Structural Concrete
1	RS MEANS Facilities Construction Cost Data
1	RS MEANS Mechanical Cost Data
1	RS MEANS Plumbing Cost Data
1	RS MEANS Electrical Cost Data
1	RS MEANS Assemblies Cost Data
1	RS MEANS Site Work & Landscape Cost Data
1	RS MEANS Interior Cost Data
1	RS MEANS Concrete & Masonry Cost Data
1	RS MEANS Square Foot Costs

These publications shall remain the property of the government.

C 106.3 Software: The Contractor shall provide one (1) network license for four (4) simultaneous terminals to operate the RS MEANS Data Base and Facility Maintenance and Repair Guides database described above shall be RS MEANS Online Enterprise (the operating system shall be Windows 11 compatible). The software shall remain the property of the Government at the termination of the contract period. The software shall be upgraded yearly at no additional expense to the Government. Software will be installed by local systems administrators on the Civil Engineering server and shall allow multi-user and multi-tasking activities simultaneously. The software will allow the local systems administrator to add negotiated non-prepriced items to the database. RS MEANS Online Software programs will include:

C 106.4.1. Program Training: The Contractor shall provide an RS MEANS Online training seminar within 45 calendar days of contract award, from a certified instructor, for up to 5 Government employees at Dyess AFB. The training shall be a 2-day hybrid course & stand-alone laptops shall be provided by the Contractor. Facility & power shall be provided by the government.

C 106.4.2. Additionally, the training in C 106.4.1 shall be repeated at the beginning of exercised Option Years 1 through 3 within 45 days if execution to ensure that personnel are fully qualified.

C 107. PRESERVING HISTORICAL AND ARCHAEOLOGICAL FINDS: All items having any apparent historical or archaeological interests which are discovered during any construction activities shall be carefully preserved. The Contractor shall leave the archaeological find undisturbed and shall immediately report the find to the Contracting Officer, or his/her designated representative, so that the proper authorities may be notified.

C 108. STANDARD PRODUCTS: Materials and equipment shall be standard products of a manufacturer regularly engaged in the manufacture of such products, which are of a similar material, design, and workmanship. The standard products shall have been in satisfactory commercial and/or industrial use for 2 years prior to use. The 2-year use shall include applications for equipment and materials under similar circumstances and of similar size. The 2 years of use must be satisfactorily completed by a product which has been sold or is offered for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures. Products having less than a

Statement of Work – Attachment 1 - page 6 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

2-year field service record will be acceptable, if a certified record of satisfactory field operation, for not less than 6,000 hours exclusive of the manufacturer's factory or laboratory tests, can be shown. The Contractor shall not purchase "close-out" products that are being discontinued by the manufacturer.

C 109. PROJECT MANAGEMENT AND SUPERVISION:

C 109.1. Project Organization Submittals. No later than fifteen (15) days after contract award, and prior to issuance of the first task order, the Contractor shall submit the following for Contracting Officer approval:

- a) Organizational Chart: A comprehensive chart illustrating the lines of authority for all personnel managing the contract. The chart must identify all key personnel, including the Program Manager, Quality Control Manager, and Site Superintendent(s). It shall clearly show the relationship between on-site staff and off-site support and include direct contact information (cell phone and email) for all individuals. The Contractor shall submit a revised chart within seven (7) days of any personnel change.
- b) Position Descriptions: A detailed description for each key position on the organizational chart. This shall include, at a minimum: a summary of responsibilities, minimum professional qualifications, and a clear definition of the individual's decision-making and financial authority.

C 109.2. On-Site Supervision:

- a) Superintendent Presence: The Contractor shall provide a competent on-site superintendent for each task order. The superintendent must be on the project site at all times when physical work is being performed.
- b) Superintendent Workload Limit: A single individual may not serve as the superintendent for more than five (5) task orders where physical construction is concurrently underway. A separate, equally qualified superintendent shall be provided for each additional group of up to five concurrent projects.
- c) Dedicated Superintendent for High-Value Projects: Notwithstanding the workload limit in paragraph (b), for any single task order, the Contractor shall provide a full-time, dedicated superintendent who shall not be assigned to any other project for the duration of that task order.
- d) Superintendent Authority: The on-site superintendent must have full authority to act on behalf of the contractor, including the authority to direct all on-site forces and immediately stop any work that does not conform to the contract

C 110. APPLICATION OF WAGE RATES AND FRINGE BENEFITS: For the application of the wage rates and fringe benefits contained in the Decision of the Secretary of Labor; attached to and a part of this contract, all work shall be considered Heavy and Highway Construction, Building Construction or Residential and the specific wage determination will be identified on each individual delivery order.

C 111. SAFETY: Compliance with the current U.S. Army Corps of Engineers "Safety and Health Requirements Manual", (EM 385-1-1); Occupational Safety and Health Act (OSHA) standards, and current Dyess AFB safety regulations is mandatory. The prime Contractor shall be held responsible to ensure that his/her workforce and any subcontractor or supplier workforce comply with the above safety requirements.

C 111.1. Dyess AFB does have a clinic on site but does not serve civilians. Should an injury occur, they can provide emergency medical transportation to a community hospital. The Contractor will be required to reimburse the Government at an established rate for non-beneficiaries in accordance with DoD Regulation 6010.15.

C 111.2. Personal Safety: Adequate protection of all persons (regardless of whom they are employed with) shall be provided at all times. Work shall proceed in a manner to prevent hazard.

C 111.3. Special Safety Requirements: The Contractor shall comply with Air Force and local fire regulations and NFPA 241-2022 "Safeguarding Building Construction and Demolition Operations." Fire extinguishers rated and approved by the National Fire Protection Association, of sufficient size, type, and quantity to cope with all known hazards, shall be provided by the Contractor at the construction site during the execution of this contract; the extinguishers shall be removed upon acceptance of the project.

C 111.4. Welding, Cutting, Brazing, Roofing Kettle Permit: Contractor shall receive a "burn" permit from the

Statement of Work – Attachment 1 - page 7 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

Dyess Fire Department prior to work.

C 112. PARTNERING:

- C 112.1. The Government intends to encourage the formation of a cohesive partnership with the Contractor. This partnership will be structured to draw on the strengths of each organization to identify and achieve reciprocal goals. The objective is to achieve effective contract performance in achieving completion within budget, on schedule and in accordance with plans and specifications. This partnership between the Contractor and the Government will be voluntary and its implementation will not be part of the contract requirements, nor will it result in a change to contract price or terms.
- C 112.2. Within 30 days of the pre-construction conference, the appropriate Contractor's key personnel and a maximum of twenty-four (24) Government key personnel will attend a team-building workshop sponsored by the Contractor. The purpose of this team-building workshop will be to discuss contract requirements and expectations to arrive at a mutual understanding of the SABER program and to build trust between the Government and the Contractor.

C 200 GENERAL CONDITIONS

C 201 LOCATION OF STAFF: The Contractor will be provided with a location on Dyess AFB. The Contractor will be allowed to set a job trailer and extend to water, sewer, & electricity. The installation & maintenance of any extension to services shall be done by the Contractor. There will be no charge by the government for utility usage. The Contractor is required to maintain a staff within a thirty (30) minute response time of Dyess AFB, during standard working hours and be equipped with cellular phone capabilities, to respond to the requirements set forth in this contract.

C 202 STAGING/STORAGE AREA: An on-base staging/storage area shall be coordinated with Base CE through the Contracting Officer. The Contractor shall be responsible for the security & maintaining of the designated area. The designated area shall be returned to its original condition upon the completion of the contract. Final payment on the last task order under this contract shall be withheld until the designated staging/storage area is restored to its original condition, to the satisfaction of the Contracting Officer.

C 203 PASS AND IDENTIFICATION ITEMS: The following procedures and requirements for construction contractors requiring access, if followed, will assist in reducing delays in gaining access to work areas.

- C 203.1. Search, Inspection, and Seizure: All vehicles, personnel, and hand-carried items, entering or exiting any base control point, or while on the base, are subject to search and inspection and seizure of any prohibited item, at any time. Random, unannounced, and regular searches and inspections will be conducted. These searches and inspections are intended to ensure prohibited articles are not introduced into, and government property is not removed from the base or its facilities.
- C 203.2. Parking: Parking of the Contractor's vehicles shall be restricted to the area of work. The company name shall be prominently displayed on all construction vehicles parked where work is being accomplished. Only drive on unpaved surfaces when necessary to deliver parts or supplies that are too heavy to carry from the nearest paved surface. Prevent rutting of unpaved surfaces and dragging mud onto streets at every possibility. Any damage will be corrected by the contractor in a timely manner.
- C 203.3. Driver's Licenses: All persons entering or working on Dyess Air Force Base shall possess a valid Driver's License or State issued ID Card.
- C 203.4. The use of seatbelts by all vehicle operators and passengers is mandatory on Dyess AFB. Vehicle operators caught not wearing seatbelts will lose their driving privileges, subject to laws governing Military and Civilian Employees.
- C 203.5. Drivers holding & using cell phones in moving vehicles is prohibited on Dyess AFB, subject to laws

Statement of Work – Attachment 1 - page 8 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

governing Military and Civilian Employees. Drivers using "handsfree" devices are currently allowed.

- C 203.6. On-base contractor employees shall ensure the proper pass and identification items required for contract performance are obtained for employees and non-government owned vehicles.
- C 203.7. All contractor personnel, commercial vehicles, and delivery trucks shall access Dyess AFB exclusively through the Tye gate. Access through the Arnold gate or any other installation access point is not authorized. In the event of a planned or unscheduled closure of the Tye gate, the Contractor shall immediately coordinate with the Contracting Officer or the 7th Security Forces Squadron for direction on an alternate access point.
- C 203.8. Upon arrival at a gate, all vehicle occupants will be required to show identification. A pictured identification such as a driver's license will be required. The person will be required to identify himself/herself and the firm he/she works for, and the information will be verified against the Entry Authority List (EAL) and may then proceed to obtain their long-term pass. The name on the EAL must match the name on the driver's license exactly. Personnel cannot show up at the gate without prior notification for access and expect to gain access. Verbal access cannot be provided.
- C 203.9. Retrieving Identification Media. The contractor shall retrieve all identification media, including vehicle passes, from employees who depart for any reason before the contract expires, e.g., terminated for cause, retirement, etc. These items should be turned into the Contracting Officer.
- C 203.10. Controlled Unclassified Information (CUI). The contractor shall comply with DoD 5200.48, and NIST SP 800-171 Rev. 2 requirements. The regulation sets policy and procedures for the disclosure of records to the public and for marking, handling, transmitting, and safeguarding CUI material.
- C 203.11. Additional Security Requirements: In accordance with DODM 5200.01, Volumes 1 through 3, and AFI 31-401, The contractor shall comply with requirements identified in AFSSI 9100, Communications Security (COMSEC), Command, Control, Communications and Computer (C4) Systems Security, Security Awareness Training Education (SATE), and Operations Security (OPSEC).
- C 203.12. Reporting Requirements. The contractor shall comply with AFI 71-101V4, "Counterintelligence Awareness and Briefing Program" requirements. Contractor personnel shall report to an appropriate authority any information or circumstances of which they are aware may pose a threat to the security of DOD personnel, contractor personnel, resources, and classified or unclassified defense information. Contractor employees shall be briefed by their immediate supervisor upon initial on-base assignment.
- C 203.13. Traffic Laws. The contractor and its employees shall comply with base traffic regulations.
- C 203.14. Key Control. The contractor shall establish in writing and implement methods of making sure all keys issued to the contractor by the Government are not lost or misplaced and are not used by unauthorized people. This established plan shall be submitted to the Contracting Officer in writing. The contractor shall not duplicate any keys issued by the Government.
- The contractor shall immediately report to the Contracting Officer occurrences of lost or duplicated keys.
- In the event keys, other than master keys, are lost or duplicated, the contractor may be required, upon written direction of the Contracting Officer, to re-key or replace the affected lock or locks without cost to the government. The government may, however, at its option, replace the affected lock or locks or perform re-keying and deduct the cost of such from the monthly payment due the contractor. In the event a master key is lost or duplicated, the government shall replace all locks and keys for that system and the total cost deducted from the monthly payment due the contractor.
- The contractor shall prohibit the use of keys issued by the government, by any persons other than the contractor's employees and the opening of locked areas by contractor employees to permit entrance of persons other than contractor employees engaged in performance of contract work requirements in those areas.
- C 203.15. Lock Combinations: The contractor shall control access to all government provided lock combinations to preclude unauthorized entry.
- C 203.16. Best Door Hardware (typical doors): Provide Best locksets on all doors, Best model 45H Series, 15 lever, S trim, 626 finish with CoreMax (1CX7X1W1626) cores. Provide hardware & accessories with stainless steel finish. Provide mortise ball bearing hinges, unless noted otherwise. Furnish locks with manufacturers' CoreMax cores and key system. CoreMax key blanks (1AXX1X1W1KS717KS714) shall be standard style stamped "US Property – Do Not Duplicate". Furnish 2 key blanks for each unpinned core provided for cutting

Statement of Work – Attachment 1 - page 9 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

by government locksmith.

C203.16.1 Contractor shall install Contractor supplied temporary construction cores in all locksets as they are installed in the doors. Final Government cores (provided under this project by Contractor & shipped DIRECTLY to the Locksmith) will be installed during/after the final inspection by the Government Locksmith. Provide 1 set of the following for every 50 cores installed in each project (1 each minimum per project): EO CSE core service parts for a A4 pin system, E1, E2, E3, E4, E5, F1, F2, F3, F4, F5, F6, F7, F8, F9, F10, F11, 22S service equipment, and SE pkg 21C caps 500 A40317. Submit registered mail tracking receipt to government on AF 3000 for tracking & documentation.

C 203.17. Controlled/Restricted Areas. The contractor shall implement local base procedures for entry to Air Force controlled/restricted areas where contractor personnel will work.

C 203.18. Antiterrorism (AT) and Security Requirements

C 203.18.1. Antiterrorism Awareness Training: In accordance with R-DFARS 252.204-7004, *Antiterrorism Awareness Training for Contractors*, and DAFI 31-145-O, all contractor and subcontractor personnel requiring access to Dyess AFB must complete Level I - Antiterrorism (AT) Awareness Training. This training must be completed within 30 days of requiring access to the installation and annually thereafter. The contractor will coordinate this training post-award and provide certificates to the 7th Contracting Office.

C 203.18.2. Contractor Screening and Access Control: In accordance with DoDM-5200.08 V3 / AFMAN 31-101 V3 (*Installation Perimeter Access Control*), the contractor shall ensure all personnel are subject to required screening, including favorable fingerprint or National Crime Information Center (NCIC) checks, to determine trustworthiness prior to being granted access to the installation, sensitive facilities, or classified areas.

C 203.18.3. Operating Instructions and Circulation Control: When required by the specific task order or when working within designated Controlled or Restricted Areas, the Contractor shall develop an Operating Instruction (OI) for internal circulation control, protection of resources, and to regulate entry. This OI must govern operations during normal, simulated, and actual emergency conditions.

C 203.18.4. AT Coordination: If an OI is required per section 203.18.3, it and any specific security mitigation measures shall be written in accordance with the local base Operations Plan and DAFI 31-145-O. All such OIs and security procedures must be coordinated through the 7th Security Forces Squadron (7 SFS, Dyess AFB, TX) prior to the commencement of work in those areas.

C 203.19. Entry Authorization Letter (EAL): Fourteen (14) calendar days prior to the initial access in any area on Dyess AFB, the Contractor shall provide Civil Engineering (7 CES/CEP) with a list of employees requiring entry. This list will include the full name, company name, date of birth, and social security number of each employee, the make, model, color, year, license number and state of each vehicle. Names provided must match the individual's driver's license exactly. Subsequent additions to the EAL may be made by letter five (5) working days in advance of the employee's arrival. The contractor shall notify the Contracting Officer and 7 CES/CEP of any employees who have been terminated or dismissed so they can be removed from the entry list immediately.

C 204 CONTRACTOR'S TELEPHONE:

C 204.1. Upon Award: At the beginning of the contract, the Contractor shall provide the Contracting Officer with a telephone number at which the Contractor, or his/her representative, may be contacted at any time.

C 204.2. Costs: All costs incurred as a result of the telephone installation and service shall be borne by the Contractor.

C 204.3. Communications Security (COMSEC): All communication with Department of Defense (DOD) organizations are subject to COMSEC review. Contractor personnel will be aware that telecommunications networks are continually subject to intercept by unfriendly intelligence organizations. The DOD has authorized monitoring of the military phone calls originating from or terminating at DOD organizations. Therefore, civilian Contractor personnel are advised that any time they place a call to or receive a call from a USAF organization, they are subject to COMSEC procedures. The Contractor will assume the responsibility for ensuring wide and frequent dissemination of the above information to all employees dealing with official DOD information.

Statement of Work – Attachment 1 - page 10 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

C 205 EMPLOYEE STANDARDS: The Contracting Officer may, in writing, require the Contractor to remove from the site any employee the Contracting Officer deems incompetent, careless, or otherwise objectionable. The following shall apply:

- C 205.1. All work under this contract shall be performed in a skillful, workmanlike, and professional manner.
- C 205.2. Proper Attire: Improper attire, i.e. attire not providing sufficient safety protection and professional appearance (minimum of long trousers, shirt and shoes) will be reported to the Ground Safety Office and the Contracting Officer respectively. In addition, no profane, illegal, offensive or discriminatory language/symbols shall be displayed.
- C 205.3. Subcontractors: The Government shall not exercise any supervision or control over the Contractor's employees performing service under this contract; such employees shall be accountable not to the Government, but solely to the Contractor, who in turn, is responsible to the Government.
- C 205.4. Unauthorized Personnel: Contractor personnel will be limited to official business only on Dyess AFB, TX. Persons in violation of the above will be apprehended and appropriately disciplined.

C 206 PROHIBITED ITEMS: Certain items are prohibited on base. Personnel who are found to be in possession of prohibited items will be challenged and the item confiscated pending an investigation. Personnel in possession of prohibited items are subject to disciplinary action, withdrawal of access authorization, or arrest and prosecution. The following non-government owned items are prohibited on base, unless an exception is noted:

- C 206.1. Smoking is permitted in designated, outdoor smoking areas only. No smoking will be allowed within any base facility.
- C 206.2. Alcohol, controlled substances including illegal drugs and associated paraphernalia, except for prescription medicine.
- C 206.3. Firearms, ammunition, and other dangerous or deadly weapons, explosives or incendiary devices.
- C 206.4. Pets, wild or domestic.
- C 206.5. Other items prohibited by law.

C 207 GOVERNMENT FURNISHED EQUIPMENT/MATERIALS: Government Furnished Equipment/Materials (GFE/M): Government furnished materials will not be furnished to the Contractor as a general rule. However, the government reserves the right to provide GFE/M to be used on any task order. In such cases, the contractor gets to charge Means installation and equipment charges only. The Contractor shall follow the instructions of the Contracting Officer's representative regarding the disposition of all government- furnished property not consumed in performance of the task order.

- C 207.1. Property Administrator: The Base Civil Engineer, or his/her authorized representative, is designated as Property Administrator for Government-furnished equipment/material to be furnished to the Contractor for performance under this contract.
- C 207.2. Transportation: The Contractor, with his/her own forces, shall transport all Government Furnished Equipment/Materials (GFE/M), if any described on the delivery order. The equipment/material shall be transported from the Government storage area to the work site indicated on the delivery order.
- C 207.3. Contractor Responsibility: The Contractor assumes the risk and responsibility for the loss or damage to the Government-furnished property.

C 208 GOVERNMENT LIABILITY: The Government shall not be liable for any loss or damage to the Contractor's property, including stock or for incidental expense to such loss or damage.

C 209 WORK:

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

- C 209.1. Scheduling: Before any of the work is initiated under any individual delivery order, the Contractor shall confer with the Contracting Officer, or his/her authorized representative(s), and agree on: a sequence of procedure; means of access to premises and building; space for storage of materials and equipment; delivery of materials and use of approaches; use of corridors, stairways, elevators, and means of communications; and the location of partitions, eating spaces, and restrooms for Contractor's employees.
- C 209.2. Work Site: Contractor shall schedule all work to include subcontract work in a manner that minimizes downtime at each project site. At no time, after a project's construction has started, shall a project be abandoned for more than five (5) working days unless approved by the Contracting Officer. Abandonment shall mean no site work for reasons other than weather, waiting for materials or at the request of the government. If abandonment of a project is approved, the contractor shall provide the Contracting Officer and the CES Project Manager with the anticipated date for re-start of construction.
- C 209.3. Permits, Utility Outages, and Base Coordination: The Contractor is solely responsible for the timely acquisition of all permits required by Dyess Air Force Base, the State of Texas, and Federal Governments, including proactively managing the routing process and adhering to all minimum required lead times. Required permits and minimum submission timelines include, but are not limited to, the AF Form 103 Work Clearance Request (Dig Permit) routed through the Civil Engineer Squadron (CES) and Contracting Officer's Representative (COR) at least 21 days prior to excavation; hot work or "burn" permits (AF Form 593) submitted to the Base Fire Department 3 to 5 days prior; and environmental permits (such as asbestos disposal, storm drainage, and transportation permits) coordinated with the CES Environmental at least 30 days prior or before the Notice to Proceed. Furthermore, if construction activities require utility outages (e.g., electrical power, water, gas, HVAC) that affect the primary work site, shared utility grids, or adjacent occupied buildings, the Contractor must submit a formal utility outage request to the CES and COR a minimum of 14 calendar days in advance. The Contractor shall coordinate directly with the COR and affected Facility Managers to ensure adjacent agencies have sufficient warning to mitigate mission impact. The Contractor remains responsible for tracking the status of all permits, and any project delays caused by the Contractor's failure to submit accurate requests within these established timelines shall not constitute valid grounds for a schedule extension.
- C 209.4. Concealed Work: All items of work to be concealed shall be Government inspected prior to concealment. Contractor shall notify the Contracting Officer's representative of his/her intention to conceal a minimum of 24 hours in advance, and no items shall be concealed until the contractor has received approval to do so from the Contracting Officer's representative.
- C 209.5. Furniture Moving: Furniture and portable office equipment in the immediate area shall be moved by the Contractor and replaced to original position as identified in each Task Order upon completion of the work. If the work required by the Task Order will not allow furniture and portable office equipment to be replaced to its original position, new locations will be designated by the Contracting Officer or the Contracting Officer's representative for replacement by the Contractor. This work will be identified in the Task Order as a line item.
- C 209.6. Material Delivery: Delivery of materials and equipment shall be made with a minimum of interference to Government operations and personnel.
- C 209.6.1. Incoming Supplies: The Contractor shall coordinate with suppliers and shippers to ensure incoming materials are properly identified with the Contractor's name, contract number, and delivery order description. Also, a designated individual shall be identified to receive shipments. No storage area is available for the Contractor's use. In restricted areas, both the individual or alternate designated to receive the shipments as well as the shipper must be identified in writing to the Contracting Officer five (5) working days prior to receipt of shipment.
- C 209.6.2. Time Sensitive Materials: Delivery of time sensitive materials such as concrete and asphalt must be coordinated with the assigned contract inspector from 7 CES/CENM.
- C 209.7. Material Testing: The Contractor shall notify the Contracting Officer or the Contracting Officer's Representative a minimum of two workdays in advance of when and where testing is to be conducted so the Government will have the option of witnessing the test.
- C 209.8. Site Fencing and Mowing: The Contractor shall provide and maintain at his/her expense adequate orange fencing around each entire delivery order work site that requires the use of fencing; all site storage areas are considered a part of the work site. When grass/weeds exceed four inches in height, all areas contained within

Statement of Work – Attachment 1 - page 12 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

each Task Order shall be mowed by the Contractor. Fencing on pavement shall be supported by weighted orange barrels or metal stands.

- C 209.9. Area: The work shall be performed in phases to minimize impact on the users of the facility. Phases shall be coordinated with 7CES, the Contracting Officer, and the user during the task order design period. Work in each phase shall be completed before work in the next phase can start. The contractor shall account for a minimum of one extra week to allow the user to move out of the work area.
- C 209.10. Early Release/Base Closure: Occasionally it is necessary to require either early release of Dyess AFB personnel, their late reporting or even base closure when weather conditions make travel unsafe. When weather conditions cause one of the above situations, contractor personnel will be denied access to the base, unless they have been notified by the Contracting Officer their contract service has been determined essential. Denied access in these situations will result in no additional cost to the Government.
- C 209.10.1. Some of the following radio and television stations broadcast and monitor Dyess AFB closing and late reporting information: KEAN (105.1 FM), KOOL (100.7 FM), KHXS (102.7 FM), KTAB (TV CH 10), KTXS (TV CH 4), and KRBC (TV CH 5).
- C 209.11. Elevators: Any temporary use of an existing elevator shall be by arrangement through the Contracting Officer and subject to his/her controls. Such use will be of an intermittent nature. The Contractor shall provide and maintain suitable and adequate protection covering for the elevator machinery, the hatchway entrance, threshold, and the interior of elevator during the period of temporary use. Loads in excess of the rated capacity of the elevator will not be permitted. On completion of the work, the Contractor shall remove the protection coverings together with any resultant dirt and debris and leave the equipment in a condition equal to or better than that in which it was found.
- C 209.12. Toilet Facilities: The Contractor shall provide portable restroom units for his/her employees on the job site at his/her expense.
- C 209.13. Security At The Work Site: Whenever facility security is breached to perform work required under this contract, the Contractor will be responsible for providing temporary measures ~~in order~~ to ensure security is maintained at the level existing prior to construction. The Contractor shall provide adequate protection at his/her cost against vandalism and theft for all parts of the building wherever work under this contract is performed. This may include such security items as fencing around a facility or closing and securing all openings in a structure during non-working hours.
- C 209.14. Equipment On The Work Site: The Contractor shall store all supplies and equipment on the project site to preclude theft or damage, ensuring that equipment remaining in-place within the area of work is covered and protected against loss or damage. Equipment removed for reuse, as required by project drawings or this Statement of Work, shall be satisfactorily stored, while temporarily removed equipment must be protected, cleaned, and replaced in a condition equal to its state prior to the start of work. Security for all equipment and materials, including those removed for temporary storage, remains the sole responsibility of the Contractor. The Contractor shall maintain the work site in a safe and orderly manner at all times; specifically, the work site shall be broom-cleaned at the conclusion of each workday, and all tools and materials shall be consolidated into a neat, organized laydown area. While comprehensive weekly site cleanups are required to maintain a professional appearance, cleanups may occur more frequently during windy conditions or as otherwise directed. The Contracting Officer or their representative may issue a stop-work order, at no cost to the Government, if site conditions are deemed unsafe or unprofessional due to a lack of daily cleanup.
- C 209.15. Fill Materials: Excess fill material, including rock, gravel, sod, broken concrete or asphalt, plaster, etc., shall be hauled off Dyess AFB grounds and disposed of in accordance with applicable state and local regulations. Additional fill material shall be hauled to the site from off the Dyess AFB grounds as a necessary part of the work.
- C 209.16. Roadways, Sidewalks & Curbs:
- C 209.16.1. Cleanliness Of Paved Surfaces: When paved surfaces are jointly used by the Air Force and Contractor, the Contractor shall keep all paved surfaces, such as runways, taxiways, and hardstands, sidewalks, curbs, and asphalt clean at all times and, specifically, free from small stones which might damage aircraft propellers or jet aircraft. In restricted areas the traveled areas shall be cleaned using a self-propelled vacuum, vacuum truck, or other appropriate equipment and shall be cleaned to the

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

approval of the using agency through the Contracting Officer's representative.

- C 209.16.2. Hauling: Loose debris on trucks leaving the site shall be loaded in a manner that will prevent dropping of materials on streets and conform to local ordinances and laws. Fasten suitable cover, such as a tarpaulin, over the load before entering surrounding streets. The Contractor shall be responsible for cleaning up materials that fall from trucks immediately after he/she becomes aware of it. This shall include cleaning up mud, rocks, trash or any other type of debris spilled or thrown from tires. Clean up shall be performed to the satisfaction of the Contracting Officer's representative.
- C 209.16.3. Load Limits On Pavement: Vehicle traffic on concrete pavement shall be restricted to equipment with pneumatic tires.
- C 209.16.3.1. The limit for vehicular loading on all areas of concrete over building structures and access bridges shall be a pickup type truck with a payload not to exceed 1,000 pounds or a gross vehicular load of 5,000 pounds.
- C 209.16.3.2. The limit for vehicular loading on concrete access ramps and "on-grade" concrete pavement shall be 5,000 pounds per vehicle wheel. For the purpose of this limitation, dual wheels shall be considered as two wheels.
- C 209.17. Traffic Control: The Contractor shall, at its sole expense, furnish, install, and maintain all signs, warning lights, barricades, and other necessary traffic control devices. All traffic control measures shall comply with the requirements of the current edition of the U.S. Department of Transportation, Federal Highway Administration's Manual on Uniform Traffic Control Devices (MUTCD) and all applicable TxDOT standards.
- C 209.18. Upkeep And Work Adjacent To Roads And Highways: In addition to the requirements in the contract clause entitled "Operations and Storage Areas," (RFO 52.236-10) the Contractor shall comply with the following requirements: Where the construction work is on or adjacent to, or involves hauling over public or private roads, streets, or highways, as herein referred to as "roads," the said roads shall, except as otherwise specified or directed, be kept open for traffic at all times during the construction period. Further, the Contractor shall, during said construction, provide, erect and maintain warning signs, lanterns or other safety devices and, when necessary, provide flagmen for protection of traffic according to the Manual on Uniform Traffic Control Devices (MUTCD). The Contractor shall keep the right-of-way of the roads free of debris that might be caused to accumulate thereon by his/her operations, and upon completion of the work, shall clean up the said roads and repair any damage to the roads caused by his/her operations under this contract to the satisfaction of the Contracting Officer. The drainage from the roads shall not be obstructed by the construction work.
- C 209.19. Cleanup And Disposal Of Debris: At the end of each workday, the Contractor shall clean the work area and stack building materials in a neat manner as approved by the Contracting Officer or his/her designated representative. Contractor shall ensure that trash is contained and not allowed to be blown around by the wind. Upon completion of the work, the Contractor shall ensure that all dirt, trash and debris resulting from construction operations is removed from the work area. Disposal of debris shall be made by the Contractor at his/her expense. All debris shall be delivered to a state approved sanitary landfill. **Notice:** The disposal of demolition waste is regulated by the Department of Natural Resources under chapter 42, TCEQ. Such waste, in types and quantities established by the department, shall be taken to a demolition landfill or a sanitary landfill for disposal.
- C 209.20. Precautionary Measures. It is the Contractor's responsibility to take all necessary precautions to minimize delays resulting from weather conditions. This may include, but is not limited to, trenching, protective covering(s), temporary structures (walls to prevent mud slides), etc.
- C 209.21. Open Pit Safety: The Contractor shall ensure all open pits or excavations deeper than five (5) feet are equipped with a ladder to provide emergency egress. Furthermore, all such pits must be secured with high-visibility orange safety fencing to prevent unauthorized access. All excavation and open pit operations shall comply with applicable Army Safety and OSHA requirements.
- C 209.22. Phasing and Occupant Coordination: For all work within occupied facilities, the Contractor shall submit a detailed Phasing Plan as part of the pre-construction submittals. This plan must be approved by the Contracting Officer and the facility manager. The plan shall detail how mission operations will be sustained, including the sequencing of work to minimize disruption. The Government reserves the right to require work

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

to be performed outside of normal duty hours (e.g., nights, weekends) to mitigate mission impact, the costs of which shall be included in the task order proposal.

C 209.23. Temporary Facilities: Where contract work requires the temporary shutdown of essential facilities (e.g., restrooms, kitchens, office space), the Contractor shall provide temporary replacement facilities. For restroom facilities, a minimum replacement ratio of two (2) temporary units for every one (1) unit taken out of service shall be provided, unless otherwise approved by the Contracting Officer. All temporary facilities must be fully functional, clean, and meet all accessibility and safety standards prior to the shutdown of the permanent facility.

C 210 AIRFIELD REQUIREMENTS:

- C 210.1. The Contractor shall coordinate with Base Operations, Dyess AFB, for construction restrictions involving the flightline, taxiway, and runway areas and shall comply with Air Force Instructions.
- C 210.2. Procedures for all vehicles, equipment, Contractor and Subcontractor personnel working on the flightline, taxiways and runways shall be addressed at the Pre-Construction Conference.
- C 210.3. Contractor shall comply with Airfield Safety Measures, See R-DFARS Clause 252.236-7005 (IA 474).
- C 210.4. The Civil Engineer Construction Manager will derive initial airfield construction phasing from AF Form 3064, Contract Progress Schedule. Form is to be submitted by the Contractor in accordance with RFO 52.236-15, *Contractor Progress Schedules*, and paragraph H-7 below.
- C 210.5. AF Form 3064 is acceptable to satisfy the requirements at clause RFO 52.236-15, *Schedules for Construction Contracts*.
- C 210.6. When a temporary airfield construction waiver (TACW) is required prior to commencement of airfield activities, AF Form 3064 shall be used to satisfy the requirement of UFC 3-260-01, *Airfield and Heliport Planning and Design, Appendix B1-2.1.4, Section 1, Waivers processing procedures, Construction Waivers*
- C 210.7. On approval by the Civil Engineer Construction Manager, and after NTP is issued by the Contracting Officer, a copy of AF Form 3064 may become a supplement to the approved TACW.
- C 210.8. The Civil Engineer Construction Manager will apply the AF Form 3064, and all subsequent AF Form 3065 to update the CENM Airfield Project Plan (APP).
- C 210.9. Additional requirements are required around the Flight Line; refer to specifications section 00 01 05 – Flight Line.

C 211 UTILITIES SERVICES: (RFO 52.236-14)

- C 211.1. Government Provision: Available water and electricity for Task Orders may be used in reasonable quantities in this work at no cost to the Contractor. The Contractor shall make arrangements for such services with the Contracting Officer or his/her designated representative.
- C 211.2. Contractor-Caused Outage: All temporary outages of any utility services required for the performance of work shall be scheduled with the Civil Engineer Squadron no less than twenty-one (21) workdays in advance of outages. Outages shall be restricted to weekdays (Monday-Friday), unless a weekend outage is explicitly required to avoid mission impact. Requests shall be made in writing to the Contracting Officer. Requests shall stipulate specific utility system(s) (and circuits) to be affected, the location of the work, the time at which the shutdown will occur, and the duration of the outage for each system. Water, gas, steam, sewer and electrical outages shall be held to a maximum duration of 2 hours unless otherwise approved in writing. Where multiple outages are required, as many outages as can be accurately scheduled shall be submitted as a group.
 - C 211.2.1. In the event of a Contractor caused utility failure/disruption, the Contractor will first make the area safe, then immediately contact the Base Civil Engineer Service Desk (325-696-4154), Fire and Emergency Services (325-696-2486, or 911), and the Contracting Officer.
 - C 211.2.2. If the damaged utilities are previously known or shown to the Contractor, or there is negligence on his/her part, the utilities will be repaired by the Contractor immediately at no cost to the Government.

Statement of Work – Attachment 1 - page 15 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

- C 211.3. Utility Connections and Acceptance: The Government will approve all utility tie-in points and perform the necessary utility isolation for the Contractor's work. The Contractor shall be responsible for making the physical connections to these designated points. Upon completion of the work, the Contractor shall coordinate with the 7th Civil Engineer Squadron (7CES) and the Contracting Officer to schedule a final inspection and acceptance of the newly installed utility systems.
- C 211.4. Interruption Of Service: The Government may not be held responsible for interruptions of utility service and will not be liable for Contractor delays, damages, or increased costs occasioned by any interruption of service.
- C 211.5. Contractor Responsibility: The Contractor shall be responsible for installing and maintaining temporary cords, lines, or other equipment in a safe condition.
- C 211.6. Prior to Final Acceptance: All temporary cords, lines, or other equipment shall be removed and the existing outlets and lines restored to the condition existing prior to the start of construction.
- C 211.7. Existing Utility Verification: The locations, sizes, and types of all utility lines shown on the Plans are for informational purposes only and are not to be relied upon without verification by exploratory digging/vacuum potholing. The Contractor shall verify the field location of all existing underground utilities in service within the immediate area of any proposed construction which may conflict with existing utilities. The Contractor shall excavate exploratory trenches in the presence of representatives from all utility companies and the Contracting Officer or the Contracting Officer's representative. The trench shall be a minimum of three (3)-feet wide and excavated to a depth at least two (2) feet below the respective construction shown on the plans, or deeper if directed by the Contracting Officer or the Contracting Officer's representative. Hand diggings, probing, and remote detection techniques shall precede machine excavation and shall be in accordance with state and local requirements for such techniques. It is the responsibility of the Contractor to protect all utilities which are to remain in service for the duration of the project construction, or until their abandonment is directed by the Contracting Officer or the Contracting Officer's representative. It is also the contractor's responsibility to shore all excavations in accordance with OSHA standards.
- C 211.7.1. When existing utilities are exposed, the Contractor shall contact 7 CES/CENM to survey any exposed utility line or feature below the surface.
- C 211.7.2. In addition, when new utility lines are installed or constructed, the Contractor shall contact 7 CES/CENM to survey all utility features below the surface.
- C 211.7.3. 7 CES/CENM must be contacted prior to the utility lines being back-filled.
- C 211.7.4. The Contractor will be responsible for any additional costs for exposing new utility lines that were not surveyed by 7 CES/CENM.
- C 211.8. Excavation permits: Refer to specification section 00 01 03 - Utilities.
- C 211.9. Utility Marking Of Yet To Be Accepted Work: The Contractor shall be required at the request of other contractors working in the area to flag the utilities being installed on his/her specific contract within ten (10) working days of the request.
- C 211.10. Base Policy For The Operation Of All Hydrants And Valves On The Base Water Distribution System: The following is the base policy for the operation of all hydrants and valves on the base water distribution system:
- C 211.10.1. The Contractor shall immediately notify the fire alarm communication center at 325-696-2486, of out-of-service hydrants, sprinkler system, stand pipes, etc. and the alarm room will also be notified when hydrants are returned to service.
- C 211.10.2. 7CES/CEOES is responsible for operation of all valves and is the only organization authorized to open or close these valves. In an emergency (water main break) the Contractor may close a valve and notify the Fire Department at 325-696-2486 immediately.

C 212. SURVEY MARKERS: Reference is made to the Contract Clause entitled "Permits and Responsibilities" (**RFO 52.236-7**), Chapter 60 of the Texas Revised Statutes 1969, and rules titled "Maintenance of the Original US Public Land Survey Corners" adopted by the Division of Geology and Land Survey, Texas Department of Natural Resources.

Formatted: Highlight

Formatted: Highlight

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

C 212.1. The Contractor shall be responsible for removing and relocating survey markers. Relocation shall be performed by a professional registered Land Surveyor.

C 300. TASK ORDER PROCEDURES

C 301 CONTRACT ADMINISTRATION: Administration of the task orders under this contract will be performed by 7th Contracting Squadron, Dyess AFB. No changes, deviations, or waivers shall be effective without a modification of the contract or delivery orders executed by the Contracting Officer authorizing such changes, deviations, or waivers.

C 301.1. Correspondence Identification: All correspondence and data submitted by the Contractor under this contract shall reference the Project Number, Task Order Number and Project Name.

C 301.2. Task Order Limitations: Task orders may be subject to statutory cost limitation.

C 301.3. Adjustments To Basic Prices: The Contracting Officer will include the current Davis-Bacon wage determination with the exercise of each option, and the Contractor will be required to pay those rates. The pricing database shall be updated annually, and line-item costs will be based on those updates. The Contractor shall bear the cost of RS MEANS Guide Software updates.

C 302 ORDERING PROCEDURES:

C 302.1. Notification of Contractor: As the need exists for performance under the terms of this contract, the Contracting Officer, or his/her authorized representative, will notify the Contractor of a new requirement. The Contractor shall receive a scope of work consisting of a Statement of Objectives (SOO) in such detail that the Contractor will be able to lay out the work using the SABER Technical Specifications. The SOO may also include preliminary sketches or advance concept drawings, depending on the complexity of the particular project. The SOO and preliminary sketches are only conceptual documents. Once the Contractor's drawings are approved by the Government and the negotiation process is complete, the Contractor shall provide a revised SOO to be approved by the Government. When approved, the revised SOO becomes Attachment One to the task order. The final quantified negotiated line items become Attachment Two. The revised and approved construction drawings become Attachment Three.

C 302.2. Contractor's Response: Upon receipt of the SOO, the Contractor shall respond to the needs of the Government as specified in Para- C 304.14 by:

C 302.2.1. Site Visits: A reasonable number of investigative visits to a proposed work site shall be completed in the company of the Contracting Officer or his/her authorized representative, Civil Engineer representative and other Government personnel as necessary. The purpose of the visit is for the Contractor to gather enough information to prepare the drawings/sketches, project estimate and revised Statement of Work.

C 302.2.2. Establishing verbal contact with the Contracting Officer or his/her authorized representative to further define the scope of the requirement if necessary.

C 302.3. Contractor's Proposal: Upon establishing the scope of the individual requirement, the Contractor shall then prepare his/her proposal for accomplishment of the task.

C 302.3.1. The RS MEANS Computerized Pricing Guide, Facilities Construction Cost Data, Mechanical Cost Data, Plumbing Cost Data, Electrical Cost Data, Assemblies Cost Data, Site Work & Landscape Cost Data, Interior Cost Data and Concrete & Masonry Cost Data shall serve as the basis for establishing the value of the work to be performed on a unit price basis. All calculations for work under this contract shall be accomplished using the **Total O&P Line-Item Cost** in RS MEANS without City Cost Coefficient.

All other Contractor's costs are to be included in the coefficient. This includes, but is not limited to: home office and field overhead, project management and site supervision (including Quality Control and Site

Statement of Work – Attachment 1 - page 17 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

Safety personnel), profit, insurance, mobilization and demobilization, small tools and general consumables, company vehicles, communication devices, administrative support, permit fees, state and local taxes, daily and final site cleanup, and all costs associated with compliance with safety, security, and environmental regulations. No separate or direct payment will be made for these items, as they are strictly bound within the negotiated coefficient.

See paragraph C304.12.1.

C 302.3.2. The total costs shall be as printed in the current RS MEANS databases, without changing the daily output, equipment, material, or labor rates. There are two exceptions to this for "Demolition" IAW paragraph C302.3.7.5, and "Remove and Reinstall" IAW paragraph C302.3.7.7 no deviation from RS MEANS labor, material, equipment, or daily output shall be authorized unless approved, in writing, by the Contracting Officer.

C 302.3.3. In RS MEANS Facilities Construction Cost Data, the introduction (**How the Book Is Built: An Overview**, Quick Start, and **How to Use the Book: The Details**) shall not be construed as permitting cost changes or deviations from RS MEANS for the purpose of this contract.

C 302.3.4. No provision shall be made for costs in excess of RS MEANS other than the Contractor's coefficient.

C 302.3.5. All line items in the RS MEANS Cost Databases include waste. Actual square footage quantities measured shall be used as quantity. No additional quantity shall be added as scrap or waste.

C 302.3.6. Line items in the RS MEANS Cost Databases include as part of that line item, all miscellaneous line items required to install that item. **EXAMPLE:** Installation of line item "Window Frame" includes costs of caulking, screws, drilling, and any other materials/labor required for complete installation of that item.

C 302.3.7. Costs Included in the Contractor's Coefficient

The Contractor's coefficient, when multiplied by the prices in the Unit Price Book (UPB), shall be considered full compensation for all direct and indirect costs, overhead, and profit. The following items are considered to be included in the coefficient and shall not be priced separately as direct line items:

- a. Category Included Costs
- b. Overhead & General
- c. Supervision, project management, quality control, safety personnel, on-site facilities, temporary utilities, and all general & administrative (G&A) expenses.
- d. Bonds & Insurance
- e. All costs for performance and payment bonds, and all required insurance.
- f. Submittals
- g. Preparation of all shop drawings, product data, samples, and other required submittals.
- h. Travel & Per Diem
- i. All travel, lodging, and per diem expenses for contractor personnel.
- j. Small Tools
- k. All hand tools and small equipment normally owned or provided by trades people.
- l. Warranty - All costs associated with fulfilling the contract's warranty requirements.
- m. Escort Fees - All fees associated with escorting personnel in controlled areas of the installation.

C 302.3.7.1. Costs of items in Division 1 of the Facilities Construction Cost Data are already included in the line-item cost extension for that item. Therefore, such items as small tools, and other Division 1 items not specifically included below are to be considered as included in the factor and the line-item extended price. The following items from Division 1 of the Facilities

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

Construction Cost Data shall not be included in the pricing factor and may be added or used as separate and distinct line items when preparing estimates for Task Orders:

- a. Field Engineering
- b. Testing
- c. Scaffolding and Scaffolding Specialties
- d. Rental Equipment (this may be used only if the other line item chosen does not include equipment necessary to perform the work).
- e. Engineering Fees, only where PE Certification is required. IAW RS MEANS, the Mechanical/Plumbing/HVAC Engineering Fees are applicable only to those specific sub-contracted portions of the project, whereas the Structural Engineering Fees are applicable to the project total.
- f. Scaffolding. Note, use of any line items will necessitate the Contractor schedule an inventory by Government Personnel and submittal by Contractor of Government Signed Inventory IAW paragraph 3.2.2
- g. Facility Maintenance.
- h. Chemical Toilets, acceptable to use as directed by the Government where latrines are not readily available at the project area construction site.
- j. Temporary fencing, chain link, 11 gauge, 6' high, acceptable to use as directed by the Government where project requires contractor to breach security fencing and is additionally required to erect temporary fencing when not at construction site.

The following Subdivisions/Major Classifications, as contained in any of the RSMeans bound or electronic databases shall not be used as line items in pricing task orders issued under this contract. These costs shall be covered in the contractor's coefficients:

- Subdivision Summary of Work, excluded in its entirety.
- Allowances, excluded in its entirety.
- Project Management and Coordination, excluded in its entirety.
- Construction Progress Documentation, excluded in its entirety.
- Regulatory Requirements, excluded in its entirety.
- Construction Facilities, excluded in its entirety.
- Construction Equipment, excluded in its entirety.

C 302.3.7.2. Construction Dumpsters and/or any spoils/rubbish handling/hauling and/or disposal fees for quantities of less than 20 Cubic Yards (8 Tons).

The following items are included in the Contractor's coefficient in any division:

- a. Equipment Rental for any hand held tool(s).
- b. Expendable items such as saw blades, drill bits, etc.
- c. Dewatering. Is partially excluded in that excavations that are called for in the delivery order that become filled with water due to inclement weather or that is resultant from the contractor's negligence through rupturing utilities shall be dewatered at the contractor's expense and not paid for as a separate line item.
- d. Hazardous material abatement, asbestos, lead, PCB, etc. All costs associated with any hazardous material abatement and/or containment not identified in part 1 section B – Supplies or Services and Prices/Costs – Asbestos Abatement of the solicitation will be accomplished as "Non-pre Priced Line Item" IAW paragraph 3.2.1.2.2. Contractor shall include all abatement state fees, removal, transportation, notifications, and disposal in pricing. Contractor shall meet

Statement of Work – Attachment 1 - page 19 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

or exceed all regulatory standards before, during, and after asbestos removal.

C 302.3.7.3. All labor, equipment, materials and rentals/fees required to provide works for these unauthorized sections shall be at no additional cost to the Government and is considered field overhead, therefore part of the Contractor's coefficient.

C 302.3.7.4. Prices associated with assemblies (where assembly costs are provided in RS MEANS Assemblies Cost Data) shall take precedence over prices for individual items.

C 302.3.7.5. Demolition. For demolition tasks accomplished under the contract where a demolition line item is not available, an installation line item for "like item" may be used as follows: the material cost will be zeroed out and the labor rate will be reduced to 25%. **EXAMPLE:** Demo one light fixture. Material cost would be 0%, labor cost would be 25% (demo) and equipment cost would be 100%.

C 302.3.7.6. Costs for expendable supplies, lubricants, wear and tear on tools, are included in the installation/construction costs in the RS MEANS cost of construction and will not be paid separately.

C 302.3.7.7. Remove and Reinstall. For remove and reinstall tasks, accomplished under the contract where a remove and reinstall line item is not available, an installation line item for "like item" may be used with as follows: the material cost will be zeroed out and the labor rate will be increased to 125%. **EXAMPLE:** Remove one light fixture, save for reinstallation and then reinstall. Material cost would be "0%". Labor cost would be 125% (remove & reinstall), and equipment cost would be 100%.

C 302.3.7.8. Applicability of Minimum and Maximum Values. When RS MEANS Cost Data Line Items reflect a maximum or minimum, the average of these two values shall be utilized.

C 302.3.8. Allowable Direct-Priced Line Items

The following items are not included in the coefficient and may be priced separately as a line item on the delivery order proposal. These costs must be reasonable and supported by certified cost or pricing data as required by the Contracting Officer.

Category Allowable Items

- a. Major Equipment
- b. Rental of large, project-specific equipment not typically part of the UPB (e.g., cranes, large excavators).
- c. Permits & Fees
- d. Specific government or jurisdictional permits, licenses, and inspection fees required for the project.
- e. Hazardous Material
- f. Costs for the testing, abatement, and disposal of regulated hazardous materials.
- g. Utility Outages
- h. Direct costs associated with planned utility outages, if required by the Government.
- i. Non-Priced Items (NPIs)
- j. Materials and labor for work not found in the Unit Price Book, priced in accordance with Section C 303.
- k. Design Costs
- l. If specifically authorized by the delivery order, costs for Architect-Engineer (A-E) services.

C 302.3.9. Pre- and Non-Priced Line Items. All line items in RS MEANS Estimating Guides and CLINs identified in part 1 section B - Supplies or Services and Prices/Costs – Asbestos Abatement are considered Pre-Priced Data (PPD). When a component, work element, or system does not exist as PPD, it shall be considered as a Non-pre Priced Item (NPI). The contractor shall submit three independent commercial quotes for each NPI. The quote shall include sales tax, sub-contractor's overhead and profit (if applicable), and prime Contractor's overhead and profit as delineated in the coefficient breakdown. All

C 302.3.10. The Contractor's proposal must be supported by necessary documentation to indicate that adequate engineering and planning to accomplish the requirement have been done. Examples of documentation that might reasonably be expected would include drawings, calculations, catalog cuts, Statement of Work – Attachment 1 - page 20 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

specifications, architectural renderings, etc.

C 302.3.11. The time allowed for submittal of the Contractor's proposal for non-emergency individual requirements will be as agreed upon by the Government and the Contractor not to exceed stated time in para C 304.14.

C 302.3.12. Best Door Hardware: Provide Best locksets on all doors, Best model 45H Series, 15 lever, S trim, 626 finish with CoreMax cores. Provide hardware & accessories with stainless steel finish. Provide mortise ball bearing hinges, unless noted otherwise. Furnish locks with manufacturers' CoreMax cores and key system. Key blanks shall be standard style stamped "US property – Do Not Duplicate". Furnish 3 key blanks for each unpinned core provided for cutting by government locksmith. Send permanent cores and key blanks, from lock manufacturer (or supplier) directly to Dyess Air Force Base by registered mail or other approved means to:

7 CES/CEOHS, Attn: Locksmith
726 Third Street, Building 8007
Dyess AFB, TX 79607-1618
325-696-4154

Contractor shall install Contractor supplied temporary construction cores in all locksets as they are installed in the doors. Final Government cores (provided under this project by Contractor & shipped to the Locksmith) will be installed during/after the final inspection by the Government Locksmith. Provide 1 set of the following for every 50 cores installed in each project (1 each minimum per project): EO CSE core service parts, E1, E2, E3, E4, E5, F1, F2, F3, F4, F5, F6, F7, F8, 22S service equipment, and SE pkg 21C caps 500 A40317.

Submit registered mail tracking receipt to government on AF 3000 for tracking & documentation.

C 302.3.13. Equipment Yard, Security Bollard Locks, & PIV (fire protection post indicator valves):

Provide Best 21B722LWC (Best 21B series, 7 pin housing, stainless steel, 1-1/2" shackle, with weather cover) for all equipment yard gates, security bollards, & PIV's.

C 302.3.14. Fire Alarm & Mass Notification: Contractor shall install fire alarm and mass notification system that is capable to perform live voice from the central station to provide real time information to building occupants during emergency situations. System shall be connected & compatible with the Base Monaco D-21 system. In addition the new or modified system shall be compatible to communicate through the Monaco BT-X Radio to the central fire station. Contractor may reuse existing components, but entire completed system shall be addressable & shall meet specifications section 28 31 76 – FA & MNS and all current UFC & NFPA requirements.

All programming & setup of the sending or receiving system shall be the responsibility of the Contractor.

C 302.4. Drawings: Graphical representations (in the quality, detail, and professionalism) documenting the work required by each Government project. The drawings must be thorough and detailed enough to allow:

C 302.4.1. The Government and the Contractor to estimate the number and type of pre-priced and non-pre-priced items required to successfully perform all work;

C 302.4.2. Government personnel to monitor and validate work compliance; and

C 302.4.3. The Contractor to satisfactorily complete all work requirements by ~~Delivery-Task~~ Order completion date, including providing required submittals and other documentation as needed.

C 302.5. Negotiation: After the Government's acceptance of the design drawings, the Contractor shall prepare a fully detailed cost estimate to complete the project. Upon receipt of the Contractor's proposal, the Government will accomplish negotiations on the proposal. The Contracting Officer or authorized representative will negotiate with the Contractor the appropriateness of selected line items, quantities required for all pre-priced and non-pre-priced items and the period of performance.

C 302.5.1. The Contractor shall provide the Contracting Officer with one (1) electronic PDF copy and one Statement of Work – Attachment 1 - page 21 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

(1) electronic RS MEANS Online file of the proposed line item identifiers with quantities.

C 302.5.2. The contractor shall provide the Contracting Officer with one (1) electronic copy of the completed AF Form 3064 detailing the period of performance.

C 302.5.3. After negotiations and upon agreement on a project cost and period of performance by the Contracting Officer or his/her authorized representative, the Contractor shall provide the Contracting Officer with one (1) electronic copy (in PDF) and one (1) RS MEANS Online file of all agreed upon line items and quantities.

C 302.5.4. Failure of the Contractor to include all necessary line items or incorrect quantity on a line item to perform all the requirements specified in the SOO will not be considered grounds for additional funds to make up for the shortcomings if there has not been a change in scope or a change in site conditions. This includes all work that is reasonably inferable from the drawings and Statement of Work as being necessary to produce a complete and usable end product. The Contractor warrants that they have conducted a thorough site investigation and that their proposal is complete. Omissions in the Contractor's proposal for work that is clearly required will not be grounds for a change order. The Contractor will still have to finish the project at the originally agreed amount and period of performance.

C 303 NON-PRICED ITEMS: Items of work not covered by this contract, but within its scope and intent, may be negotiated by the Contracting Officer and added by modification at any time during the contract period. Added items of work shall be incorporated into and made a part of the delivery order and shall be performed at the negotiated unit price. Previously non pre-priced work items may subsequently be added to the basic tasks defined in the SABER Technical Specifications after usage of only one time. The total percentage and cost of each non-priced line item shall be annotated on each delivery order.

C 303.1. Non-Priced Items (NPIs): All non-priced items shall be negotiated on an individual task order basis. The bare cost of an NPI shall be determined by a minimum of three (3) written estimates from verifiable sources (e.g., published price lists, subcontractor quotes, or supplier estimates) provided by the Contractor to the Contracting Officer for verification and approval. The estimate shall be certified by the supplier as being as low as or lower than those normally charged to the general public for the particular item.

C 303.1.1. Pricing Methodology: The cost to the Government for each NPI shall be the lowest acceptable verified bare cost (materials, equipment, and bare labor) multiplied by the Contractor's established contract coefficient. Separate manual markups for overhead, profit, or labor burden (e.g., adding 10% or multiplying by 1.5) are strictly prohibited, as these indirect costs are already fully compensated within the Contractor's competitively bid coefficient.

C 303.1.2. Labor Rates for NPIs: When bare labor hours must be calculated to establish the cost of an NPI, labor costs shall be based on the applicable Davis-Bacon Act Wage Determination for the project location. If a specific trade is not listed in the Wage Determination, the RS MEANS cost data labor rate may be used as a basis for negotiation; however, in no case shall the rate paid be lower than the federal minimum requirements set by the Department of Labor.

C 303.2. A listing of the Non-priced work by Task Order number, dollar and percentage for each fiscal year shall be provided to the Contracting Officer in writing by close of business on 1 October of each year.

C 303.3. The reuse of any non-priced line item shall be permissible only under projects priced in accordance with the same RS MEANS cost data year as the original project of record. Such items are not transferable and shall not be carried over to projects priced using a different RS MEANS cost data year.

C 304 SABER PROJECT ESTIMATING:

C 304.1. The Government may issue the Contractor a task order for all work incidental to developing a project, without obligating the Government to issue the Contractor the project. In order for the Contractor to receive monetary compensation for proposal development (design only), the Contractor will be awarded a Proposal Development Fee (Design Fee) in accordance with Bid Schedule, Proposal Development Fee. This amount is part of the overall contract award evaluation and will be stated in the Bid Schedule for the Base Year and each Option Year of the contract.

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

- C 304.2. The Government's intent is to obtain an exact price for projects that are being considered for SABER construction. It is not the Government's intent to have the Contractor provide an estimating service for projects with no initial serious SABER construction consideration. The Contractor agrees that the Government is not obligated to issue the Contractor a task order for the construction work described in the completed project estimate.
- C 304.3. Upon completion of negotiations and Government acceptance of the negotiated project price, the Contractor may immediately invoice for the completed design estimate. If, within one (1) year after Government acceptance of the project, the Government elects to have the Contractor construct the work described in the project estimate, the construction project price will be adjusted downward in an amount equal to that already invoiced for the Proposal Development Fee.
- C 304.4. If the Government and the Contractor reach an impasse and cannot come to an agreement on a project price in negotiations, the Proposal Development Fee will not be applied and the Contracting Officer will make an equitable adjustment for the Contractor's work up to that point.
- C 304.5. If the Contractor does not receive notice of the Government's intent (to have the Contractor construct the work described in the completed project estimate) within 1 year after the Government's acceptance, the Government no longer has the option of having the Contractor construct the work described in the completed project estimate while at the same time adjusting the price downward in an amount equal to that already invoiced for the Proposal Development Fee. The Government may, however, issue a Task Order to reopen the project as a new requirement with no adjustment for previous work completed by the Contractor.
- C 304.6. The target price range for this project shall be stated in each Government request for project estimating. The Contractor shall immediately notify the Contracting Officer if their project estimate will differ from or exceed the established target price range.
- C 304.7. Within one (1) year after Government acceptance of a project, any Government decision to use non-SABER methods to award a contract for other construction of work described in a SABER completed project estimate will not be based on price considerations.
- C 304.8. All estimates will reflect the coefficient factor as of the time of submission. If the coefficient factor changes by the time the Government elects to have the Contractor construct the work described in the completed project estimate, the resulting order for construction will reflect the new coefficient factor.
- C 304.9. The agreed upon contract line item prices for project estimating shall be counted as stated in Section B part of the cumulative value of ongoing work and will be subject to the limitations as explained in FAR Clause 52.216-19 "Task Order Limitations" (however, the \$2,000 minimum order limitation does not apply). Upon Government acceptance of the completed project estimate, the Contractor may decline an order to construct the work described in the completed project estimate if addition of the agreed upon project price to the cumulative value of ongoing work will result in the limits being exceeded. "Ordering" also applies to all Proposal Development Fees.
- C 304.10. Line items in the RS MEANS Pricing Data Base are not negotiable as it pertains to the production rate for labor, materials and equipment of the line items.
- C 304.11. Price of Performance: All individual costs for items of performance both pre-priced and non-pre-priced, contained in a proposed Task Order, shall be added. That sum shall be the cost to the Government of the Task Order. The individual cost for items of performance shall be determined as follows:
- C 304.11.1. Pre-priced Items: The base cost of pre-priced items of performance shall be determined based on the RS MEANS Computerized Pricing Guide, Facilities Construction Cost Data, Mechanical Cost Data, Plumbing Cost Data, Electrical Cost Data, Assemblies Cost Data, Site Work & Landscape Cost Data, Interior Cost Data and Concrete & Masonry Cost Data, which shall be updated annually at the expense of the Contractor. The cost to the Government of each pre-priced performance item shall be calculated as follows:
- C 304.11.1.1. The "Total O&P Line Item Cost" column figure for a particular performance item as dictated by the corresponding RS MEANS Computerized Pricing Guide (CPG)
- C 304.11.1.2. This product shall be multiplied by the required number of units.
- C 304.11.1.3. The resulting product is then multiplied by the corresponding coefficient. This final
- Statement of Work – Attachment 1 - page 23 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

product is the cost of that specific item of performance.

C 304.12. Negotiation may occur between the Government and the Contractor; however, that negotiation will involve only decisions concerning which particular line item is most correct for the particular item of performance, and the number of units required to fulfill the request for performance.

C 304.13. Performance Time: In working days.

DESIGN TIME ALLOWED BASED ON PROJECTED MAGNITUDE

<u>TASK DESCRIPTION</u>	<u>LEVEL 1</u>	<u>LEVEL 2</u>	<u>LEVEL 3</u>	<u>LEVEL 4</u>
	<\$100,000	\$100,001- \$250,000	\$250,001- \$500,000	>\$500,000
Visit the work site with the Contracting Officer, SABER project manager and/or designated representatives within working days:	3	3	3	3
<u>Submit Contractor Provided Design</u> after site visit within:	9	10	11	12
<u>Submit Cost Estimate</u> after finalized design approved:	5	7	7	8

In unusual circumstances (e.g., a difficult to find/price NPI item, a very complex project, etc.), additional time may be considered by the Contracting Officer if requested by the Contractor.

C 305 PREPARATION OF PROGRESS SCHEDULES AND REPORTS: The progress schedules and reports for this contract shall be prepared using AF Form 3064 (Project Schedule) and AF Form 3065 (Progress Report)

in electronic form. Project schedules shall be with 35% design. Progress reports shall be prepared for all projects with performance times 60 days and over. Progress Schedules and Progress Reports are to be submitted for review and approval via AF Form 3000, Material Approval Submittal.

C 306 MEETINGS AND CONFERENCES:

C 306.1. Pre-Construction Conference: A meeting attended by designated representatives of the Government, the Contractor and Customer after project award but before the start of work to discuss all aspects of the required work for a task order.

C 306.2. Coordination Meeting: After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the Quality Control Plan, the Contractor shall meet with the Contracting Officer or his/her authorized representative to discuss the Contractor's quality control system. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the Contractor Quality Control (CQC) operations, control activities, testing, administration of the system for on-site work, maintenance of on-site redline drawings, daily activity logs and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting shall be prepared by the Contractor, approved and signed by both the Contracting Officer and Civil Engineer Representative. The minutes shall become a part of the contract file within 3 working days. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the Contractor.

C 306.3. Work Scheduling Meeting:

C 306.3.1. Bi-Weekly: A Bi-weekly meeting between the Contractor's Project Manager, the Government's
Statement of Work – Attachment 1 - page 24 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

Construction Manager(s), and the Contracting Officer's representative may be held to discuss any problems or scheduling of work. At this meeting the Contractor will address his/her proposed work schedules and ongoing progress of projects. Required temporary utility services, time and duration of interruptions, road cuts, and repairs requiring traffic control, and protection of adjoining areas shall be included. Coordination action by the Contracting Officer relative to the items addressed will be accomplished during these meetings. The Contracting Officer may cancel or reschedule as needed.

C 306.4. Safety Assurance:

C 306.4.1. Safety Meeting: The Contractor shall keep a Safety Meeting log of meetings held with his/her employees on Safety and the Government has the right to inspect it at any time. Representatives of the Contractor shall meet with the Contracting Officer and his/her representative(s) prior to the start of repair, alteration or construction activities for the purpose of reviewing the Contractor's safety and health programs and discussing implementation of all safety and health provisions pertinent to the work to be performed under the contract. The Contractor shall be prepared to discuss, in detail, the measures he/she intends to take in order to control any unsafe or unhealthy conditions associated with the work to be performed under the contract. This meeting may be held in conjunction with the preconstruction conference, if so directed by the Contracting Officer. The conduct of this meeting is not contingent upon a general preconstruction meeting. The level of detail for the safety meeting is dependent upon the nature of the work and the potential inherent hazards. The Contractor's principal on site representative(s), the general superintendent, and his/her safety representative(s) shall attend this meeting.

C 306.4.2. Requirement for Safety Coordination: The Base Civil Engineer, or his/her authorized representative, shall be the determining office for each design requiring coordination with other safety offices, such as Ground Safety, Environmental, etc.

C 307 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER:

C 307.1. This provision specifies the procedure for determination of time extensions for unusually severe weather. In order for the Contracting Officer to award a time extension under this clause, the following conditions must be satisfied.

C 307.1.1. The weather experienced at the project site during the contract period must be found to be unusually severe, that is, more severe than adverse weather anticipated for the project location during any given month.

C 307.1.2. The unusually severe weather must cause a delay to the completion of the project. To be granted a time extension, the Contractor must demonstrate that the unusually severe weather directly impacted the critical path of the approved project schedule. The delay must be beyond the control and without the fault or negligence of the Contractor.

C 307.2. In accordance with the Contract Clauses entitled "Default" Fixed Priced Construction RFO 52.249-10 the following schedule of monthly anticipated adverse weather delays is based on Dyess AFB, TX base weather service climate 30 year brief or similar data for the project location and will constitute the base line for monthly weather time evaluations. The Contractor's progress schedule must reflect these anticipated adverse weather delays in all weather dependent activities.

C 307.3. Upon acknowledgment of the Notice to Proceed (NTP) and continuing throughout the contract, the Contractor will record on the daily CQC report, the occurrence of adverse weather and resultant impact to normally scheduled work. Actual adverse weather delay days must prevent work on critical activities for 50 percent or more of the Contractor's scheduled work day. The number of actual adverse weather delay days shall include days impacted by actual adverse weather (even if adverse weather occurred in previous month), be calculated chronologically from the first to the last day of each month, and be recorded as full days. The Contracting Officer may convert any qualifying delays to calendar days, giving full consideration for equivalent fair weather work days, and issue a modification in accordance with the Contract Clause entitled "Default (Fixed Price Construction)."

C 308 APPROVED EQUAL: The Statement of Objectives (SOO), drawings and the Technical Provisions of these specifications may, in some instances, refer to certain items of equipment, material, or article by trade name. References of this type shall not be construed as limiting competition, but shall be regarded as establishing a Statement of Work – Attachment 1 - page 25 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

standard of quality. The exception is Best lockset hardware & Monaco transceiver systems.

C 309 RECORD DRAWINGS (As-Built): The Contractor shall be responsible for creating and maintaining accurate record ("as-built") drawings throughout the entire project lifecycle. This process requires the Contractor to keep a set of working drawings current and to prepare a final record drawing package upon completion. The final submission must document all changes from the original contract plans and include one set of electronic CADD drawings, corresponding PDF files, and one set of bond paper prints. These deliverables are subject to review and approval by the Contracting Officer, and failure to maintain or submit accurate drawings may result in the withholding of monthly progress payments and will be required for final contract payment. Additionally, the Contractor shall provide all final shop drawings, warranty information, and a completed Construction Data Worksheet as part of the project closeout requirements.

C 310 DIFFERENCES IN DRAWINGS: In addition to the provisions of Contract Clause paragraph "Specifications and Drawings for Construction," the structural drawings shall govern in cases where they differ from the architectural drawings.

C 311 ACCEPTANCE:

C 311.1. The Contractor shall notify the Contracting Officer in writing five (5) calendar days prior to construction start of each individual task order to allow the Government sufficient time to notify the applicable using organization(s) unless this requirement is waived by the Government.

C 311.2. When either a Suspension of Work is lifted or a modification is issued the Contractor shall notify the Contracting Officer within two (2) working days prior to construction start to allow the Government sufficient time to notify the applicable using organization(s).

C 311.3. Pre-Final Inspection: Prior to requesting a Final Inspection, the Contractor shall request a Pre-Final Inspection. The request shall be made in writing five (5) working days prior to the anticipated date of the Pre-Final Inspection. The Pre-final Inspection shall be conducted with the Government inspector, the contract administrator, the Contractor's quality control representative, the Contractor's project manager and any technical experts or other parties as deemed necessary by the Government. Any discrepancies noted during the pre-final inspection will be corrected prior to the final inspection. If discrepancies are noted during the pre-final inspection the Contractor shall state in writing a date when the discrepancies will be corrected and upon completion of the discrepancy correction will notify the Contracting Officer or his/her representative in writing the discrepancies have been corrected and request a final inspection.

C 311.4. Notice of Completion of Task Order: When the Contractor is ready for the Final Inspection, he/she will request the inspection in writing to the Contracting Officer five (5) working days before the desired date.

C 311.5. Final Inspection: The Final Inspection will be performed with the Contractor by the Government Inspector, the Contract Administrator, and other pertinent Government personnel. If any discrepancies are found the final inspection becomes a pre-final inspection. Accepted projects will be fully operational for the purpose intended. Completed Construction Data Worksheet (or AF 1354) shall be submitted prior to the date the final inspection is made. In the event the as-built submittal is disapproved, it will be resubmitted within two calendar days after disapproval.

C 311.6. Transfer and Acceptance of Military Real Property (DD Form 1354): Projects will be divided into areas of work and property, categorized by Air Force category codes and associate cost. The DD Form 1354 shall include all installed or demolished property by building number if multiple buildings are involved in the project. Contractor will coordinate directly with 7 CES/CEIAP (Real Property) at 325-696-8883.

C 311.7. During the progress of the work, the Contractor shall keep a careful record at the job site of all the additions or demolitions in order to correctly fill out the DD 1354. Line items on the DD1354 shall include any surface changes and any subsurface improvements or demolition. The Contractor shall provide a preliminary DD1354 for the project electronically to the base Real Property Office, 7 CES/CEIAP fifteen (15) working days after the NTP is issued.

C 311.8. The Contractor shall submit a final DD 1354 to the Real Property Office and the Contract Officer upon final inspection.

C 312 CLOSEOUT OF TASK ORDER: The closing out of various features of the contract shall be done within thirty (30) calendar days after the Government contract construction completion date. The Contractor's

Statement of Work – Attachment 1 - page 26 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

specific submittals, and items are required for closeout may include but are not limited to Operation and Maintenance Manuals (O&M), training, spare parts, equipment list, guarantees, as-built shop drawings.

C 312.1. The following is a general list of the various types of closeout materials and the data required for each. (*indicate date required on initial submittal)

C 312.1.1. O&M Manuals: Descriptions, Specification Paragraph*, Date Due*, No. Copies Due*, Date Submit Action Code, Resubmit Date, Approved, Date to User, No. Copies

C 312.1.2. Training Requirements: Description*, Specification Paragraph*, Length Required*, Date Scheduled, Plan Submitted, Plan Approved, Date Training Held

C 312.1.3. Spare Parts Required: Description*, Specification Paragraph*, Quantity Required*, Date Turned Over to User

C 312.1.4. Salvaged Material: Description*, Specification-Plan Requirement*, Quantity*, Turn in Document Received

C 312.1.5. Government-Furnished Equipment: Description*, Specification-Plan Requirement*, GFCI-GFGI*, Number Required*, Date Equipment Date Required*, Date Equipment Required*, Turnover Document Provided

C 312.1.6. Utilities Provided or Relocated by Others: Description*, Relocate or Provide*, Specification-Plan Note*, Date Required*

C 312.1.7. Warranties:

C 312.1.7.1. Not later than the date the final invoice is submitted, the Contractor shall provide a listing to the Contracting Officer identifying as a minimum, the Task Order Number, the extent/location of work (Building number and extent of the work accomplished, e.g., entire roof, west wing, etc.), Project Number and Project Title; the date of final acceptance by the Government; and the date each warranty will expire.

C 312.1.7.2. In connection with these requirements, the Contractor shall furnish, in writing, the name, telephone number, and address of a licensed company which is authorized by the Contractor, to initiate and maintain warranty work action on their behalf. This single point of contact will be located within the local service area of the warranted work and will be responsive to Government inquiry on warranty, work action and status. The single point of contact will respond to a call within the time periods as follows: 4 hours for heating, air-conditioning, refrigeration, air supply distribution, critical electrical service systems and food service equipment, and 24 hours for all other systems. The names, addresses, and telephone numbers for day, night, weekend, and holiday service responses shall be furnished to the Contracting Officer and also posted at a conspicuous location in each mechanical and electrical room or close to the unit. This submittal may be provided once if it is applicable to all projects.

C 312.1.7.3. Compliance with this paragraph does not relieve the Contractor of any responsibility in connection with providing specific warranties and/or guarantees as required by this contract.

C 312.1.7.4. In the event the Contractor or his/her designated representative fails to commence and diligently pursue any warranty work required within a reasonable time after notification, the Government shall have the right to have the work performed by others, and after completion make demand for reimbursement of any and all expenses incurred by the Government while performing the work, including, but not limited to, administrative expenses.

C 312.1.7.5. Warranty repair work which arises to threaten the health or safety of personnel, or the safety of property or equipment will be handled by the Contractor on an immediate basis as directed verbally by the Contracting Officer. Failure of the Contractor to respond as verbally directed will be cause for the Contracting Officer to have the warranty repair work performed by others and to proceed against the Contractor as outlined above.

C 312.1.8. Project Closeout Report for Historical Data: The Contractor shall submit a Project Closeout Report detailing the actual labor hours expended and materials incorporated into the project.

C 312.1.8.1. Final Labor Hours: A breakdown of total hours by labor trade (e.g., Carpenter, Electrician,

Statement of Work – Attachment 1 - page 27 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

Plumber).

C 312.1.8.2. Final Materials List: A list of all major materials used, including a description and the total quantity.

C 312.2. During the phase-out period, the incumbent Contractor shall be fully responsible for completion of all task orders issued within the contract term.

C 313 CONTRACTOR-FURNISHED EQUIPMENT DATA: Prior to final inspection and acceptance of the work, the Contractor shall submit the data mentioned in the following subparagraphs.

C 313.1. Equipment List: An itemized equipment list showing unit retail value and nameplate data including serial number, model number, size, manufacturer, etc., for all Contractor-furnished items of mechanical equipment, electrical equipment, and fire protection systems installed under this contract.

C 313.2. Guarantees: A list of all equipment items, which are specified to be guaranteed accompanied by a copy of each specific guarantee thereof. For each specific guaranteed item, a name, address, and telephone number shall be shown on the list and warranty sticker for subcontractor who installed equipment, equipment supplier or distributor and equipment manufacturer. The completion date of the guarantee period shall correspond to the applicable specification requirements for each guaranteed item.

C 313.3. Warranty Stickers: The Contractor shall furnish and place equipment warranty stickers on all warranted equipment in the location designated by the Contracting Officer's representative. Warranty stickers shall include when warranty expires, who to contact for warranty work and the phone number for warranty work.

C 314 REQUEST FOR INFORMATION (RFI) PROCESS: All RFIs must be submitted in writing to the Contracting Officer. The Contractor shall clearly state the ambiguity, conflict, or omission discovered and propose a recommended solution. The Contractor shall not proceed with work affected by the RFI until a formal response is received from the Contracting Officer. No claim for a change order or price adjustment will be considered for an RFI unless the Contractor can demonstrate that the issue could not have been identified during a thorough review of the contract documents and a pre-proposal site investigation." This clause formalizes the RFI process and, critically, places the burden of proof on the contractor. It discourages using RFIs as a vehicle for generating change orders for issues that should have been caught during the bidding phase.

C 315 WITHHOLDING FOR DEFICIENT WORK: In addition to other remedies, the Contracting Officer may withhold from progress payments an amount sufficient to cover the cost of correcting any work that does not conform to the contract requirements. The amount withheld will be based on the Government's estimate of the correction cost, including administrative expenses. The withholding will be released upon correction and acceptance of the deficient work." This provides a direct, immediate financial tool for the CO to address quality issues. Instead of just noting a deficiency, the CO can apply immediate financial pressure to incentivize the contractor to fix the problem promptly.

C 400. SUBMITTAL PROCEDURES

C 401 SUBMITTAL CLASSIFICATIONS: Submittals are classified as follows:

C 401.1. Government Approved: Government approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Government approval is required for any deviations from the Solicitation or Accepted Proposal and other items as designated by the Contracting Officer. Within the terms of the Contract Clause Specifications and Drawings for Construction, they are considered to be "shop drawings."

C 402 APPROVED SUBMITTALS: The Contracting Officer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailed and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Contractor Quality Control (CQC) requirements of this contract is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a

Statement of Work – Attachment 1 - page 28 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

substitution is necessary.

C 403 DISAPPROVED SUBMITTALS: The Contractor shall make all corrections required by the Contracting Officer and furnish a corrected submittal. Corrected submittals shall be submitted within five (5) working days, after receipt of a disapproved submittal by the Contractor in the form and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" shall be given promptly to the Contracting Officer.

C 404 GENERAL: The Contractor shall make submittals as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken. Proposed deviations from the contract requirements shall be clearly identified. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby.

C 405 MATERIAL APPROVAL SUBMITTAL FORM (AF Form 3000):

C 405.1. The Contractor shall submit a completed Material Approval Submittal (AF Form 3000) listing items of equipment and materials required by the specifications. This list may not be all-inclusive and additional submittals may be required. Submit the material submittals and shop drawings to the Contracting Officer for approval within ten (10) calendar days after issuance of the Notice to Proceed (NTP) for each task order, unless otherwise specified in the task order.

C 405.2. Submittal Procedure: Submittals shall be made as follows:

C 405.2.1. Procedures: Original electronic documents are the required standard for all submittals. Scanned documents will only be accepted if original electronic versions are not available and must be clear, legible, and of sufficient resolution for review. All submittals (including the AF Form 3000, CAD drawings, specifications, and product cut sheets) shall be in PDF format and submitted via email. Files exceeding 10MB shall be submitted via DoD SAFE.

C 405.2.2. Physical Samples: When required by the task order specifications for architectural finishes (e.g., paint, carpet, tile), the contractor shall provide physical samples to the Government for color and texture verification alongside the AF Form 3000.

C 405.2.3. Submittal File Naming: All electronic submittals shall be named with the project number, brief project name, MS # (submittal sequence number), and brief submittal description. (*Example: 26-0020 Repair Dorms - MS #11 - Plumbing Fixtures & Equipment.pdf*)

C 405.3. Scheduling: Submittals covering component items forming a system or items that are interrelated shall be coordinated and submitted concurrently. Adequate time (a minimum of fourteen (14) calendar days) shall be allowed for Government review and approval in accordance with specification section 01 33 00. An extension to the fourteen (14) calendar day review time frame may be granted for unique or complex review situations.

C 406 CONTROL OF SUBMITTALS: The Contractor shall carefully control his/her procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date.

C 407 GOVERNMENT APPROVED SUBMITTALS: Upon completion of review of submittals requiring Government approval, the submittals will be identified as having received approval by being so electronically stamped, signed and dated. The electronic submittal will be returned to the Contractor by the CO.

C 408 MATERIAL USE SUBMITTAL The Contractor shall provide a Project Closeout Report detailing the actual labor hours and materials used for the performance of each task order.

QUALITY CONTROL

Statement of Work – Attachment 1 - page 29 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

C 501 REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

C 501.1. AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D3740-23 Standard Practice for Minimum Requirements for Agencies Engaged in Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction.

ASTM E329-25A Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection.

C 502 PAYMENT: Separate payment will not be made for providing and maintaining an effective Quality Control program, and all costs associated therewith shall be included in the applicable unit prices or lump-sum prices contained in the Bid Schedule.

C 503 GENERAL: The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause entitled "Inspection of Construction." The quality control system shall consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements. The system shall cover all construction operations, both on-site and off-site, and shall be keyed to the proposed construction sequence.

C 504 QUALITY CONTROL PLAN:

C 504.1. General: The Contractor shall furnish for review by the Government, not later than 20 calendar days after receipt of Award, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause entitled "Inspection of Construction" RFO 52.246-12. The plan shall identify personnel, procedures, control, instructions, test, records, and forms to be used. Construction will be permitted to begin only after acceptance of the CQC Plan by the Contracting Officer. Specific Task Orders may require supplemental CQC Plan updates based on project complexity.

C 504.2. Content of the CQC Plan: The CQC plan shall include, as a minimum, the following to cover all construction operations, both on-site and off-site, including work by subcontractors, fabricators, suppliers, and purchasing agents:

C 504.2.1. A description of the quality control system, including a chart showing lines of authority and acknowledgment that the CQC Manager shall implement the three phase control system (Paragraphs 507.1, 507.2, 507.3) for all aspects of the work specified. The CQC system manager shall report to the project manager or someone higher in the Contractor's organization. Project manager in this context shall mean the individual with responsibility for the overall management of the project including quality and production.

C 504.2.2. The name, qualifications (in resume format) or recognized certification, duties, responsibilities, and authorities of each person assigned a CQC function. Any replacements must have similar qualifications.

C 504.2.3. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract.

C 504.2.4. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, off-site fabricators, suppliers, and purchasing agents.

C 504.2.5. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. (Laboratory facilities shall be state of Texas approved.)

C 504.2.6. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures will establish verification that identified deficiencies have been corrected.

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

C 504.2.7. Procedures for managing subcontractors, tracking deficiencies and the means of correcting such deficiencies.

C 504.3. Acceptance of Plan: Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Contracting Officer reserves the right to require the Contractor to make changes in his/her CQC plan and operations including removal of personnel, as necessary, to obtain the quality specified.

C 504.4. Notification of Changes: After acceptance of the CQC plan, the Contractor shall notify the Contracting Officer in writing a minimum of seven (7) calendar days prior to any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

C 505 QUALITY CONTROL ORGANIZATION: The Contractor shall identify an individual within his/her organization at the worksite who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. This CQC System Manager shall be employed by the Contractor, except as noted in the following: an alternate for the CQC System Manager will be identified in the plan to serve in the event of the System Manager's absence. The requirements for the alternate will be the same as for the designated CQC Manager.

C 505.1. CQC System Manager: The CQC System Manager shall have a minimum of five (5) years of documented experience managing quality control across multiple construction disciplines, including mechanical, electrical, and structural work. Possession of a current US Army Corps of Engineers (USACE) Construction Quality Management for Contractors (CQM-C) certification is required.

C 506 SUBMITTALS: The CQC Manager shall be responsible for certifying that all submittals are in compliance with the contract requirements before submitting to Government.

C 507 CONTROL: The controls shall include at least three phases of control to be conducted by the CQC System Manager for all definable features of work, as follows:

C 507.1. Preparatory Phase: This phase shall be performed prior to beginning work on each definable feature of work and shall include:

C 507.1.0. A review of each paragraph of applicable specifications.

C 507.1.1. A review of the contract drawings.

C 507.1.2. A check to assure that all materials and/or equipment have been tested, submitted, and approved.

C 507.1.3. A check to assure that provisions have been made to provide required control inspection/testing.

C 507.1.4. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.

C 507.1.5. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.

C 507.1.6. A review of the appropriate activity hazard analysis to assure safety requirements are met.

C 507.1.7. Discussion of procedures for constructing the work including repetitive deficiencies.

C 507.1.8. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.

C 507.1.9. The Government shall be notified at least 48 hours in advance of beginning any of the required action by the preparatory phase, The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

C 507.2. Initial Phase: This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

C 507.2.0. A check of preliminary work to ensure that it is in compliance with contract requirements.

Statement of Work – Attachment 1 - page 31 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

- C 507.2.1. Verification of full contract compliance. Verify required control inspection and testing.
- C 507.2.2. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with the definable features sample (prototype) element as appropriate.
- C 507.2.3. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis.
- C 507.2.4. The initial phase should be repeated for each new crew to work on-site, or any time acceptable specified quality standards are not being met.
- C 507.3. Follow-up Phase: Daily checks shall be performed to assure continuing compliance with contract requirements, including control testing, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work, which may be affected by the deficient work. The Contractor shall not build upon or conceal non-conforming work.

C 508 TESTS:

- C 508.1. Testing Procedure: The Contractor shall perform specified or required tests to verify that control measures are adequate to provide a product which conforms to contract requirements. Testing includes operation and/or acceptance tests when specified. The Contractor shall procure the services of an approved testing laboratory or establish an approved testing laboratory at the project site. The Contractor shall perform the following activities and record and provide the following data to the Contracting Officer on electronic AF 3000:
 - C 508.1.0. Verify that testing procedures comply with contract requirements.
 - C 508.1.1. Verify that facilities and testing equipment are available and comply with testing standards.
 - C 508.1.2. Check test instrument calibration data against certified standards.
 - C 508.1.3. Verify that recording forms and test identification control number system, including all of the test documentation requirements, have been prepared.
 - C 508.1.4. Results of all tests taken shall be submitted in electronically to the Contracting Officer for approval as a submittal. Both passing and failing tests, will be recorded on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test will be given. If approved by the Contracting Officer, actual test reports may be submitted later with a reference to the test number and date taken. An information copy of tests performed by an off-site or commercial test facility will be provided directly to the Contracting Officer. Failure to submit timely test reports as stated may result in nonpayment for related work performed and disapproval of the test facility for this contract.
- C 508.2. Testing Laboratories
 - C 508.2.0. Capability Check: The Government reserves the right to check laboratory equipment in the proposed laboratory for compliance with the standards set forth in the contract specifications and to check the laboratory technicians' testing procedures and techniques. Laboratories utilized for testing soils, concrete, asphalt, and steel shall meet criteria detailed in ASTM D 3740 and ASTM E 329.
 - C 508.2.1. Capability Recheck: If the selected laboratory fails the capability check, the Contractor will be assessed a charge of \$2,500 to reimburse the Government for each succeeding recheck of the laboratory or the checking of a subsequently selected laboratory. Such costs will be deducted from the ~~delivery~~ task order for which the capability recheck applies.
- C 508.3. Laboratory: The Government reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.
- C 508.4. Furnishing or Transportation of Samples for Testing: Costs incidental to the transportation of samples or materials will be borne by the Contractor.

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

C 509 COMPLETION INSPECTION: At the completion of all work or any increment thereof established by a completion time stated in the Special clause entitled "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the CQC System Manager shall conduct an inspection of the work and develop a "punch list" of items which do not conform to the approved drawings and specifications. Such a list of deficiencies shall be included in the CQC documentation, as required by paragraph DOCUMENTATION below, and shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected and so notify the Government for a pre-final inspection. These inspections and any deficiency corrections required by this paragraph will be accomplished within the time stated for completion of the entire work or any particular increment thereof if the project is divided into increments by separate completion dates.

C 510 DOCUMENTATION: The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

- C 510.1. Contractor/subcontractor and their area of responsibility.
- C 510.2. Operating plant/equipment with hours worked, idle, or down for repair.
- C 510.3. Work performed each day, giving location, description, and by whom.
- C 510.4. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase should be identified (Preparatory, Initial, Follow-Up). List deficiencies noted along with corrective action.
- C 510.5. Submittals reviewed, with contract reference, by whom, and action taken.
- C 510.6. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- C 510.7. Instructions given/received and conflicts in plans and/or specifications.
- C 510.8. Contractor's verification statement: These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.
- C 510.9. Submittal: All above Documentation records shall be scanned & converted to a single pdf. This electronic file shall be submitted at project completion for the Government's records.

C 511 NOTIFICATION OF NONCOMPLIANCE: The Contracting Officer shall notify the Contractor in writing of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the worksite, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

WORK IN CONTROLLED AREAS

C 601 GENERAL ENTRY PROCEDURES: Because controlled areas are restricted access areas, working conditions will be subject to the following security restrictions and construction sequencing. All work within the controlled areas shall be performed under escort or established free zones. The Contractor shall provide a schedule

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

of work in controlled areas to the Contracting Officer at least seven (7) working days prior to the start date. This allows for the timely arrangement of required escorts.

C 601.1. Construction Of Free Zone: Before any other work begins in areas designated as free zones, the free zone barriers shall be constructed. The materials required for barrier will be addressed in the individual task order. During this period, access to the site will be through the Entry Control Point (ECP) and workmen will be escorted at all times by Air Force Personnel as described under "Standard Entry Procedures".

C 601.2. Construction Start: Once the free zone is made operational, normal construction can begin. Access to the free zone sites during this time will be through the ECP and the procedures described under "Free Zone Procedures".

C 601.3. Removal Of Free Zone: Once work under this contract is accepted as substantially complete, the free zone will be deactivated. The Contractor constructed barriers shall be removed and the ground and pavement restored to its original condition at the Contractor's expense. This work will be done under the "Standard Entry Procedures".

C 601.4. Security Exercises And Convoys: When weapons convoy inter-area movements are formed in these areas, the Contractor will be prohibited from entering or leaving the affected areas. The Contractor, if inside the area already, may be required to relocate his/her personnel from the convoy route which includes leaving the area. During security exercises, the Contractor will not normally be required to leave the area. The security forces can respond into free zones for response to alarms from the perimeter when gates are blocking inner roads.

C 602 RESTRICTED AREA ENTRY PROCEDURES: All Contractor personnel and employees will be under escort at all times while within the restricted area. The Base Escort Pool (coordinated and monitored by the 7th BW) will provide and perform all escort duties. The number of escorts will be determined by the requirements to provide at least one individual per work crew or work area. Each escort shall be able at all times to have visual contact with all members of the work crew. The Contractor shall restrict his/her personnel to the project construction areas within the restricted areas and shall limit construction operations to the work areas defined or indicated on the drawings. If access is required to other work areas, except for Base transit to enter or leave work areas, entry clearance shall be arranged through the Contracting Officer at least 72 hours in advance. Contractor shall provide a fourteen (14) calendar day notice in writing, to Contracting Officer, on all activities requiring escorts.

C 602.1. Entry Authorization Letter (EAL): Fourteen (14) calendar days prior to the initial start of construction in this area, the Contractor shall provide Civil Engineering (7 CES/CEP) and Contracting (7 CONS/PKB) with a list of employees requiring entry. This list will include the full name, company name, date of birth, and last six numbers of social security number of each employee; the make, model, color, year, license number and state of each vehicle.

Also included shall be where the restricted access is needed, why the restricted access is needed and for what duration. Subsequent additions to the EAL may be made by letter five (5) working days in advance of the employee's arrival. Employees who have been terminated or dismissed shall be removed from the entry list immediately. This is in addition to the EAL mentioned in C 203.20.

C 602.2. Personnel Entry: Only personnel on the EAL will be allowed into the area. All personnel will be subject to an I.D. check and a metal detector search each time they enter and exit the area. Once inside, they must be escorted at all times by Government personnel. All vehicles entering and/or leaving a restricted area will be searched by security personnel. Because of these personnel and vehicle searches and possible waiting time for escort arrival, the Contractor can expect short delays for personnel and vehicle processing in and out of the area. Each employee shall be required to carry two forms of identification. One form shall include a picture and both shall bear the employee's signature.

C 602.3. Vehicles: Only company-owned vehicles will be allowed inside a restricted area. No privately-owned vehicles will be permitted inside. Each vehicle must be identified by company name on both sides of the vehicle. Magnetic signs are acceptable. Vehicles and motorized equipment are not to be left unattended inside or within 100 feet of a restricted area unless immobilized by removing the key or other suitable means. Under no circumstances will vehicles be parked within 30 feet of the perimeter fence (both inside and outside of a restricted area). Pickup trucks and passenger vehicles shall be equipped with one fire extinguisher per

Statement of Work – Attachment 1 - page 34 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

vehicle rated 4 B.C. All other vehicles shall have two extinguishers per unit rated 8 B.C. Vehicles shall be able to pass a state safety inspection.

C 603 FREE ZONE PROCEDURES: If work falls within a restricted area. Operations shall be kept uninterrupted. For this purpose, contractor shall submit a request for a temporary free zone area based on the pre-coordinated/approved phasing plan. Close coordination with airfield manager, 7 SFS, 7 CONS and 7 CES shall be done to establish phases and temporary free zones.

C 604 FLAME-PRODUCING DEVICES: Flame-producing equipment such as matches and lighters are not permitted inside a restricted area.

C 605 EQUIPMENT STOCKPILES AND CONSTRUCTION DEBRIS: Equipment stockpiles and construction debris shall be kept a minimum of 50 feet away from perimeter fencing.

C 606 CONTRACTOR OPERATIONAL FACILITIES: The Contractor shall be required to provide portable latrine facilities inside the free zone and also locate, as necessary, storage trailers in the area. All trailers left inside a restricted area after hours must be lockable from the exterior with a padlock and hasp.

C 607 MISCELLANEOUS:

C 607.1. Contractor's use of CBs, recording devices, and cameras shall be prohibited in a restricted area. The use of 2-way portable radios will be allowed with prior approval from Communications Squadron.

C 607.2. During the course of this contract execution the Contractor's workforce may be within safety clear zone of explosives stored inside the igloos.

C 608 DRAINAGE: Grading and excavating shall be done in a manner to prevent standing water on existing fence sensor systems.

C 609 EMERGENCY OUTAGES: The Contractor shall notify the Contracting Officer immediately when an emergency outage of a utility occurs. No outage shall exceed four (4) hours in duration. The Contractor shall bear the cost for all repairs.

C 610 SECURITY FENCE WORK: Any digging under the security fence due to the Contractor's operations shall be backfilled by the end of the Contractor's workday so that no breach of physical security is present overnight. All excavations underneath the security fence shall be backfilled or barricaded in a manner acceptable to the Security Forces through the Contracting Officer or the Contracting Officer's representative prior to the end of each workday or when the Contractor leaves the immediate work site.

C 611 SECURITY LIGHTING/COMMUNICATION OUTAGES: All outages of the existing security lighting system must be coordinated seven (7) working days in advance through the Contracting Officer and must not exceed four (4) hours in duration. The security lighting system must be functional at all times during hours of darkness. Work on this lighting system must be scheduled and performed in stages with this requirement in mind. Lighting, being replaced by new lighting, cannot be deactivated until the new system is proven completely functional.

C 611.1. Any outages occurring to the security lighting/communication systems due to the Contractor digging in a restricted area must be repaired within four (4) hours at the Contractor's expense.

C 700. ENVIRONMENTAL PROVISIONS

C 701 ENVIRONMENTAL REFERENCES: The Contractor is responsible for strict adherence to any local, State, and Federal environmental regulations relating to this project. 7 CES/CEIE is the base point of contact for environmental compliance/non-compliance issues and will provide the Contractor a briefing of environmental requirements at the pre-performance conference for this project. Additionally, the Contractor should contact the

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

Contracting Officer whenever interpretations of environmental regulations are required. Refer to specifications section 00 01 04 – Environmental Specifications.

C 702 HAZARDOUS MATERIAL SUBMITTAL REQUIREMENTS:

C 702.1. Submittals shall be required for all hazardous materials (most materials contain hazardous constituents). For the purposes of this project, hazardous material shall be defined as any material or mixture of materials which may present a danger to the public health, occupational safety, or the environment and include:

C 702.1.1. Materials containing chemicals defined under Section 1910.122(c) of Title 29 of the Code of Federal Regulations (CFR), any extremely hazardous substance listed in 40 CFR part 355; and any pesticide for which a registration has been canceled or suspended under the provisions of the Texas Pesticide Registration Act, section 281.210 through section 281.310 of the Revised Statutes of Texas (TCEQ), and 2 Code of State Regulations (C.S.R) 70-25.010 et seq., or under the Federal Environmental Pesticide Control provisions of 7 United States Code (U.S.C.) section 136, et seq., and;

C 702.1.2. Materials containing any element, compound, mixture, solution or substance as designated pursuant to sections 101(14) and 102 of the Comprehensive Environmental Response, Compensation, and Liabilities Act of 1980 (CERCLA), codified at 42 U.S.C. sections 9601(14) and 9602, or requiring notice pursuant to section 304 of the Emergency Planning and Community Right-to-Know Act of 1986, codified at 42 U.S.C. section 11004, and;

C 702.1.3. Any hazardous material, or group or class of material, designated as hazardous by United States Secretary of Transportation under 49 U.S.C. section 5103.

C 702.2. Prior to the Contractor transporting any hazardous material onto Dyess AFB, the Contractor must provide a current copy of the manufacturer's Material Safety Data Sheet (MSDS) to the Contracting Officer for certification. The Contractor must ensure the MSDS contains at minimum, the following information and additional documentation from the manufacturer defining the values of items not directly addressed by the MSDS:

C 702.2.1. Manufacturer's Name

C 702.2.2. List 100% of the hazardous chemical components

C 702.2.3. Chemical Abstract Number (CAS Number) for each chemical component

C 702.2.4. Specific Gravity/Unit Volume and or Unit Weight

C 702.2.5. Ph (Acidity or Alkalinity) if applicable

C 702.2.6. Flash Point/Ignitability

C 702.2.7. Exact weight in pounds/ounces of the material initially brought on base

C 702.3. No hazardous materials for this project shall be allowed on base until the Contractor has received written approval of the submittal for the material in question from the Contracting Officer. If the Contractor's intent is to bring more of the product (same manufacturer) on base property after the product has received approval, only a weight submittal will be required. If it is a different manufacturer from that originally submitted, a new MSDS submittal will be required.

C 702.4. All material tracking shall be done on the Hazardous Material Tracking List which must be; 1) submitted initially, 2) whenever new hazardous materials are added to the project (minimum of sixty days between update) and 3) a final update when leftover materials are removed upon completion of the project. Prior to final acceptance of this project, the Contractor must submit a listing of all hazardous materials relating to this project. The Hazardous Materials Tracking List will include the product name, manufacturer, and exact weight of material remaining.

C 702.5. When special haul routes are required to deliver or remove hazardous materials for this project it shall be addressed by the Contracting Officer during review and approval of each hazardous material submittal.

C 703 HAZARDOUS WASTES DISPOSAL REQUIREMENTS:

C 703.1. All hazardous wastes generated by this project shall be handled in the manner required by the State of Texas and Federal regulations (40 CFR, and 49 CFR). For this project hazardous waste shall be defined as
Statement of Work – Attachment 1 - page 36 of 39

CUI

CUI

Attachment 1
STATEMENT OF WORK

Dyess AFB, Texas
SABER

any solid wastes satisfying the criteria listed in 40 CFR 261.3.

- C 703.2. The Contractor shall ensure wastes generated by this project that have been chemically altered during this project are sampled and analyzed to establish levels of all possible Resource Conservation Recovery Act contaminants.
- C 703.3. The Contractor shall perform all required training and notifications concerning hazardous waste or materials related to Contractor's activities and maintain an on-site listing of employees so trained.
- C 703.4. The Contractor shall be responsible for proper labeling, containerization, handling, and storage of hazardous wastes created from this project.
- C 703.5. As required by 40 CFR, Dyess AFB is the "generator" of all hazardous wastes originating within the confines of the installation and as such is required to certify all hazardous waste is properly prepared and shipped by signing the manifest for off-site transport. All hazardous waste shipments shall be initiated by completion of a "Hazardous Waste Manifest" EPA Form 8700-22 (Rev. 9-94) MDNR-HWG 10) obtainable from the Texas Department of Natural Resources. The Contractor shall be responsible for obtaining all necessary manifest forms and for proper completion of each required by this project.
 - C 703.5.1. The Contractor shall obtain all manifest numbers from 7 CES/CEIE.
 - C 703.5.2. Each manifest line item must have the quantity listed on the manifest in pounds except Polychlorinated Biphenyl's (PCBs) which shall have the quantity listed in Kilograms.
 - C 703.5.3. Each manifest line item must have supporting documentation to allow proper chemical characterization of the hazards as defined in 40 CFR. Sampling and analysis will be required on all wastes which have been contaminated or altered during the course of this project.
 - C 703.5.4. The Contractor shall insure all hazardous wastes are moved off base only by properly licensed hazardous waste transporters and are sent to properly licensed disposal facilities.
 - C 703.5.5. 7 CES/CEIEC shall be the only authorized agency to sign each manifest for wastes being transported off Dyess AFB. Each shipment must be evaluated by 7 CES/CEIEC for compliance with applicable environmental regulations prior to signing the manifest. The Contractor shall retain the responsibility for correction of all discrepancies noted during the pre-transport evaluation.

(Note: CEIEC personnel are available from 07:30 to 16:30, Monday through Friday).

C 704 INSPECTION LIABILITY:

- C 704.1. The Contractor shall understand that any operations on Dyess AFB property are fully inspectable (on a no notice basis) by the Department of Defense, The Department of the Air Force, Texas Department of Natural Resources (TDNR), Environmental Protection Agency (EPA), Occupational Health and Safety Agency (OSHA), and other federal regulatory agencies. Compliance with all environmental requirements pertaining to this project is mandatory.
- C 704.2. The Contractor is subject to no-notice inspections of all activities related to the project by 7 CES. Issues of noncompliance will be addressed directly to the Contracting Officer or his/her representative to ensure rapid correction of the unsatisfactory features.
- C 704.3. The Contractor is liable to the Air Force for any fines, penalties, or environmental assessments levied against the Air Force by any environmental regulatory agency that arise from, or relate to, the Contractor's performance of this contract, or the contractor's failure to perform as specified by the contract. Any such liability may result in an equitable adjustment to the contract or contract price, establishment of a contract debt, or recovery by the Government under any other judicial, administrative, or contractual remedy as may be available to the Government.

C 705 POLLUTION ABATEMENT: The Contractor shall perform all work in a manner minimizing pollution of air, water, and land, as required. Refer to specification section 00 01 04 – Environmental Specification.

C 706 POLICY FOR STORAGE OF HAZARDOUS MATERIALS ON CONSTRUCTION SITES: The

Statement of Work – Attachment 1 - page 37 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

following is the policy for storage of hazardous materials on construction sites located at Dyess AFB, TX.

- C 706.1. Definition of hazardous materials is any substance which, by reason of being explosive, flammable, poisonous, corrosive, oxidizing, irritating, or otherwise harmful, and is likely to cause death or injury.
- C 706.2. Hazardous material will not be stored in Government facilities, without special authorization from the Base. Contact point will be the Fire Department at 325-696-2486.
- C 706.3. Each construction site shall have a hazardous material storage area. This area will be the only location where hazardous material shall be stored on a construction site. Exceptions must have prior written approval from the Base. Contact point will be the Fire Department at 325-696-2486.
- C 706.4. Number every trailer, building and shed with a number at least 6 inches by 4 inches; this number will correspond with the numbers listed below in item 706.5.1.
- C 706.5. The Contractor will provide an emergency folder that will be kept on-site and up-to-date at all times (on the injury board). This folder shall contain:
 - C 706.5.1. Construction site map identifying each road, building, trailer, and shed on site by number, as well as hazardous material storage location.
 - C 706.5.2. A copy of every MSDS Material Safety Data Sheet (MSDS) with amount and location of all hazardous material on site.
- C 706.6. The Contractor will also provide a copy of each map and MSDS to the Base Fire Department, Building 5013 (Dispatch Office) immediately upon delivery of all hazardous material to the construction site.

C 707 UNEXPECTED ASBESTOS ON CONSTRUCTION (RENOVATION/DEMO): The buildings and areas to be renovated or demolished have been or will be surveyed for the presence of asbestos-containing materials. This survey is not a warranty that asbestos-containing materials are either not present or limited to the amounts found in the survey. Should suspected asbestos-containing material be encountered, the Contractor shall promptly, and before the conditions of the substance encountered is disturbed, give a written notice to the Contracting Officer of the suspected asbestos-containing material conditions encountered. As directed by the Contracting Officer, the Contractor shall remove and dispose of any and all asbestos-containing material as necessary to accomplish the required work which shall be performed in accordance with all pertinent local, state, and federal laws.

C 708 UNEXPECTED HAZARDOUS SUBSTANCES: In the event that suspected hazardous substances are revealed during construction activities, all such construction activities in the immediate area shall be immediately suspended. Hazardous substances for purposes of this specification only, shall be defined as CERCLA hazardous substances, infectious or radioactive wastes, asbestos or oil. The Contractor shall leave the materials undisturbed and shall immediately report the find by phone, followed in writing within 24 hours to the Contracting Officer so that proper authorities can be notified. The Contractor shall not resume construction activities in the vicinity of the suspected hazardous substances until written clearance is received from the Contracting Officer. Identification and removal of any such materials will be conducted in accordance with all Federal, state and local environmental laws and regulations according to the Contract Clause entitled "Differing Site Conditions" RFO 52.236-2.

C 709 DEMOLITION: Disposal of demolition waste shall be in accordance with all applicable Federal, State and local regulations and specification section 02 41 00 – Demolition.

C 800. CYBERSECURITY AND NETWORK PROTECTION

C 801 NETWORK AND INFORMATION SYSTEMS SECURITY:

C 801.1. Prohibition on Unauthorized Connections: The contractor, including all subcontractors and personnel, is strictly prohibited from connecting any contractor-owned, personally-owned, or third-party device to any United States Air Force (USAF) or Department of Defense (DoD) network. This prohibition includes, but is not limited to, connections via physical (e.g., hardwire, USB), wireless (e.g., Wi-Fi, Bluetooth), or any other communication technology. This restriction applies to all government information systems, facility-related control systems, and network infrastructure.

C 801.2. Authorization for Connection: In the rare event that a connection is required to fulfill the duties of a task order, the contractor must obtain explicit, written permission and vetting through the proper installation channels, Statement of Work – Attachment 1 - page 38 of 39

CUI

CUI

Attachment 1

Dyess AFB, Texas

STATEMENT OF WORK

SABER

including the designated Information Systems Security Manager (ISSM) and the Authorizing Official (AO). Any request for connection must be submitted well in advance to the Contracting Officer and include a detailed justification and security compliance plan. No connection of any type is permitted until formal, written approval has been granted.

C 801.3. Consequences of Unauthorized Actions: Any unauthorized connection, or attempt thereof, constitutes a direct violation of governing DoD policy and contractual obligations. Such actions will result in serious repercussions, including, but not limited to, immediate work stoppage, revocation of system and site access, breach of contractual obligations, and initiation of formal incident response proceedings. Violations may be escalated to the Authorizing Official for further enforcement and adjudication. At no time is an unauthorized connection permissible.

CUI