

TECHNICAL PROVISIONS – I

STATEMENT OF WORK

<u>PROJECT NO</u>	<u>TITLE</u>	<u>LOCATION</u>
VA-300000322266	Construct a community parking lot	USAG Humphreys

DESCRIPTION: The work to be performed for completion of this project shall be in general as described below and executed by one or more of the groups.

a. Work by Contractor:

- (1) The contractor shall provide all labor, tools, equipment, supplies and any other resources necessary to accomplish the scope of work contained herein as indicated in the drawings and in accordance with the specifications.
- (2) The contractor shall construct a community parking lot in accordance with the specifications and drawings.

b. Work by In-House Forces: Not applicable to this project.

c. Work by Troop Labor: Not applicable to this project.

PRINCIPAL FEATURES: This project includes, but will not be limited to the following principal features:

Schedule # I, Construction/Alternation (L): All work shall be in accordance with the attached drawings and specifications.

Civil work

1. Remove existing AC pavement.
2. Remove existing concrete curb & gutter.
3. Remove existing concrete sidewalk.
4. Remove existing steel post signage.
5. Remove existing steel post grating covered concrete ditch.
6. Remove existing trees.
7. Remove existing synthetic & concrete wheel stop.
8. Remove existing drainpipe.
9. Construct AC pavement with base & sub-base course.
10. Construct concrete sidewalks.
11. Construct concrete curbs.
12. Construct concrete curb & gutter.
13. Construct curb inlet.
14. Construct surface inlet.
15. Construct steel grating covered with concrete ditch.
16. Restore concrete sidewalk.
17. Provide geogrid.
18. Provide concrete ramps
19. Provide drain line with RCP.

20. Provide island
21. Provide synthetic wheel stop
22. Provide steel post signage with concrete footing.
23. Provide earthwork (filling, compaction & grading work).
24. Paint road marking and parking stripes.
25. Adjust manhole & water valve top elevation
26. Plant trees.
27. Solid sodding with topsoil.

Electrical work

1. Install exterior lighting fixtures and poles.
2. Install electrical manhole.
3. Install new electrical power line for exterior lighting fixture.
4. Install panel board, lighting contractor, photocell with supporting channel.
5. Replace existing pad mounted type transformers, primary/secondary lines and conduits with new ones.
6. Install new manhole and splice kit for well control.
7. Install underground cable line in new 4 ways of 103C PVC duct.
8. Remove existing concrete pole, cables and messenger wires.
9. Cut off roads, sidewalks and landscaping lawn, and restore them to their previous condition.

TECHNICAL DETAIL SPECIFICATIONS

<u>PROJECT NO</u>	<u>TITLE</u>	<u>LOCATION</u>
VA-300000322266	Construct a community parking lot	USAG Humphreys

GENERAL: The specification sections listed below are applicable to this project. The specifications are from the “Standard Technical Specifications for O&MA Projects, Korea, Revision 1” (2014 OMA SPECS, REVISION 1), dated 20151030, located on the http://www.usfk.mil/Portals/105/Documents/Contracting/NewContract/2014-OMA-SPECS_REVISION-1.pdf. The electronic version of the specifications is Acrobat® PDF format and can be read with the Acrobat Reader® software.

TECHNICAL PROVISIONS - III

SPECIAL CONDITIONS

<u>PROJECT NO</u>	<u>TITLE</u>	<u>LOCATION</u>
VA-300000322266	Construct a community parking lot	USAG Humphreys

1. GENERAL: In addition to the requirements specified under "GENERAL PROVISIONS" for the Fixed Price Construction Contract for this project, the Contractor shall comply with the following "SPECIAL CONDITIONS" which form a part of the contract.

2. WORK HOURS: The work will be accomplished from 0730 hours through 1730 hours, from 1 October through 30 April and from 0730 hours through 1930 hours from 1 May through 30 September, Mondays through Saturdays, except for Korean Legal Holidays: Any proposed change in working hours should be approved by the Contracting Officer (KO) and Contracting Officer's Representative (COR).

3. NOTIFICATION OF INSPECTION SECTION: Prior to starting work the contractor shall notify the COR of the actual date he intends to start work. The contractor shall also give the project inspector seven working day notice prior to each concrete placement, field test, weld application, protective coating application, or any other work deemed to require inspection.

4. INSTALLATION ACCESS AND CONTROL

4.1 Installation Access: Entry to the installation requires the following: Prior coordination with the COR or designated representative, current vehicle registration, proof of insurance, valid driver's license for the vehicle driver, and picture identification for other personnel. The Contractors/Subcontractors and their employees requiring access to the installation will be required to comply with the installation access control policy/procedures. The Contractor(s) with whom this Agreement is made shall provide a listing of vehicles that will require installation access upon the establishment of this contract (MATOC). The Government will not be responsible for damages due to delay/stoppages caused by failure to comply.

4.2 All contractors' employees shall be easily recognized by wearing uniform and/or name tag during the performance of work under this contract (MATOC). All cargo vehicles also shall be identified as performers by displaying company name during working hours.

4.3 Search and Control: Installations across South Korea are controlled access posts. All vehicles and personnel are subject to search and seizure of contraband and/or unauthorized Government property. Contractor-owned vehicles, Contractor employees, and their personal property shall be subject to searches and seizure of contraband and/or unauthorized Government property upon entering or leaving the Installation. The search and seizure provisions of AR 190-16, Physical Security, shall apply to Contractor personnel entering any installation.

5. ANTITERRORISM:

5.1. AT Level I training. *This standard language is for contractor employees with an area of performance within an Army controlled installation, facility or area.* All contractor employees, to include subcontractor employees, requiring access Army installations, facilities and controlled access areas shall complete AT Level I awareness training within 30 calendar days after contract start date or effective date of incorporation of this requirement into the contract, whichever is applicable. The contractor shall submit certificates of completion for each affected contractor employee and subcontractor employee, to the COR or to the contracting officer, if a COR is not assigned, within 7 calendar days after completion of training by all employees and subcontractor personnel. AT level I awareness training is available at the following website: <http://jko.jten.mil>.

5.2. Access and general protection/security policy and procedures. *This standard language is for contractor employees with an area of performance within Army controlled installation, facility, or area.* Contractor and all associated sub-contractors employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personal identity verification requirements (FAR clause 52.204-9, Personal Identity Verification of Contract or Personnel) as directed by DOD, HQDA and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

5.3. For contractors that do not require CAC, but require access to a DoD facility or installation. Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05/AR 190-13), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative), or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations.

5.4. iWATCH Training. *This standard language is for contractor employees with an area of performance within an Army controlled installation, facility or area.* The contractor and all associated sub-contractors shall brief all employees on the local iWATCH program (training standards provided by the requiring activity ATO). This local developed training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR. This training shall be completed within 30 calendar days of contract award and within 7 calendar days of new employees commencing performance with the results reported to the COR NLT 30 calendar days after contract award.

6. **OPERATIONS SECURITY**: Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III), Terrorist Screening Database (TSDB) (Army Directive 2014-05/AR 190-13), and all other applicable background checking processing in accordance with (IAW) the United States Forces Korea (USFK) Military Police Installation Access Control Regulation 190-7, the status of forces agreement (SOFA), and all other theater regulations.

7. **SUBMITTALS**: The contractor shall provide contract progress schedule and submittal register within 5 working days after Notice to Proceed (NTP) is issued.

8. **COORDINATION**: The Contractor shall coordinate its work with all others (subcontractor and government agencies) involved in the project and shall cooperate with all other contractors and government agencies to facilitate the general progress of the work. The contractor shall be provided a list of other government agencies and other contractors as applicable, at the pre-construction conference for coordination purposes.

9. **CONSTRUCTION**: Prior to start of any work for civil, mechanical and electrical, the contractor shall obtain written permission from the COR. The contractor shall submit a request for the construction permit in writing, at least ten (10) working days prior to the anticipated start of work. The request shall be submitted to the COR.

10. **MATERIALS COMPLIANCE**: The contractor shall make certain all materials used meet the requirements of the contract and proof thereof upon request of the COR. Materials not meeting the requirements of the contract shall not be brought to the job site. All materials shall be new and the standard products of a manufacturer regularly engaged in the manufacturing of such materials. Submittals obliged by this contract such as construction progress schedule, contractor quality control plan, safety plan, submittal registry, and ENG form 4025(including attachments) will not be accepted in paper format and must be electronic files submitted via CD/DVD to COR.

11. **HOISTING AND MOVING EQUIPMENT**: The prime contractor and subcontractor shall provide all cranes, lifts, and any other moving equipment necessary for the proper and efficient movement of materials. The equipment shall be provided with proper guidelines, bracing, safety devices, and any other associated safety measures, as required by USACE EM 385-1-1. Prime contractor and subcontractors are responsible for safe operations.

12. **EQUIPMENT**: All Contractor equipment shall be functional and must meet safety standards in accordance with USACE EM 385-1-1. It is the responsibility of the contractor to inspect all of its equipment prior to use. Equipment not completely safe or functional as determined by the Government, shall be repaired and replaced before work is initiated.

13. **RECORD DRAWINGS**: During performance under this contract, the contractor shall accurately record and delineate on a set of electronic CAD and PDF of contract drawings, all changes in such work which constitute departures from the original contract drawings. The set of drawings (electronic CAD and PDF), thus corrected and changed, usually referred to as "As-Built" drawings, shall be delivered to the COR at the final acceptance inspection by the Government of the completed work.

14. UTILITY CUTOVERS AND INTERRUPTIONS: Ensure utility cutovers and interruptions are conducted after normal working hours or on Saturdays, Sundays, and U. S. Government holidays as identified in Local Clause 5152.222-4007. Ensure that new utility lines are complete, except for the connection, before interrupting existing service. Interruption to water, sanitary sewer, storm sewer, telephone service, electric service, air conditioning, heating, fire alarm, compressed air, shall be considered utility cutovers. All utility cutovers and interruptions shall be coordinated with the Contracting Officer Representative (COR).

15. WORK OUTSIDE REGULAR HOURS: Unless specified in the task order, work outside regular working hours requires Contracting Officer's approval. A written request, substantiating the reason for this consideration, should be made at least fourteen (14) calendar days prior to such work to allow arrangements to be made by the Government for inspecting the work in progress, giving the specific dates, hours, location, type of work to be performed, contract number and project title. Based on the justification provided, the Contracting Officer may approve work outside regular hours. During period of darkness, the different areas at the work site shall be lighted in a manner approved by the Contracting Officer. The Contractor shall make utility cutovers after normal working hours or on Saturdays, Sundays, and U.S. Government holidays, unless directed otherwise.

16. WINTERIZATION: The contractor may be required to perform weather sensitive work during the winter season, which may cause additional costs to be incurred for the contractor. These additional costs are the contractor's responsibility in the event it is required to work during the winter.

APPENDIX "A"

LIST OF APPLICABLE CONTRACT DRAWING

<u>PROJECT NO</u>	<u>TITLE</u>	<u>LOCATION</u>
VA-300000322266	Construct a community parking lot	USAG Humphreys

GENERAL: The work shall conform to the attached contract drawings and the standard detail drawings (dated 30 November 2015, issued by the Department of the Army, Installation Management Agency, Korea Region Office and located 411th CSB's Web <http://www.usfk.mil/Resources/ContractingwithUSFK.aspx>, all of which form a part of the specifications.

<u>Drawing No.</u>	<u>Sheet No.</u>	<u>Ref. No.</u>	<u>Description</u>	<u>Date</u>
26-013	1 of 1	T-1	Title sheet	6 March 2026
			25 FEB 2026	
"	1 of 29	C -1	Location Plan	"
"	2 of 29	C -2	Existing site condition	"
"	3 of 29	C -3	Removal plan	"
"	4 of 29	C -4	Site layout	"
"	5 of 29	C -5	Grading plan	"
"	6 of 29	C -6	Drainage plan	"
"	7 of 29	C -7	Drain line profiles-1	"
"	8 of 29	C -8	Drain line profiles-2	"
"	9 of 29	C -9	Drain line profiles-3	"
"	10 of 29	C -10	Section-1	"
"	11 of 29	C -11	Section-2	"
"	12 of 29	C-12	Section-3	"
"	13 of 29	C-13	Parking lot layout plan	"
"	14 of 29	C-14	Layout plan	"
"	15 of 29	C-15	Miscellaneous -1	"

<u>Drawing No.</u>	<u>Sheet No.</u>	<u>Ref. No.</u>	<u>Description</u>	<u>Date</u>
26-013	16 of 29	C-16	Miscellaneous -2	6 March 2026
“	17 of 29	C-17	Miscellaneous -3	“
“	18 of 29	C-18	Miscellaneous -4	“
“	19 of 29	C-19	Concrete ditch with steel grating	“
“	20 of 29	C-20	Curb inlet	“
“	21 of 29	C-21	Surface inlet	“
“	22 of 29	C-22	Geo-grid detail	“
“	23 of 29	C-23	Lockable manhole cover	“
“	24 of 29	C-24	Triangle wooden stake installation detail	“
“	25 of 29	E-1	Abbreviations, panel board ”EL” load schedule, legend, notes “ and scope of work	“
“	26 of 29	E -2	Electrical removal plan	“
“	27 of 29	E -3	Electrical site plan	“
“	28 of 29	E -4	Exterior lighting control panel detail	“
“	29 of 29	E -5	Exterior lighting control diagram, lighting pole detail and LED type exterior light detail	“