

Statement of Work (SOW)

Replace Restroom Fixtures and Tile in Comfort Station– PMIS # 331321

Site Location

Shiloh National Military Park
1055 Pittsburg Landing Road, Shiloh Tennessee 38376
Comfort Station – FMSS # 69036

Background

The interior fixtures in this building were last updated in 2001. The existing tile is showing signs of wear as well as the fixtures and partitions.

Required Services

This work consists of a contractor providing all labor, materials, and equipment necessary to remove and replace all wall and floor tile, all fixtures such as sinks, commodes, partitions, mirrors, grab bars, urinals, and hand dryers in the comfort station restrooms, in the current footprint used as before, to Architectural Barriers Act Accessibility Standards (ABAAS), ensuring all work is done safely to Occupational Safety and Health Administration (OSHA) standards and meets county, state, and federal laws and all applicable regulations and Tennessee codes.

Specific Tasks

- Removal and disposal of construction and project debris;
 - Install new [ABAAS-approved] sinks, toilets, urinals, stalls, grab bars, partitions, electric hand dryers, and mirrors and meet ABAAS guidelines for installation.
 - Install new plumbing flush valves and drain line pipes associated with the install of new fixtures;
 - Patch drywall interior if damaged during removal. Sand, primer and paint interior area ceiling and above wall tile with two coats of quality latex paint which color the park will determine.
- *Government Furnished Property, Materials, and Supplies*
 - Contractor must furnish all labor, materials, equipment, tools, and supplies to complete the job.

Contractor Responsibilities

The contractor shall be responsible for:

- All travel related expenses;
- Removal and legal disposal of all debris and components removed from the building and/or system(s);
- Furnish all labor, materials, supplies, and equipment necessary to result in complete and fully functional systems. Installation shall include all necessary components as described herein and any additional details not included that are necessary for proper completion of the work.

