

**Statement of Work
For
Booster Test Program
28 April 2026**

1.0 BACKGROUND

Vandenberg Space Force Base is supporting Booster Test Program efforts, which started in April 2022 and is scheduled to end in November 2026. The Program is developing a new booster configuration. Two (2) 25K or 36K forklifts and one (1) 38 or 40 foot flatbed trailer are required to support this mission. The Forklifts have to be at minimum 25K and/or a maximum of 36K to perform the tasks required. A 48 foot trailer will be considered if a 38 to 40 foot trailer cannot be supplied.

2.0 OBJECTIVES

The vendor shall supply two (2) 25K or 36K forklifts and one (1) 38 to 40 foot (48ft) flatbed trailer to transport equipment.

3.0 DESCRIPTION OF WORK

3.1 Installation

- Vendor shall provide two (2) 25K or 36K forklifts with with a minimum tines size of 96in (L) x 6in (W) x 2.5in (T) and fitted with a rubber anti-static strap that drags on the ground to dissipate static electricity. NOTE: Tines must be at least 96in long but cannot be greater than 8in (W) or 4in (T)
- One (1) 25K to 36K forklift must be delivered and able to work at building 980.
- One (1) 25K to 36K forklift must be delivered and able to work at the flightline.
- One (1) 38 to 40 foot (53ft) flatbed trailer must be delivered and able to transport equipment from building 980 to the flightline and back. Trailer must include C-track/sliding winch track configuration, 10ea 4" Winch Strap with Flat Hook, 40 ft Long, with a Working Load Limit (WLL) of 5,400 lbs.

3.2 Operation

- The 25K or 36K forklifts must be able to lift and move the equipment as needed.
- The 38 or 40 foot (48ft) flatbed trailer must be able to transport the equipment as needed.

3.2 Removal

- Rentals will remain operational until they are no longer needed to support the missions needs.
- Vendor is responsible for removing all equipment after period of operation has expired.

3.3 Supplied Items

- Vendor shall perform a full inspection and any required maintenance or repair of all material prior to delivery, even if previously provided on a residual contract.
- Vendor will supply all equipment, hardware, labor, materials, pickup & delivery
- All equipment shall be UL/ETL approved.
- **Vendor will respond in 4hrs or less to address/repair any faulty equipment.**

4.0 DESIRED SKILLS AND KNOWLEDGE

- Vendor should have knowledge and ability to comply with federal, state, Air Force, local, and county laws and regulations governing the work requested in this statement.

5.0 DELIVERY TIME FRAME

- Base Period: 26 May 2026 through 27 November 2026 (6 Months)
- Option Period 1: 27 November 2026 through 28 May 2027 (6 Months)
- The vendor shall enter Vandenberg Space Force Base through the Lompoc Gate.

5.1 GOVERNMENT FURNISHED ITEMS

- N/A

5.2 GOVERNMENT FURNISHED EQUIPMENT

- N/A

6.0 POINTS OF CONTACT

6.1 Customer Representative (CR)

The following person has been designated the CR by the Contracting Officer:

[REDACTED]

6.2 Invoice Reviewer in Wide Area Work Flow

[REDACTED]