



**DEPARTMENT OF THE AIR FORCE
HEADQUARTERS 88TH AIR BASE WING (AFLCMC)
WRIGHT-PATTERSON AIR FORCE BASE OHIO**

29 April 2026

Questions and Answers Document

CONTRACTING ACTIVITY/AGENCY: Operational Contracting Division, Directorate of Contracting, Air Force Life Cycle Management Center (AFLCMC), Air Force Material Command (AFMC), Department of the Air Force.

AFLCMC/PZIBB
2275 D Street, Area B, Bldg. 16 Room 150
Wright-Patterson AFB, OH 45433

QUESTIONS

QUESTION 1: *On task 4 you stated: "Task 4: Reinstallation and Power Connectivity: Install new wiring in the existing conduit between Room 128A and Room 134." Q: What will this new set of wires feed? What is the length of the raceway and the size of the wires we need to source? The only thing we have to do with the PDU 8 is labeling, Right?*

ANSWER: *What will this new set of wires feed? The wiring will come from the junction box in RM 134, connect there and pull the wire into RM 128A, Terminate wire at PDU 8. Ensure wiring is phased correctly.*

What is the length of the raceway and the size of the wires we need to source? 160 ft, 3/0

160ft	2428868 CUT 3/0 THHN CU STRD BROWN WIRE ..	Cuts: 1@ 160 ft
160ft	2428871 CUT 3/0 THHN CU STRD ORANGE WIRE ..	Cuts: 1@ 160 ft
160ft	2428872 CUT 3/0 THHN CU STRD YELLOW WIRE ..	Cuts: 1@ 160 ft
6ea	2023799 BISR-250 250MCM IN-LINE SPLICE BUR	
6ea	2017805 BIT-250 BURNDY UNI-TAP TERM. CONN.	10-250MCM TWO-ENTRY

Above is a BOM.

The only thing we have to do with the PDU 8 is labeling, Right? Label only. Ensure label information is correct. Visit electrical room and observe labels at both ends.

Curtis V. Thomas III
Contracting Officer
AFLCMC/PZIBB

Strength Through Support