



**6th Space Warning Squadron
at
Cape Cod SFS, Massachusetts**

**CCSFS High Factory Assembled UL Level 3 Ballistic Rated
Welded Steel Booth**

**Prepared By: David L. Gajeske, MSgt, USAF
Section Chief, Plans & Programs**

**Submitted By: Michael J. Mumau, SMSgt, USAF
Security Forces Manager**

**Approved By: Bryan G. Becker, Lt Col, USSF
Commander, 6th Space Warning Squadron**

OPR: 6 SWS/S5

CONTROLLED UNCLASSIFIED INFORMATION

1. PROGRAM DATA:

Program Type. Cape Cod Space Force Station Security Forces are requesting purchasing of three (3) 4' x 6' x 8' High Factory Assembled UL Level 3 Ballistic Rated Welded Steel Booths. These will include ballistic sliding windows, trailer, PE stamped drawings, and booths already mounted to trailers. These booths will replace the three (3) currently on site which have fallen into disrepair. These booths will be maintained and stored by the Security Forces S4 Section.

A. Points of Contact.

<u>Name</u>	<u>Rank</u>	<u>Organization</u>	<u>Phone</u>	<u>E-Mail</u>
Becker, Bryan	Lt Col	6 SWS/CC	557-2277	bryan.becker.1@spaceforce.mil
Mumau, Michael	SMSgt	6 SWS/SFM	557-2248	michael.mumau@spaceforce.mil
Gajeske, David	MSgt	6 SWS/S4	557-2328	david.gajeske@spaceforce.mil
Stankiewicz, Andrew	TSgt	6 SWS/S5	557-2328	andrew.stankiewicz@spaceforce.mil

B. Mission Location/Description. Cape Cod Space Force Station is a unique installation, and all contractor personnel will need to be vetted by Security Forces before entry into the installation. Personnel will contact MSgt David Gajeske via email at david.gajeske@spaceforce.mil with the following requirements for entry:

- (1) Full Name, Date of Birth, SSN, and Driver's license number with state

C. Project Scope. The Contractors shall include the following attachments and/or products:

1. Three (3) 4' x 6' x 8' High Factory Assembled UL Level 3 Ballistic Rated Welded Steel Booths mounted to three (3) trailers
2. Three (3) Ballistic Sliding Windows (one for each booth) Standard Size
3. One (1) Optional Stamped Drawing (the specifications of the trailer)
4. The contractor will pre-wire the receptacles, lights, switch, HVAC, and supply load center attached to the building. The tie-in and Data/Communications will be handled by SFS; not contractor.

D. Reference Documents.

1. DAFI 31-101, *Integrated Defense*
2. DoDI O-200.16V1/AFI 10-245, *Antiterrorism Program*
3. Mandatory Use Policy for Security Forces MEMO

E. Level of Dissemination. This SOW will not be discussed or disseminated outside those agencies and personnel required for planning and procurement of the thermal imagers and the helmet mounts.

CONTROLLED UNCLASSIFIED INFORMATION

II. OPERATIONAL PARAMETERS:

General Description of Operational Capability. Three (3) 4' x 6' x 8' High Factory Assembled UL Level 3 Ballistic Rated Welded Steel Booths mounted to three (3) trailers. The booths will provide Security Forces with protected cover during increased FPCON posting.

A. Specific Project Design Requirements. Three (3) 4' x 6' x 8' High Factory Assembled UL Level 3 Ballistic Rated Welded Steel Booths mounted to three (3) trailers. Standard size hitch. Three (3) Ballistic Sliding Windows (one for each booth) Standard Size. One (1) Optional Stamped Drawing (the specifications of the trailer). The contractor will pre-wire the receptacles, lights, switch, HVAC (air condition/heat), and supply load center attached to the building. The tie-in and Data/Communications will be handled by SFS; not contractor.

B. Maintenance and Training Concept. A one (1) year Service and Support Warranty are part of the purchase; The Contractor shall, be responsible for any problems with the booths within that time period.

C. Testing and Certification. There are no testing or certifications that need to be acquired.

D. Long Term Maintenance Forecast. No other extra consideration is needed.

E. Schedule Considerations. After Award of this purchase, the Contractor must coordinate with the 6 SWS point of contact (TSgt Andrew Stankiewicz) for delivery.

F. Safety. All appropriate safety measures as outlined in the Occupational Safety and Health Administration (OSHA) and Air Force Occupational and Environmental Safety, fire protection, and Health (AFOSH) guidance will be utilized and adhered to throughout this effort.

G. Delivery and Timeline Expectations. The Contractor and any subcontractors associated with this contract shall ensure that work identified on the SOW is completed as described. **Three (3) 4' x 6' x 8' High Factory Assembled UL Level 3 Ballistic Rated Welded Steel Booths mounted to three (3) trailers: 1 FLAT ROCK HILL RD SAGAMORE, MA 02561, shall be completed no later than 180 days from Contract Award.**

H. List of required equipment:

(1) Please reference the Project Scope Section (1C) for further details.