



SPECIFICATIONS OF WORK

99th Readiness Division
Directorate of Public Works
Fort Dix, New Jersey 08640



21-July-2025

Project Name:	Extended MEP Lot Repair			
Project Number:	CSS#	98822		
Project Location:	Center (FACID)	VA090, FT STORY USARC # 2		
	Street	999 LINGAYAN GULF ROAD		
	City, St, Zip	FORT STORY, VA, 23459-1116		
Project POC: PRI:	RFOS/QAR:	Ty Haughn	Wk: 910-656-0251	Cell:
Project POC/ALT:	AFOS:	Manuel Santiago	Wk: 804-654-4825	Cell:
Project POC/ALT:	FAC COR:		Wk:	Cell:
Project POC/RD:	FET:		Wk:	Cell:
HQ Eng. Tech:		Edward Buscemi	Wk: 609-562-8967	Cell:

1. GENERAL CONTRACTOR:

1.1. Shall furnish all plant, labor, equipment, materials, transportation, supervision and technical expertise to perform requirements in accordance with the specifications and allotted period of performance described in this Specifications of Work (SOW).

1.1.1. Shall provide their own storage shed or trailer for on-site office accommodations and for storing of equipment and material. The "On-Site Government Quality Assurance Representative" (QAR) will assign the contractor a location for placement of their shed or trailer upon request.

1.2. Is obligated to verify all measurements and specification requirements at the on-site visit prior to starting the project. No extra compensation shall be allowed for the contractor who does not attend the on-site visit and who does not appreciate the difficulty of the contract specifications. Any discrepancies, ambiguities or changes must be verified and confirmed in writing to the Contracting Officer, Contracting Officer Representative (COR), and QAR.

1.3. Shall furnish all submittals for equipment and/or materials that vary from requirements of this SOW. All submittals are required to be turned in and approved by the QAR 30 days prior to ordering any of those materials.

1.3.1. Shall provide, unless otherwise specified, new and unused materials and/or installed equipment in the original manufacturer's packaging. All materials stored on the job site are subject to inspection by the QAR and must be protected from the elements at all times.

1.4. Shall not perform any portion of this contract without notice to proceed. Shall not commence work prior to the Government COR/QAR pre-construction meeting. Shall notify the COR/QAR a minimum of 72 hours prior to commencing work and prior to completing work on this contract.

1.5. Shall submit, prior to commencing any work: A current Certificate of Insurance (Prime and Subs); A letter appointing a construction superintendent; A schedule of operations. The construction schedule shall be subject to change so Contractor's operations do not conflict or otherwise disrupt normal operations of the government in the facility involved.

1.6. Shall perform the work between the hours of 0730 and 1600 (7:30 AM – 4:00 PM), Monday through Friday (unless otherwise specified), excluding legal holidays. NO EXCEPTIONS, any work on military training/drill weekends or federal holidays must have prior written coordination and approval between the Contractor, Project POC (Primary or Alternate), and the Facility Manager.

1.6.1. Shall submit on company letterhead to the QAR an "Entry Authorization Letter" registering all motor vehicles and driver/operators information as required to access individual installations.

1.6.2. Shall ensure all motor vehicles, drivers and operators are qualified, licensed and insured.

1.7. Shall ensure compliance with all applicable Federal, State, and Local Municipal environmental regulations concerning the protection of land, water and resources. Shall apply most stringent regulation requirements to any ambiguities, deviations must be approved in writing by the Contracting Officer or COR. The types and quantities of all hazardous materials brought to the job site shall be reported to the facility/installation environmental officer.

1.8. Shall call/coordinate, prior to any excavation, with local municipalities and the facility utilities section to identify all underground utilities.

1.8.1. Prior to any underground excavation, the contractor shall call and obtain approval from the state in which the work is being performed.

1.8.2. A copy of the approval notification letter or valid authorization number must be available for inspection at the excavation site.

1.9. Shall be responsible for any damages caused by them or their subcontractors during the performance of this contract and shall be required to reimburse the United States Government for the cost of any repairs resulting from those damages, or the Contractor/ Subcontractor shall make the necessary repairs to the satisfaction of the United States Government.

1.9.1. The contractor shall hold the Government harmless against any liability imposed by a Federal, State, or Local regulatory agency, resulting from the negligent acts or willful misconduct of the contractor to include assessment of a civil or administrative penalty or fine.

1.10. Shall be solely responsible for ensuring compliance with the provisions of this contract by subcontractors. Shall ensure work be performed by workmen skilled in their particular trades, and certified as required by Federal, State and Local laws and/or codes.

1.11. Shall be required to leave the job site in a safe and secure condition at the end of each workday. The contractor shall provide at his/her expense a Dumpster for all construction debris, dumping shall also be at contractor expense. The Contractor shall at no time use government dumpsters.

1.12. Shall clean the job site of all construction debris at the end of each working day. The daily clean-up will not alleviate the Contractor from the responsibility of the final clean-up for acceptance, upon completion of this contract. All debris removed from the job site shall be disposed of IAW all federal, state and local regulations, at a proper off post/facility landfill

or properly permitted treatment, storage and disposal facility for the type of waste, of the Contractor's own choice and at the Contractor's expense. In case of conflict among these laws and regulations, the most stringent law or regulation will apply. The Contractor shall verify that the facility receiving the waste is properly permitted or allowed to accept the type of waste being shipped to them. Due to mandating of solid waste annual reporting requirements, contractor shall provide any and all receipts, manifest/BOL, and/or other written record of types of waste and amounts disposed within 30 calendar days of the completion of the project. Records shall be provided to the RFOS/COR.

1.13. Shall ensure all work be completed in the negotiated time frame.

2. CONTRACTOR QUALITY CONTROL

2.1. The Contractor shall provide and maintain an effective quality control program that complies with the Contract Clause (FAR 52.246-12), the below stated quality control requirements and the quality control requirements stated in the respective section of the Technical Specifications. Quality control personnel shall also be charged with the responsibility of policing Contractor's Safety Program.

2.2. The Contractor shall establish a quality control system to perform sufficient inspection and testing of all items of work, including that of their subcontractors. The quality control system shall ensure conformance with applicable specifications and drawings with respect to materials, workmanship, construction, finish, functional performance, and identification.

2.3. The quality control system will be established for all construction except where the technical provisions of the contract provide for specific Government control by inspections, tests, or other means. The Contractor's quality control system will specifically include the surveillance and tests required in the technical provisions of the contract specifications. For purposes of the above description, shop manufacture or standard products are not defined as construction.

2.3.1. The Contractor's quality control system is the means by which they assures themselves their construction complies with the requirements of the contract plans and specifications. The controls shall be adequate to cover all construction operations, including both on and off-site fabrication.

2.3.2. The Contractor shall not build up or conceal any feature of the work containing uncorrected defects, and payment on deficient items will be withheld until they are satisfactorily corrected or other action has been taken as authorized pursuant to the Contract Clause entitled "Inspection of Construction".

2.3.3. The Contractor's appointed job site supervisor may be used as the Quality Representative (QR). When supplemented by special technicians or testing facilities to perform all specified tests, balancing, adjusting and/or regulating mechanical and electrical devices, equipment and/or systems it will be done in writing. As an option, an industry recognized testing laboratory approved by the Contracting Officer or COR may be used for said testing.

2.3.4. The contractor is responsible for maintaining an effective quality control system. Recurring deficiencies indicate the system is not adequate and the contractor's performance is failing to meet government's minimum acceptable standards. If, in the opinion of the Contracting Officer, an unacceptable number of deficiencies are occurring in the contractor's performance, the Contracting Officer may direct the contractor to revise its operations to correct the defective performance. Failure by the contractor to provide acceptable revisions and/or to improve contract performance may result in the termination of the contract for default.

2.3.5. In the event the Contractor utilizes the service of a commercial testing laboratory, the Contracting Officer reserves the right to check laboratory equipment for compliance with the standards set forth in the contract specifications and to check the laboratory technician's testing procedures and techniques.

3. GOVERNMENT

3.1. The Government will provide, when available, electrical power, water and existing utilities at each building required in the performance of this contract at no cost to the Contractor. Temporary extension of power and/or water lines, if necessary, shall be installed at the Contractor's expense.

3.1.1. Contractor owned construction sheds, trailers, offices or other such facilities requiring utility services shall be metered for each utility involved, and all costs involved up to the point of connection to Government owned utility systems shall be at the contractor's expense. Final connection of Contractor supplied service laterals to existing Government owned utility systems will be made at the Contractor's expense.

3.2. Contracting Officer or COR will schedule a pre-performance conference after contract award and prior to commencement of work. The Contracting Officer will notify the contractor of the time, date, and place set for the meeting, which will be held at a location to be designated by the Contracting Officer. At this meeting, the contractor will be oriented with respect to Government procedures and lines of authority, as well as contractual, administrative, and construction matters. **The contractor is required to furnish a current Certificate of Insurance and a letter appointing a construction superintendent at the meeting.**

3.2.1. **Pre-Construction Conference:** Topics will cover but are not limited to the following:

3.2.1.1. Introduction of Key players: COR/QAR, General Contractor, Job-site Supervisor, Sub-Contractors and using agencies. Other personal that may be in attendance are Environmental, Police, Fire, Safety and Health services, in addition to Distinguished Visitors.

3.2.1.2. Specifications of Work (SOW): Brief description of work, modifications to SOW, customer requests for additional work, unauthorized work, facility access and authorized personnel access.

3.2.1.3. Milestones: Period of performance, start date, schedule, phasing, completion date, work hours desired, weekend work schedule, scheduled outages/interruptions (power, water, roads, alarms, fire protection, HVAC).

3.2.1.4. Materials: Submittals, equipment, construction area, storage area, Government provided utilities, dumpster locations, Barriers (construction fence, silt fence, roadblocks, access points to facilities, etc.)

3.2.1.5. Administrative: Lines of authority, Wage rate/certified payrolls, Daily reports, Visitor control, Environmental requirements (hazards, dust and noise control), Maintenance and submission of solid waste disposal records. Safety meeting/concerns, Excavation permits, Fire (burn Permits), Police support, Payments, Liquidated Damages.

3.2.2. Contracting Officer, COR and/or their QAR may inspect the work at any time during the contract period, and reserves the right to stop or terminate the contract if all work does not comply with the specifications provided by the manufacture's recommendation of this SOW. The presence or absence of the Contracting Officer or QAR shall not relieve the Contractor from strict compliance with these plans and specifications.

3.3. Technical surveillance of workmanship and inspection of materials for work being performed under this contract shall be the responsibility of the QAR. This provision in no way authorizes anyone other than the Contracting Officer to commit the Government to changes in the terms of the contract. In the event it is determined necessary to designate a QAR for this contract, such designation shall be by a separate letter to the individual selected with a copy furnished to the contractor.

3.4. The Government, its Officers and Agents will be free from liability for any negligence occasioned by the Contractor's operations, employees, or equipment. In addition, the Contractor will reimburse the Government for any damage and/or loss that occurs as a result of the Contractor's negligent operations, employees or equipment.

3.5. The Government reserves the right to undertake performance by Government forces or other Contractors, the same type of similar work as contracted for herein, as the Government deems necessary or desirable, and to do so will not breach or otherwise violate this contract.

3.6. Federal Holidays (New Year's Day, Martin Luther King JR's Birthday, Presidents' Day, Memorial Day, Juneteenth, Independence Day, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day, and Christmas Day), that fall within the workweek will not be considered workdays. Whenever a holiday falls on a Saturday or Sunday, the proceeding Friday or following Monday respectively will be observed as a holiday. Prior to the contractor performing the work on days or at times other than those specified, the contractor shall submit a written request to the QAR for approval by the Contracting Officer. Requests for deviation shall be submitted no less than 24 hours prior to the time the contractor desires to work.

4. LIFE, SAFETY AND HEALTH REQUIREMENTS:

To better provide life, safety and health protection to all contractor employees, on-site personnel, and Government personnel performing or in any way coming in contact with this contract the specific requirements established here-in will be adhered to at all times:

4.1. 29 CFR 1910: Comply with all pertinent provisions of 29 CFR 1910 General, and with any additional measures the Contracting Officer may determine to be reasonably necessary. Copies of this manual may be obtained from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C., 20402.

4.2. OSHA: Comply with latest version of OSHA Handbook Rules and Regulations.

4.3. NFPA: Comply with the most current edition of the National Fire Codes (NFPA) and installation fire prevention standards. www.nfpa.org/catalog

4.3.1. All open flame/hot work or disconnection of fire protection alarms or suppression systems require prior written approval/coordination from one of the 99th Readiness Division (RD) POC's listed on the first page of this document.

4.3.2. Any connection, disconnection or installation of fire protection alarms or suppression systems shall require an acceptance test performed by the contractor and witnessed by the local Fire Prevention Authority having jurisdiction over that facility. In the event the fire alarm system cannot be disconnected (i.e., child development, hospital, etc.) a temporary system will be provided and certified by the local Fire Prevention Authority having jurisdiction. Work required to be performed after hours due to the nature of the facility will be at no additional cost to the government.

4.3.3. All fire alarm system components, including all smoke and heat detectors, shall be protected from dirt, dust and damage during demolition and construction.

4.4. AR 420-1: Comply with Army Regulation 420-1,
https://armypubs.army.mil/epubs/DR_pubs/DR_a/pdf/web/ARN15517_R420_1_admin_FINAL.pdf

4.5. Lockout / Tagout Procedure: The Contractor shall perform this work in accordance with 29 CFR 1910.147, The Control Of Hazardous Energy and the following general requirements.

4.5.1. Preparation: Make a survey to locate and identify all isolating devices to be certain which switches, valves, or other energy isolating devices apply to the equipment to be locked or tagged out. More than one energy source such as electrical, mechanical or others may be involved.

4.5.2. Sequence Of Lockout/Tagout Procedure:

4.5.2.1. Notify all affected personnel that a Lockout/Tagout system is going to be used and the reason therefore. The authorized personnel shall know the type and magnitude of energy the machine or equipment uses and shall understand hazards thereof.

4.5.2.2. If the machine or equipment is operating, shut it down by the normal stopping procedure such as depressing stop button, open toggle switch, etc.

4.5.2.3. Operate the switch, valve, or other energy isolating devices so that the equipment is isolated from its energy source. Stored energy such as in charged capacitors, springs, elevated machine members, rotating flywheels, hydraulic systems and other pressurized air, gas, steam, or water systems etc. must be dissipated or restrained by methods such as repositioning, blocking, or bleeding down the stored energy.

4.5.2.4. Lockout and/or tagout the energy isolating devices with assigned individual locks, tags, or additional safety measures as may be required.

4.5.2.5. After ensuring that no personnel are exposed, and as a check on having disconnected the energy sources, operate the push button or other normal operating controls to make certain the equipment will not operate.

CAUTION: Make sure the operating controls are returned to the "NEUTRAL" or "OFF" position after the test.

4.5.2.6. The equipment is now locked out or tagged out.

4.5.3. Restoring Machines Or Equipment To Normal Production Operations:

4.5.3.1. After the servicing and/or maintenance is complete and equipment is ready for normal production operations, check the area around the machines or equipment to ensure that no one is exposed.

4.5.3.2. After all tools have been removed from the machine or equipment, guards have been reinstalled, and personnel are in the clear, remove all lockout and tagout devices. Operate the energy isolating devices to restore energy to the machine or equipment.

4.5.4. Procedure Involving More Than One Person: In the preceding steps, if more than one individual is required to lockout or tagout equipment, each shall place his/her own personal lockout or tagout device on the energy isolating devices. When an energy-isolating device cannot accept multiple locks or tags, a

multiple lockout or tagout hasp shall be used. If a single lock is used to lockout the machine or equipment, the single key shall be placed in a lockout box or cabinet that allows the use of multiple locks to secure it. Each employee shall then use his/her own lock to secure the box or cabinet. As each person no longer needs to maintain his/her lockout protection, only that person shall remove his/her lock from the box or cabinet.

4.6. USACE EM 385-1-1: The Contractor shall be responsible for knowing the Corps of Engineers, Safety and Health Requirements Manual, EM 385-1-1, (use the current version at the time of task order award), and incorporate those general and additional safety requirements into daily working procedures to provide safe working conditions during performance of this contract. Copies of this manual may also be obtained from the Superintendent of Documents. <https://www.usace.army.mil/Missions/Safety-and-Occupational-Health/Safety-and-Health-Requirements-Manual/>

4.7. Site Safety Plan: The Contractor shall submit in writing a Site Safety Plan and present the overall safety program via in-person conference with the Contracting Officer and/or Primary Project POC. The Site Safety Plan shall follow the requirements of the EM 385-1-1 and include all relevant Accident Prevention and Activity Hazard Analyses. The Site Safety Plan shall include provisions to deal with hazardous materials, pursuant to the Contract Clause entitled "Hazardous Material Identification and Safety Data".

4.7.1. With respect to hazardous materials, the plan will consist of:

4.7.1.1. A plan for protecting personnel and property during the transport, storage, and use of the materials.

4.7.1.2. An index of hazardous materials to be introduced to the site.

4.7.1.3. Safety Data Sheets (SDS) for materials listed in the index of the plan and not required in the technical section of the specification.

4.7.1.4. Procedures for spill response and disposal.

4.7.2. The Contractor shall not turn in hazardous waste generated during performance of the contract, for disposal by the government, unless such disposal is explicitly provided for in the contract. If specified in the contract, the Contractor shall provide an SDS for each hazardous material/waste turned in to the government for disposal.

4.7.3. The contractor shall not dispose hazardous materials/waste in any dumpster, sanitary sewer, storm sewer or dispose of hazardous materials/waste by any other means on government property.

4.7.4. The contractor shall not sign any hazardous waste manifest. Signature authority for hazardous waste manifests is delegated only to certain personnel within the Environmental Office. The contractor shall provide copies of all manifests or bills of lading for the transportation and disposal of all asbestos or asbestos containing materials to the Environmental Office.

4.8. HAZARDOUS MATERIAL CONTACT (PCB, Asbestos or Lead Material): If material is encountered which may contain PCB's, hazardous materials, asbestos and/or lead and must be disturbed, DO NOT touch the material. Should the discovery of such suspected material affect the Contractor's planned work schedule, the Contractor shall redirect the work crew to other portions of the unaffected work and modify the schedule at no additional cost to the Government.

4.8.1. Contractor shall contact/notify RFOS from page one of this specification of work immediately if suspected material as described in section 4.8. is encountered.

4.8.2. Contractor shall in writing, address circumstances and concerns to be addressed by the RFOS regarding the discovery of the suspected material and of any adverse impact the Contractor may expect to incur due to this situation.

4.8.3. The RFOS as identified will, within 14 calendar days, perform laboratory tests to determine if the material is a hazard. If there is not a danger, the RFOS will direct the Contractor to proceed in the identified area without change. If the material is identified as hazardous, before proceeding, the RFOS will determine the most cost-effective means for removal. The hazardous material will be removed, abated or rendered harmless before work commences.

4.9. Environmental Protection Requirements: Provide and maintain strict compliance with all federal, state, county and local environmental protection requirements including but not limited to, water, air, soil, and noise pollution during the life of this contract.

4.9.1. In the event of a spill, initiate containment operations utilizing personnel properly trained and protected for such situations and immediately notify the Contracting Officer and/or On Site Representative/POC from page one.

4.9.2. Plan for and provide environmental protective measures to control pollution that develops during normal construction practice.

4.9.2.1. Prevent oily or other hazardous substances from entering the ground, drainage areas, storm drainage system, or local bodies of water.

4.9.2.2. Keep dust down at all times, including during nonworking periods. Sprinkle or treat with dust suppressants, the soil at the site, and other areas disturbed by operations. Dry power brooming will not be permitted. Instead use vacuuming, wet mopping, wet sweeping, or wet power brooming. Only wet cutting will be permitted for cutting concrete, and bituminous concrete.

4.9.2.3. Handle generated hazardous waste in accordance with federal, State, county and local regulations including 40 CFR 262.

4.9.3. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Dispose of hazardous waste in strict accordance with federal, State, county and local regulations including 40 CFR 263 and 40 CFR 264.

4.9.4. Make the maximum use of low-noise emission products, as certified by the EPA. Blasting or the use of explosives is prohibited.

4.10. Ozone Depleting Substances (ODS): The Contractor shall not knowingly vent or otherwise dispose of any ODS in a manner that would permit their release into the environment. ODS's are generally found in refrigerants, fire-fighting agents, and solvents.

4.10.1. The Contractor shall use only those products that are approved and listed by the EPA Significant New Alternatives Program (SNAP).

4.10.2. The Contractor shall furnish a material safety data sheet to the Government representative prior to use of any ODS or SNAP product on station.

4.10.3. Class I ODS's: The use on installations or the removal off an installation is strictly prohibited without the prior knowledge and consent of the Contracting Officer.

4.10.4. Class II ODS's: Shall be used only when specified by the Government.

4.10.5. When ODS's of any class are used or saved for reuse, the Contractor shall list this amount in pounds on the "Daily Report To Inspector" form and the Contractor's invoice.

4.10.6. ODS's shall be captured and recycled in conformance with all applicable Federal, State, and local regulations.

4.11. Safety Officer: The Installation Safety Officer will be responsible for monitoring the contractor in the area of safety and accident prevention. Additional information may be provided and Contractor shall comply with the safety rules of the Government installation concerning related activities not directly addressed in this contract.

4.11.1. The Contractor's personnel, when operating motor vehicles, shall not exceed ten (10) miles per hour when passing military troops on the roadways, and abide by post speed limits otherwise.

4.12. Occupancy:

4.12.1. It shall be the Contractor's responsibility to coordinate with QAR to schedule and perform his work in such a manner as to create the least possible interference with the conduct of normal activities within the areas.

4.12.2. The Contractor shall not receive any additional compensation due to the conditions brought about by this occupancy and usage of the Government.

4.12.3. Contractors are only authorized to occupy areas in which active construction, maintenance, repair or associated work in the performance of the contract is required to be done.

4.12.4. The Contractor shall not block more than one access of the building at any time, nor shall he disrupt the existing parking arrangement at any of the building parking areas without prior coordination with the QAR.

5. CONDUCT OF EMPLOYEES

5.1. The contractor is fully responsible for the performance and conduct of his employees at all times while on post performing under the contract. The Contractor shall not allow any employee to perform work under the contract while under the influence of alcohol, drugs or any other incapacitating agent.

5.1.1. Contractor employees will abide by the DOD Smoking Policy.

5.2. Military police and other law enforcement personnel on post have the right to deny entry to post or remove from post any contractor employee for misconduct which endangers the health or safety of people or property or for reasons of security. In addition, the Post Commander may bar an individual from entering the post under the authority of 18 U.S.C. 1382.

5.3. Removal from post of a contractor employee in accordance with above shall not relieve the Contractor from the requirement to meet all of the terms and conditions of the contract.

6. SECURITY

6.1. At all times during the performance of work within the facilities, the Contractor and their employees shall remain cognizant of security restrictions existing within the facility. The Contractor's employees shall ensure any doors, windows or access panels which may have been opened for them during the course of the work period are secured at the end of the day.

6.2. The Contractor shall report any incident in which no escort is provided for scheduled work within secured areas of the building or any occurrence during which an escort leaves the Contractor's employees while within a secure area.

6.3. The Contractor and their employees may store tools and equipment within the work area. However, recognize they do so at their own risk even if the area can be secured.

7. INSPECTOR GENERAL'S (IG) AUTHORITY TO INSPECT CONTRACTORS

7.1. The Inspector General shall have access to the Contractor's facilities, employees, operations, and records at the site where work is being performed at all times to conduct inspections or for other purposes. Where feasible, advance notification of an IG inspection or investigation will be provided to the Contractor by the Contracting Officer.

8. DEFINITIONS

8.1. Where the words "Special Contract Clauses" or "Special Clauses" appear in test provisions, the Technical Specifications, or on contract drawings, it shall be taken to mean "Special Contract Requirements".

8.2. Throughout this contract, the word "indicated", "shown", or "specified" shall mean indicated, shown, or specified in the drawings and/or specified in the specifications.

8.3. Throughout this contract, the words "as directed" "inspected", "selected", or "accepted" shall mean as directed, inspected, selected, or accepted by the QAR. The words "approved" or "authorized" shall mean approved or authorized by the Contracting Officer. These definitions are provided as guidance for the contractor and shall service as the governing interpretation when this language appears within the body of this contract and apparently conflicts with the above.

9. APPLICABLE PUBLICATIONS:

Those applicable publications that are not listed in the Applicable Publication paragraph of the Technical Specifications sections but are found elsewhere in the text of those specifications, also form a part of this contract.

10. SUBMITTALS / DELIVERABLES

10.1. SUBMITTALS: Contractor shall provide submittals to the COR for submittal approval minimum 30 days prior to scheduled installation of any referenced materials substituted in the technical sections herein, unless otherwise noted. Submittals shall be approved prior to installation of any referenced materials substituted.

10.1.1. Original and four (4) copies of each submittal shall be provided and signed by the contractor. Once approved, original and four copies will be stamped “Approved”, signed and dated by the COR.

10.1.2. Distribution of submittals: Approved submittals will be included in the deliverables portion as stated in paragraph 10.2 below.

10.2. DELIVERABLES: Send a minimum of 30 days prior to contract completion date original and four (4) copies of ALL final documentation; submittals, certifications, laboratory tests, descriptive data, test reports, required shop drawing, site surveys, and warranties. Send via First Class Mail, FedEx, or UPS to:

99th Readiness Division; HQ

Attn: DWP Operations: Contract# _____

Fort Dix, NJ 08640

10.3. The Contractor shall furnish to the above address the original manufacturer’s documentation and four (4) copies demonstrating material proof of compliance requirements in regards to Technical Specifications for this contract.

10.3.1. Certificate of Compliance:

10.3.1.1. Name and address of the Contractor.

10.3.1.2. Project name.

10.3.1.3. Location.

10.3.1.4. Quantity.

10.3.1.5. Dates of shipment or delivery to which the certificates apply.

10.3.1.6. Each certificate shall be signed by an authorized officer of the manufacturing company.

10.3.2. Laboratory Tests: Reports submitted with the certificate shall contain:

10.3.2.1. Name and address of the testing laboratory.

10.3.2.2. Date of the tests to which the report applies.

10.3.3. Samples: The Contractor shall furnish samples of materials for approval, as required by the applicable sections of the technical specifications that differ from the specification.

10.3.4. Descriptive Data: The Contractor shall furnish the manufacturer’s descriptive data, installation instructions, and maintenance instructions, for approval, as required by the applicable sections of the technical specifications.

10.3.5. Test Reports: The Contractor shall furnish copies of test reports for approval to demonstrate compliance with the applicable sections of the technical specifications that differ from the specification.

10.3.6. Shop Drawings: Consist of illustrations, schedules, performance charts, instructions, brochures, diagrams, drawings and other information to illustrate and/or demonstrate compliance to the applicable sections of the technical specifications.

10.3.6.1. The Contractor shall furnish for approval, one copy “DRAFT Shop Drawing”. Each rendition shall be dated and numerically annotated until final approval.

10.3.6.2. The Contractor shall furnish finalized drawing copies “AS BUILTS” and all applicable support data once agreed upon by the Contracting Officer/COR and/or Project POC. Each submission shall include:

- Drawing index in MS Excel listing of all submitted electronic files including a description, directory structure, and name for each file submitted. For all Sheet files, include a list of sheet titles and sheet numbers.
- Electronic drawing set with any associated files via email, electronic file transfer, or other arranged method; drawing sets in both PDF and CAD format (CAD files can be Microstation.dgn files or AutoCAD .dwg files. Provide editable CAD sheet files for any BIM files, if included. Any geo-referenced files to conform with WGS84 coordinate system. Refer to CAD practices outlined in latest documented release of ‘U.S. Army Corps of Engineers, Engineer Research and Development Center, A/E/C CAD Standards for Layering and Drafting Practices’, as practical. (<https://cadbimcenter.erdcdren.mil/>). Must include an electronic copy of the specifications associated with the project.

10.4. Documentation shall not be construed as relieving the Contractor from furnishing satisfactory material, if after tests are performed on selected samples of the material is found not to meet the specific requirements.

11. TECHNICAL SPECIFICATIONS:

CSS# 98822 – Extended MEP Lot Repair

Center FT STORY USARC # 2
Street 999 LINGAYAN GULF ROAD
City, St Zip FORT STORY, VA, 23459-1116

11.1. PERIOD OF PERFORMANCE: The Contractor shall have **120 Calendar Days** from the Notice to Proceed Date to complete ALL TASKS associated with the Specification of Work.

11.1.1. SECURITY:

The Contractor Superintendent of the project shall inform their employees (contractors) about suspicious activity reporting, iWatch procedures and Antiterrorism/OPSEC Awareness. The COR shall keep proper accountability of their personnel. In the event of an escalated FPCON, there may be extra security measures put in place and it may cause a hindrance to complete the project in the allotted time according to the contract. This will be at no expense to the government.

The correct web address for AT Level I is: <https://jkodirect.jten.mil>

Non CAC card holders also have to complete AT Level I, training available at:

<http://jko.jten.mil/courses/at1/launch.html>

OPSEC Training: OPSEC Fundamental Course (OPSE-1301) CBT, <https://www.iad.gov/ioss/>

AT Level I training. All contractor employees, to include subcontractor employees, requiring access Army installations, facilities and controlled access areas shall complete AT Level I awareness training within 30 calendar days after contract start date or effective date of incorporation of this requirement into

the contract, whichever is applicable. The contractor shall submit certificates of completion for each affected contractor employee and subcontractor employee, to the COR or to the contracting officer, if a COR is not assigned, within 5 calendar days after completion of training by all employees and subcontractor personnel. AT level I awareness training is available at the following website:
<http://jko.jten.mil>

11.1.2. (2) **Access and general protection/security policy and procedures.** Contractor and all associated sub-contractors employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personal identity verification requirements (FAR clause 52.204-9, Personal Identity Verification of Contractor Personnel) as directed by DOD, HQDA and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

11.1.3. (2b) **For contractors that do not require CAC, but require access to a DoD facility or installation.** Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05/AR 190-13), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative), or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations.

11.1.4. (4) **iWATCH Training.** The contractor and all associated sub-contractors shall brief all employees on the local iWATCH program (training standards provided by the requiring activity ATO). This local developed training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR. This training shall be completed within 30 calendar days of contract award and within 5 calendar days of new employees commencing performance with the results reported to the COR NLT 5 calendar days after contract award.

11.1.5. (7) **For contracts that require OPSEC Training.** Per AR 530-1 *Operations Security*, the contractor employees must complete Level I OPSEC Awareness training. New employees must be trained within 30 calendar days of their reporting for duty and annually thereafter.
ACC-NJ OPSEC

11.2. GENERAL REQUIREMENTS:

11.2.1. The Contractor shall provide all plant labor, equipment, tools, materials, supervision, and transportation to accomplish the following work which consist of but is not limited to:

- Removal and replacement of approx. 1000 L.F. of existing chain link fence surrounding the Military Equipment Parking (MEP) lot.
- Removal of one (1) existing double swing manual gate approximately 28 LF, and installation of one (1) new 28 LF manual cantilever gate.
- Provide and install four (4) new dual head 30' aluminum parking lot lighting poles, bases and all necessary wiring. See attached plot map.
- The MEP lot requires additional repairs which shall include but not be limited to:
 - Milling Lot Approximately 46,000 SF
 - Paving Lot Approximately 46,000 SF
 - Grubbing vegetation 10' outside perimeter fence.
- The contractor shall notify the QAE or Project Manager a minimum of **72 hours** prior to commencing work, and prior to completion of work on this contract.

All quantities are estimated. The contractor **shall** field verify all dimensions and quantities prior to ordering material. The contractor is responsible for having all site utilities marked in the area of construction before any earthwork is performed. Failure of the contractor to conduct a site visit and appreciate the complexity of the specifications herein shall not indemnify said contractor from contract obligations as stated. All work completed herein shall be in accordance with but not limited to:

- UNIFIED FACILITIES GUIDE SPECIFICATIONS (UFGS) –
[HTTPS://WWW.WBDG.ORG/FFC/DOD/UNIFIED-FACILITIES-GUIDE-SPECIFICATIONS-UFGS](https://www.wbdg.org/FFC/DOD/UNIFIED-FACILITIES-GUIDE-SPECIFICATIONS-UFGS)
 - DIVISION 03- CONCRETE
 - DIVISION 31- EARTHWORK
 - DIVISION 32- EXTERIOR IMPROVEMENTS
 - DIVISION 02- SITE CONDITIONS
 - DIVISION 26- ELECTRICAL
 - DIVISION 32- EXTERIOR IMPROVEMENTS
- UFC – UNIFIED FACILITIES CRITERIA
 - UFC- 1-200-01 DoD BUILDING CODE
 - UFC- 4-022-03 SECURITY FENCES AND GATES
 - UFC- 3-501-01 ELECTRICAL ENGINEERING
 - UFC- 3-530-01 INTERIOR AND EXTERIOR LIGHTING SYSTEMS
 - UFC- 3-550-01 EXTERIOR ELECTRICAL POWER DISTRIBUTION
 - UFC- 3-250-03 UFC- 3-250-03 STANDARD PRACTICE MANUAL FOR FLEXABLE PAVEMENT
 - UFC-3-270-01 ASPHALT AND CONCRETE PAVEMENT MAINTENANCE AND REPAIR
- ARMY REGULATION 420-1
 - RCRA – RESOURCE CONSERVATION AND RECOVERY ACT
 - EM 385-1-1, SAFETY and HEALTH REQUIREMENTS MANUAL

11.2.2. Contractor and associated sub-contractors shall provide a safe and healthful work environment for their employees as prescribed in FAR 52.236-13, 29 CFR Part 1910, pertinent provisions of AR 385-10, and local regulations, policies, and SOPS. Contractor/s shall safeguard public and government personnel, property and equipment, as well as avoid interruption of Government Operations. The Contractor shall report accidents or losses to the Contracting Officer as specified in relevant regulations and standards. Whenever the contractor becomes aware of serious or imminent danger to Government, civilian or contractor personnel, the contractor shall take immediate corrective action.

11.2.3. Contractor shall maintain work areas in a neat, clean, and safe condition. The Contractor shall be responsible for providing, installing and the removing any temporary signage, barriers, barricade tape, etc., which may be required to control pedestrian and/or vehicle traffic in the work area.

11.2.4. This Army Reserve Facility is an active workplace. The contractor shall provide a proposed schedule of work at time of proposal to perform work in stages to minimize disruption of day-to-day activities throughout the facility and grounds. The contractor shall make best efforts to adhere to said schedule and will have full cooperation from facility employees. RFOS and Facility Commander or other authorized Government Official shall approve schedule. Contractor shall provide a minimum of weekly project updates to RFOS/COR as to progress on project and adherence to schedule.

11.2.5. In an effort to allow the government the opportunity to fully to evaluate and validate contractor pricing and desired intent of the cost proposal; the Contractor shall provide a written narrative to support the cost data in the contractors cost proposal. Detailed breakout for all pricing in proposal is required; lump sum pricing is unacceptable. Cost proposal shall include a detailed narrative describing the approach to accomplishing the scope of work and clearly stating all assumptions included in the proposal price. As the basis for the contractor pricing and in an effort to assist the government with the reconciliation of which items in the contractor's price proposal are considered New vs Re-used the contractor shall include a spreadsheet with the cost proposal that clearly state what those items are.

11.2.6. The contractor shall submit proper and complete documentation to the COR verifying that all hazardous wastes generated were disposed of properly offsite in accordance with federal and state RCRA regulations. The contractor shall also submit proper and complete documentation verifying the recycling or disposal of all Universal wastes and non-hazardous wastes generated. All aforementioned records must be submitted in accordance with the provisions of section 11.6 Cleanup, Removal & Disposal Records.

11.2.7. NATIVE AMERICAN GRAVES PROTECTION AND REPATRIATION ACT:

In the event of an inadvertent discovery of Native American human remains or other cultural items, i.e. shard or examples of former encampment, the vendor must cease activity in the area and immediately contact the 99th Readiness Division Environmental Team, Stephanie Weiss, Conservation Program Coordinator, at (609)562-2762 or stephanie.r.weiss.civ@army.mil to remain in compliance with 43 CFR 10.2 (g)(4)."

11.3. PROJECT SPECIFICATIONS:

11.3.1. The Fort Story USARC, located at 999 Lingayan Gulf Road, Fort Story Virginia, requires repairs to the existing Military Equipment Parking (MEP) lot. This shall be accomplished by replacing approximately:

- 1000 LF of existing fencing to include but not limited to:
 - Chain link fabric to be removed and new install
 - Terminal, corner and line poles to be removed and new install
 - Fencing ties to be removed and new install
 - Barbed wire top guard to be removed and new install
- Remove and replace the one (1) manual double swing gate with one (1) manual sliding cantilever gate. Approximately 28 LF
- Grubbing 10' past fence line perimeter see attached plot map
- Supply and installation of approximately four (4) new parking lot light poles, to include but not be limited to:
 - Excavation for concrete light pole base and conduit trench
 - Placement of encapsulated concrete conduit across road
 - Concrete light pole bases
 - 30' Aluminum parking lot light poles, to include 2 head luminaires on each pole
 - Conduit shall be run from existing pole to new pole's see attached plot map
 - Power to be run from the main distribution panel to power light poles through existing conduit and newly installed conduit.
- Repaving approximately 46,000 SF of MEP lot but not limited to:
 - Milling of approximately 2" of MEP lot
 - Saw cutting asphalt as required for trenching across road
 - Protection for overspray
 - Inspect for structural deficiencies

- Clean surface
- Crack repair in milled surface
- Spray tack coat
- Apply wear course of approximately 2" of MEP lot
- Seal edges
- Ensure gate clearance is 2"

11.3.2. REQUIRED: PRE-CONSTRUCTION MEETING - (PCM): Prior to commencing the work, the Contractor shall meet with the Regional Facilities Operations Specialist (RFOS) and/or the project COR to present and review, as appropriate, the items in this specification of work. The Contractor's Competent Person(s) who will be on-site shall participate in the PCM meeting. The PCM meeting is to discuss and define contractor procedures and materials to be used during the project execution and shall be formally approved by 99th Readiness Division (RD) personnel as defined above. All measurements and locations shall be field verified by contractor at PCM and confirmed by RFOS/COR.

11.3.3. Lighting Specifications:

11.3.4. Prior to the start of any excavation, the contractor shall contact VA811- Dig with Care to verify and mark out the location of all existing utilities. The contractor shall reference the attached site plan for location details.

11.3.5. The contractor shall use photometric analysis to design exterior lighting systems to minimize energy consumption, to reduce maintenance costs, improve lighting quality on DoD Installations, at the lowest life cycle cost.

11.3.6. The contractor must contain erosion materials from entering any adjoining storm drain so as not to cause soil to run off to area streams. The containment of excavated soil can be accomplished through exclusion with erosion control devices or by blocking any existing storm drain so the soil cannot enter it during excavation.

11.3.7. A concrete base shall be provided for each outdoor luminaire, unless noted otherwise. Base types shall be provided as detailed on the Drawings supplied. 24" dia. light pole bases (pre-manufactured or cast-in-place with forming tubes) with recommended reinforcement. Light bases shall be level, plumb and 48" above Finish Grade and 8' below grade. All forming tubes shall be removed after the base is fully cured. All concrete light pole bases shall be constructed as follows:

- All concrete shall be 4000 PSI. The contractor shall provide a bill of lading from the concrete company stating the concrete is 4000 PSI.

11.3.8. Pole erection of 2 arm 30' aluminum lighting poles. Light poles shall be installed in accordance with the pole manufacturer's instructions.

11.3.9. Only galvanized or stainless-steel bolts, nuts, washers, and screws shall be used for mounting luminaires or luminaire outlets.

11.3.10. All electrical work shall be performed under the direct supervision of a licensed Master Electrician.

11.3.11. All electrical work shall be in accordance with the latest revision of the National Electrical Code.

11.3.12. Must install a pole grounding connection designed to prevent electrolysis when used with copper ground wire. Provide aluminum standard with a M18 x 2 as specified in ISO 261 and ISO 262 1/2-inch square nut, 13 threads per inch, as specified in ISO 263, welded to the inside of the pole for ground connections. See attached drawing.

11.3.13. All conduit and wiring to power the lighting poles shall be at a depth of no less than 36" below finish grade. Wire shall be copper conductor, type THWN, unless otherwise specified. Wire gauge shall be sized appropriately for power demand and shall be field verified by contractor prior to ordering materials. Conduit shall be a minimum of 1". All buried conduits shall have 6" marking tape placed above it before backfilling.

11.3.14. Conduit that is to be in the trench crossing the road shall be encased concrete.

11.3.15. LED light fixtures for new lighting poles. The lights supplied shall be a minimum 0.2-foot candles. All new LED fixtures must have a minimum L70 life of 100,000 hours. The heads of the fixture shall be capable of being angled in different directions to provide the required lighting in the specific section of the MEP. The lighting provided shall be based on the DLC Qualified products list. Fixtures shall have dusk till dawn/timer feature to be determined by RFOS. The contractor shall be required to produce a photometric analysis with project submittals.

Performance Requirements:

- Horizontal Illuminance (average +/-10%) – 2 lux at grade
- Vertical Illuminance (average +/-10%) – 1 lux at 5'-0" AFF
- Horizontal Illuminance Uniformity – 20:1 Maximum to Minimum

11.3.16. Lenses, refractors, and glassware shall be clean and free from cracks or chips. All reflectors, shades, luminaire bodies, etc. shall be free from dents and scratches, thoroughly cleaned, and properly aligned before installation is accepted by the RFOS/COR. All exposed tags and labels other than UL and emergency ballast identifiers shall be removed.

11.3.17. The Contractor shall repair any damage incurred by the Contractor to original working condition at no additional cost to the Government. The Contractor shall ensure that the job site has been returned to its original appearance.

11.3.18. The contractor shall perform a complete demonstration of full system functionality per contract specifications to the RFOS/COR at the time of the project conclusion.

11.3.19. Fence Specifications

11.3.20. Approximately 100-line post shall be 2-1/2" diameter, schedule 40, 10 feet on center (O.C.) maximum spacing with concrete footings no less than 10" diameter x approximately 4' deep in concrete.

- Concrete mix shall conform to ASTM C 94/C 94M, using 3/4-inch maximum size aggregate, and having minimum compressive strength of 3000 psi at 28 days. No concrete work shall be performed when the temperature is below 38 degrees. All concrete, at finished grade, shall be sloped to drain away from fence posts.

11.3.21. Approximately 8 fence corner and gate posts shall be 4" diameter, schedule 40. Posts to be set 6 feet above grade. Post shall be zinc-coated steel, aluminum coated steel, aluminum alloy, or PVC over zinc-coated steel (material and coating is subject to the approval of RFOS prior to purchase and installation). To be set with concrete footings no less than 10" diameter x approximately 4' deep in concrete.

- Concrete mix shall conform to ASTM C 94/C 94M, using 3/4-inch maximum size aggregate, and having minimum compressive strength of 3000 psi at 28 days. No concrete work shall be performed when the temperature is below 38 degrees. All concrete, at finished grade, shall be sloped to drain away from fence posts.

11.3.22. Fencing fabric shall be minimum 9-gage wire mesh and mesh openings must not be greater than 2-inches (51 mm) per side. Fence fabric material shall be galvanized steel, PVC coated steel fabric. Fence Fabric Height UFC 4-022-03 Unless otherwise directed all security and perimeter fencing must have a minimum fabric height of 6 feet (2.13m), excluding the top guard. Fence height including outriggers must be a minimum of 7 feet (2.44m). The bottom of the fence shall not exceed two inches from final grade along the entire bottom of the fence line.

11.3.23. 18-inch barbed wire extension arms at the top of each post with (3) strands barbed approximately 3000 LF of wire equally spaced. Extension arms shall meet the following specifications:

- Extension arms material and coating shall be galvanized steel, PVC coated steel fabric, or aluminum coated steel fabric. Extension arm material and coating is subject to the approval of RFOS prior to purchase and installation.
- Extension arms shall be at a 45° angle for line posts and a 35° angle for corner posts.
- Extension arms shall angle towards threat side (away from the facility).
- Extension arms shall be permanently affixed to the fence posts with screws or by spot welding. Screws used to affix outriggers to posts must be made tamper-proof either by design, peening, or welding.

11.3.24. Grounding and bonding of the perimeter systems must be in accordance with the National Electric Safety Code (NESC) - IEEE C2. Fences that are required to be grounded by NESC must be designed to limit touch, step, and transferred voltages in accordance with industry practices. IEEE Std 80™-2000 - IEEE Guide for Safety in AC Substation Grounding is one source that may be utilized to provide guidance in meeting these requirements. The grounding connections must be made either to the grounding system of the equipment enclosed or to a separate ground.

- Fences must be grounded at each side of a gate or other opening.
- Gates must be bonded to the grounding conductor, jumper, or fence.
- A buried bonding jumper must be used to bond across a gate or other opening in the fence, unless a nonconducting fence section is used.
- If barbed wire strands are used above the fence fabric, the barbed wire strands must be bonded to the grounding conductor, jumper, or fence.
- When fence posts are of conducting material, the grounding conductor must be connected to the fence post or posts, as required, with suitable connecting means
- When fence posts are of nonconducting material, suitable bonding connection must be made to the fence mesh strands and the barbed wire strands at each grounding conductor point.

11.3.25. The contractor shall restore damage to grounds and plantings caused by the contractor's personnel or equipment. Topsoil shall be provided to fill any ruts and grass seed is to be raked into the soil.

11.3.26. Chain-link cantilever manual sliding vehicle gate for entrance and exit of MEP area. The MEP entrance gate shall be approximately 28 ft. The gate shall be constructed using 7-foot chain link fabric

topped by three evenly spaced strands of barbed wire. The bottom of the gate shall not exceed two inches from final grade along the entire bottom of the gate.

11.3.27. Milling Specifications

11.3.28. The Contractor shall provide all plant, labor, equipment, tools, materials, supervision, and transportation to accomplish the following work which consist of but is not limited to:

11.3.29. Cut a section road for concrete conduit see attached drawing. Approximately: 30'L x 2'W x 1'D

11.3.30. Mill/profile approximately 46,000 SF of Wear Course to the depth of 2 inches from the surface of the MEP Lot.

11.3.31. Inspect and advise the RFOS/COR of any areas of structural deficiencies in the subbase and Binder Course that could cause premature failure of the new asphalt Wear Courses. RFOS/COR shall advise the contractor of repairs to be performed prior to the application of the new asphalt.

11.3.32. Repair any cracks in milled surface that are 1/8 inch to 1/2 inch wide with an approved joint sealant. Crack sealant shall be Crack Master PL hot pour crack sealant, as manufactured by SealMaster Industries, Inc., or Parking Lot Sealant Type 1, as manufactured by Crafcro, Inc., or an approved equal. The substrate and air temperature shall be above 40°F. The contractor shall supply and apply heated crack sealant using either a pump and wand system or a pour pot. The sealant depth to width ratio shall not exceed 2 to 1 (2 inches deep to 1 inch wide). Using a sealing shoe or squeegee, band the material 2 to 3 inches wide over the crack. The cooled sealant height shall not exceed 1/8 inch above surrounding pavement. If required or needed.

11.3.33. Repair any cracks in milled surface less than 1 inch wide with an approved joint sealant. The Contractor shall apply crack sand sealant to all cracks 1/2 inch to 1 inch in width. Crack sand sealant shall be Crack Master PL hot pour crack sealant, as manufactured by SealMaster Industries, Inc., or Parking Lot Sealant, as manufactured by Crafcro, Inc., or an approved equal. The substrate and air temperature shall be above 40°F. The contractor shall supply and apply heated crack sand sealant using either a pump and wand system or a pour pot. The sealant depth to width ratio shall not exceed 2 to 1 (2 inches deep to 1 inch wide). Using a sealing shoe or squeegee, band the material 2 to 3 inches wide over the crack. The cooled sealant height shall not exceed 1/8 inch above surrounding pavement.

11.3.34. Cracks or joints greater than 1 inch shall be filled with an acceptable HMA bituminous mixture and applied in the same manner as the wear course (thoroughly cleaned, tack coat applied, then patched, and compacted).

11.3.35. Clean the surface of loose material with power brooms, power blowers and/or vacuums. The Contractor shall ensure the removal of all dirt, clay, and other loose material or foreign matter. At no time shall the Army reserve dumpsters and/or property be used for refuse of any kind during project execution.

11.3.36. Clean all cracks found in the bituminous pavement to prep them for sealant prior to the installation of the new asphalt. Cracks shall be free from grass, moisture, dust, loose aggregate, and any undesirable material. Cracks shall be cleaned with compressed air heat lance immediately prior to diluted emulsified asphalt application.

11.3.37. Apply a Tack Coat of diluted emulsified asphalt on approximately 46,000 SF of the milled surface and all non-vegetative edges or area that new asphalt shall come in contact with. The substrate and air temperature shall be above 40°F.

11.3.38. Furnish and install a new heavy duty HMA Wear course of asphalt to the areas that it was removed from. Asphalt shall be placed in one lift and shall be placed immediately after the Tack coat is applied and prior to its drying. Approximately 46,000 SF. The thickness shall be flush with all existing components that it comes in contact with after compaction. The Wear course shall be crowned and/or sloped in such a way to shed water to storm drains and/or sheet flow uniformly over an area without any ponding or puddling.

11.3.39. Seal all seams and edges, of newly placed asphalt with an approved emulsified asphalt joint sealant. The substrate and air temperature shall be above 40°F.

11.3.40. Ensure that all gates at facility have a 2" clearance between the bottom of the gate fabric and the surface of the finished pavement as required in UFC 4-022-03 Chapter 3.

11.4. DEMO

11.4.1. The contractor shall stipulate in the project work plan as to the intended method of disposal for all anticipated wastes generated. DoD prefers and encourages recycling of waste materials generated rather than disposal.

11.4.2. Fence

11.4.3. The contractor shall remove all existing fencing components, to include but not be limited to:

- Chain link fence fabric
- Line posts
- Corner posts
- Top rails
- Bracing
- Barbed wire top guard
- Reinforcing wire
- (1) Manual double swing gate
- Concrete fence post bases

11.4.4. The contractor shall provide clearing and grubbing along outside of the existing fence, to provide a 10' clear space on outside of property fence. All natural materials will be removed via the clearing and grubbing. Materials shall be disposed of offsite by the contractor IAW the strictest federal, state and local laws and regulations. See attached drawing for location specifics. All locations of work shall be confirmed with the RFOS/COR at PCM.

11.4.5. Lighting

11.4.6. Contractor shall excavate a trench:

- The trench shall be approximately 900 L.F. from the existing power pole to all new lighting locations.
- Trench shall be at a depth of least 36" below final grade 8"W. See attached site plan for location details.
- The trench shall be 4-6 ft outside of the fence line.

- The contractor shall follow Lighting Pole Base Detail for excavation. The contractor shall prep for four (4) light pole bases as per attached drawing. Pole base locations shall be in the trench line. Excavation shall be approximately 4'Wx10'D large enough for concrete base and stone for a base
- All excess excavated material not required for backfill or finish grading/restoration is to be disposed of off-site IAW all local, state and federal laws, regulations and guidelines

11.4.7 Asphalt Demo

11.4.8. The contractor shall Mill approximately 46,000 SF of MEP Lot

11.4.9. The contractor shall saw cut and excavate asphalt section of road approximately 60' L by 2'w by 6" d

11.5. INSTALL AND SERVICE

11.5.1. Fence

11.5.2. The contractor shall supply and install all new fencing components, to include but not be limited to:

- Supply and installation of chain link fence fabric.
- Supply and installation of line posts, See attached plot map.
- Supply and installation of corner posts, See attached plot map.
- Supply and installation of top rails.
- Supply and installation of bracing components.
- Supply and installation of barbed wire top guard and barbed wire.
- Supply and installation of reinforcing wire.
- Supply and installation of Fence Grounding.
- Supply and installation of (1) Manual cantilever gate.
- Supply and installation of concrete fence post bases.

11.5.3. Fence Installation

The contractor shall follow all specifications for the demo of existing fence and the installation of approximately 1000LF of new chain link fence with barbe top starting with but not limited to: 11.3.18.- 11.3.25. and 11.4.1.-11.4.4. And follow all UFC but not limited to: UFC 4-022-03 and manufacture specifications.

11.5.4. Lighting

The contractor shall supply and install approximately four (4) new parking lot light poles, to include but not be limited to:

- Supply and installation of new conduit in trench from existing light pole to new light pole locations, for power distribution See attached plot map. The contractor shall verify location of power distribution at PCM with RFOS.
- Supply and installation of encased concrete conduit in trench crossing the road.
- Supply and installation of concrete light pole bases.
- Supply and installation of approximately four (4) 30' Aluminum parking lot light poles, to include 2 head luminaires with dusk to dawn/timer feature .
- Supply and installation of all the required wiring to power new light poles.
- Power shall be from the main distribution panel/location through existing conduit into an existing lighting pole used as a junction point for new conduit to power all new poles installed. See attached drawing.

11.5.5. Lighting Installation

The contractor shall follow all specifications for lighting installation and demo as provided starting with but not limited to: 11.3.3.-11.3.17. and 11.4.1., 11.4.5., 11.4.6. And follow all UFC but not limited to: UFC's 1-200-01, 3-501-01, 3-530-01, 3-550-01, and manufacture specifications.

11.5.6. Lot Paving

11.5.7 The contractor shall supply and install all material for paving approximately 46,000 SF of MEP lot but not limited to:

- Supply and installation of asphalt patch as required due to trenching across road
- Supply and installation of protection for overspray
- Provide inspection reports for structural deficiencies
- Clean surface
- Supply and installation of crack repair in milled surface
- Supply and installation of spray tack coat
- Supply and installation of wear course of approximately 2" at MEP lot
- Supply and installation for sealed edges
- Ensure gate clearance is 2"

11.5.8. The contractor shall follow all specifications for MEP Lot Paving and demo as provided starting with but not limited to: 11.3.27.-11.3.40., 11.4.8.-11.4.9. And follow all UFC but not limited to: UFC-3-270-01, 3-250-03 and manufacture specifications.

11.6. CLEANUP AND REMOVAL AND DISPOSAL RECORDS:

11.6.1. The contractor shall remove all contract-generated debris from the construction site and dispose of the debris off site at an approved landfill/facility. Due to mandating of solid waste annual reporting requirements, contractor shall provide any and all receipts, manifest/BOL, and/or other written record of types of waste and amounts disposed within 30 calendar days of the completion of the project. Disposal shall be in accordance with Local, State and Federal laws and regulations. In case of conflict among these laws and regulations, the most stringent law or regulation will apply.

12. THIS CONCLUDES THE REQUIREMENTS OF THIS SOW: