

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Temporary materials may be new or used, but must be adequate in capacity for required usage, must not create unsafe conditions, and must not violate requirements of applicable codes and standards.
- B. Chain-Link Fencing: Minimum 2 inch (50 millimeters), 0.148 inch (3.76 millimeters) thick, galvanized steel, chain-link fabric fencing; minimum 6 feet (1.8 millimeter) high with galvanized steel pipe posts; minimum 2-3/8 inch (60 millimeters) OD (outside diameter) line posts and 2-7/8 inch (73 millimeters) OD corner and pull posts, with 1-5/8 inch (42 millimeters) OD top rails
- C. Portable Chain-Link Fencing: Minimum 2 inch (50 millimeters), 9-gage, galvanized steel, chain-link fabric fencing; minimum 6 feet (1.8 millimeters) high with galvanized steel pipe posts; minimum 2-3/8 inch (60 millimeters) OD line posts and 2-7/8 inch (73 millimeters) OD corner and pull posts, with 1-5/8 inch (42 millimeters) OD top and bottom rails. Provide concrete or galvanized steel bases for supporting posts.
- D. Safety Barrier Fence: Orange plastic fence, minimum height, 4 feet.
- E. Lumber and Plywood: Comply with requirements in Division 06 Section "Rough Carpentry".
- F. Insulation: Unfaced mineral-fiber blanket, manufactured from glass, slag wool, or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively.
- G. Polyethylene Sheet: Reinforced, fire-resistive sheet, 10 mil (0.25-millimeter) minimum thickness, with flame-spread rating of 15 or less per ASTM E 84 and passing NFPA 701 Test Method 2.

2.2 TEMPORARY FACILITIES

- A. Field Offices, General: Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.
- ~~B. Contracting Officers Field Office: Field office shall be a separate structure from Contractor's office.
 - 1. Prefabricated, job built, or a mobile unit; excellent condition, structurally sound, non-flammable exterior construction, weather tight, minimum 300 square feet.
 - 2. Operable windows and security screens, adjustable ventilation.
 - 3. Restroom (minimum of lavatory and toilet, with exhaust fan if room is windowless) or accessible Contractor facilities if available.
 - 4. Air conditioner and heater.
 - 5. Interior partition with lockable door to divide office
 - 6. Paneling or freshly painted walls, acoustical tile or painted ceilings, and resilient flooring.
 - 7. Two exterior doors with dead bolts keyed from outside,
 - 8. Minimum 20-square-foot landing and steps at each exterior door.~~

- C. Storage and Fabrication Sheds: Temporary weather tight sheds or other covered facilities for storage of materials subject to weather damage. Number and size of structures shall be subject to Contracting Officer's approval.
- D. Toilets: Sufficiently lighted and ventilated toilet facilities in weatherproof, sight proof, accessible, sturdy enclosures with privacy locks.
 - 1. Provide separate toilet facilities for men and women.

2.3 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.
- ~~B. Direct Digital Control (DDC) Internet Connection: Furnish, install and maintain a high-speed connection (Digital Subscriber Line (DSL) or similar) between the project's DDC system and the internet through a Contractor furnished internet service provider. Contractor is responsible for maintenance of this connection and costs associated with internet service provider through warranty period of this contract. Upon completion of warranty period, service shall be transferable to the Government at which time future costs for connection will no longer be the responsibility of Contractor.~~
- C. Contracting Officers Field Office
 - 1. Outlets: Minimum of two quad outlets with surge protection.
 - 2. Refrigerator: Under counter, 3.2-cubic-foot volume with 0.8-cubic-foot freezer with dedicated power receptacle.
 - 3. Fire Extinguisher: UL listed and FM (Fire Pump Motors) approved, minimum rating of 2-A:10-B:C, dry chemical.
 - 4. First-Aid Kit: General office/light industrial kit.
 - 5. Two desks with five drawers each and two chairs with casters; two drafting tables (minimum 40 inches wide by 5 feet long) and two stools; drawing rack; two 2-drawer and one 4-drawer legal size locking filing cabinets with keys; 8 feet of 12 inch deep shelving; coat rack; two additional guest chairs; two desk lamps; two drafting table lamps; and a maximum/minimum thermometer.
 - 6. Manufactured computer work station, capable of containing CPU (central processing unit), monitor, keyboard, printer; work station chair.
 - 7. Additional tables necessary for FAX machine and copier.
 - 8. Two 5-gallon trash cans and one 30-gallon trash can with lid.
 - 9. Ceiling mounted general lighting fixtures.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.

- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
 - 1. Arrange with utility company, NPS, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services. Acquire necessary permits.
- B. Storm Sewers and Drainage: Provide temporary utilities to remove effluent lawfully.
 - 1. Connect temporary sewers to private system indicated as directed by the agency(ies) with jurisdiction.
- C. Non-potable water for construction is not available within the park boundaries. Contractor shall furnish non-potable water from a source outside park boundary.
- D. Potable water is not available on site. Furnish cool, potable water for construction personnel in locations convenient to work stations.
- E. Sanitary Facilities: Provide temporary toilets, and wash facilities for use by construction personnel.
 - 1. Place in approved locations secluded from public observation and convenient to work stations. Relocate as work progress requires.
 - 2. Maintain and clean toilet facilities at least weekly.
 - 3. Completely remove sanitary facilities on completion of work.
- F. Electric Power Service: Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.
- G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, and inspections.
 - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
- H. Telephone Service: No telephone service is available on site for Contractor's use. Make arrangements with Telephone Company and pay costs.

3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
 - 1. Provide incombustible construction for offices, shops, and sheds located within construction area or within 50 feet of building lines. Comply with NFPA 241.
 - 2. Maintain support facilities until near Substantial Completion. Remove structures, equipment, and furnishings, and terminate services after punch list is 100 percent

completed or when directed by Contracting Officer. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Contracting Officer.

~~B. Contracting Officers Field Office:~~

- ~~1. Provide Heat, lights, power, air conditioning, temporary water pressure and sewage holding tanks.~~
- ~~2. Provide office, furnishings, and utility connections no later than 7 days after date of Notice to Proceed. Exact location will be determined by Contracting Officer.~~
- ~~3. Maintain equipment, furnishings, and structures. Provide equipment replacement elements as needed. Provide weekly cleaning services and trash disposal. Maintain and service water and sewer holding tanks as required.~~

C. Traffic Controls: Erect and maintain barricades, lights, danger signals, and warning signs in accordance with Manual on Uniform Traffic Control Devices (MUTCD), Part 6, latest edition.

1. Protect existing site improvements to remain including curbs, pavement, and utilities.
2. Maintain access for fire-fighting equipment.
3. Illuminate barricades and obstructions at night; keep safety lights burning from sunset to sunrise.
4. Adequately barricade and post open cuts in or adjacent to thoroughfares.
5. Install Barrier Tape where directed by Contracting Officer. Keep a minimum of two rolls on site.

D. Parking: Use designated areas of existing shown on drawings parking areas for construction personnel.

E. Dewatering Facilities and Drains: Comply with requirements of the agency(ies) with jurisdiction. Maintain Project site, excavations, and construction free of water.

1. Dispose of rainwater in lawful manner that will not result in flooding Project or adjoining properties nor endanger permanent Work or temporary facilities.
2. Remove snow and ice as required to minimize accumulations.

F. Project Identification and Temporary Signs: Provide Project identification and other signs. Fence, barricade, or otherwise block off the immediate work area to prevent unauthorized entry.

1. Provide temporary, directional signs for construction personnel and visitors.
2. Maintain and touchup signs so they are legible at all times.
3. Erect and maintain sufficient detour signs at road closures and along detour routes.

G. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of agency(ies) with jurisdiction.

H. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.

1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.