

STATEMENT OF WORK (SOW)

FOR

Engine shop area upgrades

1.0 General:

1.1 Scope: The contractor shall provide all personnel, equipment, tools, materials, supervision, and quality control necessary, except as specified in Paragraph 3.0 as Government Furnished, for the Engine shop area upgrades, as defined in this PWS.

1.1.1 Objectives: Demo and remove buildings 115, 131, 133, tent structure 321, abandoned electrical components, guardrail, fencing, and concrete and asphalt areas as shown on the demolition plan and remove 12K underground storage tank near B124. Purchase and install storm water control structures as shown in the drawings to include catch basins, piping, and trench drains to provide a proper flow channel and remove water from the areas allowing the grounds to be maintained. Purchase and install the required electrical conduit and wiring to support new fabric shelters. Prepare areas for placement of a new concrete access road, concrete tent pad, and concrete approach around building 137 and an asphalt shoulder patch as shown on the pavements plan. Purchase and install two new tensioned fabric shelters with liners, electrical equipment, interior lights, and doors as shown on attached drawing with one shelter having dehumidification equipment for humidity control. The contractor shall provide all labor, equipment, tools, appliances, transportation, materials, disposal and all documentation associated with the project.

1.2 Background: The existing buildings, pavements, electrical, and drainage around the engine shop facility are unusable to the current and future mission and creates hazards for aircraft operations due to deteriorated pavements. The storm drainage issues causes excessive vegetation that cannot be maintained by base personnel creating flight safety bird hazards and erosion of the North road – road base and the old 12K tank creates environmental risk to the storm drainage system.

1.3 Period of Performance (PoP): The Period of Performance shall be 120 days after issuance of the notice to proceed.

1.4 General Information:

1.4.1 Place and Performance of Services: The contractor shall provide services between the hours of 0700 - 1600 on Monday through Friday except on recognized US holidays or when the Government facility/installation is closed due to local or national emergencies, administrative closings, or similar Government-directed facility/installation

closings. Performance shall be in and around building 137 and the Northgate road at the 180th Fighter Wing, 2660 S. Eber Rd., Swanton, OH 43558. The contractor shall at all times maintain an adequate work force for the uninterrupted performance of all tasks defined within this PWS when the Government facility/installation is not closed for the above reasons. When hiring personnel, the contractor shall keep in mind that the stability and continuity of the work force are essential.

1.4.1.1 Telework: Not Applicable.

1.4.1.2 Unscheduled gate closures by the Security Police may occur at any time causing all personnel entering or exiting a closed installation to experience a delay. This cannot be predicted or prevented. Contractors are not compensated for unexpected closures or delays. Vehicles operated by contractor personnel are subject to search pursuant to applicable regulations. Any moving violation of any applicable motor vehicle regulation may result in the termination of the contractor employee's installation driving privileges.

1.4.1.3 The contractor's employees shall become familiar with and obey the regulations of the installation; including fire, traffic, safety and security regulations while on the installation. Contractor employees should only enter restricted areas when required to do so and only upon prior approval. All contractor employees shall carry proper identification with them at all times and shall be subject to such checks as may be deemed necessary. The contractor shall ensure compliance with all regulations and orders of the installation, which may affect performance. The Government reserves the right to direct the removal of an employee from Government property or revoke access to Government systems for misconduct, security reasons, or any overt evidence of communicable disease. Removal of contractor employees for reasons stated above does not relieve the Contractor from responsibility for total performance of this contract.

1.4.2 Recognized Holidays: The following are recognized United States (US) holidays. The contractor shall not perform services on these days unless otherwise approved in advance by the COR and the contracting officer. Requests to work holidays shall be made a minimum of 3 working days prior to the requested day(s).

- 1.4.2.1 New Year's Day: January 1st
- 1.4.2.2 Martin Luther King, Jr.'s Birthday
- 1.4.2.3 President's Day
- 1.4.2.4 Memorial Day
- 1.4.2.5 Juneteenth National Independence Day: June 19th
- 1.4.2.6 Independence Day: July 4th
- 1.4.2.7 Labor Day
- 1.4.2.8 Columbus Day
- 1.4.2.9 Veteran's Day: November 11th
- 1.4.2.10 Thanksgiving Day
- 1.4.2.11 Christmas Day: December 25th

1.4.3 Quality Control (QC): The contractor shall develop and maintain an effective QC Plan (QCP) to ensure services are performed in accordance with this PWS. The contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The contractor's QCP is the means by which it assures itself that its work complies with the requirements of the contract. As a minimum, the contractor shall develop QC procedures that address the areas identified in Technical Exhibit 1, Performance Requirements Summary (PRS).

1.4.4 Quality Assurance (QA): The Government will evaluate the contractor's performance under this contract in accordance with the Quality Assurance Surveillance Plan (QASP). This plan is primarily focused on what the Government will do to ensure that the contractor has performed in accordance with the performance standards. It defines how the performance standards will be applied, the frequency of surveillance, and acceptable quality level(s) or defect rate(s).

1.4.5 Access and General Protection/Security Policy and Procedures. The contractor shall comply with all applicable installation/facility access and local security policies and procedures, which may be obtained from the Contracting Officer's Representative (COR). The contractor shall also provide all information required for background checks to meet installation access requirements to be accomplished by the local installation's Security Forces, Director of Emergency Services or local Security Office. The contractor shall ensure compliance with all personal identity verification requirements as directed by DoD, Headquarters Air Force (HAF) and/or local policy. Should the Force Protection Condition (FPCON) change, the Government may require changes in contractor security matters or processes.

a. The contractor shall obtain base identification and vehicle passes, if required, for all contractor personnel who make frequent visits to or perform work on the Air Force installation(s) cited in the contract. Contractor personnel are required to wear or prominently display installation identification badges or contractor-furnished, contractor identification badges while visiting or performing work on the installation.

b. The contractor shall submit a written request on SFS FORM 77 to the contracting officer listing the following: contract number, location of work site, start and stop dates, and names of employees and subcontractor employees needing access to the base. The letter will also specify the individual(s) authorized to sign for a request for base identification credentials or vehicle passes. The contracting officer will endorse the request and forward it to the issuing base pass and registration office or Security Forces for processing. When reporting to the registration office, the authorized contractor individual(s) should provide a valid drivers license, current vehicle registration, valid vehicle insurance certificate, and [insert any additional requirements to comply with local security procedures] to obtain a vehicle pass.

c. During performance of the contract, the contractor shall be responsible for obtaining required identification for newly assigned personnel and for prompt return of

credentials and vehicle passes for any employee who no longer requires access to the work site.

d. Reserved.

e. Upon completion or termination of the contract or expiration of the identification passes, the prime contractor shall ensure that all base identification passes issued to employees and subcontractor employees are returned to the issuing office.

f. Failure to comply with these requirements may result in withholding of final payment.

1.4.5.1. For Contractors Requiring Common Access Card (CAC). Not Required.

1.4.5.2 For Contractors that do not require CAC, but require access to a DoD Facility and/or Installation. Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) (Air Force Instruction (AFI) 10-245, AFI 31-101 and Air Force Manual (AFMAN) 31-113), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by Government representative)

1.4.5.3 Antiterrorism Awareness Level I Training (AT Level I). All contractor employees, to include subcontractor employees, requiring access to US Government installations, facilities and controlled access areas shall complete AT Level I training within 15 calendar days after contract start date or effective date of incorporation of this requirement into the contract, whichever is applicable. AT Level I may be accomplished by a Level I qualified instructor; completing the Force Protection computer-based training (CBT) course on the Advanced Distributed Learning System (ADLS) or Joint Knowledge Online at <http://jko.jten.mil>. Tracking for each contractor or subcontractor employee is the responsibility of the unit AT Representative. The contractor shall submit certificates of completion for each affected contractor and subcontractor employee to the COR within 15 calendar days after completion of training by each employee or subcontractor personnel.

1.4.5.4 Reserved.

1.4.5.5 Communications Security/Information Technology (COMSEC/IT) Security. All communications with DoD organizations are subject to COMSEC review. All telephone communications networks are continually subject to intercept by unfriendly intelligence organizations. DoD has authorized the military departments to conduct COMSEC monitoring and recording of telephone calls originating from, or terminating at, DoD organizations. Therefore, the contractor is advised that any time contractor personnel place or receive a call they are subject to COMSEC procedures. The contractor shall

ensure wide and frequent dissemination of the above information to all employees dealing with DoD information. The contractor shall abide by all Government regulations concerning the authorized use of the Government's computer network, including the restriction against using the network to recruit Government personnel or advertise job openings.

1.4.5.6 Reserved

1.4.5.7 Reserved.

1.4.5.8 Reserved

1.4.5.9 Reserved

1.4.5.10 Reserved

1.4.5.11 Requirement for OPSEC Training. In accordance with AFI 10-701, Operations Security, OPSEC PMs/Signature Managers/Coordinators will provide OPSEC training or training materials to contract employees within 30 days of employees' initial assignment to the contract and prior to having access to any critical information (CI) and annually thereafter. General organizational orientations may need to be supplemented by duty-related orientations in the work center targeted toward specific critical information and vulnerabilities associated with the work. Initial training (OPSE 1301 - OPSEC Fundamentals) is located on the ADLS website and refresher OPSEC training is conducted annually (at Commander's Call). The contractor shall submit certificates of completion for each contractor employee to the COR within 15 calendar days after completion of training.

1.4.5.12 OPSEC Plan. Not Required.

1.4.5.13 Contracts that require Handling or Access to Classified Information: Not Required.

1.4.6 Physical Security. The contractor shall safeguard all Government property provided for contractor use. At the close of each work period, Government facilities, equipment and materials shall be secured.

1.4.6.1 Key Control: Not Required

1.4.7 Special Qualifications: Reserved.

1.4.8 Post Award Conference/Periodic Progress Meetings: The contractor agrees to attend any post award conference convened by the KO in accordance with FAR 42.5. The KO, COR and other Government personnel, as appropriate, may meet periodically with the contractor to review the contractor's performance. At these meetings, the KO will apprise the contractor of how the Government views the contractor's performance

and the contractor shall apprise the Government of problems, if any, being experienced. The contractor shall resolve outstanding issues raised by the Government. Contractor attendance at these meetings shall be at no additional cost to the Government.

1.4.9 Contract Manager (CM): The contractor shall designate a CM who shall ensure performance under this contract. The name of this person, and an alternate who shall act for the contractor when the CM is absent, shall be designated in writing to the KO. The CM or alternate shall have full authority to act for the contractor on all contract matters relating to daily operation of this contract. The CM shall work through the COR to resolve issues, receive technical instructions, and ensure adequate performance of services. The CM shall ensure that contractor employees do not perform any services outside the scope of the contract without an official modification issued by the KO. The CM shall ensure contractor employees understand that services performed outside the scope of the contract are performed wholly at the expense of the contractor.

1.4.10 Identification of Contractor Employees: All contractor personnel attending meetings, answering Government telephones and working in other situations where their contractor status is not obvious to third parties are required to identify themselves as such to avoid creating an impression that they are Government employees. The contractor shall ensure that all documents or reports produced by contractor personnel are suitably marked as contractor products or that contractor participation is appropriately disclosed. The contractor's status as a "contractor" shall be predominantly displayed in all correspondence types (to include signature blocks on e-mail) and dealings with Government or non-Government entities. Contractor personnel shall wear identification badges distinguishing themselves as such. The badges shall have the company name, employee name and the word "contractor" displayed.

1.4.10.1 The contractor shall retrieve all identification media (including vehicle passes) from its employees who depart employment for any reason. The contractor shall return all identification media (i.e., badges and vehicles passes) to the KO within 14 days of an employee's departure.

1.4.11. Combating Trafficking in Persons: The United States Government has adopted a zero tolerance policy regarding trafficking in persons. Contractors and contractor employees shall not engage in severe forms of trafficking in persons during the period of performance of the contract; procure commercial sex acts during the period of performance of the contract; or use forced labor in the performance of the contract. The Contractor shall notify its employees of the United States Government's zero tolerance policy, the actions that will be taken against employees for violations of this policy. The contractor shall take appropriate action, up to and including termination, against employees or subcontractors that violate the US Government policy as described at FAR 22.17.

1.4.12 Contractor Travel: Not Applicable

1.4.13 Data Rights: Not Applicable

1.4.14 Organizational Conflicts of Interest (OCI): The contractor and subcontractor personnel performing services under this contract may receive, have access to or participate in the development of proprietary or source selection information (e.g., cost or pricing information, budget information or analyses, specifications or work statements, etc.) or perform evaluation services which may create a current or subsequent OCIs, as defined in FAR Subpart 9.5. The contractor shall notify the KO immediately whenever it becomes aware that such access or participation may result in any actual or potential OCI and shall promptly submit a plan to the KO to avoid or mitigate any such OCI. The contractor's mitigation plan will be determined to be acceptable solely at the discretion of the KO. In the event the KO unilaterally determines that any such OCI cannot be satisfactorily avoided or mitigated, the KO may impose other remedies as he or she deems necessary, including prohibiting the contractor from participation in subsequent contracted requirements which may be affected by the OCI.

1.4.15 Phase In / Phase Out Periods: Not Applicable

2.0 Definitions and Acronyms:

2.1 Definitions:

2.1.1 Contractor: A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

2.1.2 Defective Service: A service output that does not meet the standard of performance associated with the PWS.

2.1.3 Deliverable: Anything that can be physically delivered and includes non-manufactured things such as meeting minutes or reports.

2.1.4 Key Personnel: Contractor personnel that are evaluated in a source selection process and that may be required to be used in the performance of a contract by the PWS. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the persons that are listed in the proposal.

2.1.5 Physical Security: Actions that prevent the loss or damage of Government property.

2.1.6 Quality Assurance: The Government procedures to verify that services being performed by the Contractor are performed according to acceptable standards.

2.1.7 Quality Assurance Surveillance Plan (QASP): An organized written document specifying the surveillance methodology to be used for surveillance of contractor performance.

2.1.8 Quality Control: All necessary measures taken by the Contractor to ensure that the quality of an end product or service shall meet contract requirements.

2.1.9 Subcontractor: One that enters into a contract with a prime contractor. The Government does not have privity of contract with the subcontractor.

2.2 Acronyms:

AEI	Army Enterprise Infostructure
AR	Army Regulation
AT/OPSEC	Antiterrorism/Operational Security
BI	Background Investigation
CM	Contract Manager
COR	Contracting Officer Representative
DA	Department of the Army
DD254	Department of Defense Contract Security Classification Specification
DFARS	Defense Federal Acquisition Regulation Supplement
DoD	Department of Defense
DSCA	Defense Counterintelligence and Security Agency
FAR	Federal Acquisition Regulation
GFP/M/E/S	Government Furnished Property/Material/Equipment/Services
HQDA	Headquarters, Department of the Army
HSPD	Homeland Security Presidential Directive
IA	Information Assurance
IS	Information System(s)
KO	Contracting Officer
NGB	National Guard Bureau
OCI	Organizational Conflict of Interest
PII	Personally Identifiable Information
PIPO	Phase In/Phase Out
POC	Point of Contact
PRS	Performance Requirements Summary
PWS	Performance Work Statement
QA	Quality Assurance
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Program
SCR	Service Contract Reporting
SSN	Social Security Number
TE	Technical Exhibit
USD(I)	Under Secretary of Defense for Intelligence

3.0 Government Furnished Property, Material, Equipment and Services (GFP/M/E/S):
The Government will provide the property, material, equipment, and/or services listed below solely for the purpose of performance under this contract:

3.1 Property: None

3.2 Materials: None

3.3 Equipment: None

3.4 Services: None

3.5 Utilities: All utilities in the facility will be available for the contractor's use in the performance of this contract. The contractor shall instruct employees in utilities conservation practices. The contractor shall operate under conditions that preclude the waste of utilities, which include turning off the water faucets or valves after using the required amount.

4.0 Contractor Furnished Property, Materials, and Equipment (CFP/M/E): RESERVED

5.0 Requirements: The contractor shall furnish all supervision, labor, materials, equipment, and supplies and other items of expense required to perform the work specified in this document in strict accordance with the specifications and drawings for this project and provide the government a complete and useable end product.

Facility 115:

5.1.1 Contractor shall install silt protection as required by the 180th SWPP.

5.1.2 Disconnect, remove, and properly dispose of existing electrical equipment and wiring. Underground conduits can remain but must be demo'd and capped at least 1' below grade where the facility was located.

5.1.3 Demo the remaining structure and dispose of the materials.

5.1.4 Demo the structures concrete pad to include the approach as shown on the demo plan.

5.1.5 Reclaim any easily accessible stone for reuse without disturbing soil beneath.

5.1.6 Fill in and blend topsoil to final grade prep and seed/straw with netting. (Seed shall be determined based on best product for time of year planted)

Facility 131, 133, 321:

5.1.7 Contractor shall install silt protection as required by the 180th SWPP.

5.1.8 Disassemble existing fabric shelter and electrical equipment in the shelter for re-erection at a later date.

5.1.9 Disconnect, remove, and properly dispose of existing electrical equipment and wiring. Underground conduits can remain but must be demo'd and capped at least 1' below grade where the facility was located.

- 5.1.10 Demo the remaining structures to include guardrail and fence shown on the demo plan and dispose of the materials.
- 5.1.11 Demo the concrete pad and foundations down to soil or 2 feet below grade as shown on the demo plan. Contractor shall minimize soil disturbance.
- 5.1.12 Reclaim any easily accessible stone for reuse without disturbing soil beneath.

Pavements:

- 5.1.13 Contractor shall install any additional silt protection as required by the 180th SWPP.
- 5.1.14 Field verify elevations for the access road, new tent pads, tent pad approach, and B137 approach.
- 5.1.15 Remove topsoil as required for new pavement stone base and store soil on site for reuse in this project.
- 5.1.16 Install stone base as required and per pavements plan. Note the thickened edge on the perimeter of each tent outline.
- 5.1.17 Install trench drains, drain piping, and electrical conduit as required per pavements plan.
- 5.1.18 Place concrete as required per pavements plan.

Storm Drainage:

- 5.1.19 Contractor shall install any additional silt protection as required by the 180th SWPP.
- 5.1.20 Field verify elevation inverts for existing drainage pipes and outfalls, new proposed catch basins as shown on the Engine facility pavements and storm extension drawings.
- 5.1.21 Purchase and install catch basins, gate valves, and piping to create a functional flow channel as annotated on the drawings.
- 5.1.22 Utilize stored onsite soil and procure and install additional soil required to fill in and contour around the new catch basins and piping to create proper slope for drainage of the areas.
- 5.1.23 Clean the storm culverts on in the project area to ensure flow to the outfalls.
- 5.1.24 Blend topsoil to final grade, prep and seed/straw to establish grass.

12K Underground Tank Removal:

- 5.1.25 Excavate soil and gravel around the tank and plan to reuse suitable material.
- 5.1.26 Remove and dispose of the contaminated wastewater contained in the tank, testing results available but contractor to confirm results due to testing age.
- 5.1.27 Remove and dispose of 12K recovery tank to include concrete ballast pad.
- 5.1.28 Remove utilities around tank and Cap/seal pipes where they leave the tank area.
- 5.1.29 Cap the Diverter Valve connection(Ductile Iron) that leads to the 12K tank.
- 5.1.30 Contractor will sample surrounding soils where the tank was located to verify no POL products are present in soils.
- 5.1.31 Contractor shall fill, level and grade worksite to match adjacent soils.
- 5.1.32 Blend topsoil to final grade, prep and seed/straw to establish grass.

Fabric Structures:

5.1.33 Purchase and install 2 fabric shelters as shown on the drawings. Shelters shall be ~80' x 60', be sealed to the concrete, include 1 roll up door, 1 man door, and have an interior liner to better seal the shelter for humidity control.

5.1.34 Purchase and install required electrical conductors, 480V 3ph electrical panel, lighting transformer, interior lights, switches, outlets, roll up garage door, de-humification units in the east shelter. 20A Outlets will be located near the transformer and by the man door with the light switch. Shelter shall have 2 exterior aimable overhead lights, each located near the rollup door upper corner.

5.1.35 Purchase and install electrical conductors, interior lights, switches, outlets, roll up garage door in the west shelter. 20A Outlet will be located by the man door with the light switch. Shelter shall have 2 exterior aimable overhead lights, each located near the rollup door upper corner.

5.2 Submittals: Submit technical data, catalog cut sheets, samples, test reports or other items as listed below:

5.2.1 Submittals: cut sheets for catch basins, Concrete design, trench drains, fabric shelters, electrical panel, lighting transformer, 12k tank Liquid and soil testing results.

5.2.2 180th FW Ozone Depleting Substances Form for all material & equipment containing refrigerants(driers) – N/A

5.2.3 As-built drawings – Provide an as-built drawing of new or modified electrical circuits.

5.2.4 Operations and maintenance manuals, and operating instructions for all installed equipment.

5.2.5 Submittals shall be provided with an AF Form 3000 filled out and signed by the contractor certifying the material is in compliance with the project requirements.

5.3 General:

5.3.1 Portable Toilet: Not applicable for this project – use facility bathrooms

5.3.2 Some of the work area is adjacent to the aircraft parking apron and is a secure restricted area.

5.3.3 Vehicles and equipment going onto the parking apron shall be inspected and checked for Foreign Object Debris (FOD) by the contractor prior to going on to the apron. All debris and objects which could become FOD shall be removed and properly disposed of or secured.

5.3.4 Smoking on base is only allowed in designated areas (smoking sheds are marked with signs).

5.3.5 The contractor shall verify existing dimensions and conditions prior to submitting a bid and again prior to beginning work.

5.3.6 The contractor shall provide the government project manager or COR 7 days written notice before performing any disturbance of the ground to a depth below 3". The notice shall include a drawing of the area where the work is to be done. Mark the work area and proposed excavations with white flags or marking paint if required by the government, so existing utilities can be properly identified before

beginning any demolition or excavation. Contractor shall ensure an approved Air Force Form 103 Work Clearance is issued before beginning any excavations.

- 5.3.7 Provide a minimum of 7 days advance notice in writing to the Contracting Officer or COR prior to the shutdown of any building utility system, street, or parking lot.
- 5.3.8 The contractor shall ensure that all work complies with all federal state and local laws and ordinances applicable to the construction of this project. Install all equipment according to the manufacturer's written instructions. If a conflict is found, notify the Contracting Officer for resolution of the conflict prior to proceeding.
- 5.3.9 Prior to performing any operation requiring use of an open flame, or spark producing work obtain a burn permit from the base fire department (419-868-4116). The contractor shall provide and maintain fire extinguishers and other safety equipment at the job site at all times as required to perform the work.

5.6 Service Contract Reporting: Reserved for projects over \$3 million.

6.0 Applicable Publications: Publications applicable to this PWS are listed below:

Publication (Chapter/Page)	Date of Publication	Mandatory or Advisory	Website
Federal Acquisition Regulation		Advisory	https://www.acquisition.gov/?q=browsefar
Defense Federal Acquisition Regulation Supplement		Advisory	http://www.acq.osd.mil/dpap/dars/dfarspgi/current/index.html or https://www.acquisition.gov/dfars
Joint Travel Regulation (JTR)		Advisory	https://www.defensetravel.dod.mil/site/travelreg.cfm
DoDM 1000.13-M-V1 DoD Identification (ID) Cards (Enclosure 2, paragraph 3.b)	01/23/2014 (Change 1: 07/28/2020)	Advisory	http://www.esd.whs.mil/Directives/issuances/dodm
Federal Information Processing Standards (FIPS) Publication 201-2 Personal Identity Verification (PIV) of Federal Employees and Contractors (paragraph 9)	August 2013	Advisory	http://nvlpubs.nist.gov/nistpubs/FIPS/NIST.FIPS.201-2.pdf
DoDM 5200.2 Procedures for the DoD Personnel Security Program (PSP)	04/03/2017	Advisory	https://www.esd.whs.mil/Directives/issuances/dodm/
DoDI 5200.46 DoD Investigative and Adjudicative Guidance for Issuing the Common Access Card (CAC)	09/09/14 (Change 1: 05/04/2018)	Advisory	https://www.esd.whs.mil/Directives/issuances/dodi/
Homeland Security Presidential Directive (HSPD)-12 Policy for a Common Identification Standard for Federal Employees and Contractors	08/27/2004	Advisory	https://www.dhs.gov/homeland-security-presidential-directive-12
DoDI 5400.11 Department of Defense Privacy and Civil Liberties Programs	01/29/2019	Advisory	https://www.esd.whs.mil/Directives/issuances/dodi/
DoD 5400.11-R Department of Defense Privacy Program	05/14/2007	Advisory	https://www.esd.whs.mil/Directives/issuances/dodm/

DoDD 8140.01 Cyberspace Workforce Management	10/05/2020	Advisory	https://www.esd.whs.mil/Directives/issuances/dodd/
DoD 8570.01-M Information Assurance Workforce Improvement Program	12/19/2005 (Change 4: 11/10/2015)	Advisory	https://www.esd.whs.mil/Directives/issuances/dodm/
DoD 5220.22-M National Industrial Security Program Operating Manual (NISPOM)	02/28/2006 (Change 2: 05/18/2016)	Advisory	https://www.esd.whs.mil/Directives/issuances/dodm/
AFI 10-245 Antiterrorism	03/28/2013 (Certified current 03/30/2017)	Advisory	https://www.e-publishing.af.mil/Product-Index/#/?view=pubs&orgID=10141&catID=1&series=-1&modID=449&tabID=131
AFI 31-101 Security Forces Standards and Procedures	08/18/2020	Advisory	https://www.e-publishing.af.mil/Product-Index/#/?view=pubs&orgID=10141&catID=1&series=-1&modID=449&tabID=131
AFMAN 31-113 Security Forces Standards and Procedures	03/05/2013 Change 1: 12/02/2015	Advisory	https://www.e-publishing.af.mil/Product-Index/#/?view=pubs&orgID=10141&catID=1&series=-1&modID=449&tabID=131
AFPD 17-1 Information Dominance Governance and Management	04/12/2016	Advisory	https://www.e-publishing.af.mil/Product-Index/#/?view=pubs&orgID=10141&catID=1&series=-1&modID=449&tabID=131
AFMAN 17-1301 Computer Security (COMPUSEC)	02/12/2020	Advisory	https://www.e-publishing.af.mil/Product-Index/#/?view=pubs&orgID=10141&catID=1&series=-1&modID=449&tabID=131
AFI 10-701 Operations Security	7/24/2019 (Change 1: 06/09/2020)	Advisory	https://www.e-publishing.af.mil/Product-Index/#/?view=pubs&orgID=10141&catID=1&series=-1&modID=449&tabID=131

6.1 Applicable Forms: Forms applicable to the PWS are listed below:

Form	Date	Website
AF Form 3000 Material Approval Submittal	Most recent version	https://static.e-publishing.af.mil/production/1/saf_aq/form/af3000/af3000.pdf

TECHNICAL EXHIBIT 1

Performance Requirements Summary (PRS)

This PRS includes performance objectives the Government will use to determine contractor performance and will compare contractor performance to the Acceptable Quality Level (AQL).

Performance Objective	Performance Standard	Acceptable Quality Levels (AQL)	Surveillance Method / By Whom
Demolition and disposal of materials	Complete removal of demo'd facility materials, concrete, tank, and unusable fill.	100% of existing materials removed and properly disposed of per environmental regulations	Visual inspection and disposal documentation review by the 180 th Environmental office.

Performance Objective	Performance Standard	Acceptable Quality Levels (AQL)	Surveillance Method / By Whom
Provide and install stone base, drainage structures, piping, electrical conduit, and any utility piping caps.	Proper drainage and flow channels, leak free joints, and proper elevations for finish grade structures	100% compliance with performance specifications verified through operational testing	Performance testing with survey equipment and flow of water by 180 th COR
Provide and install concrete, and any associated rebar, dowels, sealants, sealers.	All concrete work per drawings, specifications and 3-270-01 Unified Facilities Criteria (UFC)	100% drawings and UFC specifications unless given COR approval to deviate	Concrete testing, visual inspection 180 th COR
Provide and install appropriate electrical components	All electrical work compliant with NEC standards and local codes	100% code compliance with zero electrical deficiencies	Electrical inspection and testing verification 180 th COR
Provide and install Fabric Structures to include electrical and HVAC equipment	All work meeting manufacturers requirements and compliant with NEC standards and local codes	100% code compliance with zero electrical deficiencies with Warranty's provided from manufacturer or installer.	Inspection by manufacturer or 180 th COR depending on component.
Complete grading for proper drainage and flow with establishment of grass along with proper silt protection throughout project	Fully operational site meeting all performance requirements upon project completion	100% system functionality with successful startup and performance verification	Commissioning test and operational demonstration. 180 th COR and 180 th Environmental

TECHNICAL EXHIBIT 2

Deliverables Schedule

PWS Reference / Deliverable Title	Frequency	Number of Copies	Medium/Format	Submit To
5.2.4 As-built drawing	Once, at completion	1	Electronic Submission (PDF)	COR
1.4.5.3 AT Level 1 Awareness Training Certificates	Provide within 15 calendar days after employee completes training.	1	Electronic Submission	COR
1.4.5.11 OPSEC Training Certificates	Provide within 15 calendar days after employee completes training.	1	Electronic Submission	COR