

Statement of Work

Replace Boiler Bldg. 2310/Bldg. 1610

Revised 2/24/2026

GENERAL:

The contractor shall furnish all personnel, equipment, supervision, and materials necessary to remove, install, and commission a complete and functional boiler in B2310 and B1610 that will be fully integrated into the existing facility infrastructure IAW the SOW.

Requirements:

Contracting is requiring the removal of two boilers, one located in Bldg. 2310 and the other in Bldg. 1610 and replaced with new units. The following work shall be IAW with manufacture instructions in conjunction with the SOW.

The contractor shall furnish and install two Lochinvar boilers or equal with the following required features to replace existing equipment. The minimum salient characteristics of the boiler are as follows.

- a. Bldg. 2310 Lochinvar KnightXL Model KBX-1000N-M13 (1 EA) or equal.
- b. Bldg. 1610 Lochinvar KnightXL Model KBX-0400N (1 EA) or equal.
- c. Minimum 7" touchscreen LCD display
- d. 97% Thermal Efficiency
- e. Flow Switch
- f. Condensate trap Neutralizer
- g. 10:1 Turndown Modulating burner

System Installation:

The following items will be inspected to ensure compliance:

1. Connect new boiler to existing electric, water, and gas lines.
2. Isolate existing boilers from main loop. If the loop must be drained because existing valves fail, or no valves available contractor must notify Project Manager prior to draining.
3. Provide and install a new appliance regulator as required and coordinate with existing building gas pressure. If an in-line regulator is used, it must be a minimum of 10 feet from boiler. Ensure interior regulator is vented to the outside.

4. Install condensate neutralizer kit on boiler and ensure a union is installed for future maintenance and is plumbed to floor drain not to be connected to any other drain system.
5. Provide BMS with BACnet (over IP) cards with the new boiler.
6. Re-establish existing ECS capability in each boiler if they are currently connected.
7. Install exhaust and intake ducts as required by manufacture instructions. (PVC is acceptable where manufacturer allows).
8. Install Supply and Return isolation valves between existing systems and unions on the new boiler. Valves need to be full port ball valves sized to boiler connections.
9. Install Supply and Return tee connections between existing system and new isolation valves to include Full port ball valves on offset of the tee for future emergency connection capped or plugged. Tee and offset connection valves to be sized to boiler connections. Ensure location of emergency hook up is within reasonable reach for future tie ins. Field verification of location by Project Manager prior installation. Tie ins will be 2 ½”.
10. Install new wye strainer on the boilers return line with a blow down valves and plugged/capped.
11. Install field flow switch tying it back to the boiler’s controls. (In the event boiler manufacture does not provide one.)
12. Minor modification will be required to the existing supply and return lines connecting to the boilers to ensure proper flow between boilers and the system. Field verification will be required for pipe sizing and material.
13. Insulate all new piping.
14. Perform new boiler start-up and place into operation by a manufacture specific certified start-up technician and submit manufacture start-up performance sheet results. *Note* Two copies, one left with the boiler and one presented to the PM.
15. Install either a manufacturer’s Outdoor sensor or provide one tying it into the boiler controls for outdoor reset.
16. Program boilers to base HVAC Shop’s parameters as follows:
17. Set-Point of 140 Degrees.
18. Cascade features to be wired-up if more than one boiler is installed. Building 2310 will be off outside air reset.
19. Outdoor reset schedule of minimum temperature set to outdoor temperature of 78 degrees making boiler 80 degrees and maximum temperature set to outdoor temperature of 25 Degrees making boiler 140 degrees.

Prior to final inspection, contractor shall attend final acceptance site meeting and demonstrate boiler operation.

Provide all Operation and Maintenance Manuals for all equipment installed under this project.

All work shall be in accordance with the current Mountain Home AFB Temporary Environmental Controls section 01 57 19. (See Attachment).

Contractor will be furnished with the equipment room key which will be returned upon completion of the project.

List of required submittals:

1. All O&M manuals for equipment installed.
2. Start-up performance sheet result.

Work Plan

Roles and responsibilities of project administration:

- a. During performance under contract, the contractor shall participate in administrative tasks inherent to the administration, surveillance, and oversight

Role and Resume of Contract Employees:

- b. All contract personnel must be able to read, write, speak, and understand English fluently. Contract personnel shall present a neat appearance and be easily identified as a contract employee. The contractor shall obtain base identification, and vehicle passes for all employees who make frequent visits to or perform work on Mountain Home AFB in accordance with the current installation access/entry requirements. Contractor personnel are required to wear or prominently display installation identification while visiting or performing work on the installation. The contractor shall not employ people for work on this contract, identified to the contractor by the CO as a potential threat to the health, safety, security, general well-being, or operational mission of the installation and its population. Each employee will be easily identified by wearing distinctive clothing bearing the name of the company or by wearing appropriate badges that contain the company name and employee name(s). The contractor should not employ any person who is an employee of the Government, if employing that person would create a conflict of interest. The contractor is cautioned that off-duty active military personnel hired under this contract may be subject to permanent change of station, change in duty hours, or deployment. Military Reservists and National Guard members may be subject to recall to active duty. The abrupt absence of these personnel could adversely affect the service provider's ability to perform; however, their absence at any time shall not constitute an excuse for non-performance under this contract.

Period of Performance:

Coordinate boilers replacement for late spring, summer, and/or early fall 2026, boilers must be installed and functioning by 2 October 2026. Plan for minimal impact on occupants. Note: service interruptions are NOT allowed during cold weather months when boilers are in use for facility heat. A site walk through will be conducted with interested contractors.

During the three stages of the project, (Dismantling, Installation, and Final) site visits will be made by Base Civil Engineering Quality Assurance to evaluate, but not limited to, the following:

- h. Dismantling – Disconnect and remove existing boiler, Dispose/recycle/salvage boiler.
- i. Installation – inspection of new units, fixtures, and plumbing for neatness (straight, level, and plumb) and in accordance with statement of work requirements and manufacturers installation requirements along with local codes.
- j. Final – inspection of all installed components and their functionality to include pumps, filters, valves, exhaust, combustion air, condensate lines and neutralizers, boiler settings, and boiler controls (ECS).

Throughout the following stages, the contractor must have:

- a. All debris must be disposed of by contractors.
- b. The site is maintained in a neat and orderly fashion to prevent debris migration.
- c. Disconnect and remove the existing boiler. Contractor to dispose/recycle/salvage boiler.

PRE-Construction meeting:

Contractor shall attend a pre-planning meeting scheduled by the government (approximately one hour in length) on base prior to start of work. No work shall begin without an official notice to proceed (NTP) issued.

Pre-Commissioning Cleaning:

- i. The Base HVAC shop will ensure Boiler water chemistry is within the following ranges and adjust as needed ensuring system is within factory requirements prior to replacement:
 - 1. Dissolved Solids <2000 ppm
 - 2. pH Level 6.5 to 9.5
 - 3. Chloride <150 ppm

Attachments

1. 015719 Temporary Environmental Controls MHAFB Env Spec