

STATEMENT OF WORK (SOW)

FOR

Repair Airfield Cracks

Project Number HAAW262001

174th Attack Wing Hancock Field, Syracuse, NY
Hancock Field Air National Guard Base
6001 East Molloy Road
Syracuse, New York 13211

10 February 2026

TABLE OF CONTENTS

- 1.0 PROJECT GENERAL DESCRIPTION
- 2.0 SCOPE OF WORK
- 3.0 PERIOD OF PERFORMANCE
- 4.0 DESCRIPTION OF WORK
- 5.0 GENERAL CONDITIONS
- 6.0 MATERIALS & EQUIPMENT
- 7.0 ENVIRONMENTAL
- 8.0 APPLICABLE PUBLICATIONS & FORMS
- 9.0 DEFINITIONS & ACRONYMS
- 10.0 ATTACHMENTS

1.0 PROJECT GENERAL DESCRIPTION

- 1.1 This project, **Repair Airfield Cracks**, consists of 3000 LF of localized crack sealing throughout the airfield (Reference **Attch 10.1 Upper Ramp**, **Attch 10.2 Lower Ramp**) while also applying a surface treatment to 88,000 SY of asphalt on the lower ramp. (Reference **Attch 10.2 Lower Ramp**) Reference **Attch 10.3 Airfield Cracks** to see examples as to the size and severity of the cracks. The result of this project **Repair Airfield Cracks** is a fully functional network of airfield pavements that meet or exceed FAA and DoD standards with materials recommended by the Air Force Civil Engineer Center for the local area.
- 1.2 Hancock Field is synonymous with the 174th Attack Wing New York Air National Guard which is often shortened to 174 ATKW. All references to Hancock Field here after in this SOW are equivalent to the 174th Attack Wing.
- 1.3 The contractor shall provide all labor, materials, tools, equipment, supervision/quality control, and project management necessary to complete the Project **Repair Airfield Cracks** at the 174th ATKW Hancock Field, Syracuse, NY. This includes but is not limited to demolition/recovery/disposal of existing materials, delivery/receiving of all equipment to the airfield. Use of Government equipment should not be considered during any cost estimation.
 - 1.3.1 All work must be completed without damage to any other government property outside the SOW. The Contractor bears the responsibility of restoring or replacing any item damaged during this contract. This includes but is not limited to buildings, pavements, sidewalks, fences, gates, utilities, lawns, landscaping, government owned equipment, and all components of the aforementioned.
 - 1.3.2 All work performed under this SOW shall be conducted in accordance with all applicable state and federal laws and regulations, Department of Defense policies, Unified Facilities Criteria (UFC), and New York State Code. DoD Building Code is described in UFC 1-200-01. In the case of discrepancies among regulations, the most stringent regulation applies. Any requests to deviate from the most stringent regulation shall be submitted in writing to the 174th Base Civil Engineer for approval.
- 1.4 The Government will not exercise any supervision or control over the contract service providers performing the services herein. The Prime Contractor shall be responsible for the projects management, quality control, on-site supervision, and safety of all subcontractors. Such contract service providers and subcontractors will be accountable solely to the Prime Contractor who, in turn, is responsible to the Government. The prime Contractor is defined as the contractor signing the contract or agreement with 174 Base Contracting Officer (KO). The Contracting Officer Representative (COR) or Project Manager (PM) shall be the primary Point of Contact (POC) with the Contractor.
- 1.6 Labor, equipment, material/parts, and overhead/administration shall be separate cost categories.

- 1.7 Material and parts shall be further itemized with long lead times greater than 30 days identified in the Preliminary Schedule.
- 1.8 The Contractor shall provide all personnel, equipment, tools, materials, supervision, and quality control necessary to perform the maintenance, rehabilitation, and restriping of the airfield pavements specified in the Solicitation, Contract, and Statement of Work.
- 1.9 All on site work will be performed at the following location:
174th Attack Wing
Hancock Field Air National Guard Base
6001 East Molloy Road
Syracuse, New York 13211
Airfield (Upper and Lower Ramp)
Reference ATTACH 9.1 Base location Map

2.0 SCOPE OF WORK

Contract work associated with **HAAW262001 Repair Airfield Cracks** shall achieve a fully functional network of airfield pavements that meet or exceed FAA and DoD standards. **All work shall be performed by technicians with a minimum of 5 years' experience working on airfield asphalt pavements and certified as required in UFGS 32-12-15.13 Asphalt Paving for Airfields.** Registration for the Airfield Asphalt Pavement Certification Program can be found at www.airfieldasphaltcert.com.

- 2.1 Perform 3000 LF of localized crack sealing on the airfield asphalt pavement. Cracks range in size from 1/4" to 2" in width and 1/4" to 2" in depth. There is approximately 300 LF of localized crack sealing that is required on the upper ramp. Most of the crack sealing will take place on the lower ramp
- 2.2 Apply a spray-applied emulsified asphalt surface treatment (GSB-88 or similar) to 88000 SY of airfield asphalt pavements on the lower ramp.
- 2.3 Additional details are further described in the DESCRIPTION OF WORK within this SOW.

3.0 PERIOD OF PERFORMANCE

The Period of Performance (POP) shall be **183 calendar days**. This includes the Closeout Phase of the contract. The On-Site work may be less than the Contract POP and shall be noted in the Contractor's Proposed Schedule.

4.0 DESCRIPTION OF WORK

4.1 The work specified by this Section 4.0 DESCRIPTION OF WORK consists of the Contractor furnishing all labor, equipment, tools, appliances, transportation, and materials to complete the repair and maintenance of airfield pavements. All work must be completed without damage to any other government property outside of this work scope. The contractor

shall provide all required daily on-site project management, supervision, and quality control. All necessary measures will be taken by the contractor to ensure that the quality of a product or service shall meet contract requirements. This includes but is not limited to review of AF3000 Materials Submittals to ensure that materials, installation, and testing procedures meet or exceed Federal, State, Municipal and manufacturer's requirements.

4.2 All work performed under this SOW shall be conducted in accordance with all applicable state and federal laws and regulations, Department of Defense (DoD) policies and regulations, Whole Building Design Guide (WBDG), and Federal Aviation Administration (FAA) policies and regulations. This includes but is not limited to the DoD regulation series UFC 03 00 00, FAA AC 150 series regarding airport pavement surfaces, ASTM D2995 Standard Practice for Estimating Application Rate and Residual Application Rate of Bituminous Distributors, ASTM D6690 Standard Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements, ASTM D977, Standard Specification for Emulsified Asphalt, MS-4, The Asphalt Handbook, MS-16, Asphalt in Pavement Preservation and Maintenance. Any discrepancies among regulations, the most stringent regulation applies. Any requests to deviate from the most stringent regulation shall be submitted in writing to the 174th Base Civil Engineer for approval.

4.3 Seal 3000 LF of cracks in asphalt pavement greater than 1/4' wide:

4.3.1 Apply the materials only when the ambient air temperature and the pavement temperature within the joint wall are at least 50 degrees F and rising. Do not apply sealant if moisture is observed in the crack. Use crack sealant conforming to ASTM D6690, *Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements*. When selecting a sealant, consider climatic regional temperature performance. Sealant shall be submitted in writing with an AF3000 coversheet to the COR for approval.

4.3.2 L/T cracks and other meandering cracks are located throughout the airfield on both the upper and lower ramps. Some cracks have vegetation growing in them that needs to be removed. If necessary, use a router to widen meandering cracks or a saw with a small-diameter blade to widen straight cracks. Seal cracks only after they have been cleaned and inspected. If the depth of the crack is greater than 0.75 inch, insert a backer rod material. If the depth of the crack is not deep enough to accommodate the backer rod and maintain a sealant depth of 0.5 to 0.75 inch, then the crack can be routed, or the backer rod material omitted. Apply the sealant uniformly from the bottom to the top to avoid trapping air or causing voids. Sealant should remain below the existing pavement surface.

4.4 Airfield asphalt surface treatment (88000 SY):

4.4.1 Apply a spray-applied emulsified asphalt surface treatment (GSB-88 or similar) to airfield asphalt pavements on the lower ramp. Surface treatment shall be submitted in writing with an AF3000 coversheet to the COR for approval. Thoroughly clean the surface prior to application. Spray a small test section with different application rates

to determine the best rate to apply. Adjust the rate so the treated surface has good friction, is not unstable, and does not contain excess material remaining on the surface after 12 to 24 hours of curing. Apply the material with the calibrated asphalt distributor. Allow surface treatment to cure for 12 to 24 hours.

4.5 Additional Performance Requirements:

4.5.1 Testing: Contractor will submit test results, commissioning reports and as-built drawings in both paper and electronic format in Adobe® Portable Document Format. The test reports shall match the manufacturer's inspection standard and format. In cases where the manufacturer's report format is not available, the industry standard format, local or Federal inspection forms shall apply. The contractor will accompany the Base Civil Engineer or their designated representatives and the COR on an inspection of the work. The system will be visually inspected for workmanship, damage, construction flaws, and defects and to ensure all components are properly marked, visible/accessible for future maintenance and labeled addresses where applicable. The installer will correct all deficiencies noted during the inspection in accordance with the terms of the contract. The contractor will furnish the manufacturer, model number, and date of calibration for all test equipment used on the job site to perform testing. Contractor will submit all test results identified in unit facilities guide specifications to the COR and Contracting Officer timely and with acceptable test results. Submit test results, photographs, and screen shots with direct references on as-built drawings in both paper and electronic format. Submit two papers and one electronic copy, either in Adobe® Portable Document Format or Microsoft® Word format, of test results to the contracting officer.

4.5.2 Progress Schedules: Required for all construction projects with a performance period of 30 days or longer. Project Schedules must be approved by the government and mandatory for projects at the 174 ATKW.

4.5.2.1 Contractor's proposed schedule (AF Form 3064 or detailed progress chart), prepared by the Contractor and submitted through the Base Civil Engineer/Facilities Management (BCE/FMO) to the Contracting Officer, must be accomplished within ten (15) days after award. The Progress Schedule shall indicate the order in which the Contractor proposes to perform the work, the date which work will begin, and the date of anticipated completion. The schedule must continue through the entire contract period, even if earlier completion is anticipated.

4.5.2.2 The schedule shall begin in the form of a Progress Chart of suitable scale to indicate appropriately the percentage of work scheduled for completion at any time.

4.5.2.3 In the event of differing site conditions, change in specifications, additional work, etc., which would require a time extension more than 60 calendar days, a revised schedule is to be prepared. The revised schedule will reflect work completed up to the date of revision, the percentages adjusted accordingly, and performance time extended to the new completion date established by a Modification (MOD) to the contract as a result of the change.

4.5.3 Maintenance Plan: Contractor will submit a maintenance plan as specified.

Manufacturer's O&M manuals may be used pending approval from the COR. Contractor will warranty system for at least One Year from the Final Government Acceptance Inspection. This includes replacement parts and repairs as specified in clause(s) 52.246-19 and by Contracting Officer. The contractor will perform daily area cleanup at all upgrade/installation locations until completion of work at each site. The contractor will remove all excess debris (boxes, wrapping, cables, etc.) and return location to previous condition once all upgrade/install actions are complete. The contractor will repair and/or replace all facilities and/or equipment damaged by the Contractor, or their subcontractors and warranty said facilities and/or equipment for the specified warranty period of new equipment of like kind, no less than one year. All affected areas will be restored to their original condition.

4.5.4 Documentation: Contractor will provide accurate, complete documentation for this contract 99% of time. In the event of errors, the contractor will provide corrections timely. Exceptions or exclusions to the following document require approval from the Contracting Officer. Additional documentation submittals provided through a Submittal Schedule (AF Form 66) attached in the Solicitation.

5.0 GENERAL CONDITIONS

- 5.1 General Requirements: The primary responsibility for overall management and control of work and documentation lies with the contractor. The contractor is required to develop an organized project management process and controls. The Air National Guard does not follow a specific project documentation format for sustainment, minor renovation, and restoration projects. The 174 AW does accept the use of USACE Engineering Regulation 1110-1-8155 Engineering Design Specifications and Construction Specifications Institute (CSI) Division 1 General Requirements. Contractors shall use Air Force form AF3000 Submittal Form for all materials and documentation requiring Government approval. Contractors shall use Air Force form AF1477 Construction Inspection Report for documenting daily progress.
- 5.2 A Notice to Proceed (NTP) for work described in this SOW from the Contracting Officer will be issued once all applicable CSI Division 1 documents have been sent from the Contractor and a Pre-Construction Meeting or "Kickoff" meeting lead by the Contracting Officer has been accomplished.
- 5.3 Quality Control (QC): The contractor shall develop and maintain an effective QC Plan (QCP) to ensure services are performed in accordance with this SOW. The contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The contractor's QCP assures that all contract and subcontracted work complies with the requirements of the contract.

5.4 Bring any unforeseen project conditions to the attention of the KO immediately. Differing site conditions, which may alter the scope of work, shall be approved by the KO prior to such work being performed.

5.5 Recognized Holidays: The following are recognized United States (US) holidays. The contractor ***shall not*** perform services on these days:

- 5.5.1 New Year's Day: January 1st
- 5.5.2 Martin Luther King, Jr.'s Birthday
- 5.5.3 President's Day
- 5.5.4 Memorial Day
- 5.5.5 Juneteenth: June 19th
- 5.5.6 Independence Day: July 4th
- 5.5.7 Labor Day
- 5.5.8 Columbus Day
- 5.5.9 Veteran's Day: November 11th
- 5.5.10 Thanksgiving Day
- 5.5.11 Christmas Day: December 25th

5.6 Working Hours/Duty Day: The contractor shall provide services between the hours of 7:00 a.m. – 4:15 p.m. on Monday through Friday, except on recognized US holidays or when the Government facility/installation is closed due to local or national emergencies, administrative closings, or similar Government-directed facility/installation closings. **The duty day hours may be adjusted if previously identified and approved by the Base Civil Engineer or designee.** Performance will be in the Controlled Area at 174th ATKW New York Air National Guard Base, Syracuse, NY. The contractor shall at all times maintain an adequate work force for the uninterrupted performance of all tasks defined within this SOW when the Government facility/installation is not closed for the above reasons. When hiring personnel, the contractor shall keep in mind that the stability and continuity of the work force are essential.

5.7 Unscheduled gate closures by the Security Forces may occur at any time causing all personnel entering or exiting a closed installation to experience a delay. This cannot be predicted or prevented. Contractors are not compensated for unexpected closures or delays. Vehicles operated by contractor personnel are subject to search pursuant to applicable regulations. Any moving violation of any applicable motor vehicle regulation may result in the termination of the contractor employee's installation driving privileges.

5.8 The contractor's employees shall become familiar with and obey the regulations of the installation, including fire, traffic, safety, security environmental regulations while on the installation. Contractor employees should only enter restricted areas when required to do so and only upon prior approval. All contractor employees shall carry proper identification with them at all times and shall be subject to such checks as may be deemed necessary. The contractor shall ensure compliance with all regulations and orders of the installation which

may affect performance. The Government reserves the right to direct the removal of an employee for misconduct, security reasons, or any overt evidence of communicable disease. Removal of contractor employees for reasons stated above does not relieve the Contractor from responsibility for total performance of this contract.

- 5.9 Security Requirements. The contractor shall comply with all applicable installation/facility access and local security policies and procedures, which may be obtained from the COR. All contractor (and sub-contractor) personnel shall always have a minimum of one government-issued photo identification with them.
- 5.10 The contractor and all associated subcontractor employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. The contractor shall ensure compliance with all personal identity verification requirements as directed by Department of Defense (DoD), Headquarters Department of Army (HQDA) and/or local policy. Should the Force Protection Condition (FPCON) change, the Government may require changes in contractor security matters or processes.
- 5.11 For contractors that do not require a CAC, but require access to a DoD facility or installation: Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05/AR 190-13), and applicable installation, facility and area commander installation/facility access, and local security policies and procedures (provided by a government representative).
- 5.12 Communications Security/Information Technology (COMSEC/IT) Security. All communications with DoD organizations are subject to COMSEC review. All telephone communications networks are continually subject to intercept by unfriendly intelligence organizations. DoD has authorized the military departments to conduct COMSEC monitoring and recording of telephone calls originating from, or terminating at, DoD organizations. Therefore, the contractor is advised that any time contractor personnel place or receive a call they are subject to COMSEC procedures. The contractor shall ensure wide and frequent dissemination of the above information to all employees dealing with DoD information. The contractor shall abide by all Government regulations concerning the authorized use of the Government's computer network, including the restriction against using the network to recruit Government personnel or advertise job openings.
- 5.13 AT Level 1 Awareness Training (AT): When deemed applicable by the Contracting Officer, contractor employees, to include subcontractor employees, requiring access to Government Installations, Facilities and Controlled Access areas shall complete AT Level I awareness training within 10 calendar days after contract start date or effective date of incorporation of this requirement into the contract, whichever is applicable. Certificates of completion for each affected contractor employee and subcontractor employee will be maintained by the COR or Antiterrorism Representative. AT level I Awareness Training is

available through the Joint Knowledge Online website:<https://jko.jten.mil/courses/AT-level1/launch.html>

5.14 iWATCH Training: When designated by the Contracting Officer, the contractor and all associated subcontractors with an area of performance within an Army-controlled installation, facilities or area shall brief all employees on the local iWATCH program. This local developed training shall be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR or the KO. This training shall be completed within 30 calendar days of contract award and within 30 calendar days of new employees commencing performance. The contractor shall report completion for each contractor employee and subcontractor employee to the COR within 15 calendar days after completion of training. This contract is not anticipated to occur on any Army –controlled installations. Air Force Eagle Eye program may be used only at New York Air National Guard bases.

5.15 OPSEC Training: When designated by the Contracting Officer, Operations Security (OPSEC) PMs/SMO/SMNCOs/Coordinators will provide OPSEC training or training materials to contract employees in accordance with AFI 10-701, Training will occur within 90 days of employees' initial assignment to the contract and annually thereafter. General organizational orientations may need to be supplemented by duty-related orientations in the work center targeted toward specific critical information and vulnerabilities associated with the work. Initial training (OPSE 1301 - OPSEC Fundamentals) and refresher training (Protecting Sensitive Information) are both available on the ADLS website.

5.16 Safety Requirements:

5.16.1 The contractor is directly responsible for complying with Federal and State OSHA standards for its employees including subcontractors.

5.16.2 Health and Safety Plan. When applicable, the Contractor shall submit a written, site-specific Health/Safety Plan and Accident Prevention Plan to the local Contracting Office. The Prime Contractor Superintendent, Project Manager, Foreman shall ensure all employees and subcontractors understand the Health and Safety plans submitted for this project. The contractor shall be familiar with the Health Protection Conditions (HPCON). The HPCONs may increase or decrease rapidly depending upon the local health threat. The 174 ATKW leadership determines the specific policies that will be followed. The Center for Disease Control (CDC) guidance and posture is generally followed at the 174 ATKW. The 174 ATKW Commander may adopt additional protective measures as local Health threats and CDC guidance change or are updated. Contractors will be notified immediately of any changes in local guidance on base.

5.17 FOD Mitigation Plan. When applicable, Contractors shall submit a FOD Mitigation plan before any on site work begins. The 174 ATKW Airfield Manager is the approving official. There is not a local format requirement. The FOD Mitigation Plan format used by the FAA is acceptable.

5.18 All work shall follow be performed in accordance with OSHA & DoD Regulations. If there is a conflict in regulations, the most stringent applies. Contractors are required to have a representative on staff with a current OSHA 30-Hour Construction Training Certificate. Contractors working on site shall have a current OSHA 10-Hour Construction Training Certificate.

5.19 Welding/Hot Work Permits. All Hot Work shall be permitted through the Installation Fire Department and Ground Safety. Permits are issued following the routing and approval of AF Form 592 *Hot Work Permit*. Wet Signatures are required unless all persons requiring signature have the ability to digitally sign the AF Form 592. Digital Signatures cannot be mixed with Wet Signatures. The AF Form 592 routing list is as follows:

Office	Phone Number	Email Address
Safety Office	(315) 233-2143	David.Roe@us.af.mil
Bio-environmental Engineering Office	(315) 233-2477	Stephen.bitler@us.af.mil
Fire Emergency Services	(315) 233-2663 (315) 233-2534	Lecleaise.smith@us.af.mil or Jeffery.chrissley.1@us.af.mil

5.20 Physical Security. The contractor shall safeguard all Government property provided for contractor use. At the close of each work period, Government facilities, equipment and materials shall be secured.

5.21 Key Control. All references to keys include key cards. The contractor shall establish and implement methods of ensuring that no keys/key cards issued by the Government are lost or misplaced or are used by unauthorized persons. No keys issued by the Government shall be duplicated. Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas. The contractor shall immediately report any occurrences of lost or duplicated keys/key cards to the COR.

5.22 In the event keys, other than master keys, are lost or duplicated, the contractor shall, upon direction by the KO, re-key or replace the affected lock or locks; however, the Government, at its option, may replace the affected lock or locks or perform re-keying. When the Government replaces or re-keys the locks, the Government will deduct the total cost of lock replacement or re-keying from the monthly payment due the contractor. In the event a master key is lost or duplicated, the Government will replace all locks and keys for that system and will deduct the total cost from the monthly payment due the contractor.

5.23 The contractor shall prohibit the use of the Government issued keys/key cards by any persons other than the contractor's employees. The contractor shall prohibit the opening of locked areas by contractor employees to permit entrance of persons other than contractor employees engaged in the performance of services in those areas, or personnel authorized entrance by the KO.

5.24 Lock Combinations: The contractor shall establish and implement methods of ensuring that no lock combinations are revealed to unauthorized persons. The contractor shall ensure

that lock combinations are changed when personnel having access to the combinations no longer have a need to know such combinations.

- 5.25 Post Award Conference/Periodic Progress Meetings: The contractor agrees to attend any post award conference convened by the KO in accordance with FAR Subpart 42.5. The KO, COR, and other Government personnel, as appropriate, may meet periodically with the contractor to review the contractor's performance. At these meetings, the KO will apprise the contractor of how the Government views the contractor's performance and the contractor shall apprise the Government of problems, if any, being experienced. The contractor shall resolve outstanding issues raised by the Government. Contractor attendance at these meetings shall be at no additional cost to the Government. The Contractor shall email a meeting agenda to the Government in advance of the Periodic Progress Meeting. The Contractor shall email the Meeting Minutes with bullet points of all topics discussed during the meeting no longer than seven calendar days following the end of the Progress Meeting.
- 5.26 Contract Manager (CM): The contractor shall designate a CM who shall ensure performance under this contract. The name of this person, and an alternate who shall act for the contractor when the CM is absent, shall be designated in writing to the KO. The CM or alternate shall have full authority to act for the contractor on all contract matters relating to daily operation of this contract. The CM shall work through the COR, to resolve issues, receive technical instructions, and ensure adequate performance of services. The CM shall ensure that contractor employees do not perform any services outside the scope of the contract without an official modification issued by the KO. The CM shall ensure contractor employees understand that services performed outside the scope of the contract are performed wholly at the expense of the contractor.
- 5.27 Identification of Contractor Employees: All contractor personnel attending meetings, answering Government telephones, and working in other situations where their contractor status is not obvious to third parties are required to identify themselves as such to avoid creating an impression that they are Government employees. The contractor shall ensure that all documents or reports produced by contractor personnel are suitably marked as contractor products or that contractor participation is appropriately disclosed. The contractor's status as a "contractor" shall be predominantly displayed in all correspondence types (to include signature blocks on e-mail) and dealings with Government or non-Government entities. Contractor personnel shall wear identification badges distinguishing themselves as such. The badges shall have the company name, employee name and the word "contractor" displayed. The contractor shall retrieve all identification media (including vehicle passes) from its employees who depart employment for any reason. The contractor shall return all identification media (i.e., badges and vehicles pass) to the KO within 14 days of an employee's departure.
- 5.28 Combating Trafficking in Persons: The United States Government has adopted a zero-tolerance policy regarding trafficking in persons. Contractors and contractor employees shall not engage in severe forms of trafficking in persons during the period of performance of the contract; procure commercial sex acts during the period of performance of the

contract; or use forced labor in the performance of the contract. The Contractor shall notify its employees of the United States Government's zero tolerance policy, the actions that will be taken against employees for violations of this policy. The contractor shall take appropriate action, up to and including termination, against employees or subcontractors that violate the US Government policy as described at FAR 22.17.

5.29 Data Rights: The Government has unlimited rights to all documents/materials produced under this contract. All documents and materials, to include the source codes of any software, produced under this contract shall be Government owned and are the property of the Government with all rights and privileges of ownership/copyright belonging exclusively to the Government. These documents and materials may not be used or sold by the contractor without written permission from the KO. All materials supplied to the Government shall be the sole property of the Government and may not be used for any other purpose. This right does not abrogate any other Government rights.

5.30 Organizational Conflicts of Interest (OCI): The contractor and subcontractor personnel performing services under this contract may receive, have access to or participate in the development of proprietary or source selection information (e.g., cost or pricing information, budget information or analyses, specifications, or work statements, etc.) or perform evaluation services which may create a current or subsequent OCIs, as defined in FAR Subpart 9.5. The contractor shall notify the KO immediately whenever it becomes aware that such access or participation may result in any actual or potential OCI and shall promptly submit a plan to the KO to avoid or mitigate any such OCI. The contractor's mitigation plan will be determined to be acceptable solely at the discretion of the KO. In the event the KO unilaterally determines that any such OCI cannot be satisfactorily avoided or mitigated, the KO may impose other remedies as he or she deems necessary, including prohibiting the contractor from participation in subsequent contracted requirements which may be affected by the OCI.

5.31 Fines. Any Federal, State, or local government fines imposed on the 174 ATKW by other government agencies due to the Contractor's action or non-compliance with this contract or Government regulations shall be transferred to the Contractor. Additional Liquidated Damages may be enforced by the Contracting Officer if the Government incurs additional administrative work as a result of the Contractor's non-compliance to Federal, State and local government standards.

6.0 MATERIALS AND EQUIPMENT

6.1 Government Furnished Property, Material, Equipment and Services (GFP/M/E/S)

6.1.1 Property: NONE

6.1.2 Materials: NONE

6.1.3 Equipment: NONE

6.1.4 Services: Access to Water

6.2 Utilities

- 6.2.1 A reasonable amount of water will be made available by the Government for during demolition.
- 6.2.2 The contractor shall instruct employees in utilities conservation practices. The contractor shall operate under conditions that preclude the waste of utilities, which include turning off the water faucets or valves after using the required amount.
- 6.2.3 Hook up will be to existing spigots and will require coordination with the COR.
- 6.2.4 Water outlets without a suitable backflow prevention device already installed must have one provided by the contractor prior to use. The backflow prevention device must be submitted to the KO for approval before installation or use. Submittal instructions apply to backflow prevention device approvals.
- 6.2.5 **Any planned utility outage requests or notifications shall be routed to the Contracting Officer not less than twenty-one (21) working days prior to the planned outage.**
- 6.3 Contractor Furnished Property, Materials, and Equipment (CFP/M/E):
- 6.3.1 Construction materials must meet relevant code specifications and the New York State building code for northern construction and weather conditions.
- 6.3.2 The contractor shall submit to the Contracting Officer (KO) for approval all items listed on attached Material Submittal Schedule within 10 calendar days of the notice to proceed (NTP). Alternatively, the contractor may, within 10 calendar days of the NTP, provide the KO with a schedule indicating when each material submittal shall be submitted for approval.
- 6.3.3 Use an AF Form 3000 for transmitting material submittals.
- 6.3.4 Ensure that any disapproved submittal will not impact the approved project execution schedule, as a disapproved submittal shall not be considered grounds for a time extension.
- 6.3.5 Allow for a minimum of 15 working days for the Government's processing of submittals.
- 6.3.6 The contractor shall not order, deliver, nor install any materials and/or equipment without KO's approval or remove any materials on site that have not been properly approved.
- 6.3.7 In addition to model and serial numbers, the contractor shall provide 1 hard copy of the operations & maintenance (O&M) manual for each installed equipment item unless otherwise specified. Final payment (up to 10% of awarded amount) will be withheld until O&M manuals are received by the COR.

6.3.8 Except for those items specifically stated to be Government-Furnished in Paragraph 6.1, the contractor shall furnish everything required to perform these services as indicated in Section 1.0

6.3.9 The **specification hierarchy** is the collection of technical specifications to be used for all projects. The hierarchy is listed in the order of precedence (i.e. “A” supersedes “B”, “B” supersedes “C”, etc.). Any conflict in specifications shall be resolved by following the more stringent requirement. The local approving authority is the 174th Base Civil Engineer. The hierarchy is as follows:

- A. Federal Specifications (i.e. UFC, DoD, ANG, or FAA)
- C. State of New York Code
- D. Any Specifications/Installation guidance by the Manufacturer
- E. MATOC or Contract Default Specifications

7.0 ENVIRONMENTAL

7.1 All spills shall be reported to the COR or the Base Environmental Office to determine the level of reporting required and risk involved. Historically, most spills by vendors are due to oil, hydraulic fluid or gasoline leaking from service vehicles. Acceptable Safety & Environmental plans include spill kits on service vehicles.

7.1.1 Spill kits are required while working on base. Required spill kits shall match the level of risk associated with the scope of work.

7.1.2 In the event of an emergency, small scale spill kits are available at various locations around base. Government provided spill kits used in an emergency shall be restocked by the vendor at the vendor’s expense.

7.2 Hazardous Materials A hazardous material (HM) is any item that is:

7.2.1 a health hazard or physical hazard as defined in 29 CFR 1910.1200(c), or

7.2.2 regulated in its disposal by the Environmental Protection Agency in 40 CFR, or

7.2.3 hazardous as defined by Department of Transportation regulation in 49 CFR, or

7.2.4 hazardous as defined by the Dangerous Goods Regulations of the International Air Transportation Association

7.3 If hazardous material is required to complete this contract, the contractor shall submit to the KO a HM storage plan and Chemical/Hazardous Material Request Authorization Form (AF Form 3952).

7.4 Any Federal, State, or local government fines imposed on the 174 ATKW due to the Contractor's non-compliance with this contract or Government regulations shall be transferred to the Contractor. This includes but is not limited to Environmental fines, Storm Water Pollution violations, EPA and NYS Department of Environmental Conservation. (DEC).

Office	Phone Number	Email Address
Environmental Management Office	(315) 233-2111 or (315) 233-2692	Jason.preston.4@us.af.mil Christopher.wunderlich.1@us.af.mil
Bio-environmental Engineering Office	(315) 233-2477	Stephen.bitler@us.af.mil

7.5 Additional Environmental Considerations

7.5.1 Contractor shall clean up after each work period and dispose of all debris at the close of each day.

7.5.2 The contractor shall not use any government disposal bins, dumpsters or trash receptacles for any reason at any time unless otherwise specified in this SOW. The contractor shall provide appropriate disposal bins and/or trash receptacles. Approval of disposal bins/trash receptacle location(s) shall be coordinated through the COR.

7.5.3 The contractor shall not allow debris to leave the work area risking damage to aircraft engines and other government property.

7.5.4 All debris or trash shall be disposed of off base. All demolition debris shall be disposed of at a permitted landfill, with landfill authorization, unless other arrangements have been coordinated through the Environmental Management Office (EMO). Contractor shall coordinate with the base EMO prior to disposing any materials off base.

7.5.5 Provide documentation of all disposal and recycling of solid waste, such as landfill receipts; waste manifests, or weight tickets from the landfill that accepts the debris.

8.0 APPLICABLE PUBLICATIONS AND FORMS

Publication (Chapter/Page)	Date of Publication	Mandatory or Advisory	Website
UFC 1-200-01 DoD Building Code	06/12/2023	Mandatory	ufc_1_200_01_2022_c2.pdf (menlosecurity.com)
UFC 3-270-01 O&M Manual: Asphalt and Concrete pavement Maintenance and Repair	02/021/2018 Change 1 03/17/2022	Mandatory	https://www.wbdg.org/ffc/dod/unified-facilities-criteria-ufc/ufc-3-270-01
UFGS 32-12-15.13 Asphalt Paving for Airfields	Nov 2020	Mandatory	https://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/ufgs-32-12-15-13
UFC 3-260-02 Pavement Design for Airfields	06/30/2001	Advisory	https://www.wbdg.org/dod/ufc/ufc-3-260-02
UFGS 32-12-36.13 Bituminous Fog Seal	Nov 2023	Mandatory	https://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/ufgs-32-12-36-13

Publication (Chapter/Page)	Date of Publication	Mandatory or Advisory	Website
Federal Acquisition Regulation		Mandatory	https://www.acquisition.gov/?q=browsefar or http://farsite.hill.af.mil/
Defense Federal Acquisition Regulation Supplement		Mandatory	http://www.acq.osd.mil/dpap/dars/dfarspgi/current/index.html or http://farsite.hill.af.mil/
DoDM 1000.13-M-V1 DoD Identification (ID) Cards (Enclosure 2, paragraph 3.b)	01/23/2014	Mandatory	http://www.esd.whs.mil/Directives/issuances/do dm/
DoDM 5200.2 Regulation 5200.02 Procedures for the DoD Personnel Security Program (PSP)	04/03/2017	Mandatory	http://www.dtic.mil/whs/directives/corres/pub1.htm
AR 381-12 Threat Awareness and Reporting Program (TARP) (Section II, ¶ 2-4.b)	06/01/2016	Mandatory	http://armypubs.army.mil/ProductMaps/PubForm/AR.aspx
AFI 91-202 The USAF MISHAP Prevention Program Chapter 12	03/21/2020	Mandatory	https://static.e-publishing.af.mil/production/1/af_se/publication/afi91-202/afi91-202.pdf
DoD 5400.11-R Department of Defense Privacy Program	05/14/2007	Mandatory	http://www.dtic.mil/whs/directives/corres/pub1.htm

Publication (Chapter/Page)	Date of Publication	Mandatory or Advisory	Website
Homeland Security Presidential Directive (HSPD)-12 Policy for a Common Identification Standard for Federal Employees and Contractors	08/27/2004	Mandatory	https://www.dhs.gov/homeland-security-presidential-directive-12
DoDD 5400.11 Department of Defense Privacy Program	10/29/2014	Mandatory	http://www.dtic.mil/whs/directives/corres/dir.ht ml#
AR 190-13 The Army Physical Security Program	02/25/2011	Mandatory	http://www.apd.army.mil/ProductMaps/PubFor m/AR.aspx

Form	Date	Website
DD 441 Department of Defense Security Agreement	Jan 2017	http://www.dtic.mil/whs/directives/forms/dd/ddforms000 1-0499.htm
DD 250 Material Inspection and Receiving Report	Aug 2000	http://dtic.mil/whs/directives/forms/dd/ddforms0001- 0499.htm
AF3000 Material Approval Submittal	Sep 2003	https://static.e- publishing.af.mil/production/1/saf_aq/form/af3000/af300 0.pdf

Form	Date	Website
AF Form 3064 Contract Progress Schedule	Jun 1990	PDF available from COR
AF IMT 3065 Construction Progress Report	Apr 1996	PDF available from COR
AF Form 3952 Chemical/Hazardous Material Request Authorization	Mar 2005	https://static.e- publishing.af.mil/production/1/af_a4/form/af3952/af3952.pdf
AF IMT 1477 Construction Inspection Report	Jul 1980	https://static.e- publishing.af.mil/production/1/af_a4/form/af1477/af1477 .pdf
AF Form 66 Submittal List		PDF available from COR

9.0 Definitions and Acronyms

9.1 Definitions:

- 9.1.1 Contractor: A supplier or vendor awarded a contract to provide specific supplies or service to the government. The term used in this contract refers to the prime.
- 9.1.2 Contracting Officer (KO): A person with authority to enter into, administer, and or terminate contracts, and make related determinations and findings on behalf of the government. Note: The only individual who can legally bind the government.
- 9.1.3 Contracting Officer Representative (COR): An employee of the U.S. Government designated by the KO to monitor contractor performance. Such appointment will be in writing and will state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.
- 9.1.4 Defective Service: A service output that does not meet the standard of performance associated with the SOW.
- 9.1.5 Deliverable: Anything that can be physically delivered and includes non-manufactured things such as meeting minutes, reports, testing & commission, drawing & schematics.
- 9.1.6 Key Personnel: Contractor personnel that are evaluated in a source selection process and that may be required to be used in the performance of a contract by the SOW. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the persons that are listed in the proposal.
- 9.1.7 Physical Security: Actions that prevent the loss or damage of Government property.
- 9.1.8 Quality Assurance: The government procedures to verify that services being performed by the Contractor are performed according to acceptable standards.
- 9.1.9 Quality Assurance Surveillance Plan (QASP): An organized written document specifying the surveillance methodology to be used for surveillance of contractor performance. The QASP requirement can be found in FAR Chapter 46. The role of a Trusted Agent (TA) and COR, assumes Quality Assurance duties. The COR monitors contractor performance to ensure compliance with the contract requirements.
- 9.1.10 Quality Control: All necessary measures taken by the Contractor to ensure that the quality of a product or service shall meet contract requirements.

9.1.11 Subcontractor: One that enters a contract with a prime contractor. The Government does not have privity of contract with the subcontractor.

9.2 Acronyms:

AEI	Army Enterprise Infrastructure
AF	Air Force
ANG	Air National Guard
AR	Army Regulation
AT/OPSEC	Antiterrorism/Operational Security
AV	Audio-Visual
BI	Background Investigation
CFR	Code of Federal Regulations
CM	Contract Manager
CMRA	Contractor Manpower Reporting Application
COR	Contracting Officer Representative
DA	Department of the Army
DD254	Department of Defense Contract Security Classification Specification
DFARS	Defense Federal Acquisition Regulation Supplement
DoD	Department of Defense
FAR	Federal Acquisition Regulation
GFP/M/E/S	Government Furnished Property/Material/Equipment/Services
HSPD	Homeland Security Presidential Directive
IA	Information Assurance
IS	Information System(s)
KO	Contracting Officer
MOD	Modification
NGB	National Guard Bureau
OCI	Organizational Conflict of Interest
PII	Personally Identifiable Information
PIPO	Phase In/Phase Out
POC	Point of Contact
POP	Period of Performance
PRS	Performance Requirements Summary
PWS	Performance Work Statement
QA	Quality Assurance
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Program
SOW	Statement of Work
SSN	Social Security Number
TA	Trusted Agent
TE	Technical Exhibit
UFC	United Facility Criteria
UFGS	United Facility Specification Guide
WBDG	Whole Building Design Guide

10.0 ATTACHMENTS

Attch 10.1: Upper Ramp

Attch 10.2: Lower Ramp

Attch 10.3: Airfield Cracks