

Statement of Work (SOW)
FOMA Paint Maintenance Buildings and Bally Building
National Park Service

1. Project Description: The National Park Service has a need to paint clean, prep, seal all joints, and paint all exterior features on the maintenance and Bally (Natural Resource Office) buildings of the Fort Matanzas (FOMA) National Monument Visitor's Center at 8635 A1A S, St. Augustine, FL 32080. The exterior paint color for the Bally Building is Navajo White for all siding, window trim, doors, door trim, etc. The exterior paint color for the maintenance buildings is Platinum Gray for all siding, White for the fascia, soffit, window/door trim, Oxford Blue for the overhead doors. ***Include these details in Volume II, Tab 4 of your proposal***

2. Building Data and Conditions: The contractor should visit the sites to examine the buildings to determine the field conditions under which the contractor is obligated to work. All work shall be coordinated with the Contracting Officer Representative (COR).

3. Standards: The contractor shall comply with all applicable standards to include, but not limited to the following:

- a) Occupational Safety and Health Act (OSHA) 29 CFR 1910, 29 CFR 1904 [Regulations \(Standards - 29 CFR\) | Occupational Safety and Health Administration \(osha.gov\)](#)
- b) NPS 2006 Management Policies, chapter 9 [MP Ch 9: Park Facilities - Policy \(U.S. National Park Service\) \(nps.gov\)](#)
- c) Florida Building Code [Florida Building Code Online](#)

4. Requirements: Contractor shall provide all labor, supervision, material, tools, equipment, supplies, transportation and incidentals necessary to clean, prep, and paint the exterior of the buildings. The paint will be Benjamin Moore Regal Select Exterior Paint (Soft Gloss) or equivalent that is approved by the COR. Prep & paint the entire exterior which includes but is not limited to: walls, fascia, soffit, doors, roll-up doors, window, and overhead door openers. All doors and roll-up doors will be painted on the exterior side of the doors which includes the portion of the exterior door that may be concealed by the door jamb, casing, weather stripping, etc. when installed. The prep work will include the pressure washing of the buildings, sealing all joints with a similar color matching polyurethane sealant, priming the surface(s). There will be a minimum of two coats of the finish paint applied to all surfaces. Paint splatter or overpainting is prohibited, and temporary removal and reinstallation of items that are attached to the exterior, such as signage, to provide a complete paint job is required. Masking of non-movable items, such as hardware is required. The work breakdown is not all inclusive and other work may be required to achieve an acceptable level of workmanship for the painting of the buildings. If additional work or repairs are required and not included in this statement of work, you must address it during the open question period. All products shall:

a) Tasks:

- 1) Clean and prep all the exterior of each building removing loose paint, applying polyurethane sealant to joints and gaps, doors, windows, and areas of entry (A/C lines, electrical lines, water lines, etc.).
- 2) Paint the exterior with a minimum of two coats of the finish paint. Paint splatter or overpainting is prohibited, and temporary removal and reinstallation of items that are

attached to the exterior, such as signage, to provide a complete paint job is required. Masking of non-movable items is required.

- 3) Remove all debris from the National Park property.
- 4) Return construction areas back to their original condition.

b) Stipulations.

- 1) Staging: The contractor will coordinate the staging area with the COR prior to the delivery of any material or equipment.
- 2) Safety: The contractor shall protect from damage all existing improvements and utilities at or near the work site, the locations of which are made known to or should be known by the contractor.
 - a) The contractor must comply with all Federal and State OSHA requirements. The contractor shall be responsible for the safety of their employees and equipment, and for any injury or damage done to or by them from any source or cause. The contractor shall save and hold the United States free from all claims for damages to all persons and (or) property arising from the execution of the work covered by these specifications.
 - b) Incorporate traffic control, when necessary. Traffic control shall meet or exceed the specifications laid out in the Standard Specifications for Construction of Roads and Bridges on Federal Highway Projects, FP-96, sections 156 Public Traffic and 635 Temporary Traffic Control or most recent version of FL Standard Specifications for Road and Bridge Construction.
 - c) Accident Prevention - The contractor shall conduct operations to prevent accidents, injuries, and damages. Additionally, the contractor shall comply with applicable state and local safety, health, and sanitation laws.
 - d) Accident Reporting - The contractor shall immediately notify the COR of all accidents to which the contractor's employees are a party or witness; and, of all accidents involving his/her employees or equipment working under this contract.

5) Submittals: The contractor will submit to the Contracting Officer and Contracting Officer Representative the following submittals for approval prior to purchasing materials/items:

- 1) Cleaning product(s)
- 2) Polyurethane sealant
- 3) All paint type and color for each area of the buildings

5. Public Use Areas: The site is open to park employees and extreme care shall be used when entering, leaving, and operating on park grounds. Work area shall be roped or barricaded by the contractor to prevent public ingress and egress to work areas. The contractors' equipment shall be removed from the site daily. If other storage needs are required, arrangements can be made with the COR.

6. Site Features: These structures are located adjacent to, or near streetlamps, wood fences, boardwalks, historic and non-historic buildings, and other site features. The contractor shall use extreme care to protect site features from damage. Any damage resulting from the contractor's operation shall be

repaired and/or replaced with like-in-kind material at the approval of the COR, at no additional cost to the Government.

7. Hours of Work: Work shall be conducted between the hours of 7:00 a.m. and 4:30 p.m., Monday through Friday. Work shall be completed within **60** days after Contracting Officer distributes the fully executed contract. No work shall be performed after 4:30 p.m. or before 7:30 a.m., nor on Saturdays, Sundays, or federal holidays, unless requested and approved in advance by the COR.

8. Site Examination: Prior to quotation submission, the contractor should carefully examine the site and should familiarize himself/herself with the conditions under which the work shall be accomplished. A walk through can be arranged with the COR.

9. Security: The contractor shall be solely responsible for the security of the job site, and for all project work and materials until receipt of written notification of final acceptance of the contracted work by the COR.

10. Photos: See Attachment 1

11. Field Verification: Measurements and quantities are approximations and offerors must field verify all proposed dimensions and materials necessary before submitting a proposal.

12. Standards: While performing work, the contractor shall comply with the latest applicable versions of the following:

- a) Florida Building Code
- b) National Electric Code
- c) National Plumbing Code
- f) OSHA

-Applicable building codes shall be followed, and all products shall have Florida Building Code Product Approvals.

