

Performance Work Statement (PWS)

COMPACFLT Berthing and Messing Program Operational Support

1 SCOPE

1.1 BACKGROUND

Commander, U.S. Pacific Fleet (COMPACFLT) Berthing and Messing Program requires operational level (O-Level) maintenance, service call work, system/equipment familiarization and port husbandry services to Service Craft (Non-Self Propelled) covered under this contract. The Berthing and Messing Barge Program maintains and operates Duty Crew Berthing Barges that are used by the Fleet when ships become uninhabitable during CNO scheduled overhaul and repair periods. The barges perform a vital function in that they provide office, berthing and messing facilities in close proximity to the ships. Many of the barges are over 60 years old and require regular preventive maintenance to support present day fleet requirements.

1.2 MISSION

The COMPACFLT Berthing and Messing Program mission is to maintain the Quality of Life (QOL) Standards for the berthing and messing of crews on ships or submarines undergoing Chief of Naval Operations (CNO) scheduled maintenance.

1.3 PURPOSE AND OBJECTIVE

The contractor shall provide unclassified operational support for assigned program Duty Crew Berthing Barges to include a full range of organizational level maintenance, repairs, service call work, system/equipment familiarization, and port husbandry requirements. The contractor support team shall align itself to support the government requirements holder with the most cost-effective mix and number of contractor support personnel, utilizing an adaptable, flexible structure that is best suited to accomplishing both planned and emergent work in support of the Berthing and Messing Program. The contractor support should be led by management using continual process improvement to assist the government requirements holder and Contracting Officer Representative (COR) with timely notification and feedback affecting contract execution as it relates to performance, schedule, cost, and regulatory compliance.

1.3.1 Barge Organizational Level (O-Level) Maintenance shall be conducted by the contractor. Organizational maintenance is the day-to-day work performed on installed equipment in support of Barge operations. The purpose of O-level maintenance is to maintain all installed equipment in a full-mission capable status while improving the maintenance process. Maintenance at this level includes inspections, servicing, handling, periodic preventive maintenance, and corrective maintenance of equipment with associated checks and tests as provided by the installed 3M maintenance system. O-level maintenance also includes repairs and minor adjustments that do not require shop facilities as well as the removal and installation of components. All O-Level repairs beyond the scope of work shall be annotated in the individual barge Current Ship Maintenance Project (CSMP) to provide a baseline for future barge Depot level repairs. The requirements of this contract cover Organizational Level only. The contractor shall immediately notify the government via email of critical work identified that would consider the Barge inhabitable for tenant commands (i.e. Duty Crews).

***No Barge Depot Level (D-Level) maintenance shall be scheduled or conducted. Barge D-Level repairs and maintenance are performed normally in the private sector facilities or pier-side onboard Naval Stations ships. (D-Level maintenance requires major overhaul or a complete rebuilding of parts, assemblies, subassemblies, and end items, including the manufacturing of parts, modifications, testing, and reclamation).**

1.3.2 The contractor shall provide labor, tools and materials necessary to accomplish inspection, testing, diagnostics for preventative and corrective maintenance, servicing, and equipment installation support for all installed systems and equipment systems onboard Duty Crew Berthing and Messing Barges. The contractor shall be responsible to provide the required scaffolding in order to support the maintenance requirement. The contractor shall ensure scaffolding is tested and certified prior to conducting maintenance.

When the complete replacement of a piece of installed equipment is required (e.g. the replacement of a complete air conditioning unit, or a complete ice maker unit, etc.), the provisioning of that item is not permissible under this contract. The replacement item will be procured by the government and be provided to the contractor as Government Furnished Property (GFP), section 1.10. The contractor will be responsible for the installation of that replacement piece of equipment and the preventive maintenance and servicing of it thereafter. Installation may require removal of the old equipment and re-configuration of the installation location to accept equipment of a different design. Alteration and design drawings, if required, will be provided by the designated planning yard, Puget Sound Naval Shipyard (PSNS) & Intermediate Maintenance Facility (IMF).

1.4 LOCATION/HOURS OF WORK

1.4.1 Accomplishment of the results contained in this PWS requires work in the Pacific Northwest (Bremerton, Tacoma, Bangor, Seattle and Everett) Washington, (Portland) Oregon; the Pacific Mid-West (San Francisco) California, the Pacific Southwest (San Diego) California; the Middle Pacific (Pearl Harbor) Hawaii; the Western Pacific (Yokosuka and Sasebo) Japan; and (Apra Harbor) Guam.

1.4.2 Regular Working Hours: The regular working hours under the terms of this contract are between 0630 hours to 1500 hours, Monday through Friday except for Federal Holidays. Support contractor personnel shall work eight-hour days, 40 hours week. Alternate schedules and shifts are permitted with prior approval from the Government oversight and the COR. The contractor shall observe the established eleven (11) Federal holidays, unless overtime is required on those days.

New Year's Day
Martin Luther King Jr.'s Birthday
President's Day
Memorial Day
Juneteenth
Independence Day

Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day Christmas Day

1.4.3 Outside Regular Working Hours: Except as specified, all work will be performed during regular working hours. Overtime work, to include weekends and federal holidays, may be required. Some situations may require short notice, and the contractor may need to keep workers past normal working hours.

1.5 REPORT DELAYS

The contractor shall notify and obtain permission from the COMPACFLT Program Administrator, TA, and/or COR of any work to be performed that could potentially disrupt normal government business operations. In the event the contractor anticipates or encounters difficulty in meeting requirements and/or complying with the contract schedule dates, the contractor shall provide written notification by the next business day citing the pertinent details (E-mail is acceptable). Receipt of this notification by the government is not to be construed as a waiver of the requirements or delivery schedule, nor does it waive

the government's rights or remedies provided by this contract as it pertains to timely contract performance. If delays are justifiable and will not harm the government's ability to conduct its berthing and messing business, the COR or Contracting Officer will negotiate a new performance schedule for the specific job and notify the contractor in writing that the one-time delay is acceptable and state the new completion date for the job. If the delay is not justifiable, the contractor shall immediately take action to complete work within the original time frame; or the matter shall be referred to the Contracting Officer for remedial action. In a case where a dispute arises between the contractor and the COR or ACOR, the matter shall be immediately referred in writing to the Contracting Officer for resolution by the Contracting Officer's Representative (COR) and the COMPACFLT Program Administrator.

1.6 TRAVEL / TEMPORARY DUTY (TDY)

Temporary Duty (TDY) is not normally authorized for this contract. TDY reserved to AOR(s) with no Regional Maintenance Center (RMC) technical support (Guam) or management of 3M/PMS Program. It is anticipated that the contractor support may be required to travel to support maintenance and repair when authorized. Contractor personnel shall be able to support emergent and routine travel requests to include having passports. Travel will be authorized on a case by case basis to be approved by the Contracting Officer's Representative (COR) and/or the COMPACFLT Program Administrator. Only required labor categories under this contract are authorized TDY/Travel. Any travel request submitted must be in accordance with the PWS.

1.6.1 Contractor personnel supporting activities and performing functions outside of the United States shall register in the Synchronized Pre-deployment and Operational Tracker – Enterprise Suite (SPOT-ES) application. Support contractor personnel shall conform to the working hours (eight-hour days) 40 hour weeks. Elective alternative schedules and shifts shall not be permitted without prior written concurrence from both COMPACFLT Program Administrator and the COR. The contractor shall observe the established eleven (11) Federal holidays, unless overtime is required on those days.

1.7 SECURITY

Contractor personnel assigned to perform work under this contract will require and shall obtain/maintain Common Access Card (CAC) and/or Defense Biometric Identification System (DBIDS) access card to gain access to locations under this contract by completely filling out the Secretary of the Navy (SECNAV) form 5512/1 and submitting the form to the COR.

1.7.1 The contractor shall ensure all support contractor personnel shall be able to access Navy installations with a Common Access Card (CAC) within sixty (60) days of contract award or date of hire. Any exceptions shall require written concurrence by the applicable Program Administrator and the COR. Pier and Turnstile Access will be requested when Defense Biometric Identification System (DBIDS) are applied for.

1.7.2 The contractor shall ensure support contractor personnel have a CAC in-hand before providing direct support to the Berthing and Messing Program. A DBIDS pass shall not be used in the interim for support contractor personnel requiring a CAC for computer system access who are not yet eligible, without prior written concurrence from both Program Administrator and the COR, and then for a duration not to exceed three (3) months.

1.7.3 The contractor shall ensure all support contractor personnel are easily identifiable as contractors throughout Navy installations while providing direct support (e.g. support contractor personnel having their contractor CAC or company identification badge clearly visible at all times or having shirts with company identification clearly visible).

1.7.4 The contractor's management is responsible for notifying the COR within two (2) working days of departure when its personnel who has been issued a CAC/DBIDS leave the contractor's company. This section describes the security and safety for this effort. The contractor's company must collect the DBIDS and turn over to the COR within two working days of the personnel's departure.

1.7.5 SPECIAL REQUIREMENTS FOR INDIVIDUAL COMPACFLT LOCATIONS

1.7.5.1 Pearl Harbor and Puget Sound Special Requirements: All Pearl Harbor and Puget Sound personnel are required to have a SECRET Security Clearance. Berthing and Messing Barges are assigned to support crews of nuclear powered ships undergoing CNO scheduled availabilities at Pearl Harbor and Puget Sound Naval Shipyard/Bangor IMF. There are certain areas aboard Berthing Barges where restricted data is present or stored. Such areas include nuclear classrooms and office areas. Routine access into any such restricted areas that may be required shall only be granted to selected contractor personnel to troubleshoot, replace, and calibrate equipment. Additionally, minor screening for habitability items aboard ex-nuclear ships and submarines for possible re-use aboard COMPACFLT Berthing Barges is required. To enter nuclear training classrooms, office or any other restricted areas while Messing and Berthing Barge(s) is (are) occupied or to gain access to ex-nuclear vessels for habitability item screening; requires Access to Restricted Data/Area clearance by Pearl Harbor and Puget Sound Naval Shipyard. The contractor and cognizant Alternate Contracting Officer Representative (ACOR) government shall jointly coordinate the special access authorization requirement with Director of the applicable Shipyard's Pass and ID Office.

1.7.5.2 Special Requirements and Authorizations for Contractor Personnel in Japan: The contractor shall be responsible for obtaining any passports and visas that may be required by its personnel to support work performed under this contract. The contract price includes all costs related to passports and visas. The government will provide logistic support to all contractor employees and their dependents residing in Japan to include commissary, exchange, service, registration of vehicles, banking, purchase of oil products, communications, postal, transportation, medical and dental services, local recreational facilities (including clubs, theaters, libraries, craft shops, and sport facilities), the use of leave and rest centers and the use of Department of Defense schools. In addition, they will be provided a uniformed services identification card, DD Form 1203, to reflect those privileges. These services are provided at no cost to the contractor or COMPACFLT.

1.7.5.3 Special Requirements for Contracted Personnel in Guam: There are certain areas aboard Berthing and Messing Barges where restricted data is present or stored. Such areas include nuclear classrooms and office areas. Routine access into any such restricted areas that may be required shall only be granted to select contractor personnel to troubleshoot, replace, and calibrate equipment. To enter nuclear training classrooms, office or any other restricted areas while Berthing and Messing and Barge(s) is (are) occupied requires Access to Restricted Data/Area clearance by the Submarine Squadron Commander. The contractor and government will jointly coordinate the special access authorization requirement with the submarine squadron.

1.7.5.4 Special Requirements for Barge IT/ADP Personnel: All support contractor IT personnel will be required to have SECRET Clearances performed under this contract.

1.7.5.5 Shipyard Access Insurance Requirements

The contractor is required to access the shipyards around NBSD, including BAE, NASSCO, and Huntington Ingalls Industries [formerly Continental Maritime San Diego (CMSD)]. The contractor is required to have shipyard access insurance and comply with all commercial shipyard security requirements. In order to obtain insurance requirements, the contractor shall contact the shipyards using the below points of contacts:

1.8 CACS, NMCI/IT SYSTEMS ACCESS/CONTRACTOR CHECK-IN/CHECK OUT

The government will provide CACs, Navy/Marine Corps Intranet (NMCI) computer network, and information technology (IT) system/database access for support contractor personnel/positions requiring for the performance of duties under this contract. An open Tier 3 investigation and “clean” fingerprint checks are the minimum requirements for CAC issuance and NMCI access, unless otherwise provided by the Security Division. Contractor program management and FSO are responsible for notifying the government COR and the Trusted Agent (TA) when a support contractor who has been issued a CAC leaves the company or transfers to another program/project. In the case of an employee no longer working for the company, the company shall ensure the CAC is turned in to the TA within two (2) working days of the employee’s departure as part of the support contractor check-out process. The contractor shall ensure all support contractor personnel are checked-in and checked-out of the command by completing the contractor Check-In/Check-Out Form provided by the COR. The contractor shall retain a copy, and provide the completed original to the COR within one (1) week of support contractor check-in or check-out completion.

1.9 MANDATORY TRAINING AND CERTIFICATIONS/QUALIFICATIONS/LICENSES

The contractor shall accomplish/verify accomplishment and track all training requirements as mandated by DoD and DoN by the due dates provided by the COR. Many of these mandatory training requirements are required to be accomplished by all support contractor personnel, whether or not they possess a CAC and have access to the NMCI network/Navy computer-based training modules. The contractor shall comply with changes and updates to training requirements when provided. The contractor shall track completion of all mandatory and required training for all support contractor personnel. Training records for support contractors shall be maintained and made available upon request. The contractor shall comply with changes and updates to training requirements by keeping support personnel in compliance with the most current instructions. Refresher training is required at least annually. The contractor shall track and ensure all support contractor personnel possess current, valid certifications, qualifications, and licenses as required by the specific area of support.

The contractor shall ensure personnel are adequately and regularly trained on all systems, equipment, repair, and maintenance requirements in order to maintain the Barges.

1.10 GOVERNMENT FURNISHED PROPERTY

In accordance with FAR 52.245-1 "Government Property" contained herein, the government will provide the contractor certain government owned facilities, equipment, services, and materials for use in connection with this contract. All such facilities, equipment, services, and materials will be provided in "as is" condition. The use of any Government Furnished Property and services for purposes outside the scope of this contract, is prohibited.

1.10.1 Government Furnished Facilities (GFF). The government will not provide program management office space or general operational facilities to the contractor. The contractor shall secure and maintain the necessary office space and other facilities required for the company's overall management of this contract at his/her own expense. However, the government will furnish the contractor with office space, workshops, and staging areas for the foreman, clerical and dispatching help, and the work crews who report on a daily basis to the barge program location in San Diego, CA, Pearl Harbor, HI, Puget Sound, WA, Yokosuka and Sasebo, JA and Apra Harbor, GU. The Contractor shall obtain written approval from the government prior to making any modifications or alterations to these spaces. At the completion of the contract, all facilities shall be returned to the government in the same condition as received, except for reasonable wear and tear. The contractor shall be held responsible for the cost of any repairs caused by negligence or abuse on its part, or on the part of its employees.

1.10.2 Government Furnished Equipment (GFE). The government will provide the contractor the use of existing and available government owned tools, and equipment in the performance of this contract. Should the contractor choose to use the Government Furnished Equipment (GFE), the contractor shall perform periodic servicing, maintenance, and repair of these items an integral part of the services provided under this contract with a government provided maintenance program. The contractor will check out any tools equipment necessary to accomplish the task at the beginning of the work day and such items will be checked back in at the end of the work day. The contractor shall return GFE that can no longer be economically repaired, or becomes worn out due to normal wear and tear to the government. Contractor shall be responsible for providing Cartridges, Toners, and Fusers for all Government Provided Copy Machines, Printers, and fax machines if used in the execution of this contract. The total or partial breakdown, or failure of, the government furnished equipment will not relieve the contractor of its responsibility to fully perform the work of the contract. The contractor shall provide and maintain inventory list of GFE to the government on a monthly basis. The contractor shall not remove GFE from the military base or used for any other work or purpose outside the parameters of this contract.

Equipment, which can no longer be economically repaired, or become worn out due to normal wear and tear, shall be returned to the government and replacement of such items will be the responsibility of the government. The contractor shall report and provide the government a list of frequently replaced or worn GFE on a monthly basis. Upon completion or termination of the contract, all government, equipment, and published works shall be returned to the government in the same condition as received, except for normal wear and tear. The contractor shall be responsible for the cost of any repairs or replacement caused by negligence or abuse by the contractor or its employees.

1.10.3 Government Furnished Material (GFM). The government will provide the contractor repair and replacement parts required to accomplish preventive and corrective maintenance under this contract. If not available, the contractor shall notify the government of any additional or new materials, which would be required to accomplish the work. Any parts and material required in performance of any task will be recorded on an inventory sheet maintained by contractor's tool room and parts custodian. Upon

completion of each job, the contractor shall return all excess GFM to custodian to be placed back in inventory. The contractor shall provide and maintain an inventory list of GFM to the government on a monthly basis. The contractor shall be responsible for ensuring that supplies, materials, and parts are not pilfered by its personnel.

1.10.4 Contractor Furnished Material (CFM). The contractor shall provide emergent replacement parts as required. Emergent replacement parts constitute any parts or material that may be necessary to accomplish emergent work that would impact health, safety, and proper operation of any system or sub-system that would prevent barge from supporting the fleet. The contractor shall provide emergent repair parts or material that are not in stock as GFM necessary to accomplish emergent repair work required herein. Contractor installed replacement parts become the property of the government. The contractor shall use only new or refurbished replacement parts where the quality is equal to or better than the Original Equipment Manufacturer (OEM) original part.

1.11 Availability of Utilities. The government will furnish the following utility services at existing outlets, for use in those facilities provided by the government and as required for the work to be performed under this contract: electricity, steam, natural gas, fresh water, telephone, sewage service, and refuse collection (from existing collection points). The government shall furnish the utilities specified at no cost to the contractor.

1.12 TRANSPORTATION

The contractor shall provide vehicle transportation for its contracted personnel.. The contractor is responsible for providing at minimum one reliable, fully maintained, and properly registered vehicle to each Area of Responsibility, noting that certain AORs may require multiple vehicles based on operational volume. Each vehicle must be capable of transporting several personnel and delivering equipment, tools, and material. Vehicles must meet all security and access requirements for entry into controlled industrial areas. . All support contractor personnel shall possess a valid state-issued driver's license and current insurance.

1.12.1 Support contractor personnel shall have a valid forklift driver's license for operation of up to 10-ton forklifts, in accordance with NAVFAC P300 within **ninety (90) calendar days** of providing direct support when required by specific tasking/area of support.

1.13 TRANSITION

The contractor shall follow the transition plan submitted as part of the proposal and keep the government fully informed of status throughout the transition period. This contract is expected to be executed seamlessly with no disruption, in day to day services provided by the incumbent and new contractor and totally transparent to the customer in support of the Fleet Response Plan.

2.0 GENERAL REQUIREMENTS

2.1 Business Relations

The contractor shall successfully integrate and coordinate all activity needed with the Barge Area Manager to execute the requirement. The contractor shall manage the timeliness, completeness and quality of problem identification. The contractor shall provide corrective action plans, proposal submittals, timely identification of issues and effective management of subcontractors. All contractor personnel shall conduct business in a professional and ethical manner.

2.2 Contract Administration and Management

2.2.1 The contractor shall execute the scope of work in a manner that provides professional, high quality, timely and well-integrated support services. Execute the work accurately, effectively, efficiently, and responsibly. Be professional in all communications and dealings, including with all internal and external customers. Support contractor personnel shall possess and practice good communications and customer relation skills to effectively interact with military and civilian customers.

2.2.2 The contractor shall establish clear organizational lines of authority and responsibility to ensure effective management of the resources assigned to the requirement. The contractor must maintain continuity between the support operations and the contractor's offices. The contractor shall arrange and schedule completion of work requirements to ensure there is no disruption with normal government business and mission. Contractor program management responsibilities shall include all activities necessary to ensure the accomplishment of timely and effective support performed in accordance with the requirements contained in this PWS, to include ensuring appropriate company policies and procedures are in place to maintain a professional and productive workforce. The contractor shall provide and enforce the following company policies applicable to all support contractor personnel: timekeeping policy, break and lunch policy, cell phone and Internet usage policy, and dress code policy.

2.2.3 For contractor program management personnel, the senior/main Program Manager (PM) shall obtain and maintain Project Management Professional (PMP) certification, and additional PM(s) under this contract shall obtain and maintain PMP or Certified Associate in Project Management (CAPM) certification (with PMP being the preferred certification) within **ninety (90) calendar days** of contract award or of personnel replacement.

2.2.4 The contractor shall furnish daily management, supervision, and labor necessary to ensure satisfactory habitability, minor installation and repairs, service call work, system/equipment, familiarization and port husbandry requirements for the COMPACFLT Berthing and Messing Program barges in accordance with the performance based requirements stated herein. The contractor shall provide and designate fore person/supervisor and team lead for each areas of responsibility responsible for managing the numerous contractor personnel, ensuring proper maintenance of Barges and equipment, and implementing preventative maintenance programs supporting this effort. The contract shall ensure efficient and safety completion of maintenance task, while also managing resources and adhering to regulations. The contract shall assign a Barge Manager to each Barge to walk and inspect the Barges daily, meet with the ship appointed Barge Manager, and check the trouble log located on the Quarter Deck.

2.2.5 The contractor shall have a single point of contact between the government and contractor personnel assigned to support contracts. The contractor shall assign work effort and maintaining proper and accurate time keeping records of personnel assigned to work on the requirement. The contractor shall establish processes and assign appropriate resources to effectively administer the requirement.

2.2.6 The contractor program management team and COR shall meet bi-weekly to discuss support contractor personnel employment actions, contract action items and concerns, and other important contract-related items. The contractor shall provide an agenda of topics and issues to be discussed.

2.2.7 The contractor shall conduct daily musters and provide status of all support contractor personnel to the cognizant government requirements holders within 30 minutes of the start of each work day.

2.2.8 The contractor shall respond to government requests for contractual actions within one business day.

2.2.9 The contractor shall have email capability and the necessary connectivity to ensure constant communication ability with the government. The contractor shall ensure that the corporate email application used is fully compatible with Microsoft Outlook (which is used by government personnel), in order to communicate and coordinate meetings and schedules.

2.2.10 All support contractor personnel shall obtain and maintain Quality Assurance (QA) Craftsman 301 qualification within **ninety (90) calendar days** of providing direct support.

2.2.11 Support contractor personnel providing support in this area shall be qualified riggers in accordance with Reference 7.22 within sixty (60) calendar days of providing direct support. This qualification requires completion of the U.S. Navy 40-Hour Rigger course.

2.2.12 Support contractor personnel providing shipfitter/pipefitter/welder support shall obtain and maintain the following weld qualifications in compliance with References 7.25 and 7.27 within ninety (90) calendar days of providing direct support.

2.2.13 The contractor personnel shall provide an effective mix of experience and technical expertise that is suited to accomplishing maintenance, repair, and emergent work. Emphasis shall be placed on a team structure that maximizes productivity, efficiency, and accountability within the labor-hour estimates provided by the Government

2.2.14 The contractor shall provide rigging services, scaffolding, transportation, disposal, and required services and support to accomplish the work specified in this contract.

2.2.15 The contractor shall perform the total work effort associated with maintenance and operations of all Berthing Barges required herein, to assure adequate and timely completion of these services.

2.2.16 Work Control. Due to the fact that most of the effort is expected to be accomplished on berthing and messing barges which are in a "ready to occupy" status, scheduling can be volatile and planning, estimating and resource acquisition could be immediate and intensive. The contractor shall implement all necessary work control procedures to ensure timely accomplishment of work requirements, as well as to permit tracking of work in progress. The contractor shall plan and schedule work to assure material, labor and equipment are available to complete work requirements within the specified time limits and in conformance with the quality standards established herein. The contractor shall provide a written status of any work item within two regular working hours when requested by the government.

2.2.17 Records and Reports. The contractor shall maintain management, operation and service records and reports as described herein. All related data specifically designed to track the work performed under this contract will be considered government owned property and proprietary information.

2.2.17.1 A work file Current Ship's Maintenance Program (CSMP) for each barge (identified by hull number) shall be maintained by the Contractor. Each file shall contain at a minimum:

- (a) Listing of work needed to be completed at Organizational Level and Depot Level
- (b) Job sequence number (JSN)
- (c) Description of discrepancies identified
- (d) Corrective action needed to be taken
- (e) Material or part number
- (f) Date completed
- (g) Additional comments

2.2.17.2 The Contractor shall maintain major maintenance history records (last overhaul, dry-docking, underwater hull inspections, and material inspections data) on all COMPACFLT berthing and messing barges. The Government will provide a work file CSMP for each barge to the Contractor upon contract award.

2.2.17.3 The contractor shall maintain inspection, service call, maintenance, and repair work or job records that shall include at least:

- (a) The dates on and area in which the work was performed
- (b) Listing of each category and number of hours used (e.g., straight time, overtime, comp time, etc.)
- (c) Total number of hours expended
- (d) Listing of equipment, materials, parts and components used (other than pre-expended bin materials and supplies)
- (e) Discrepancy log tracking

2.2.17.4 The contractor shall maintain maintenance history records on the equipment preventive/corrective maintenance and provide any reports requested by the government.

2.2.17.5 The contractor shall maintain and update technical library for all Original Equipment Manufacturer (OEM) and all applicable references outlined in this contract.

2.2.17.5 The contractor shall ensure and track timely accomplishment for work requirements and work in progress.

2.2.18 Additional Reporting Requirements

2.2.18.1 The contractor shall provide all cost, performance and earned value management reports in accordance with [CDRL A001]

2.2.18.2 The contractor shall provide a Status Update Report in accordance with CDRL A002.

2.2.18.3 The contractor shall provide a Government property inventory report in accordance with CDRL A003.

2.2.18.4 The contractor shall provide a Material Procurement status report in accordance with CDRL A004

2.2.18.5 The contractor shall provide Meeting Agenda report in accordance with CDRL A005

2.2.19 The contractor shall maintain maintenance history records on the equipment preventive/corrective maintenance and provide any reports requested by the government.

2.2.20 Any and all records, data, and reports shall be turned over to the government (Contracting Officer or COR) within five calendar days after an individual request or contract completion (Maintenance history records and material inspections data, etc.).

2.2.21 At request of the government, the contractor shall provide oral and written reports on any barge or contract-related work records within two working days, unless a different time frame is stipulated elsewhere in the contract.

2.2.22 The contractor shall research and prepare an monthly validation and update of the berthing barge inventory report on all berthing and messing barges. The contractor shall prepare general maintenance recommendations and corresponding reports for the COMPACFLT Program Administrator, COR and regional TA.

2.2.23 Staffing. The contractor shall continuously maintain an adequate staff with suitable supervisory, clerical and administrative expertise to assure work is scheduled, completed, recorded and reported in accordance with these specifications. The contractor also shall continuously maintain an adequate on-site staff of laborers, mechanics and tradesman to complete all day-to-day work in accordance with the time and quality standards specified in the contract.

2.2.24 Coordination with COR. Within ten calendar days of commencing work under the contract, the contractor shall provide the contractor's management, supervisory, scheduling and contractor personnel along with a brief description of their delegated authorities to the government. The contractor shall ensure that these listings are constantly updated monthly and provided to the government throughout the life of the contract.

2.2.25 Continuity of Services. Support of Naval Crew Members displaced from their ships during scheduled availabilities onboard berthing and messing barges is the primary mission of the COMPACFLT Berthing and Messing Program. To ensure continuity of essential services, the contractor shall be prepared to fully commence work on the start date of this contract and should not assume that government or previous contractor employees will be available to guide, direct or specifically orient each contractor personnel. It is imperative that there are no disruption of services to naval crews currently embarked onboard the barges. As part of being fully ready to commence work, the contractor shall be prepared to accept backlogged service calls and in-progress general work jobs in the COMPACFLT Berthing and Messing Program on the contract start date. Each COMPLACFLT Berthing and Messing Barge shall have one (1) Barge Manager per Barge to inspect and walk the Barge daily, meet with the ship's force appointed and/or assigned Barge Mayor to check the trouble log located on the Barge quarter deck, and all maintenance requirements assigned to each Barge. The contractor shall complete all backlogged and in-progress jobs within ten working days after the contract start date. The government will provide a copy of the backlog/ discrepancy log to the contract at the start of the contract. If the contractor is unable to meet this deadline, the contractor shall provide a written notice to the COMPACFLT Program Administrator, COR, or Contracting Officer detailing the extent of the repairs and a plan of action to complete all backlogged services no later than five working days after the contract start date.

2.2.25.1 The contractor shall conduct ship checks on Duty Crew Berthing and Messing Barges as designated by the Regional Technical Advisor (TA) to prepare an integrated, prioritized listing of the work items to be accomplished.

2.2.25.2 The contractor shall identify needed work by conducting analysis and technical evaluations of spaces, equipment, components, furnishings, assemblies, and subassemblies. The contractor shall participate in arrival and departure walk-through inspections and, as appropriate other condition assessment inspections and then reporting its findings to the Contracting Officer's Representative or Regional TA. This will be accomplished using the CSMP and a government furnished maintenance program. A copy of the CSMP will be emailed to COMPACFLT Program Administrator, COR and regional TA upon completion of updates.

2.2.25.3 The contractor shall arrange and schedule completion of work requirements for no interference with normal government business and mission.

3.0 SERVICE CALLS

Service calls are defined as maintenance, minor repair, and other miscellaneous work requirements which are called into a work reception center maintained by the contractor. Generally speaking, service calls are brief in scope; require no more than eight total working hours per worker to accomplish; and do not usually require detailed job planning. Multiple maintenance, minor repair requirements received for the same trade on the same barge at the same time will be combined into one service call.

Service calls will be classified as Routine, Emergency & Urgent at the discretion of the COMPACFLT Program Administrator, COR and/or regional TA.

Generally, urgent calls will consist of providing services or correcting failures which do not immediately threaten personnel, property, or activity missions; but which will soon inconvenience or affect the health and well-being of personnel, lead to property damage, or lead to disruptions in operational and training missions.

3.1.1 The contractor shall receive, classify, and document Service Call Requests for service call receipt records.

3.1.2 The contractor shall provide adequate procedures for receiving and responding to routine, emergency and urgent service calls during and after regular working hours, provide a single local or toll free telephone number for receipt of all service calls or the service calls, and provide an individual fully familiar with the contractor's work control procedures and the terms and conditions of this contract to answer and respond to all telephone calls and voice messages.

3.1.3 The government's work reception centers shall be manned by suitable contractor personnel. Service calls may occur outside of regular working hours. A description of the problem or requested work, date and time received, location, and other appropriate information will be logged and transmitted to the contractor in a format mutually agreed upon following contract award. If the call is classified as emergency or urgent, the contractor receptionist will notify COMPACFLT Program Administrator, COR and/or regional TA that a call has been received and the contractor shall dispatch workers to the site where the work is to be performed upon approval. Service Call Classification definitions to be used are:

3.1.4 ROUTINE CALLS

Service calls will be classified as routine when the work does not qualify as an emergency or urgent call as determined by COMPACFLT Program Administrator, COR and/or regional TA. Examples of routine calls include (but are not limited to): inoperative electrical switches or outlets, dripping faucets, broken floor tile, repairs to mechanical, galley, food service, or laundry equipment, broken trimmings, broken non-electrical or unplumbed fixtures, countertop, cabinet, and locker repairs, interior door repairs in non-critical areas, suspended ceilings, replacement of light bulbs, and key making, etc. The contractor shall respond and complete repairs for service calls.

3.1.5 All routine calls shall be completed within two working days of receipt. Routine calls will be considered as received by the contractor at the time and date an authorized government representative makes a work authorization form available for pick-up or electronically transmits the work authorization information to the contractor. Work will be accomplished during regular working hours, Monday through Friday.

3.1.6 If the contractor responds to service calls and believes that the work required is beyond the scope of emergent or urgent service call, as defined above, the contractor must contact the COMPACFLT Program Administrator, COR and/or regional TA within one hour of discovering the facts leading to this belief.

3.1.7 If the COMPACFLT Program Administrator, COR and/or regional TA disagrees with contractor's classification of service call, the COR or ACOR may confer with the Contracting Officer to reclassify the work as a routine, emergency, or urgent call. Once reclassified, the contractor shall proceed with the job following the procedures of the new work classification.

3.1.8 EMERGENCY CALLS

Service calls will be classified as emergency at the discretion of the COMPACFLT Program Administrator, COR and/or regional TA. Generally, emergency calls will consist of correcting failures that constitute an immediate danger to personnel, threaten to damage property, or threaten to disrupt activity operational or training missions. Examples include outages in utility (including phones), ventilation, security, fire, or other systems; clogged drains; broken water or steam pipes; gas leaks; inoperable pumps; leaks in systems or components which must be watertight; electrical defects which may cause fire or shock; unlocking of locks or safes; etc. Emergency calls may require response outside of regular working hours.

3.1.9 If further labor and material (follow up work) are required to complete the repair, COMPACFLT Program Administrator, COR and/or regional TA will reclassify the call as either urgent or routine, as appropriate, and the corresponding completion time will then apply. Such follow up work will be considered part of the original service call.

3.1.10 The contractor shall be on the job site and working within three hours after receipt of an emergency call. Emergency calls will be considered received by the contractor at the time and date the telephone call is placed by the government work reception center or other authorized Government representative. The contractor shall work continuously without interruption and arrest the emergency condition before departing the job site (e.g., shut off water, close gas valve, temporarily patch, etc.).

3.1.11 URGENT CALLS

Service calls will be classified as urgent at the discretion of the COMPACFLT Program Administrator, COR and/or regional TA. Generally, urgent calls will consist of providing services or correcting failures which do not immediately threaten personnel, property, or activity missions; but which will soon inconvenience or affect the health and well-being of personnel, lead to property damage, or lead to disruptions in operational and training missions. Calls will also be classified as urgent when the service or failure has upper level management (i.e., the Commander, Pacific Fleet, Commanding Officer and Executive Officer) attention. Urgent calls may require a response outside of regular working hours.

3.1.12 The contractor shall be on the job site and working within eight hours after receipt of an urgent call. Urgent calls will be considered received by the contractor at the time and date the telephone call is placed by the government work reception center or other authorized government representative. The contractor shall execute work during regular working hours, unless the COMPACFLT Program Administrator, COR and/or regional TA requires contractor personnel to work after hours. In such cases, after hours' work will be followed up upon completion by the COMPACFLT Program Administrator, COR and/or regional TA the following business day. After the contractor responds to an urgent call and believes that the work required is beyond the scope of an urgent service call, as defined above, the COMPACFLT Program Administrator, COR and/or regional TA shall be contacted within one hour for adjudication to determine if reclassification of the work is appropriate.

4.0 SPECIFIC TASKS

3.2 INTERIOR WORK

Interior work shall be performed in areas such as (but not limited to) berthing compartments, passage ways, messing areas, heads, laundry rooms, wardrooms, recreation rooms, lounges, store rooms, and interior decking.

- a) Applies to all Interior Repairs: Prior to the installation of any item therein, the surface will be prepared in accordance with the manufacturer's instructions and the Steel Structures Painting Council (SSPC) Surface Preparation Standards. The contractor shall adhere to the most recent versions of SSPC-SP-1, Solvent Cleaning, and SSPC-SP-2, Hand Tool Cleaning.

3.2.1 The contractor shall repair, replace (if needed), and restore original condition for damaged or deteriorated flooring and subflooring. Original condition is defined as a structurally sound, uniform, and aesthetic surface which is free of cracks, breaks, chips, tears, gouges, stains, and buckling. Flooring replacement shall include removal and disposal of old tiles; subfloor surface preparation; and installation and finishing of flooring.

- a) Resilient Tiles: Damaged or deteriorated tiles shall be replaced with tiles of the same material, style, size, and color (provided by the government). Damaged tiles or tiles to be replaced shall be removed without affecting adjacent tiles. If tile is replaced adjacent to a bulkhead, any existing vinyl baseboard/coving shall also be replaced. Installation shall be in accordance with manufacturer's instructions and the surface preparation standards as listed above.
- b) Carpet: Carpeting shall be patched or repaired as required to match existing carpeting.
- c) Ceramic Tile. Ceramic tile floors that are broken, missing, cracked or discolored shall be repaired as required with tiles of the same material, style, size, and color. Floor tiles shall be grouted, as required, to provide a waterproof seal. In those cases, where replacement tiles of an exact match cannot be found, the Contractor may be required to remove and replace non-defective tiles to create a pattern and minimize the visual effect of the mismatch.

3.2.2 The contractor shall replace (if needed) and repair to original condition for damaged and deteriorated bulkheads, overheads and related trim. Trim items and fixtures shall be removed as necessary to provide access to the damaged area. Upon completion of the repair work, fixtures and trim items shall be reinstalled, repainted, or refinished to restore them to their original condition.

- a) When removing bulkhead or overhead sheathing or coverings, the contractor shall inspect the supporting structural system and notify the COMPACFLT Program Administrator, COR and/or regional TA of any need for additional repairs before proceeding. Additional repairs shall be approved by the COMPACFLT Program Administrator, COR and/or regional TA prior to commencement of work.
- b) Vinyl Bulkhead Covering: Bulkhead covering, which has been ripped, scarred, stained, or otherwise damaged, shall be repaired or replaced as necessary to original condition. Bulkhead covering shall be repaired if the damaged area can be patched and not noticeable. Bulkhead covering which is extensively damaged, or for which a matching bulkhead covering is not available, shall be repaired by replacing the bulkhead covering on the entire bulkhead. If matching bulkhead covering is not available, the contractor shall find a comparable substitute. COMPACFLT Program Administrator, COR and/or regional TA will approve all replacement bulkhead coverings which do not match the existing bulkhead covering. Replacement bulkhead covering shall be hung according to the manufacturer's recommendations.
- c) Ceramic Tile: Ceramic tile surfaces that are broken, missing, cracked or discolored shall be replaced with like or similar tiles of matching existing tile, as required. Tiles shall be grouted as required to provide a waterproof seal. In those cases, where replacement tiles of an exact match

cannot be found, the Contractor may be required to remove and replace non-defective tiles to create a pattern and minimize the visual effect of the mismatch.

- d) **Suspended Ceilings/Overhead:** Broken, stained, and missing ceiling/overhead tiles shall be replaced with tiles of the same material, style, size, and color. Damaged and broken suspended grid system shall be repaired or replaced as necessary to provide a suspended overhead system as designed. Tasks for suspended ceiling replacement shall include the removal, disposal, and installation of any and all suspended overhead components. Overhead components may include t-shaped main runners, crosspieces, wall angles, ceiling panels, louvered ventilation system registers, and sandwich or egg crate panels that cover registers. The contractor shall provide and use stainless steel blind-type pop rivets secure or connect components to ceiling and walls. The contractor shall ensure proper fit so no ceiling component bows or ripples and no panels hang out or drop out of the grid work.

3.3.3 The contractor shall replace (if needed), maintain, and repair original operational doors for all contract covered barges.

- a) **Replaced Doors:** The replaced doors shall be the same type and have the same finish as the original doors (in accordance with the approved planning yard drawings). All replacement doors shall be installed with the hardware from the damaged door unless the hardware is not repairable. Small holes in door faces shall be filled and finished to match surrounding door surface.
- b) **Repaired Doors:** Door repairs shall match color, texture and hardware of existing door.

3.3.4 The contractor shall secure, repair, maintain, replace, and refinish original operational ladders and handrails for loose treads, risers, stingers, handrails, brackets, and other components.

- a) **Repair or replace to match original components.** Damaged finish shall be repaired. Trim items susceptible to damage during the repair activity shall be removed and reinstalled upon completion of the repair activity. Handrails and ladder rungs or treads shall be fabricated, connected, welded, brazed, and fired into craft structure. Welds shall be ground smooth and fasteners, if applicable, shall be smoothly seated to prevent personnel safety hazards. Flanged or coupled joints shall not be used.
- b) **All broken and/or cut handrails and ladders have to be repaired and tested in accordance with the Joint Fleet Maintenance Manual (JFMM).**

3.3.5 The contractor shall repair and replace (if needed) to an operating condition for sagging and non-functional traverse or curtain rods.

- a) **Loose brackets shall be secured. Broken cords shall be replaced. Broken or missing drapery slides shall be replaced. Rods shall be level and parallel with the overhead. Additional support brackets shall be installed to support sagging rods. Curtains shall be hung.**
- b) **Economical Replacement:** If beyond economical repair, as determined by the Barge Program Administrator and/or TA, rods shall be replaced.

3.3.6 The contractor shall repair and alter to an original fabric condition for cushions, seats, exterior awnings, furniture, and other fabric articles.

Fabrics may include (but not limited to) vinyl, leatherette, and canvas.

- a) **The contractor shall take measurements and make patterns and layouts. The contractor shall mark, cut, fit, and sew parts together, using hand- or power tools and equipment and knowledge of fabrics and construction methods. Workmanship shall be of good quality and to industry standards using top sticking on all seems, tucked corners and seams, non-ferrous fasteners and, where applicable, heavy duty zippers. When necessary, new gliders shall be installed, fire**

retardant marine plywood shall be used and all previously installed staples will be removed and replaced.

3.3.7 The contractor shall repair damaged metal furniture and fixtures (such as bunks).

- a) File scrapes, or sand parts to remove dirt, paint, or rust,
- b) Melt solder into holes and cracks,
- c) Grind solder until smooth and flush with surrounding metal,
- d) Bend or hammer dented or twisted parts to original shape,
- e) Tighten or replace loose screws, nuts and bolts,
- f) Replace missing or broken parts (e.g., hinges, door and drawer handles, latches, and furniture arms and legs).

3.3.8 The contractor shall repair and replace (if needed) to original condition for cabinets, lockers, shelving, countertops, and tabletops.

Damaged or deteriorated cabinets, lockers, shelving, countertops (including stainless steel) and tabletops.

- a) Countertops and tabletops shall be repaired; free of warped, chipped, burned, cut, or otherwise marred areas. Replacement of laminated countertops/tabletops shall conform to the requirements of American National Standards Institute publication A161.1. When painting or finishing of repaired or replaced cabinets or lockers is required, all cabinets and lockers in the compartment shall be painted or finished, if required, to match original cabinets or lockers.

3.3.9 The contractor shall repair and replace (if needed) to original condition for interior accessories.

- a) Damaged, inoperative, or missing interior accessories including, but not limited to, paper holders, soap trays, dispensers, towel bars, shower curtain rods, medicine cabinets, mirrors, smoke detectors, and door stops.
- b) Loose accessories shall be secured by tightening or replacing pop rivets. Deviations shall be approved prior to installation. Installation shall be accomplished using nonferrous fasteners or stainless steel blind pop rivets. Fixtures shall not be installed utilizing pressure tape, expansion friction or welding. Damaged or missing items shall be replaced with items matching the original. Replacement hardware shall conform to the Building Hardware Manufacturer's Association Product Standard (BHMA.) Hardware items requiring lubrication shall be lubricated and restored to original condition.

3.4 EXTERIOR WORK

Exterior work shall be performed in areas such as (but not limited to) seams, metal flashing, exterior trim, downspouts and drain pipes, exterior accessories, ladders and stairs, doors, hatches, covers and windows, and exterior decking.

3.4.1 The contractor shall repair and replace (if needed) to a watertight condition for seams between ports, windows, door frames, and exterior bulkheads in accordance with the maintenance cards.

- a) Old joints shall be scraped and cleaned with a solvent recommended by the caulking manufacturer. The caulking shall be applied according to the manufacturer's directions.

3.4.2 The contractor shall repair and replace to match existing for exterior trim.

- a) Exterior trim includes all exterior moldings, metal flashings, and millwork.

Surfaces to receive trim shall be thoroughly cleaned of sealant and paint build-up prior to installation of trim. Damaged or deteriorated underlayment shall be replaced with material of the same type, thickness, and quality. Screens and vents shall be intact and free of corrosion and missing pieces.

3.4.3 The contractor shall repair, replace (if needed), and clean to original condition for downspouts and drain pipes.

- a) Loose hangers and fasteners shall be tightened. Missing guards, hangers, fasteners and splash blocks shall be replaced. Splash blocks shall be properly positioned to receive the impact of drainage water.

3.4.4 The contractor shall repair and replace (if needed) to original condition for exterior accessories.

- a) Exterior accessories include (but not limited) to exhaust fan, vent, stack, or chimney caps. Accessories must be repaired with material of the same type, or replaced, as required, with similar.

3.4.5 The contractor shall repair and replace (if needed) to original condition for ladders and stairs.

- a) Ladders and stairs include (but not limited) to stair treads, risers, nosings, stringers, brackets, balustrades, handrails, and other components. Ladders and stairs must be replaced with material used of the same type or replaced with same or similar item.

3.4.6 The contractor shall repair and replace (if needed) to original condition for doors, hatches, covers, windows, and associated hardware.

- a) Applies to Doors, Hatches, Covers and Windows: Caulking, glazing, and weather-stripping shall be fully intact to maintain a fully watertight seal. Replacement glass shall be of the same size, type, and quality as the existing glass.
- b) For Doors: Damaged, deteriorated, warped, and sagged doors shall be repaired to original condition or replaced with doors the same type and size. Exterior doors shall be removed and replaced the same workday. All replaced doors shall be installed with hardware from existing doors of similar or like material of what is being replaced. Cracked and broken glass in doors shall be replaced with the same quality, type, and size.
- c) For Hardware: Damaged, inoperable, or missing hardware such as hinges, locks, striker plates, latches, keepers, window operating mechanisms, door closures, springs, etc. shall be repaired to original condition, or replaced as required. Replacement hardware shall match existing hardware in type, size, quality and finish and meet the Building Hardware Manufacturer's Association (BHMA) Product Standards. Hardware shall be installed in accordance with the manufacturer's recommendations.

3.5 ELECTRICAL WORK

3.5.1 The contractor shall maintain, repair, and replace (if needed) in order to operate as originally intended and designed for all electrical equipment.

- a) Electrical equipment includes, service connections, distribution panels, connections, grounds, outlets, switches, wiring, branch circuits, ground fault circuits, lighting fixtures, photo cells, and power cords.
- b) Cracked, broken, or missing receptacle and switch faceplates shall be replaced with new plates of the same or original color and size. All workmanship and materials shall conform to the National Fire Protection Association (NFPA) 70 National Electrical Code.

3.5.2 The contractor shall install, troubleshoot, program, maintain, modify, repair, and replace (if needed) to original condition for voice and non-voice communication systems.

- a) Voice and non-voice communication systems includes (but not limited) to switching equipment, consoles, relay racks, miscellaneous radio, intercom and public address systems; alarm systems; and telephone key systems; computer data circuits, etc. Contractor shall run cables or wire to telephone sets, terminal connectors, lugs, pins, or screws, associated with key telephone equipment and terminating equipment for non-voice circuits.

- b) Damaged or deteriorated telephone or other telecommunication wiring shall be repaired to original condition or replaced from the pier side connection point to the craft including telephone jacks. Cracked, missing, or inoperative plug-in or screw connected telephone jacks shall be replaced.

3.5.3 The contractor shall repair and replace (if needed) to original condition for all lighting fixtures.

- a) Lighting fixtures include (but not limited to) florescent light fixture tube bulbs, starters, ballasts, and translucent diffuser panels on fluorescent light fixtures. Install similar or like material.
- b) Provide and replace batteries, perform testing unit after completion of repairs to ensure proper operation.

3.6 SECURITY, FLOODING, AND FIRE PROTECTION ALARM SYSTEM REPAIRS

- a) Security, Flooding and Fire Alarm systems include various electrical systems including (but not limited to) intrusion panel alarm systems, watertight door position indicator systems, video surveillance systems (including cameras, multiplexers and monitors) and interior communication system (general announcing systems).

3.6.1 The contractor shall inspect, test, repair, and replace (if needed) to original operational condition for Craft's central security, flooding and fire alarm systems.

- a) Repairs may be limited to the resetting and reprogramming of power supply, alarms and indication panel and logic system. Repairs shall include, but will not be limited to, the cleaning, adjusting, lubricating, repairing or replacing of defective components of the control and indication portions of the systems. Replacement parts may include, but will not be limited to, wiring, detectors, sensors, circuits, fuses, and relays. All work must be IAW OEM and National Fire Prevention Association standards for the system being repaired. An example, of a standard that will commonly be used aboard crafts is NFPA 25, Inspection, Testing and Maintenance of Water-Based Fire Protection Systems.

3.7 INTERNAL COMMUNICATION (IC) SYSTEM SERVICES

- a) Internal communication (IC) systems includes telephone, communications, IMC, CATV, fire/flooding system and barge security system.

3.7.1 The contractor shall maintain, repair, and replace (if needed) to operate as originally intended and designed for all internal communication systems.

- a) Service includes repair or replace speakers, microphones, GEMS sensors, remote heat detectors, wiring, perform wiring fieldwork on power supply and amplifier system, reprogram power supply, alarm, indication panel, and logic system. Electrical and minor mechanical repairs may also include (but not limited to) testing of circuits for continuity and grounds, fusing, indicator lights, visual inspection, set-points and controls.
- b) Telephone services to include but not limited to: programming, telephone system maintenance, new installations and training for onboard crews utilizing the Berthing and Messing Barges. New installations shall include removal and disposal of old telephone systems, installation, configuration, and maintenance of new systems.

3.8 MAINTENANCE AND REPAIR OF FIREFIGHTING EQUIPMENT

3.8.1 The contractor shall inspect, test, repair, replace (if needed), recharge, and certify and record to operate as originally intended and designed for all firefighting equipment as per the maintenance index card

- a) Inspect, test, repair, replace, recharge, certify and record in accordance with National Fire Protection Association (NFPA) guidelines and regulations. On-line or printed subscription to NFPA Standards is available at www.nfpa.org
- b) Fire hoses shall be inspected, tested, and certified (stenciled) utilizing the current year's version of NFPA 1962, Standard for the Care, Use, Service and Testing of Fire Hose, Including Couplings and Nozzles.
- c) Fire extinguishers shall be inspected, tested, recharged and certified (labeled) utilizing the current year's version of NFPA 10, Standard for Portable Fire Extinguishers.
- d) Repair Standard: Provide an electronic report to the COMPACFLT Program Administrator, COR and/or regional TA within two working days following the inspection and test, indicating the following:
 - Problems, component failures, or area of unsatisfactory operation;
 - Recommended corrective action and, if applicable, in accordance with the NFPA Standard
 - A list of required material including manufacturer's name, part numbers, and quantities

3.9 LOCK AND LATCH INSTALLATION SERVICES

- a) Lock work shall include, but not be limited to the repair of key locksets; the fabrication and replication of keys; opening of key locksets; and the installation, maintenance, repair, replacement, removal, opening, and resetting of mechanical and electronic combination or cipher locks.

3.9.1 The contractor shall maintain, repair, replace (if needed), and reset to operate as originally intended and designed for mechanical and electronic combination and cipher locks.

- a) Lock work shall include, but not be limited to the repair of key locksets; the fabrication and replication of keys; opening of key locksets; and the installation, maintenance, repair, replacement, removal, opening, and resetting of mechanical and electronic combination or cipher locks. Activities also include unlocking of doors, safes, and vaults (with or without combination or key) to gain access when authorized; and the improvement, alteration, and adaptation of locking devices and systems.
- b) Door lock replacement and repairs shall be accomplished using commercially available material and according to acceptable practices and standards of the commercial security industry.
- c) For fabrication and replication of keys: Identical keys of the same material and fit shall be provided by the contractor.
- d) Combinations shall be set in accordance with the combination that is given by the Government.

3.10 PLUMBING AND PIPEFITTING SERVICES

- a) Plumbing and pipefitting work shall include maintenance and repair of the piping and plumbing systems, components and fixtures of each barge.

3.10.1 The contractor shall assemble, install, and repair original operable condition for pipes, fittings, fixtures of steam, heating, and drainage systems.

- a) Contractor may be required to conduct minor weld holding fixtures or hanger to steel structural members. Water and steam lines are defined from pier side connection to, and including, any valve, tap or plumbing fixture. Steam, water and gas lines are defined from and including the cut-off valve at the pressure regulator and pier side connector to, and including, the appliance, heater, water, or water heater connection.
- b) Work must be conducted in accordance with OEM specifications and shall meet the workmanship and material requirements of the American National Standards Institute A40.8-55 and National Plumbing Code.

3.10.2 The contractor shall repair and replace (if needed) to original and operable condition for plumbing fixtures.

- a) Plumbing fixtures are defined as but not be limited to all sinks, tubs, toilets, urinals, basins, faucets, heads, lavatories, showers, drain lines. All fixtures and components thereof that cannot be repaired to original condition shall be replaced.
- b) Work must be conducted in accordance with OEM specifications and shall meet the workmanship and material requirements of the American National Standards Institute A40.8-55 and National Plumbing Code.

3.10.3 The contractor shall repair and replace (if needed) to original and operable condition for water heaters.

- a) Water heaters and components that cannot be repaired to original condition shall be replaced in accordance with OEM specifications and shall meet the workmanship and material requirements of the American National Standards Institute A40.8-55 and National Plumbing Code.
- b) Water heaters shall be firmly secured to support structures, and free of movement and vibration.
- c) Water heater insulation jackets shall be installed on all replacement water heaters and on existing units when excessively worn, damaged, or missing.

3.10.4 The contractor shall repair and replace (if needed) to original and operable condition for drinking fountains.

- a) Work should be conducted in accordance with OEM specifications and shall meet the workmanship and material requirements of the American National Standards Institute A40.8-55 and National Plumbing Code.
- b) Fountains shall be firmly secured to support structures, and free of movement and vibration.

3.10.5 The contractor shall repair and replace (if needed) to original and operable condition for pipes and piping system.

- a) Pipe repairs and replacement shall include (but not limited to) cutting, bending, threading, brazing, assembling, coupling and fastening pipe and pipe hangers. All work should be conducted in accordance with OEM specifications and shall meet the workmanship and material requirements of the American National Standards Institute A40.8-55 and National Plumbing Code.
- b) The contractor shall test piping to ensure proper pressures and that the pipe and system maintain flow.

3.11 MACHINE, WELDING AND METAL WORKING SERVICES

- a) Provide maintenance, repair to original condition, or replacement of metal components of barges and their installed equipment and facilities, and shall construct and install metal components in support of other repair activities as required by this section.

3.11.1 The contractor shall maintain, repair, fabricate, and replace (if needed) to original and operable condition for metal working requirements.

- a) Metal working requirements will include (but not limited to) heating and bending to form metal shapes, drilling, torch cutting, hammer forging, grinding, welding, sawing and fitting of metal parts.

3.11.2 The contractor shall maintain and repair original and operable condition for barges, structures, and appurtenances

- a) Welding shall be performed on, but not limited to, light, heavy gauge and hardened metals using flat, vertical, horizontal, and overhead positions. Processes include, but not limited to, preheating, brazing, bead welding, tack welding, flame cutting, pressure welding and heat-treating.
- b) The contractor shall provide an adequate fire watch and the required fire extinguishing equipment.
- c) Welding, burning and open flame work will be permitted, but must be approved by the COR or ACOR. The Contractor shall inform the COMPACFLT Program Administrator, COR and/or regional TA prior to any work of this nature being performed.

3.11.3 The contractor shall perform supporting repairs for machinist tasks.

- a) Machinist tasks include but not limited to drilling, tapping, boring, reaming, and grinding a variety of materials such as steel, stainless steel, aluminum, copper, and brass.
- b) The contractor shall install equipment requiring critical alignment of items such as pumps and blowers.

3.12 PAINTING SERVICES

- a) Painting will include both the interior and exterior of all types of surfaces on the barges. Interior and exterior painting performed under this contract shall be in conjunction with service work, recurring work, and other services required.

3.12.1 The contractor shall protect and restore to original condition for furnishings, equipment, floor coverings, and other surfaces.

- a) Items such as hardware, hardware accessories, machined surfaces, blinds, curtains, plates, light fixtures, and similar items in contact with painted surfaces shall be removed, masked, or otherwise protected prior to surface preparation.
- b) All removed items shall be repositioned and furnishings and other property returned to their original position. Painted items such as windows, doors, and cabinets shall operate smoothly without binding. The Contractor shall be responsible for the cost of repairing any damage caused to Government or personal property.

3.12.2 The contractor shall clean free of irregularities for surfaces to be painted.

- a) Free of Irregularities is defined as: All scratches, nicks, cracks, gouges, spalls, alligating, and irregularities due to partial peeling of previous paint shall be repaired, sanded, spackled, caulked, or otherwise treated to render such defects practically imperceptible.
- b) Clean is defined as: Remove all dirt, dust, rust, scale, splinters, mildew, chalked paint, loose particles, disintegrated coatings, grease, oil, and other deleterious substances.
- c) Sanding, wire brushing, washing, and chemical treatments shall be used, as necessary, to properly prepare the surface for painting.
- d) Caulking and other compounds shall be allowed to cure for the times stated in the manufacturer's literature prior to painting.
- e) Existing enamel and other glossy surfaces shall be sanded. Any surfaces bared by surface preparation and exposed metals shall be primed.

3.12.3 The contractor shall apply smooth finish for paint.

- a) Paint shall be carefully applied with clean brushes, rollers, or approved airless sprayers.
- b) Smooth finished surfaces are defined as: free from runs, drops, ridges, waves, laps, brush marks, variations in color, or other defects.

- c) Two coats shall be applied to all new surfaces, or surfaces bared by surface preparation and as required to completely cover stains and marks. Each coat shall be dry and of sufficient thickness to completely cover the preceding coat or surface.

3.13 HEATING, VENTILATION, AIR CONDITIONING AND REFRIGERATION EQUIPMENT (HVAC AND R) SERVICES

- a) This work includes the preventive maintenance of all components, devices, equipment and associated systems, including but not limited to refrigerants, compressors, blowers, motors, drive assemblies, fans, service valves, dampers, condensers, cooling coils, piping, pumps, purge units, control systems and wiring, duct work, burner assemblies, combustion chambers, thermostats and temperature controls, registers, condensate and drip pans and drains, grills, evaporators, air filters, heat/air conditioning units, and all other items of equipment essential to the proper operation of HVAC and R equipment and systems.
- b) If heat/air conditioning and refrigeration units cannot be repaired, the contract shall be responsible for renting replacement units until such units are repaired.

3.14 GALLEY AND FOOD SERVICE EQUIPMENT SERVICES

- a) Food service type equipment is defined as but not limited: stoves, ovens, grills, ranges, exhaust fans and hoods, deep fat fryers, toasters, coffee urns, microwave ovens, food serving, and salad bars, beverage coolers, choppers, slicers, and dishwashers, beverage and ice dispensers, refrigerators and freezers.

3.14.1 The contractor shall maintain, replace parts, and repair to original and operable condition for food service equipment.

- a) Contractor shall inspect and accomplish minor repairs for food service equipment in accordance OEM Maintenance Manuals to include routine preventative maintenance, cleaning and charging, cooler and fan cleaning and servicing, and control and indication calibration and settings.

3.15 LAUNDRY EQUIPMENT SERVICES

3.15.1 The contractor shall repair and replace (if needed) to original and operable condition for laundry equipment.

- a) Laundry equipment may include, but are not limited to, replacement of belts, water pump, mixer valves and solenoids, control switches and timers, drive motors, reduction gears, agitator, drums, water inlet hose, wastewater discharge hose, ducts, flashing and other associated hardware.
- b) During all maintenance and repair work in accordance OEM Maintenance Manuals, the Contractor shall also, but are not limited to, clean screens, filters, traps hoses, and ducts by removing lint and other substance buildup to assure free-flow of air and water.
- c) When directed, the Contractor shall remove existing and install government furnished household style washers and dryer I accordance with OEM Installation Instructions, including double stacked washer dryer combination units; and modify power resources so they fit, conform, and are compatible with new laundry equipment's power requirements.

3.16 SYSTEMS SUPPORT MAINTENANCE

3.16.1 The contractor shall provide preventative maintenance and corrective repairs for Local Area Network Equipment. Preventative maintenance and corrective repairs shall be provided for the following:

- a) A Secure Room to house the networking equipment.

- b) A pier side connection device that is compatible with the normally installed connectors used to support other vessels.
- c) Cabling as required to connect the pier side to the barge secure room.
- d) Racks, networking equipment and Uninterruptible Power Supplies in the secure room to support the distribution of both SIPRNET and NIPRNET data.
- e) Racks to support installation of servers in the secure room.
- f) Cabling to distribute SIPRNET and NIPRNET to bulkhead mounted jacks.

The contractor shall be responsible for all the maintenance and repairs for the announcing systems aboard all Barges, all the repairs and maintenance for the battery/powered smoke alarm systems, all maintenance, repairs and testing of the alarm systems aboard all Barges, all maintenance and repairs of the refrigerant alarm systems aboard all Barges, and the maintenance and repairs of the telephone systems aboard all Barges in accordance with the maintenance requirement and technical manuals.

3.16.2 The contractor shall identify, install, configure, and update as required to original and operable condition for hardware and software configuration.

- a) All minor deficiencies shall be corrected as part of barge operational maintenance.
- b) Deficiencies beyond the scope of operational maintenance shall be documented in the CSMP and identified to the Planning Yard for solution.

3.16.3 The contractor shall maintain the cabling and networking equipment as specified below. Configuration of the networking equipment is the responsibility of the ship.

- a) Install, maintain, repair or replace the pier connection and associated cabling as required.
- b) Install the networking equipment (mount switches and routers in racks) as required. Connect all equipment to power supplies and distribution panels. Provide the required cabling.
- c) Remove, store and prepare for turn-in, all equipment being replaced or refreshed.
- d) Repair or replace all distribution panels, network cabling and bulkhead jacks that have been identified as failing or damaged.
- e) Identify any equipment (switches, routers, power supplies, etc.) that require replacement to the government for procurement.

3.17 RIGGING

The contractor shall ensure all weight handling (i.e. chain fall, lifting straps, etc.) equipment shall be inspected and tested in accordance with NAVFAC P-307, Reference 7.22

- a) Support contractor shall provide equipment rigging services to the Berthing and Barge program.

3.18 TAG-OUT AND HOT WORK

- a) The contractor shall maintain the Berthing and Messing Barge tag-out program for systems and equipment needing to be taken offline to conduct repairs and maintenance.
- b) The tag-out program and hot work shall comply with the requirements in OSHA 1910.46, 1915.14, 1915.503 subpart NAVSEA Standard Items 009-70, 009-07, and 009-24, and S0400-AD-URM-010/TUM.

4.0 PORT HUSBANDRY BARGE MAINTENACE SUPPORT

4.1 The contractor shall properly secure/moor barges to pier side or ashore connectors, utilizing mooring cables, lines and other hardware, as required. The contractor shall ensure mooring lines (in use) are inspected daily in accordance with Maintenance Requirement Card (MRC). Ensure rat guards are

installed securely. The contractor personnel shall ensure mooring line handling safety (OSHA 4392) training is completed.

4.1.1 The contractor shall connect, phase, energize, waterproof, and complete utility services hook-ups to assure proper seal, fit, and support from the barge to pier. Contractor de-installation effort shall include the proper disconnection, securing and stowage of the barge and pier side or ashore equipment, connectors, mooring cables, lines, and other applicable hardware. This is to include setup, operation and securing of accommodations ladders.

4.1.2 The contractor will deliver to and receive barges from assigned customers. This entails documentation of turnover walk through inspections to determine and verify Barge material condition upon delivery or receipt.

5.0 SYSTEM/EQUIPMENT FAMILIARIZATION

5.1 Once the barge is delivered to the customer, the contractor will conduct a monthly refresher barge system/equipment familiarization training for the customer to ensure the purpose functions and operation of installed systems and equipment are understood by the customer. Particular attention is to be placed on Fire Fighting, damage control, safety systems and equipment. Contractor system and equipment monthly training shall have a training syllabus, to ensure all regions are providing the same level of training. All training will require a muster (attendance sheet) and will be submitted to the government.

6.0 SAFETY, HEALTH AND ENVIRONMENTAL REQUIREMENTS

Nothing contained in this PWS relieves the contractor of any obligations it may have to comply with Occupational Safety and Health Administration (OSHA) Regulations. The Contractor shall, as a minimum, comply with Occupational Safety and Health Standards (OSHA Regulations, 29 CFR 1910) and Occupational Safety and Health Standards for Shipyard Employment (OSHA Regulations, 29 CFR 1915). OSHA regulations are available at <http://www.osha.gov/> or <http://www.gpo.gov/>. The Contractor shall comply with all current year National Fire Protection Association (NFPA) Standards. The Contractor shall comply with NFPA 51B, Standard for Fire Prevention During Welding, Cutting and Other Hot Work; NFPA 306, Standard for Control of Gas Hazards on Vessels; NFPA 70E, Standard for Fire Protection in the Workplace, and NFPA 312, Standard for Fire Protection of Vessels during Construction, Repair and Lay-up. NFPA Standards are available via an on-line subscription at <http://www.nfpa.org/>.

6.1 ENVIRONMENTAL, SAFETY AND HEALTH

The contractor shall comply with Environmental, Safety and Health (ESH) programs in accordance with the Occupational Safety and Health Act and instructions, standard operating procedures (SOPs), and other applicable guidance.

6.1.2 OCCUPATIONAL NEAR-MISHAP/INJURY/ILLNESS REPORTING AND DART RATE

The contractor shall verbally report all near-mishaps, incidents, injuries, and illnesses of support personnel related to the performance of this contract to the COMPACFLT Program Administrator, COR and/or regional TA immediately upon becoming aware of such an incident. An initial incident report utilizing the NAVSEA Standard Item 009-74 form shall be provided to these same parties within eight (8) working hours of the incident. A final incident report of the same format, complete with root-cause analysis, shall be provided promptly after incident investigation has been completed.

The contractor shall provide an OSHA 300A report initially and annually thereafter to the COMPACFLT Program Administrator, COR and/or regional TA. The report shall include Total Case Incident Rate (TCIR); and Days Away, Restricted, and Transfer (DART) rate data, along with hours worked for under this contract during the annual period.

6.1.3 MISHAP PREVENTION AND ACCIDENT/INCIDENT INVESTIGATION

The contractor shall participate in each Regional Maintenance Center (RMC) mishap prevention programs and processes as they relate to support contractor personnel under this contract. The contractor shall support accident, incident, near-miss, and/or property damage critiques and investigations related to the performance of this contract, or when the contractor is witness to any accident, incident, near-miss, and/or property damage that is critiquing and/or investigating. This includes interviews, support contractor personnel statements, photographs, and any other processes involved/included in the critique and/or investigation.

6.1.4 OCCUPATIONAL INJURY/ILLNESS DOCUMENTATION

The contractor shall maintain all records, documentation and reporting requirements associated with injuries and illnesses of contractor personnel related to the performance of this contract, as required by Reference 7.24.

6.1.5 JOB HAZARD ANALYSES, ERGONOMIC STUDY, AND INDUSTRIAL HYGIENE ANALYSIS

The contractor shall conduct Job Hazard Analyses (JHAs) and monitoring for support personnel, to ensure sufficient protection protocols are being utilized for work tasks performed throughout the areas of responsibility. This analysis/monitoring includes developing JHAs (or alternatively, the adoption, provided in writing, of specific or all approved JHAs). The contractor shall maintain a JHA tracking system, and shall verify all support personnel are trained on JHAs prior to any related job/task being accomplished. If any differences are noted between the contractor's and RMC's analyses/JHAs/instructions, the contractor shall contact the COMPACFLT Program Administrator, COR and/or regional TA to request a joint conference with ESH Department. The contractor shall review all JHAs on an annual basis. Additionally, the contractor shall conduct an ergonomic study and an industrial hygiene analysis initially and any time that working conditions/environment change. Industrial hygiene analysis shall be conducted/authorized by an American Conference of Governmental Industrial Hygienists (ACGIH)-certified industrial hygienist.

6.1.6 SAFETY PROGRAM SUPPORT

Support contractor personnel shall provide assistance to the RMC's safety programs. Support contractor personnel shall participate in safety training, participate in safety inspections, participate in command safety surveys, and promote personnel involvement in RMC's safety programs. The contractor shall participate in researching and developing opportunities to increase personnel participation in and awareness of the RMC's safety programs. The contractor shall participate in meetings with department and command safety representatives to invigorate and sustain safety programs within the department and the command.

6.1.7 TRAINING AND ESH PROGRAM MANAGEMENT

The contractor shall ensure all support contractor personnel are trained to implement controls to mitigate the hazards that they may potentially be exposed to in the performance of work under this contract. This training shall incorporate applicable RMC's instructions, operations, and protocols.

6.1.8 FALL PROTECTION

For support contractor personnel working in areas where they may be exposed to fall hazards, the contractor shall have a Fall Protection Program that conforms to the applicable regulatory requirements, to include having a designated, qualified Fall Protection Competent Person. Support contractor personnel shall be trained and qualified to the contractor's Fall Protection Program, as required by specific area of support/duties and/or as determined by the contractor Fall Protection Competent Person. The contractor Fall Protection Competent Person shall review and verify the sufficiency of the Fall Protection Plan prior to support contractor personnel conducting work with fall protection hazards. (or alternatively, the adoption, provided in writing, of specific or all RMC's-approved Fall Protection Plans)

6.1.9 CONFINED SPACES

When support contractor personnel are working onboard vessels where their duties/tasks could require entrance to a confined space, the contractor shall ensure support contractor personnel have received general awareness confined space training. If support contractor personnel will enter any confined space onboard a vessel, the contractor shall possess and maintain (to include current calibration) the equipment necessary to perform atmosphere testing and ensure their Competent Person (CP) (formerly known as Shipyard Competent Person - SYCP) certifications are current in accordance with NAVSEA Standard Items (Reference 7.25) 009-07 and Reference 7.2. Likewise, support contractor personnel shall not enter any shore side confined space without the necessary equipment, training, and program as required by the applicable regulatory requirements. At no time shall support contractor personnel utilize a RMC's confined space certification or a Marine Chemist Certification obtained by COMPACTFLT or any other DoD command.

6.1.10 PERSONAL PROTECTIVE EQUIPMENT (PPE)

The contractor shall provide all required safety equipment, including personal protective equipment (PPE), for support contractor personnel to accomplish the tasks required in this PWS. Required PPE includes, but is not limited to: safety glasses/goggles/face shields, hearing protection (ear plugs and/or ear muffs), gloves, hard hats, safety boots, coveralls, flashlights and fall-protection harnesses, and respiratory protection when required by specific area of support and/or contractor's hazard analysis. Support contractor personnel shall not acquire or utilize any RMC's safety equipment including PPE. The contractor shall train all support contractor personnel on proper usage and hazard protection capabilities associated with each PPE item issued, as required by Reference 7.1.

6.1.11 HAZARDOUS MATERIAL (HAZMAT)

The contractor shall train all support contractor personnel that use and/or are exposed to hazardous materials on proper and safe usage. The training shall include Authorized User Lists (AULs) and Safety Data Sheets (SDSs) in accordance with References 7.26 and 7.1.

6.1.12 REGULATORY COMPLIANCE

The contractor shall comply with all applicable federal, state, and local laws, regulations, ordinances, and codes in their entirety. Any reference to a specific portion of a federal, state, or local law, regulation, ordinance, or code specified herein shall not be construed to mean that relief is provided from any other sections of the law, regulation, ordinance, or code.

6.1.13 OSHA TRAINING

Within **ninety (90) calendar days** of hire, all support contractor personnel providing direct support under this contract shall take/pass an OSHA Maritime Safety Course (10-hour course; formerly referenced as OSHA 7615).

6.2 The contractor shall, at a minimum, comply with the following Environmental Protection Agency (EPA) Regulations (which are available at <http://www.epa.gov/> or <http://www.gpo.gov/>): National Emission Standards for Hazardous Air Pollutants (NESHAP) for Shipbuilding and Ship Repair (40 CFR 63); Uniform National Discharge Standards for Vessels of the Armed Forces (40 CFR 1700) EPA Solid Waste Regulations and Standards (40 CFR Subchapter I); EPA Toxic Substance Control Act (40 CFR Subchapter R).

The contractor shall comply with Certified Unified Program Agency (CUPA) listed under San Diego, Title 6, Division 8, Chapter 9, Section 68.905.

The contractor shall comply with any other applicable Federal, State, and local safety, health, and environmental protection laws, codes, ordinances, and regulations in their entirety. Any reference to a specific portion of a Federal, State, or local law, code, ordinance, or regulation in this contract will not be construed to mean that relief is provided from any other sections of the law, code, ordinance, or regulation.

The contractor shall provide adequate protection of barge, personnel, and equipment when handling materials and while performing the work authorized by this contract.

The contractor shall ensure adequate and required safety notifications are given to contractor and government personnel, permits and notifications are properly posted in work areas, safety precautions and fire protection procedures are adhered to, and personal protective gear is worn by contractor personnel during all phases of work performance, including curing periods. Some examples of tasks which may require regulatory safety, health, and environmental procedures and precautions are: surface preparations, resurfacing, lamination, gluing, applying stains, finishes and coatings, welding and smooth finishing of metals and electrical work.

The contractor shall submit a legible copy of Safety Data Sheets (SDS) for all hazardous material that is procured by the contractor and intended for use aboard any barge. The SDS will be submitted to the COR or Government Barge Manager for written approval at least 2 working days prior to the planned date for the onboard storage or use of any hazardous material. The contractor shall assure that all material is removed from the barge daily or adequately and safely secured in a government authorized storage area during the work performance period.

The contractor shall not store combustible materials on barges. Work performed under this contract will be on barges docked or moored in a "No-Discharge Zone" as described in 40 CFR 1700 and OPNAVINST 5090.1 (current edition).

The contractor shall remove and dispose of all spent material, debris, sand, dust, metals, wood, gaseous, liquid and solid wastes, and all other industrial waste as work progresses and immediately upon completion of jobs to ensure a clean, safe, and healthy working environment.

The contractor shall also prevent those wastes from entering the air or surrounding waters in accordance with Federal, State and local air and environmental pollution laws, codes, ordinances and regulations. The Government does not anticipate requiring contractor personnel to handle, remove, or dispose of any asbestos during the performance of this contract. If contractor personnel suspect asbestos, contractor personnel will not proceed with work and the Contractor shall notify the COR or Government Barge Manager immediately for action.

The contractor shall, when required by Federal, State or local government, prepare required paperwork and forms; apply for, obtain and post applicable permits and licenses; and provide appropriate notification to Federal, State and local environmental protection agencies in compliance with the applicable laws, codes, ordinances, and regulations.

The contractor shall submit legible copies of permits obtained and notification(s) provided to any regulatory authority for work aboard the barge to the COMPACFLT Program Administrator, COR and/or regional TA Manager within two working days of date obtained or provided from or to the regulatory authority.

For operations at Naval Facilities or private contractor facilities, the contractor shall comply with all state and local regulations.

The contractor shall stop work immediately and notify the COMPACFLT Program Administrator, COR and/or regional TA Manager regarding work that has the potential to generate hazardous waste. In that event, the Government will identify the types and amounts of hazardous wastes. In the event the COR/ACOR expects there will be work that will generate hazardous waste the government will complete Form 007-001.

The contractor shall comply with the requirements of Commander, Navy Region Southwest Water Quality Program Storm Water Best Management Practices Policies and Procedures Manual Requirements for Working on Navy Piers, Wharves and Quay Wall Areas and NAVBASESANDIEGOINST 5450.80 Parts 244, 245 and 246 while performing work under this contract and during the execution of each modification.

All waste generated deemed non-hazardous shall be removed from the pier daily and will not be allowed to accumulate. Waste generated deemed as hazardous shall be removed from the pier within 14 days and/or no later than the last day of the assigned performance period.

The contractor shall submit all required permits to Code 106-B for all contractor-owned or rented equipment prior to start of work.

The contractor shall comply with permit conditions for all APCD permitted equipment while performing work under this contract and during the execution of each modification.

The contractor shall comply with Title 13 California Code of Regulations part 2450 thru 2465, Title 17 California Code of Regulations part 92200 and part 93116 thru 93116.5, and San Diego Air Pollution

Control District Rule 10, 11, 12.1, 50, 51.71, 67.17, 67.18, 67.21, 69.4.1 while performing work under this contract.

The analysis of any waste requiring the services of a testing laboratory shall be performed by a laboratory certified by the California Department of Public Health to be competent and equipped to conduct the specific type of analysis to be performed.

The contractor shall comply with California Hazardous Waste Control Law, Health and Safety Code, Chapter 6.5, and California Code of Regulations, Title 22, Division 4.5, Environmental Health Standards for the Management of Hazardous Waste.

The Contractor shall complete all blocks required to be filled in by the generator on the Uniform Hazardous Waste Manifest EPA Form 8700-22 and, if necessary, the Manifest Continuation Form EPA Form No. 8700-22A.

Include contract number on the manifest in block 14 prior to turning over the hazardous waste to the hauler.

Submit a copy of the completed and generator signed Hazardous Waste Manifest form to the Hazardous Waste Management Division, Code 106-B, no later than three (3) days after generator signature. Submit a copy of the signed treatment, storage, and disposal facility (TSDF) manifest. TSDF manifest must be received by the generator no later than thirty-five (35) days after the manifest date. Provide a written report to C106-B in the event that signed TSDF copies are not received thirty (30) days after the manifest date.

Trucks intended for hauling hazardous waste shall be state certified and licensed for transporting hazardous waste.

The contractor shall comply with NAVSEA Standard Items 009-40 for all contracts that may result in the use of a crane for the accomplishment of work.

7.0 APPLICABLE GENERAL REFERENCE/DOCUMENTS

Various U.S. Navy, military and industrial technical documents, to include specifications, standards, handbooks, and technical manuals will be required to perform the duties described within this Performance Work Statement (PWS). The contractor shall ensure that the latest available versions of all documents are being utilized by verifying against the appropriate database. The contractor shall comply with all documents listed below as mandatory and referenced under paragraph Performance Requirements.

When technical documents are required from an original equipment manufacturer (OEM), the contractor shall coordinate with the COR or requirements holder, in order to gain access to the specific documents, and shall ensure that all proprietary rights are observed. The contractor shall maintain an accurate accounting of all regulations, specifications, and relevant documentation utilized in the performance of work under this contract. The responsibility to obtain and maintain the most current versions of the references specified within this PWS are solely those of the contractor.

The contractor shall comply with all applicable federal, state, and local laws, regulations, ordinances, and codes, in their entirety. Any reference to a specific portion of a federal, state, or local law, regulation, ordinance, or code shall not be construed to mean relief is provided from any other sections of the law, regulation, ordinance, or code.

- 7.1 Occupational Safety and Health Administration (OSHA) Regulations, 29 CFR 1910
- 7.2 OSHA for Shipyard Employment (OSHA) Regulations, 29 CFR 1915
- 7.3 National Fire Protection Association (NFPA) Standards for current year
- 7.4 NFPA 51B, Standard for Fire Prevention
- 7.5 NFPA 306, Standard for Control of Gas Hazards on Vessels
- 7.6 NFPA 312, Standard for Fire Protection of Vessels
- 7.7 National Emission Standards for Hazardous Air Pollutants (NESHAP) for Shipbuilding and Ship Repair (40 CFR 63)
- 7.8 Uniform National Discharge Standards for Vessels of the Armed Forces (40 CFR 1700)
- 7.9 EPA Solid Waste Regulations and Standards (40 CFR Subchapter I)
- 7.10 EPA Toxic Substance Control Act (40 CFR Subchapter R)
- 7.11 No-Discharge Zone (40 CFR 1700)
- 7.12 OPNAVINST 5090.1 Environmental Readiness Program.
- 7.13 Original Equipment Manufacturer (OEM) Service Manuals
- 7.14 NSTM 3000 Naval ship Technical Manuals.
- 7.15 OPNAVINST 5100.19 Series Navy Safety and Occupational Health.
- 7.16 NAVSEAINST 5100.19 Series
- 7.17 Berthing and Messing Barge Maintenance Plan (B&MBMP) Vol. 1
- 7.18 OPNAVINST 4790.4 Maintenance and Material (3M) Manuals.
- 7.19 Joint Fleet Maintenance Manual (JFMM)
- 7.20 SWRMCINST 11240.3, POLICY AND PROCEDURES FOR MANAGEMENT, MONITORING, AND UTILIZATION OF VEHICLES/SLOW MOVING VEHICLES/MATERIAL HANDLING EQUIPMENT (MHE)/BICYCLES
- 7.21 NAVFAC PUBLICATION 300 (P-300), MANAGEMENT OF CIVIL ENGINEERING SUPPORT EQUIPMENT
- 7.22 NAVFAC PUBLICATION 307 (P-307)
- 7.23 COMUSFLTFORCOMINST 4790.3
- 7.24 29 CFR 1904, RECORDING AND REPORTING OCCUPATIONAL INJURIES AND ILLNESSES
- 7.25 NAVSEA STANDARD ITEMS 009-12; WELD, FABRICATE, AND INSPECT; ACCOMPLISH
- 7.26 SWRMCINST 5100.8, SWRMC SAFETY AND OCCUPATIONAL HEALTH PROGRAM
- 7.27 NAVSEA S9074-AQ-GIB-010/248, REQUIREMENTS FOR WELDING AND BRAZING PROCEDURE AND PERFORMANCE QUALIFICATION
- 7.28 NSTM Chapter 034 focuses on Service Craft
- 7.29 NAVSEAINST 9091.2 Crew Livability Standards for Industrial Availabilities
- 7.30 COMPACTFLTINST 4720.2
- 7.31 OPNAVINST 4700.7
- 7.32 S0400-AD-URM-010/TUM

8.0 QUALITY

This section describes the Quality Control components for this effort. The following sub-sections provide details of various considerations on this effort.

9.0 QUALITY MANAGEMENT SYSTEM (QMS)

The contractor shall obtain and maintain an approved ISO 9001:2015 Quality Management System (QMS), meeting the requirements of NAVSEA Standard Item 009-04 (Reference 2.9; Paragraphs 3.1 through 3.4) within sixty (60) calendar days of contract award. SWRMC Quality Assurance (QA) Department is the QMS approving authority. Note that the contractor may submit a QMS approved by

any NAVSEA RMC to SWRMC QA Department for verification, which will suffice to meet this requirement.

10. DELIVERABLES

The contractor shall provide deliverables as outlined below. Deliverables shall be specified by the government. Format and delivery schedule for deliverables shall be outlined in CDRLs and/or other means TBD.

Number	Name	Frequency	Quantity
A001	Performance and cost report	Monthly	As required
A002	Progress/Status Report	Weekly	As required
A003	Government Furnished Property Report	Monthly	As required
A004	Material Status Report	Weekly	As Required
A005	Meeting Agenda Report	Bi-Weekly	As Required