

ATTACHMENT J-1503010-06
 REQUIREMENTS FOR REFINISHING & REPAIR OF GYMNASIUM FLOORS

REPAIRS	1. The Contractor shall ensure existing bleachers on basketball court are in the fully retracted position exposing as much of floor as possible prior to sanding existing floor to raw wood.	a. The areas under the fully retracted bleacher shall not be required to be refinished. b. The newly refinished floor shall be blended into the area that are not under bleachers section. c. Contractor may use hand held sander and hand sanding to blend floor for smooth transition. d. Contractor shall ensure the sealer and finishing products do not interfere with the existing bleacher rollers.
	2. Contractor shall remove by sanding all layers of floor finish.	a. Contractor shall take all precautions to minimize the spreading of any dust particles created by this sanding. b. Contractor is responsible for removing and properly disposing of all sawdust and litter on a daily basis. c. Contractor shall if needed or desired, to cut off all air flow systems to gym flooring area.
	3. Contractor shall repair any split boards or seriously damaged areas of the wood surface.	a. To be repaired as needed.
	4. The gym flooring shall be sanded with a minimum of three cuts using coarse, medium, and fine sandpaper. The final sanding shall be performed with a screen and sanded and shall provide a smooth and even surface, free from scratches, drum stop marks, or gouges.	a. Either the first pass or the second pass of drum-type sander shall be at angle of forty-five (45) degrees to the grain, other passes of the drum-type sander shall be in the direction of the grain of strip flooring. b. Finished edges not reached by the sander shall be performed within hand-held sander or by hand sanding.
	5. Perform the final sanding at a time and in a manner that will permit immediate	a. Contractor shall ensure there is adequate ventilation and humidity

ATTACHMENT J-1503010-06
REQUIREMENTS FOR REFINISHING & REPAIR OF GYMNASIUM FLOORS

	application of the first seal coat as specified by sealer's manufacturer's specifications.	controls in the area to allow for proper drying. b. Finish flooring in accordance with the Commercial Grade Oil Base Polyurethane finish shall consist of two (2) sealer coats and two (2) finish coats.
	6. Contractor shall thoroughly clean floor surface prior to applying a liberal and uniform coat of penetrating sealer with the minimum coverage per manufactures instructions.	a. Contractor shall schedule proper drying time per manufacturer's instructions. b. Contractor shall use a clean lamb's wool screen back disk pad or as recommended by sealer's manufacturer's instructions. c. Buff with steel wool screen back disk pad or as recommended by sealers manufacturer's instructions.
	7. Contractor shall apply a second coat of sealer in same manner as the first coat and allow drying time to completely dry.	
	8. Vacuum and tack rag the floor in preparation for court layout.	
	9. Contractor shall re-apply per manufacturer's instructions all name, logos, basketball court with NCAA volleyball game lines (<u>if applicable</u>).	a. Contractor shall use oil base enamel paint that is designed and approved by Commercial Grade Oil Base Polyurethane. b. All game lines shall have distinct edges with no overlap and match existing lines. c. Contractor shall paint Marine Corps emblem in center court, emblem to match existing (<u>if applicable</u>). d. Contractor shall paint Boarder and nomenclature on boarder.
	10. Contractor shall apply two (2) coats of finish	a. Immediately before applying the first coat of finish, the court floor shall be thoroughly tack ragged giving particular attention to edges and corners.

ATTACHMENT J-1503010-06
REQUIREMENTS FOR REFINISHING & REPAIR OF GYMNASIUM FLOORS

		b. Apply an even first coat of finish in accordance with the manufacturer's instruction specifications. <u>ALLOW TO DRY COMPLETELY.</u> c. Dry time completed lightly abrade with steel wool or screen to break the surface tension for bonding with the next finish coat. d. Vacuum the whole gym floor, then double tack rag the floor. Apply a second coat of finish in accordance with the finish manufacturer's specifications. <u>DO NOT ABRADE</u> the final coat.
	11. Contractor shall install new three (3) inch by four (4) inch vented cove base per manufacturer's instructions.	a. Contractor shall miter all inside corners. b. Contractor shall use pre-molded outside corners.