

CUI

STATEMENT OF NEED

FOR

MATERIAL FOR C-17 PARTIAL LOAD DECK

PREPARED FOR

502d Contracting Squadron (CONS/JBKCA)

PREPARED BY

Air Education Training Command (AETC)

502d Trainer Development Squadron/Trainer Development (502d TDS/TD)

JBSA-RANDOLPH, Texas

DATE

23 April 2026, release v.2.0

CUI

CUI

1.0 Background

The 502d Trainer Development Squadron (TDS) on Joint Base San Antonio – Randolph, designs, develops, manufacturers, and maintains training devices and simulators for the entire Department of War (DoW) community. The 502 TDS performs the mechanical design, development, fabrication, and installation of complex training devices used by flying, fighting, air mobility, technical, and aeromedical training operations throughout the Air Education Training Command (AETC), United States Air Force (USAF), Department of Defense (DoD), and by partnered Allied Nations through Foreign Military Sales (FMS).

The 502 TDS is currently designing a C-17 Partial Load Deck Trainer which will be sized and configured for a Negatively Pressured Conex (NPC) to be permanently placed on the trainer cargo floor. The cargo floor will be configured for Aerial Delivery System (ADS) load of the NPC and will have guardrails around the perimeter. The C-17 Partial Load Deck Trainer will fulfill mission training requirements for the United States Air Force School of Aerospace Medicine (USAFSAM) for the simulated loading and unloading of patients in the NPC to support the training of the Infectious Diseases Air Transport Course standing up at C-STARS Omaha.

In support of this effort, the 502 TDS requires the procurement of metal material to manufacture the trainer.

2.0 Scope

The scope of this effort includes the procurement of metal material to manufacture the C-17 Load Deck Trainer.

3.0 Objectives

The purpose of this Statement of Need is to set forth the requirements to procure the materials for the C-17 Load Deck Trainer.

3.1. Tasks

The Contractor shall provide and deliver the following materials in support of this effort:

Line #	Qty	Item/Description	Width	Length	Weight, lb
1	1	APL61500 1/2" ALUMINUM PLATE 6061-T651	48 in	96 in	236.480
2	36	AST61212212250 2-1/2 X 2-1/2 X 1/4" 6061 SQUARE ALUM TUBE B8A	-	-	2,166.048
3	26	AST61212212250 2-1/2 X 2-1/2 X 1/4" 6061 SQUARE ALUM TUBE B8A	-	20 ft	1,303.640

CUI

CUI

Line #	Qty	Item/Description	Width	Length	Weight, lb
4	1	AAN613214 3 X 2 X 1/4" ALUMINUM ANGLE 6061 T6	-	25 ft	35.075
5	10	SSRO414 1/4" STAINLESS STEEL ROUND T- 304	-	12 ft	20.040
6	10	AFL615810 5/8 X 10 ALUM 6061-T6 FLAT BAR	-	12 ft	879.960
7	10	AFL61584 5/8" X 4" 6061-T6 FLAT ALUMINUM	-	12 ft	352.800
8	3	AFL61146 1/4 X 6" ALUMINUM FLAT 6061-T6	-	12 ft	63.504
9	3	AFL61121 1/2 X 1" ALUMINUM FLAT 6061-T6	-	12 ft	21.168
10	3	AFL611212* 1 X 2-1/2" ALUMINUM FLAT 6061	-	12 ft	105.840
11	5	AFL6112 1 X 2" ALUMINUM FLAT 6061-T6	-	12 ft	141.120
12	3	AFL611124 1-1/2 X 4" ALUMINUM FLAT 6061-T6	-	12	254.016
13	2	AFL6138312 3/8" X 3-1/2" ALUMINUM FLAT 6061- T6	-	12 ft	36.960
14	24	APL61250 1/4" ALUMINUM PLATE 6061-T651	60 in	144 in	5,328.00
15	3	SSFL414 1 X 4" STAINLESS STEEL FLAT 304	-	12 ft	489.960

CUI

CUI

Line #	Qty	Item/Description	Width	Length	Weight, lb
16	3	SSFL416 1 X 6" STAINLESS STEEL FLAT 304	-	12 ft	75.120
17	3	SSRO438 3/8" STAINLESS STEEL ROUND T-304	-	12 ft	13.536
18	15	APL61250 1/4" ALUMINUM PLATE 6061-T651	48 in	144 in	2,664.00
19	8	APL61375 3/8" ALUMINUM PLATE 6061-T651	48 in	144 in	2,127.360
20	1	APL61500 1/2" ALUMINUM PLATE 6061-T651	48 in	144 in	354.720
21	1	APL61750 3/4" ALUMINUM PLATE 6061-T651	48 in	96 in	354.240
22	1	APL611000 1" ALUMINUM PLATE 6061-T651	48 in	96 in	472.320
23	25	AAN612214 2 X 2 X 1/4" ALUMINUM ANGLE 6061-T6	-	25 ft	693.750
24	1	ACH614150 4" X 2" X .150 6061T6 CHANNEL ALUMINUM ASSOCIATION	-	25 ft	43.50
25	6	AIB613150AA 3" X 2-1/2" X .150 ALUMINUM ASSOC. I-BEAM 6061-T6	-	25 ft	304.500
26	4	AIB6185230AA 8" X 5" X.230 ALUMINUM I-BEAM ALUM. ASSOC. 6061-T6	-	25 ft	618.100
27	32	APL75250T7351	60 in	144 in	7,104.00

CUI

CUI

Line #	Qty	Item/Description	Width	Length	Weight, lb
		1/4" ALUMINUM PLATE 7075 - T7351			

4.0 Program Requirement

4.1. Material Ordering

The Contractor shall consider “Green” (energy efficient) materials and equipment first and foremost when ordering materials. The Sustainable Products Identification Form as required.

4.2. Delivery

The Contractor shall deliver any required components at the following location:

502D Trainer Development Squadron
 664 A Street West,
 NW Corner of Building #241,
 Joint Base San Antonio - Randolph, TX 78150-4515

In the presence of the designated Government official, the Contractor shall ensure that the materials are free of potential shipping damage. If the materials are found to be damaged upon delivery, the Contractor shall bear responsibility for return and re-procurement, as well as any additional charges resulting from damage.

4.3. Warranty

No warranty required as a part of this effort.

5.0 Operational Requirements

5.1. Security Requirements

5.1.1. Base Security

While at the 502 TDS Government location, the Contractor shall comply with the JBSA - Randolph Visitor Security procedures and policies, and provide appropriate visitor data, in addition to complying with all local, state, and Federal safety guidelines. Visitor procedures include the background check and verification of United States citizenship for all personnel who require access to the Government site. If Contractor personnel requiring access do not have United States citizenship, the Contractor shall provide a valid passport to coordinate base access with the Visitor Center.

- NOTE: Security Requirements and visitor policy information will be provided upon award.

5.1.2. Registration of Vehicles

CUI

CUI

All Contractor employees' vehicles used for the performance of this contract shall comply with all local, state, and federal regulations. Additionally, any pass shall be surrendered to Security Forces upon demand to positively identify a person's need to be on a federal installation.

The Contractor shall obtain a vehicle pass from the JBSA - Randolph Visitor Center for each vehicle that will be utilized on Government property for delivery. The Contractor shall provide a valid driver's license and proof of insurance along with any other additional documentation requirements to the JBSA - Randolph Visitor Center to obtain a vehicle pass.

6.0 Order Requirements Information

6.1. Delivery Period

Delivery Period is expected to be 45 days after award.

6.2. Government Furnished Property/Government Furnished Equipment (GFP/GFE)

The Government shall provide a forklift and man lift for Contractor use during the delivery effort as needed.

6.3. Contractor Employee Guidelines

The Contractor shall not employ persons on this task order if such employees are identified to the Contractor by the client representative as a potential threat to the health, safety, security, general well-being, or operational mission of the installation and its population.

7.0 SON Attachment and Appendix List

Attachment 1: Points of Contact

CUI

CUI

ATTACHMENT 1
POINTS OF CONTACT

3.1 Contracting Officer

Name:	Catherine Hardy
Organization:	502d Contracting Squadron
Email:	barbara.jewett.1@us.af.mil
Phone:	210-960-7728

3.2 502 TDS POC

Name:	Clint Harrison
Organization:	502 TDS
Email:	clinton.harrison.1@us.af.mil
Phone:	210-652-5152

CUI