

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE		PAGE 1 OF 7 PAGES		
2. AMENDMENT/MODIFICATION NUMBER 0002		3. EFFECTIVE DATE 05/06/2026		4. REQUISITION/PURCHASE REQUISITION NUMBER		5. PROJECT NUMBER (If applicable)	
6. ISSUED BY NPS SER EAST MABO 100 Alabama St., SW 1924 Building Atlanta GA 30303-8701				7. ADMINISTERED BY (If other than Item 6) CODE NPS SER EAST MABO 100 Alabama St., SW 1924 Building Atlanta GA 30303-8701			
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)				9A. AMENDMENT OF SOLICITATION NUMBER (X) 140P5126Q0021			
				9B. DATED (SEE ITEM 11) (X) 04/26/2026			
				10A. MODIFICATION OF CONTRACT/ORDER NUMBER			
				10B. DATED (SEE ITEM 13)			
CODE		FACILITY CODE					

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

See continuation page

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
		Edward Dingle	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

Previous edition unusable

CONTINUATION SHEET	REFERENCE NO. OF DOCUMENT BEING CONTINUED	PAGES
	140P5126Q0021/0002	PAGE 2 OF 7
NAME OF OFFEROR OR CONTRACTOR		

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	The purpose of this amendment is to provide response to Questions received in response to the solicitation. Questions and Answers are provided as attachment 0006. As-Builts are provided as attachment 0007. Drawings are provided as attachment 0008. Elevator Shaft Plans are provided as attachment 0009. Period of Performance: 05/18/2026 to 03/01/2027				

Mammoth Cave National Park

Provide Maintenance Repairs for Elevator

Cables and Painting of Structure

Solicitation #140P5126Q0021

Questions and Answers

Question 1. Will it be acceptable to use PPQ's from other agencies?

Answer: Yes, if they are recent, relevant, and in accordance with the terms and conditions of the solicitation.

Question 2. Can the Owner provide as-built drawings of the framework?

Answer: The available as-builts drawings are provided as attachment 0007 of this amendment. This is all the park has for this structure.

Question 3. Clarification of what is included in the "framework" as they have pictures of the motors and stands, ladders, platforms, etc. and curious what the actual limits of the cleaning and coating are?

Answer: All steel, permanent, non-moving structures in the elevator shaft are what is included in the scope to be clean and coated, including emergency ladder.

Question 4. Where will the staging area be located?

Answer: The staging and contractor parking area will be limited to behind the elevator building.

Question 5. Are the existing coatings hazardous? If so, will SSPC/AAMP QP-2 certification be required of the Contractor to disturb, handle, and dispose of the waste?

Answer: a. The existing coatings are non-hazardous. Lead abatement was completed in 2015. Original construction in the 1950's might have contained lead, but since then, multiple cleaning and coating projects have been completed without lead based products being used. The Contractor is responsible to conduct appropriate testing of their own and complying with the requirements of OSHA for the protection of its workers.

Question 6. Will SSPC/AAMP QP-1 certification be required for the coatings application on this project?

Answer: No, but the applicable SSPC sections are required to be adhered to, see below.

- C. The Society of Protective Coatings (SSPC)
1. SSPC-SP 1, Solvent Cleaning
 2. SSPC-SP 2, Hand Tool Cleaning
 3. SSPC-SP 3, Power Tool Cleaning
 4. SSPC-SP 6, Commercial Blast Cleaning
 5. SSPC-SP 7, Sweep Off Blast
 6. SSPC-SP 15, Commercial Grade Power Tool Cleaning
 7. SSPC-PA 2, Measurement of Dry Film Thickness with Magnetic Gages
 8. SSPC-VIS 1, Visual Standard for Abrasive Blast Cleaned Steel
 9. SSPC-VIS 3, Visual Standard for Power- and Hand-Tool Cleaned Steel
 10. Guide 6, Guide for Containing Debris Generated During Paint Removal Operations

Question 7. What is the ambient temperature throughout the elevator shaft? Does that stay constant or does it fluctuate with season or depth?

Answer: Approximately, 55 degrees Fahrenheit, +-5 degrees consistently.

Question 8. The safety requirements refer to personnel being trained in elevator shaft safety, is there a specific training certification?

Answer: No, the contractor is responsible for ensuring that employees are physically qualified to perform their assigned duties in a safe manner. This includes being able to climb the ladder(s) adjacent to the elevator structure from the bottom to the top of the elevator shaft, and to be able to walk from the bottom of the elevator to the Carmichael Entrance. The elevator shaft is a hard hat area. Barriers must be provided at the top of the elevator shaft that will prevent unauthorized people from entering the work area.

Question 9. Regarding the paint system for this project, are there approved products to meet the rust inhibitive primer and high-performance epoxy or that pending submittal approval?

- a. Yes, see below. The coating materials will be Noxyde as provided by “Rust-Oleum” or approved equal. Applicable ASTM requirements will need to be followed.**

Coat	Product	Dry Film Thickness (mils)
Primer	<u>Noxyde red</u> On all edges and corners Full coat on entire surface	20 mils wet
Finish	<u>Noxyde federal gray</u>	20 mils wet
Total Dry Thickness		20 mils

- A. American Society for Testing and Materials (ASTM)
1. ASTM D3359, Standard Test Method for Measuring Adhesion by Tape Test
 2. ASTM D4138, Standard Test Method for Measurement of Dry Paint Thickness of Protective Coating Systems by Destructive Means
 3. ASTM D4285, Standard Test Method for Indicating Oil or Water in Compressed Air
 4. ASTM D4414, Standard Practice for Measurement of Wet Film Thickness by Notch Gages
 5. ASTM D4417, Standard Test Methods for Field Measurement of Surface Profile of Blast Cleaned Steel
 6. ASTM D4541, Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers

- a. Is it noted in Item 12 – 2.1 Paint System that “noxyde primer and finish are to be applied” but these are not epoxy coatings, and instead a water based elastomeric coatings. So, we are curious which system governs?

Answer: See response to Question 9 above.

i. In discussions with Sherwin Williams given the structure and environment it is in, they have recommended (2) systems for approval to satisfy each system identified.

1. System #1 Primer – Sherwin Williams Macropoxy 646
2. System #1 Topcoat – Sherwin Williams Macropoxy 646
3. System #2 Primer – Sherwin Williams Macropoxy 646
4. System #2 Topcoat – Sherwin Williams Fast Clad HB

Answer: Please see table above in question #6. If these systems adhere to the requirements cited in Question #5, the submittal will be approved.

Question 10. Is a bid bond required for this project?

Answer: No.

Question 11. What are the allowable workdays and hours?

Answer: Mon-Fri, 7:00am to 6:00pm is the typical work hours, but due to the now emergency nature of this project, work on weekends, holidays, and nighttime can be approved via 24-hour verbal notice to the COR.

Question 12. Is the elevator currently operable?

Answer: The elevator is currently in-operable.

Question 13. Can the cable replacement be done post coatings application to ensure protection without masking?

Answer: No, the priority is to replace the cable first.

Question 14. Is the backside of the framing facing the elevator shaft insulation to be cleaned and painted?

Answer: Yes.

a. In order to access this area, due to the tight clearance, the panels may need to be removed and replaced. If required, please provide details on how they are affixed to the cave walls.



Answer: The contractor is only responsible for painting the exposed structures. These “panels” are an enclosure around the elevator and structure to guard against the water infiltration from the rock (sweating and occasional water courses), as well as rock fall protection. Behind the white panels is wire mesh netting, that can be seen from the other as-builts, and they are connected to the rock surface every 50-ft. They would be complicated to remove and replace for this project.

Question 15. Due to the stated complexity of this SOW, the environmental constraints and the sited SSPC standards required, will the USDA be verifying the Contractor AMPP Certifications required to responsibly perform this project?

Answer: USDA verification is not required.

Question 16. Are you going to require a licensed elevator tech to be on sight with the contactors during the entire project? To run the elevator manually for them, while the painting etc., is

going on in the elevator shaft?

Answer: Yes, TKE, or approved elevator technician, will need to be on-site for certain critical functions. Such as opening the doors, manually stopping the elevator at the bottom for upper-shaft work, and certification of elevator cables (if necessary).

Question 17. Who is required to attend progress meetings and/or what meetings are subcontractors required to attend throughout the project?

Answer: Prime Program Managers (s) and active site superintendent's and Quality Ccontrol (QC) managers.

Question 18. Is a licensed elevator technician required to be on site during the surface prep/painting/ shaft protection portion of the project? The entire project? Or only during their portion of the project?

Answer: The elevator technician would need to be onsite essentially every morning to open the doors (as they would have the key), and they would need to override the elevator functioning. The elevator remains at the top of the shaft, so it'll automatically return there. To have access to the upper part of the shaft, a technician would need to override that and keep it at the bottom.

Question 19. Pictured on page 18 of the SOW is a picture of the governor. Is the governor rope being replaced? - it is not hoisting rope and 13.2 states "all existing cables under controlled hoisting." While the governor cables are not hoist cables, they are safety cables - Should these be replaced as well?

Answer: Yes.

Question 20. Regarding the prevailing wage form, elevator mechanics/technicians aren't listed. Does this include them?

Answer: Yes.

Question 21. Is the stripe coat to be applied with the primer, topcoat, or both?

Answer: Park facilities and resource management are unclear what a stripe coat is, and do not believe it is necessary, unless "stripe coat" is known by another more common name