

PERFORMANCE OF WORK STATEMENT

CVD RECREATION AREA GROUNDS MAINTENANCE SERVICES

CESPN-ORM

REVISED: 1/22/2026

Part 1

GENERAL INFORMATION

1. **GENERAL:** This is a non-personal services contract to provide grounds maintenance services at Coyote Valley Dam (CVD) and Lake Mendocino. The Government shall not exercise any supervision or control over the contract service providers performing the services herein. Such contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government.
 - 1.1. Description of Services/Introduction: The contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary to perform grounds maintenance services as defined in this Performance Work Statement (PWS) except for those items specified as government furnished property and services. The contractor shall perform to the standards in this contract.
 - 1.2. Background: Lake Mendocino is a flood control reservoir in Northern California, with numerous day use areas, campgrounds and lake access areas managed by the U.S. Army Corps of Engineers. The public service areas at Lake Mendocino offer a wide variety of recreation facilities including boat launching ramps, campgrounds, picnic areas, and sand swimming beaches. Many routine maintenance items are contracted to the private sector. Vegetation management, refuse collection, grounds maintenance, and janitorial services are just a few of the activities that are performed by private contractors for the U.S. Army Corps of Engineers at Lake Mendocino.
 - 1.3. Objectives: To find a Contractor qualified to carry out the specifications of this Contract to provide for the safe and sanitary recreation experience of the visiting public at Coyote Valley Dam & Lake Mendocino.
 - 1.4. Scope: The Contractor shall provide all manpower, labor, equipment, materials/supplies, transportation, fuel, tools, supervision and other items and services necessary to provide ground maintenance services for the public recreation areas at Lake Mendocino, as described herein the PWS and elsewhere within the solicitation. Services also consist of attending annual pre-work conferences, meetings as necessary, and preparing worksheets and invoices. The Contractor is responsible for ensuring that all Contractor employees, Subcontractors and Subcontractor employees have a full knowledge of the scope of work for the contract. The Contractor shall perform to the standards in the contract.
 - 1.5. Contractor Requirements: This contract will be a BEST VALUE acquisition. Interested

Contractors shall have been in business for a minimum of two (2) years and provide evidence in its past performance of providing similar grounds maintenance services with their quote submittal.

- 1.6. Period of Performance: The period of performance shall be for one (1) Base Year and two (2) option years. The Period of Performance reads as follows:

Base Year	Date of award – April 30, 2027
Option Year I	May 1, 2027 – April 30, 2028
Option Year II	May 1, 2028 – April 30, 2029

1.7. Hours of Operation

- 1.7.1. PREFERRED SEQUENCE FOR WORK SCHEDULES: The Contracting Office Representative (COR) will provide the contractor with a preferred sequence or frequency schedule, of areas in which work is to be accomplished for each contractor-preformed service (a sample frequency schedule is located in the list of attachments). The contractor is then required to submit a work schedule for each service indicating the date and time for each service, listed by area or location. A schedule must be submitted to the COR within five (5) days after the preferred sequence has been issued. This work schedule shall then be updated each month, as required, and submitted to the COR at least seven (7) days before the effective date of that schedule. If no schedule change is requested, no schedule update will be required. **This schedule is extremely important** as it controls the times at which the quality assurance inspections are performed, ensuring that the said inspections are done only after the required service has been completed. Any variation or unforeseen change, such as being ahead or behind schedule, must be reported immediately by radio, telephone or in person to the COR or COR-designated field representative.

- 1.7.2. Normal Operating Hours: Normal duty hours at Lake Mendocino are from 7:30 AM to 4:30 PM, Monday through Friday. During the recreation season (1 MAY – 30 SEP), normal duty hours will be from 7:30 AM through 4:30 PM, Monday through Sunday, seven days a week, including federal holidays.

- 1.7.3. Routine Work: Routine inspection and maintenance work shall be accomplished during normal working hours, Monday through Sunday during the recreation season () and Monday through Friday during the non-recreation season (1 OCT – 30 APR).

1.7.3.1. Weekend Operations: For the purposes of this contract, 'weekend' shall be defined as Friday through Sunday, during the rec season (1 May – 30 Sept). Given that visitation peaks during weekends and most holiday weekends, it is essential to ensure services are maintain to the required standards.

1.7.3.2. Weekday Holidays: If, during the rec season (1 May – 30 Sept), a holiday falls on a weekday, that day will also be considered a “weekend” for the

purposes of this contract. Services required during these days shall be conducted in accordance with the agreed-upon schedule. A list of holidays is available in section 1.7.6.

1.7.3.2.1. Example: Should an observed holiday occur on a Monday, the services provided on that day will mirror those offered on a typical weekend day because we expect increased visitation.

1.7.4. Recreation Season and Visitation: The contractor shall recognize that during the designated recreation season (1 MAY – 30 SEP), certain areas of the project may experience increased visitation compared to others. This heightened activity will necessitate additional efforts to maintain cleanliness and ensure compliance with the standards outlined in the contract.

1.7.4.1.1. Transient Visitation: The Contractor shall be prepared for sanitation requirements that may fluctuate due to a large transient and unhoused population in Mendocino County. The Contractor is responsible for dynamically adjusting its cleaning schedules and resources to meet these non-standard cleaning demands, especially in high-traffic locations. The Contractor will promptly notify the Contracting Officer's Representative (COR) of any significant issues involving transient visitors. The Contractor and its personnel are not authorized or responsible for enforcing park rules, including those specified in 36 CFR.

1.7.5. Emergency Work: All emergency work shall be accomplished whenever required and shall be carried out to completion without interruption, notwithstanding normally scheduled working hours, weekends or holidays unless released by the COR. Response to emergency service calls during normal work hours shall not exceed one hour and response during non-work hours shall not exceed four (4) hours regardless of the time, day or night, weekends, or holidays. Response to urgent calls shall not exceed eight (8) working hours. Response for fire suppression services shall meet requirements of AR 420 90.

1.7.6. Recognized Holidays: Except during the recreation season, routine work shall not be scheduled on observed holidays. When a service is required less than three (3) times a week and the schedule for that work falls on a holiday, the work shall be accomplished on the day following or preceding the holiday. Written notices of which day the work will be conducted shall be submitted to the COR no later than seven (7) days prior to the day the work is to be performed. The federal holidays are as follows:

- (1) New Years Day (January 1st)
- (2) Martin L. King's Birthday (3rd Monday of Jan)
- (3) President's Day (3rd Monday of Feb.)
- (4) Memorial Day (last Monday of May)
- (5) Independence Day (4th July)
- (6) Labor Day (1st Monday of Sept)

- (7) Columbus Day (2nd Monday of Oct)
- (8) Veterans Day (11th Nov)
- (9) Thanksgiving Day (4th Thursday of Nov)
- (10) Christmas Day (25th Dec)

Note: When one of the above designated holidays falls on a Sunday, the following Monday will be observed as a legal holiday. When a legal holiday falls on a Saturday, the preceding Friday is observed as a Holiday.

- 1.8. Facility Closures: The contractor will not be reimbursed when the government facility is closed due to unforeseen circumstances such as, but not limited to, local or national emergencies, administrative closings, or similar Government directed facility closings. The Contractor must at all times maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons. When hiring personnel, the Contractor shall keep in mind that the stability and continuity of the workforce are essential to completing the duties listed within this PWS.

- 1.8.1. Park Closures: When an unforeseen park closure occurs on a regular scheduled day of work, the government will either:

- (A) Reschedule the work to be performed the following day or as soon as possible/ weather permitting, unless the following day is Saturday or Sunday and routine work is not scheduled for Saturday or Sunday.
- (B) Reschedule the work on a day that is mutually satisfactory
- (C) When mutually agreed, to forgo the work and reduce payment due to the contractor accordingly for the work not performed.

- 1.8.2. Alternative Schedule During High Water Years: During periods of high Lake water levels at Lake Mendocino, services may be reduced or restricted due to limited access. Certain parking areas may experience flooding, and the road to the Bushay area may become inaccessible by vehicle. The Contracting Officer's Representative (COR) will collaborate with the contractor to adjust the service schedule as necessary under these conditions. High water conditions typically occur between February and August, coinciding with our camping season. This alternative schedule permits the delay of camping services until access to the campground is restored. This schedule will apply exclusively to Inlet Road, Bushay Recreation Area, and Miti Campground. "Peak season" dates are adjusted for these areas. As directed by the Park Manager, the COR will inform the contractor if the alternative schedule is to be implemented. The alternative schedule will replace the normal schedule for the remainder of the option year. The COR and Park Manager will notify the contractor no later than May 1 regarding the schedule to be used. The contractor shall not receive payment for services not performed.

- 1.9. Place of Performance: The work to be performed under this contract will be performed at Coyote Valley Dam & Lake Mendocino in Ukiah, CA. Lake Mendocino is located on the east fork of the Russian River approximately five (5) miles north of Ukiah, California in the county of Mendocino. It was formed by the construction of Coyote Dam in the 1950s. The developed recreation areas comprise nearly 450 acres of the parks total 1,330 land acres. It is strongly encouraged that any interested contractor attend the site meeting before bidding on this contract.
- 1.10. Type of Contract: The government will award a Firm-Fixed Price Contract.
- 1.11. Physical Security: The contractor shall be responsible for safeguarding all government equipment, information and property provided for contractor use. At the close of each work period, government facilities, equipment, and materials shall be secured.
- 1.12. Post Award Conference/Periodic Progress Meetings: The Contractor agrees to attend any post award conference convened by the contracting activity or contract administration office in accordance with Federal Acquisition Regulation Subpart 42.5. The contracting officer, Contracting Officers Representative (COR), and other Government personnel, as appropriate, may meet periodically with the contractor to review the contractor's performance. At these meetings the contracting officer will apprise the contractor of how the government views the contractor's performance and the contractor will apprise the Government of problems, if any, being experienced. Appropriate action shall be taken to resolve outstanding issues. These meetings shall be at no additional cost to the government.
- 1.13. Contracting Officer Representative (COR): The (COR) will be identified by separate letter. The COR monitors all technical aspects of the contract and assists in contract administration. The COR is authorized to perform the following functions: assure that the Contractor performs the technical requirements of the contract: perform inspections necessary in connection with contract performance: maintain written and oral communications with the Contractor concerning technical aspects of the contract: issue written interpretations of technical requirements, including Government drawings, designs, specifications: monitor Contractor's performance and notifies both the Contracting Officer and Contractor of any deficiencies; coordinate availability of government furnished property, and provide site entry of Contractor personnel. A letter of designation issued to the COR, a copy of which is sent to the Contractor, states the responsibilities and limitations of the COR, especially with regard to changes in cost or price, estimates or changes in delivery dates. The COR is not authorized to change any of the terms and conditions of the resulting order.
- 1.14. Key Personnel: The following personnel are considered key personnel by the government: Contract Manager and Alternate Contract Manager. The contractor shall provide a contract manager who shall be responsible for the performance of the work. The name of this person and an alternate who shall act for the contractor when the manager is absent shall be designated in writing to the contracting officer. The contract manager or alternate shall have full authority to act for the contractor on all contract matters relating to daily operation of this contract. The contract manager or alternate shall be available between

8:00 am – 5:00 pm Monday thru Friday except Federal holidays or when the government facility is closed for administrative reasons.

- 1.15. Identification of Contractor Employees and Subcontractor Employees: The contractor shall furnish their employees, other than office and clerical personnel, uniforms (coveralls or shirts), with a company identification patch on the breast pocket or on the left sleeve at the top of the arm, within 30 days after notice of the award of the contract. (See EM 385-1-1 for restrictions on clothing). All contractor personnel attending meetings, answering telephones, and working in other situations where their contractor status is not obvious to third parties are required to identify themselves as such to avoid creating an impression in the minds of members of the public that they are Government officials. They must also ensure that all documents or reports produced by contractors are suitably marked as contractor products or that contractor participation is appropriately disclosed
- 1.16. Accident Prevention Plan: An accident prevention plan is a safety and health policy and program document that is contract specific. The accident prevention plan shall comply with the requirements set forth in the Abbreviated Accident Prevention Plan in the USACE EM 385-1-1 in Appendix A.
- 1.17. Documents and Correspondence: After award, all documents and related correspondence shall be routed through the COR located at the Lake Mendocino Project Office.

1.18. **Payment**

Payment will be made monthly in accordance with Prompt Payment. Invoices shall be submitted no later than the 7th of each month. The Contractor shall submit a monthly invoice for the work completed during the billing period. The invoice shall include all scheduled services and any supplementary services completed during the billing period, itemized in congruence with the respective contracting line items (CLINs). Each invoice should also include the following information: the contractor name exactly as it appears on the awarded contract documents (no abbreviations), the unique awarded contract number, service description for line items, unit prices, quantity, invoice total and an invoice date. Invoices shall be typed/computer generated, legible, and accurate. Under the terms of this contract, invoices are to be submitted monthly to the COR.

1.19. Expected COR:

Kevin Haney
1160 Lake Mendocino Drive
Ukiah, CA 95482
Telephone: 707-467-4234
Email: kevin.j.haney@usace.army.mil

- 1.20. (See section 1.5 for invoice payment)

1.21. Contractor Personnel

- 1.21.1. Minimum Manpower Requirement: The Contractor shall maintain a sufficient number of staff/employees to perform the required services. In the event the Contractor is unable to perform contract duties, the Government reserves the right to terminate the contract.
- 1.21.2. Clothing: Contractor personnel shall present a neat appearance and be fully clothed at all times while performing services ordered under the contract. "Fully clothed" shall be deemed to mean that a sleeved shirt (or T-shirt), trousers, and shoes shall be worn at all times; except that this requirement shall not be construed to replace or eliminate the necessity for wearing appropriate protective clothing or devices as may be required for the safe performance of services or for the application of various approved chemicals. The Contractor shall provide their own attire. Clothing shall not contain commercial advertising, with the exception of the Contractor's business information.
- 1.21.3. Conduct: Contractor personnel shall utilize tact, diplomacy, and courtesy at all times during contact with the public and with Government personnel. The Contracting Officer's Representative reserves the right to disapprove any individual whom he/she considers to be incompetent to perform the work required. Such disapproval will be given to the Contractor by written notice. Any such decision is final. Any illegal or criminal activity on the part of the Contractor or staff, employees, or other personnel may result in termination of the contract. In order to assure the required services be performed at an acceptable level, the Contractor shall designate in writing a supervisor and/or foreman, who shall serve as a contact for matters involving quality, performance, or nonperformance of required services. The Government reserves the right to discuss matters with any Contractor employee on-site and currently employed by the Contractor.
- 1.21.4. Personal Safety Equipment: When engaged in work that requires other protection, employees shall be required to wear the proper protective apparel in accordance with EM 385 1-1:
https://www.publications.usace.army.mil/Portals/76/Publications/EngineerManuals/EM_385-1-1.pdf
- 1.21.5. Pre-screen candidates using E-Verify Program: The Contractor must pre-screen Candidates using the E-verify Program website (<http://www.uscis.gov/e-verify>) to meet the established employment eligibility requirements. The Contractor must ensure that the Candidate has two (2) valid forms of Government issued identification prior to enrollment to ensure the correct information is entered into the E-verify system.
- 1.21.6. Smoking Policy: Smoking is not allowed in any Government buildings, including shower buildings, comfort stations, storage areas, etc. Smoking is not allowed by the

Contractor while in direct contact with the public.

- 1.21.7. Firearms and Weapons: The Contractor shall not possess, during the performance of this contract, any item, including firearms, which could be used as a weapon. Title 36 regulates firearms on Federal property
- 1.22. Equipment Breakdown: Equipment breakdown shall not relieve the Contractor of the responsibility of performing the work as specified. It shall be the responsibility of the Contractor to assure that he/she/they has, or can obtain on short notice, sufficient backup equipment to continue the services as specified without interruption in the event of mechanical failure of primary equipment.
- 1.23. Safety and Security: Appropriate measures shall be taken to protect the general public from accidental injury. All services shall be performed in accordance with applicable safety requirements set forth by OSHA and by USACE Manual EM-385-1-1, "Safety and Health Requirements Manual" and supplements thereto (copies are available from the Project Office). ANY EQUIPMENT OR MATERIALS NOT IN CONFORMITY WITH THE SAFETY MANUAL SHALL BE REMOVED FROM GOVERNMENT PROPERTY IMMEDIATELY. The Contractor will be expected to take a vital interest in safety, hazard, and educate their employees to work and plan their work safely. Proper driving techniques and defensive driving will be practiced to prevent vehicle accidents and property damage. In order to provide safety controls for protection to the life and health of employees and other persons; for prevention of damage to property, materials, supplies and equipment; and for avoidance of work interruptions in the performance of this contract, the Contractor shall comply with all pertinent provisions of the Federal, State, and local regulations and shall take or cause to be taken such additional measures as the Contracting Officer may determine to be reasonable and necessary for the purpose. Any injury, property damage equipment malfunction or safety hazard observed by the Contractor shall be immediately reported to the COR and project personnel. The Contractor shall open and close gates within the contracted boundary areas. The Contractor shall securely lock any gate that is opened by him/her, upon completion of the required work. The Contractor shall safeguard all Government property
- 1.24. Controlled Areas: Security gates, storage yards and office compounds shall remain locked except when authorized employees are in the immediate area. All storage buildings, storage rooms, equipment rooms, pipe chases, and park buildings shall remain locked except when being cleaned. Stricter measures may be implemented by the Park Manager during periods of heightened security
- 1.25. Keys: Government-furnished keys may be provided to the Contractor. The Contractor shall establish and implement methods of making sure all keys issued by the Government to the Contractor for the Contractor's use are not lost or misplaced and are not used by unauthorized persons. The Contractor shall immediately report to the Contracting Officer or the COR any occurrences of loss, unauthorized use, or unauthorized duplication of keys. In the event keys, other than master keys, are lost or

duplicated, the Contractor may be required upon written direction of the Contracting Officer, to re-key or replace the affected lock or locks without cost to the Government. The Contractor shall safeguard keys issued to them to perform the services required by this contract. All keys shall be returned to the Government upon request and/or completion of the contract. Failure to return keys can result in withholding of payment.

- 1.26. Allowable Personnel: Only the Contractor, Contractor's employees, or authorized subcontractors are permitted to be in public service areas while performing work for the contract. Friends and family of the contractor, contractor's employees, or authorized subcontractors are not permitted to accompany workers in the performance of their duties, unless said individuals are also a contractor employee or authorized subcontractor employee.
- 1.27. Public Access: The Contractor shall not allow members of the public to enter buildings, compounds or parking areas when a USACE employees are not present. The Contractor shall not allow the public access to the Wildlife Management Area, Marina Area, Winery Point Access Road, or any other area closed to the public that requires access through a locked gate at any time.
- 1.28. Training: All contractor employees requiring access to Army installations, facilities, controlled access areas, or require network access, shall complete AT Level I awareness training within 30 calendar days after contract start date or effective date of incorporation of this requirement into the contract, whichever is applicable. Upon request, the contractor shall submit certificates of completion for each affected contractor employee and subcontractor employee, to the COR or to the contracting officer (if a COR is not assigned), within 5 calendar days after completion of training by all employees and subcontractor personnel. AT Level I awareness training is available at the following website: <http://jko.jten.mil/courses/at11/launch.html> or it can be provided by the RA ATO in presentation form which will be documented via memorandum.
- 1.29. Accident and Damage Reports: The contractor shall comply with OSHA and other regulatory requirements for records keeping and reporting of all accidents resulting in death, trauma, occupational disease or environmental damage. The contractor shall provide a verbal report to the COR within one (1) hour of occurrence and a written follow up report within two (2) working days of occurrence in the matter and on the forms prescribed by the KO whenever an accident involving personal injury occurs. In all instances where government property and/or equipment are damaged by contractor employees, a full written report of the facts and extent of such damage shall be submitted to the CO within 24 hours of the occurrence. A fire report shall be completed on DA Form 3985 or DD Form 2324 1 and submitted to the KO within 10 working days of the fire.
- 1.30. Personnel Security: All contractors and associated employees shall comply with applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative). The contractor shall also provide all information required for background checks to meet installation/facility access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personal identity verification requirements (FAR clause 52.204-9, Personal Identity Verification of Contractor Personnel) as directed by DOD, HQDA and/or local policy. In addition to the changes otherwise authorized by the

changes clause of this contract, should the Force Protection Condition (FPCON) at any installation or facility change, the Government may require changes in contractor security matters or processes. Contractor and all associated employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05 / AR 190-13), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative, as NCIC and TSDB are available), or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations. The contractor and all associated sub-contractors shall receive a brief/training (provided by the RA) on the local suspicious activity reporting program. This locally developed training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the project manager, security representative or law enforcement entity. This training shall be completed within 30 calendar days of contract award and within 30 calendar days of new employees commencing performance with the results reported to the COR NLT 5 calendar days after the completion of the training.

- 1.31. Communication: The Contractor shall furnish a local telephone number (within Mendocino County) where the Contractor or their representative can be contacted 24 hours a day, 7 days a week, throughout the contract period for special work and or discussion of any contractual matters. Phone message recorders are an acceptable point of contact as long as the response to special work is initiated within two (2) hours of the time of the message. The Government shall not be expected to call a series of phone numbers to locate the contractor or designated representative. Once the USACE representative has notified this contact, the Contractor will be considered official notified when called for special service or other work.
- 1.32. Quality Control (Contractor's Responsibility): The contractor shall develop and maintain an effective quality control program to ensure services are performed in accordance with this PWS. The contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The contractor's quality control program is the means by which they assure themselves that the work complies with the requirement of the contract. Contractor shall provide a quality control plan (QC) within 30 days after contract award, one copy of a comprehensive written QC shall be submitted to the contracting office (KO) and contracting office representative (COR) within five (5) working days when changes are made thereafter. After acceptance of the quality control plan, the contractor shall receive the contracting officer's acceptance in writing of any proposed change to their QC system.
 - 1.32.1. The Contractor shall designate, in writing, a supervisor and/or foreman who shall serve as a contact for matters involving quality, performance or non-performance of the required work. The supervisor and/or foreman shall have the authority to correct non-performance. The Contracting Officer may disapprove any individual whom he considers to be incompetent to perform the work required. Such disapproval will be

given to the Contractor by written notice, and the Contracting Officer's decision shall represent a final decision.

1.33. Quality Control (Government's Responsibility)

1.33.1. Quality Assurance: The government shall evaluate the contractor's performance under this contract in accordance with the Quality Assurance Surveillance Plan (QASP). This plan is primarily focused on what the Government must do to ensure that the contractor has performed in accordance with the performance standards. It defines how the performance standards will be applied, the frequency of surveillance, and the minimum acceptable defect rate(s).

1.34. Defective Facilities: Damaged defective and/or inoperative facilities shall be reported to the Park Manager or COR as soon as possible, but no later than 24 hours after discovery. The Contractor shall complete a repair work order (provided by USACE) identifying the necessary repairs. The decision to close a facility will be made by the Park Manager or COR.

1.35. Environmental Controls

1.35.1. Compliance with Laws and Regulations: The Contractor shall be knowledgeable of, and shall comply with, all applicable Federal, State, and Local laws, environmental requirements, and instructions. The Contractor shall ensure policies and procedures are established that protect the health and safety of employees and the community to minimize or eliminate the risk of environmental pollution.

1.35.2. Hazardous Materials: The Contractor is responsible for advising his/her employees of all environmentally hazardous material handling and is also required to provide to the COR the Safety Data Sheets (SDS) for all materials used by the Contractor in accordance with Federal and State laws and/or regulations.

1.35.3. Notification of Environmental Spills: If the Contractor or employee(s) of the Contractor spills or releases any substance into the environment, the Contractor shall immediately report the incident in accordance with local procedures and shall also notify the Project Manager and COR, or in his/her absence the Contracting Officer (KO). The Contractor shall be liable for containment and environmental cleanup of the spill or release of such substance(s).

1.35.4. Fire Prevention: The contractor and their employees shall be cognizant of, and shall observe, all requirements for handling and storage of combustible supplies and materials, daily disposal of combustible waste, trash, etc., in accordance the National Fire Code and National Board of Fire Underwriters. The contractor shall familiarize him/herself and employees with methods of turning in a fire alarm. The contractor is also responsible for exercising care when working in wooded areas to prevent forest or brush fires.

1.35.4.1. Fire Prevention Plan: The fire plan serves as a guide for prevention and suppression of building fires and forest/brush fires at USACE recreation areas, flood control projects, dam and yards. The plan provides for training of personnel, preventive measures to reduce incidents of fire, procedures in case of

a fire and provisions for necessary equipment and tools for prompt suppression activities.

1.36. **Meeting and Contractor Submittals**

1.36.1. Pre-Performance Meeting: At least one week prior to the pre-work meeting, the Contractor shall submit to the COR all information required under this contract. If the contract is awarded less than 30 days prior to the contract start date, required pre-work meeting submittals will be furnished on a schedule mutually agreed upon by the COR and the Contractor. For the remainder of the contract during the Base Year, and any subsequent Option Year exercised by the Government, the Contractor shall be responsible for producing complete, competent, properly coordinated, and thoroughly checked documents within agreed upon schedules.

1.36.2. Customer Care Meeting: All Contractor employees shall attend a training session about serving the public prior to working at the park. The training session will be held one week prior to the start of services. If the contract is awarded less than seven (7) days prior to the start date, the meeting will be held as soon as possible. The date of the meeting will be mutually agreed upon by the COR and Contractor.

1.36.3. Contractor Submittals Prior to Pre-Performance Meeting

1.36.3.1. Certificate of Insurance

1.36.3.2. A typed list of names, phone numbers and addresses of all persons performing services prior to beginning work. The list shall include a copy of the employees' valid vehicle driver's license. This list shall be maintained during the entire contract period.

1.36.3.3. Name of Supervisor and Alternate Supervisor

1.36.3.4. Safety Plan: The Contractor shall formulate and furnish to the Park Manager and COR in writing a comprehensive program to implement the general policies and procedures for safe operation and maintenance in accordance with applicable provision of OSHA and EM 385-1-1, U.S. Army Corps of Engineers Safety and Health Requirements Manual. The program shall include provisions for equipment maintenance, employee responsibilities for working safely and training verification of contract employees. A current version of the EM 385-1-1 can be located at <https://www.publications.usace.army.mil/usace-publications/engineer-manuals/>

1.36.3.5. Safety Hazard Analysis

1.36.3.6. Quality Control Inspection Plan

1.36.3.7. Uniform Plan

1.36.3.8. Material Safety Data Sheets for each chemical product used by the contractor

1.36.3.9. Composition of paper products used

1.37. Monthly Contract Submittals: Required monthly submittals shall be submitted by the 6th business day of each month. The Government reserves the right, if deemed necessary and requested in writing by the KO or COR, to increase the frequency of

monthly submittals.

- 1.37.1.1. Safety Exposure Report: The Contractor shall maintain records of the number of person-hours worked at Lake Mendocino each month. Using these records the Contractor will complete the Safety Exposure Report (SPD FORM 94) which is furnished by the Government
 - 1.37.1.2. Quality Control Inspection Plan
 - 1.37.1.3. Two copies of the monthly, computer generated invoice
 - 1.37.1.4. Any deviation from the set schedule
- 1.38. Invoice Submittals: Invoices for payment shall be submitted in duplicate upon completion of task as outlined in the pricing/payment schedule. Invoices shall include all necessary information, including contract number and any necessary supporting documentation submitted to:
- ATTN: Poppy Burkhead
U.S. Army Corps of Engineers: Lake Mendocino
1160 Mendocino Drive
Ukiah, CA 95482
- 1.38.1.1. Project Service Area (PSA) Delineation: The invoice shall be submitted to the COR with the delineations made by PSA so that the COR may see how the line items are divided throughout the year. A sample invoice shall be provided at the pre-performance meeting.
- 1.39. Site Meeting: Prior to submitting a bid, interested parties are strongly encouraged to attend a site meeting. This meeting allows interested bidders to become familiar with the layout and geographical location of the facilities, their proximity to one another and the current conditions of the facilities. The site meeting will be decided upon by the Operations Project Manager (OPM) and COR of the Contract.
- 1.40. Lost and Found: The Contractor shall report to the Park Manager or a Park Ranger all personal articles found by the contractor or their employees to be processed/disposed of as per Title 36, Chapter III, Part 327.16. Found articles shall be turned in the same day as found.
- 1.41. Coordination with Other Contractors: The Government may undertake or award other contracts for additional work. The Contractor shall fully cooperate with such contractors and government employees and carefully fit the contract work to such additional work as may be directed by the COR. The Contractor shall not commit nor permit any act which will interfere with the performance of work by any other contractor or by government employees.
- 1.42. Unauthorized Work: The Contractor is advised that any work performed at the direction of unauthorized personnel will not be credited as work accomplished under this contract.
- 1.43. Award of Other Contracts: The services provided under this contract shall be independent of all services provided under other contracts at this project or any other project for which the contractor may receive award.

PART 2

DEFINITIONS & ACRONYMS

2. DEFINITIONS AND ACRONYMS:

2.1. General Definitions

- 2.1.1. **CONTRACTOR.** A supplier or vendor awarded a contract to provide specific supplies or services to the government. The term used in this contract refers to the prime.
- 2.1.2. **CONTRACTING OFFICER.** A person with authority to enter into, administer, and/or terminate contracts, and make related determinations and findings on behalf of the government. Note: The only individual who can legally bind the government.
- 2.1.3. **CONTRACTING OFFICER'S REPRESENTATIVE (COR).** An employee of the U.S. Government appointed by the contracting officer to administer the contract. Such appointment shall be in writing and shall state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.
- 2.1.4. **DEFECTIVE SERVICE.** A service output that does not meet the standard of performance associated with the Performance Work Statement.
- 2.1.5. **DELIVERABLE.** Anything that can be physically delivered but may include non-manufactured things such as meeting minutes or reports.
- 2.1.6. **DISCREPANCY REPORT (DR).** A written record of unsatisfactory performance by the contractor as observed by the Quality Assurance Inspector, issued to the contractor when the number of rejects exceeds the acceptable quality level
- 2.1.7. **PHYSICAL SECURITY.** Actions that prevent the loss or damage of Government property.
- 2.1.8. **QUALITY ASSURANCE.** The government procedures to verify that services being performed by the Contractor are performed according to acceptable standards.
- 2.1.9. **QUALITY ASSURANCE SURVEILLANCE PLAN (QASP).** An organized written document specifying the surveillance methodology to be used for surveillance of contractor performance.
- 2.1.10. **QUALITY CONTROL.** All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.
- 2.1.11. **SUBCONTRACTOR.** One that enters into a contract with a prime contractor. The Government does not have privity of contract with the subcontractor.
- 2.1.12. **WORK DAY.** The number of hours per day the Contractor provides services in accordance with the contract.

- 2.1.13. WORK WEEK. Monday through Friday, unless specified otherwise.
- 2.1.14. RECREATION SEASON: 1 May – 30 September
- 2.1.15. NON-RECREATION SEASON: 1 October – 30 April
- 2.1.16. HIGH WATER, REC SEASON: 1 Aug – Dec 31 (Bushay Recreation Area only)
- 2.1.17. TRANSIENT VISITOR: Individuals who lack a permanent residence and may move from place to place, often staying temporarily in public spaces or shelters.
- 2.2. SITE-SPECIFIC TERMS AND DEFINITIONS: For this contract the following terms shall related as follows:
 - 2.2.1. BUSHAY CAMPGROUND. Campground located on the northeast end of the project. Its area encompasses the project's eastern boundary line to the water's edge, and from the ranger's station to the south fire gate. It contains an amphitheater, a dump station, restrooms, water points, and approximately 180 campsites. Out of the 180 sites, 2 areas within the Bushay campground are designated for group camping. This is a class A campground.
 - 2.2.2. CHEKAKA CAMPGROUND (Closed). This campground was permanently closed in 2011. As of 2025 this area is currently being redeveloped to have walking trails, a playground and picnic area. This is a legacy name for the area. This area is located west of the coyote valley dam parking lot, and encompasses the area between Kaweyo Horse Area and Coyote Dam day use, from the road to the bluff.
 - 2.2.3. COYOTE VALLEY DAM RECREATION AREA. The day use area located just north of the entrance to Coyote Dam to the restroom at the south end of the dam. It contains shelters, a weather station, benches, restroom, dam road and a parking lot. Includes the former Chekaka Campground listed in section 2.2.2
 - 2.2.4. INLET ROAD. Day use area located from the Hwy 20 exit to the Bushay ranger station and from the project boundary line to the water's edge. The day use area contains picnic units, portable restrooms, and pullouts for parking.
 - 2.2.5. JOE RILEY DAY USE AREA. Day use area located on the south end of the project just north of the South Boat Ramp and the Chekaka Campground, extending from the western hillside to the water's edge (*Note- the shoreline area of the Joe Riley Day Use area is often called 'Jet Ski Beach'*). Joe Riley contains picnic units, a parking lot, a restroom, water points, and a playground.
 - 2.2.6. KYEN CAMPGROUND. Campground located on the north end of the project from the northern boundary line to the water's edge, and from the north boat ramp to the Pomo Day Use area. Kyen contains an amphitheater, a dump station, restrooms, water points, and approximately 100 campsites. Marina Drive runs east and west directly through the campground. This is a class A campground
 - 2.2.7. MESA DAY USE AREA. Day use area located within the Bushay Campground. The Mesa's eastern boundary is at the Bushay campground fence line and extends down to the water's edge. It contains single and group picnic shelters, a restroom, public water spigots, a playground, and a footpath down to the water.
 - 2.2.8. MITI CAMPGROUND. This boat-in campground located on the eastern shore of the lake. Miti encompasses the area 200 ft east of the restrooms to the water's edge. It contains vault restrooms and about 17 campsites. This is a class E campground.

- 2.2.9. **NORTH BOAT RAMP.** Is located on the north end of the project and encompasses the area from the old marina to the Oak Grove day use area and from the northern hillside to the water's edge. The North boat ramp contains a lower and upper parking lot, a restroom, water points, as well as a courtesy dock for launching purposes. Marina drive goes directly through the upper parking area.
- 2.2.10. **NORTH DISC GOLF COURSE.** Is located on the north end of the project and encompasses the area on the north side of Marina Drive from the west side of the Kyen campground to the west boundary of the project and from the northern hillside south to Marina Drive.
- 2.2.11. **OAK GROVE DAY USE AREA.** Day use area located on the north end of the project in between the North Boat Ramp and the Kyen campground. It also encompasses the area including Marina drive to the water's edge. Oak Grove contains picnic units, a restroom, a parking lot, water points and a footpath.
- 2.2.12. **OVERLOOK DAY USE AREA.** Day use area located off of Lake Mendocino drive and encompasses the area from the western boundary line to the Joe Riley Day Use area. The Overlook contains a restroom, picnic units, water points, a parking lot, and a disc golf course. Lake Ridge road runs directly through this day use area.
- 2.2.13. **PARK HEADQUARTERS.** Is the offices and outbuildings located on Lake Mendocino Drive. It contains a parking lot and is surrounded by a chain link fence.
- 2.2.14. **POMO DAY USE AREA.** Day use area that is on the north side of the project. It encompasses the area from the western boundary line to the water's edge and from Marina drive from the north to the Angel's Camp access gate. It contains three delineated areas named Pomo A, Pomo B and Pomo C. The Pomo's contain a swim beach, playground, picnic units, parking lots, restrooms, footpaths, water points, a dog beach, and the Pomo Cultural Center.
- 2.2.15. **PROJECT.** Referring to the Lake Mendocino area and the related lands, waters and facilities.
- 2.2.16. **REFUSE RECEPTACLES.** Any receptacle used for disposal of trash. This also includes those receptacles that are intended solely for the disposal of animal waste. This excludes any large capacity dumpsters.
- 2.2.17. **SOUTH BOAT RAMP.** Is on the south end of the project and encompasses the area from Chekaka campground to the water's edge. Lake Mendocino Drive runs directly through the area. It contains a parking lot, water points, a restroom, and a courtesy dock.
- 2.2.18. **SOUTH DISC GOLF COURSE.** Is on the south end of the project and is situated to the west of the Overlook Day use area and to the north of Lake Mendocino Drive with Lake Ridge Road passing through the middle of the course.
- 2.2.19. **ANGELS CAMP.** Is an open grass area south of Pomo-C between the road and the lake. This area has picnic tables, a fire ring, and water. This area is currently unused.
- 2.2.20. **KAWEYO HORSE STAGING AREA.** This is a dirt parking lot west of the former Chekaka Campground until the end of the bluff. This area has facilities for horse trailers, including water and hitching poles.

2.2.21. EASTSIDE/KAWEYO TRUCK ROAD. This unimproved dirt road that runs along the entire length of the east side of the Lake, from Bushay Campground to the Deerwood Trailhead. This is the only road to access Miti Campground. This road will flood in multiple places during high water years, and cannot be used during the rainy season.

2.2.22. DEERWOOD TRAILHEAD. This is an unimproved trailhead in the southeast corner of the lake. This area encompasses the road, parking pads immediate adjacent to the road, from the road to the lake's boundary fence line.

2.3. ACRONYMS:

ACOR	Alternate Contracting Officer's Representative
AFARS	Army Federal Acquisition Regulation Supplement
AR	Army Regulation
CCE	Contracting Center of Excellence
CFR	Code of Federal Regulations
CONUS	Continental United States (excludes Alaska and Hawaii)
COR	Contracting Officer Representative
COTR	Contracting Officer's Technical Representative
COTS	Commercial-Off-the-Shelf
DA	Department of the Army
DD250	Department of Defense Form 250 (Receiving Report)
DD254	Department of Defense Contract Security Requirement List
DFARS	Defense Federal Acquisition Regulation Supplement
DMDC	Defense Manpower Data Center
DOD	Department of Defense
FAR	Federal Acquisition Regulation
KO	Contracting Officer
OCI	Organizational Conflict of Interest
OCONUS	Outside Continental United States (includes Alaska and Hawaii)
ODC	Other Direct Costs

PIPO	Phase In/Phase Out
POC	Point of Contact
PRS	Performance Requirements Summary
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Program
TE	Technical Exhibit

PART 3

GOVERNMENT FURNISHED PROPERTY, EQUIPMENT, AND SERVICES

3. Equipment Storage:

- 3.1. Government Furnished Supplies and Materials: The Government will not furnish any supplies or materials under this contract, other than water for cleaning purposes, and keys for contractor personnel for work within the scope of this contract. If the government must use its own supplies in a special cleaning, the Contractor shall promptly replace the inventory used.
- 3.2. Water: Water required for cleaning shall be potable unless directed otherwise by the Park Manager. It may be obtained from the Government water supply or from a source approved by the Park Manager. If water is obtained from sources other than the Government water supply system, all arrangements, and payments, if any, will be made by the Contractor.

No Government space or facilities shall be provided for contractor supplied equipment under this contract.

Part 4

CONTRACTOR FURNISHED ITEMS AND SERVICES

4. Contractor Furnished Items and Services: The contractor shall furnish all plant, facilities, vehicles, vessels, equipment, supplies and materials necessary to accomplish the services specified in this PWS. All contractor furnished equipment, vehicles, vessels, supplies, parts, and materials shall meet applicable federal, Department of Defense, Army, state, and local laws.
- 4.1. Contractor Furnished Supplies and Materials: The Contractor shall furnish all equipment, supplies, items, labor, materials, services, etc. to accomplish the services specified in this PWS. Contractor furnished items found not meeting acceptable standards shall be replaced by the contractor at the contractors' expense. All supplies, parts and materials must be approved by the COR prior to incorporation into the contract.
- 4.2. Contractor Furnished Equipment:
 - 4.2.1. General: The Contractor shall furnish equipment necessary to accomplish all of the work required by this contract within the time frames specified. All equipment used to perform work under this contract must be in good operating and mechanical condition and comply with EM 385-1-1, U.S. Army Corps of Engineers Safety and Health Requirements.
 - 4.2.2. Equipment Inspections: The COR may inspect equipment at any time it is operated on Government property and may inspect equipment monthly at a time and location that they will specify. After consultation with the Contractor, the COR shall establish the time and locations for these inspections. Any equipment found deficient shall be taken out of service immediately until repaired or replaced. Such failure shall not be cause for the Contractor to reduce any service or performance.
 - 4.2.3. Quantity and Quality of Equipment: The Contractor shall utilize equipment that equals or exceeds the quantity and quality set forth in this solicitation and evaluated by the Government for award of the contract. If the Contractor is unable to accomplish work in accordance with the requirements of this contract, they shall immediately obtain additional equipment necessary to fulfill requirements of this contract.
 - 4.2.4. Condition of Equipment: All equipment used to perform work under this contract must be in good operating and mechanical condition and comply with EM 385-1-1, U.S. Army Corps of Engineers Safety and Health Requirements. A regular schedule of preventative maintenance must be followed on all equipment. All equipment and any repair to same equipment shall be provided by the Contractor.
 - 4.2.5. Failures: Contractor furnished equipment or items inoperable or unserviceable for whatever reason, including failure to meet Federal, State, or local safety requirements shall be removed from the work site, repaired or upgraded to meet requirements within 48 hours after failure. Such failure shall not be cause for Contractor to reduce any service or performance.
 - 4.2.6. Specialized Equipment: Requirements for specialized equipment will be set forth in the specifications for each required service.
 - 4.2.6.1. Vessel: A vessel, to be provided by contractor, will be required for access

to Bushay (including Deer Camp) and Miti Campgrounds, and the Mesa Day Use Area during times when high water levels prevent access by vehicle.

- 4.2.7. Fuel: Fuel required for completion of this contract shall be provided by the Contractor.

4.3. Vehicles

4.3.1. Vehicle Registration: All vehicles operated in support of the contract, including Contractor and Contractor employee's privately owned vehicles or subcontractor vehicles, shall be properly registered, insured, licensed and safety inspected in accordance with applicable Federal, State, and local requirements. Additionally, all operators shall have a valid State-Government issued operator's license, and shall carry said license, proof of vehicle registration and insurance on their person or in the vehicle at all times while operating in support of the contract.

4.3.2. Vehicle Appearance: All vehicles operated in support of the contract, including Contractor and Contractor employee's privately owned vehicles or subcontractor vehicles shall be considered "equipment." Vehicles operated in support of this contract must be in good operating and mechanical condition and comply with EM 385-1-1, U.S. Army Corps of Engineers Safety and Health Requirements. Vehicles used in support of the contract showing excessive body damage, excessive worn or peeling paint, excessive dirt or grime, or otherwise deemed by the COR to have an unprofessional appearance shall be repaired or replaced by the Contractor immediately upon notification of the COR.

4.3.3. Vehicle Markings: All vehicles utilized in administration of this contract shall have at least three professionally made door signs identifying the vehicle with Contractor name and phone number, using a font no less than four inches in height. The signs shall be placed on the front driver's side door, the front passenger side door, and rear hatch, tailgate or trunk. Vehicle signage that becomes ripped, torn, damaged, cannot fully adhere to the vehicle surfaces (peeling), or otherwise is deemed to have an unprofessional appearance, shall be repaired or replaced by the Contractor within three (3) business days upon notification by the COR.

4.3.4. Vehicle Parking: While performing work under the contract, vehicles shall be parked only on public roads, parking areas or pullouts unless the Park Manager authorized parking elsewhere.

4.3.5. Vessels: (SEE SECTIONS 4.2.6.1)

4.4. Personnel:

4.4.1. Supervision: The contractor shall give their personal superintendence to this contract. Contractor shall appoint in writing, subject to the approval of the COR, a minimum of one foreman/superintendent. The superintendent will be on the job site at all times during the recreation season and have full authority and power to act for the contractor on items pertaining to overall work performance, management, coordination and supervision. These individuals may also serve as quality control inspectors provided that their job performance in each category is maintained at an acceptable level to the COR. The superintendent and alternate shall be able to understand, speak, read and write the English language. The superintendent or alternate shall be available by telephone 24 hours a day, throughout the contract period.

- 4.4.2. Minimum Personnel Requirements: The Contractor shall provide an adequate number of fully qualified personnel to perform the specified services properly and efficiently within the time limits specifics
- 4.4.3. Identification of Contract and Subcontract Employees: SEE SECTION 1.15
- 4.4.4. Employee Conduct: The Contractor shall conform and require Contractor personnel to conform to similar standards of conduct as Government personnel.
- 4.4.4.1. Intoxication/Under the Influence: Personnel conditions such as being under the influence of intoxicating beverages, drugs, etc. which may interfere with the performance of the contract services will not be permitted. No possession or consumption of intoxicating beverages, illegal drugs, or intoxicating quantities of legally prescribed drugs is permitted on Federal property. Misconduct as set forth in this paragraph shall cause the Contractor to take disciplinary action against Contractor employees which could result in the removal of Contract employees from Government property and work under the contract. When it is necessary to remove Contractor personnel the Contractor shall immediately provide a qualified replacement out the services performed.
- 4.4.4.2. All personnel employed under this contract must be legal residents of the United States and able to read, write, speak and understand the English language.
- 4.4.4.3. All personnel employed under this contract must be able to understand written and oral rules and regulations and apply them in a tactful and non-confrontational manner.
- 4.4.4.4. All personnel must be qualified to perform the tasks assigned in accordance with Government regulations.
- 4.4.4.5. Under no circumstance shall the Contractor or employee of the Contractor enter a restroom being used by a person or persons of the opposite gender.
- 4.4.4.6. No unauthorized use of Federal telephones except in emergency cases.
- 4.4.4.7. No unauthorized use of Federal computers.
- 4.4.4.8. All personnel shall abstain from smoking in vehicles that are used to carry out the duties and specifications of the contract.
- 4.4.4.9. All personnel shall abstain from smoking while carrying out the duties and specifications of the contract.
- 4.4.4.10. Loitering and any other activities not directly related to the scope of this contract, by the contractor, contractors employees, subcontractor or subcontractors employees is also considered misconduct under this section of the contract.
- 4.4.5. Contractor Personnel Removal: The COR may require the contractor to immediately remove from the work site any employee of the contractor or subcontractor who, in the opinion of the COR, is incompetent, endangers persons or property, or whose physical or mental condition is such that it would impair their ability to safely and satisfactorily perform the work. Notification to the contractor will be promptly made in writing if time and circumstances permit. Otherwise, notification shall be telephonic and shall be confirmed in writing as soon as possible. No such removal however, will reduce the Contractor's obligation to perform all work required under this contract and immediate replacement will be made as required. This requirement shall not be made the basis of any claim for compensation

or damages against the United States or any of its officers or agents.

4.4.6. Clothing, Uniforms and Personal Safety Equipment: See sections 1.21.2

4.4.7. Information: A copy of this contract shall be maintained on the job site and made available to any interested Contractor employee. Each Contractor shall be given a copy of the section of contract that particular employee is assigned to perform.

4.5. Permits: The contractor shall, at no additional cost to the government, obtain all appointments, licenses and permits required for performance of work and for complying with all applicable federal, state and local laws. Evidence of such permits and licenses shall be provided to the COR during the phase-in period before commencement of work. This includes current drivers' licenses for all employees, subcontractors and subcontractors employees.

4.6. Inspections and Meetings

4.6.1. Contractor Quality Control (CQC): The Contractor is responsible for establishing and maintaining adequate quality control to insure satisfactory performance of contract work in accordance with specifications. This feature will be assured by a comprehensive Quality Control Plan developed by the Contractor and approved by the COR or designated representative prior to initiating work.

4.6.2. Quality Control Inspector: To ensure and maintain adequate quality control, the Contractor will appoint a Quality Control Inspector. This appointment must be submitted in writing to the COR and be approved by the COR before any inspections occur. Quality Control Inspectors must be submitted with the Quality Control Plan prior to the Pre-Performance Meeting.

4.6.3. Quality Control Plan: The Contractor shall submit for COR approval, a plan depicting in detail, an inspection system covering all work performed under this contract. This plan shall include, at minimum, the following information:

- a. Inspector's name
- b. Park
- c. Date
- d. Weather
- e. Time in/out of park
- f. List of sites inspected
- g. Defects encountered
- h. Corrective action taken
- i. Safety violations
- j. List of damaged, inoperable, or vandalized facilities
- k. Any facilities closed temporarily by CQC

4.6.4. Inspections: The Government will monitor and inspect all work to assure compliance with the Contractor Quality Control and that the Contractor's performance meets contract specifications. When directed by the COR, the Contractor shall accompany the Government representative on these inspections.

4.6.5. Quality Control Inspection Reports: The Contractor shall maintain a current record of all Quality Control Inspection Reports. These reports shall be furnished to the COR each month or more often, if requested in writing. The records of inspections shall cover all work items scheduled and shall be signed and dated by the

Contractor's Quality Control Inspector. The frequency of these inspections shall be of an adequate number to insure all contract specifications are met. The COR reserves the right to require daily inspection reports if necessary. Inspections will be conducted within 15 minutes of the cleaning.

- 4.6.6. Inspection Deficiencies: The COR reserves the right to request the Contractor return to the job site and address any items which fail to meet the technical cleaning specifications. Any deficiencies must be corrected by the Contractor not less than two (2) hours after being notified. Payment will not be made for work which was not performed or does not meet government specifications. After the initial two (2) hour notification, the Government reserves the right to have a third party perform any scheduled work which was not done or has not been done satisfactorily. In such a case, the Government will charge these third party costs to the Contractor. Inspections will be completed within 15 minutes of the cleaning.

4.7. Meetings

- 4.7.1. Pre-Performance Meeting: Prior to the beginning of the contract, the Contractor shall meet with the Park Manager, COR or designated Point of Contact to discuss all elements of this contract. At least one week prior to this meeting, the contractor shall submit to the Park Manager all information required as specified in section 1.37.3. A Certificate of Insurance will be sent to the COR. The date, time and location of this meeting will be determined by the Park Manager or COR. Critical elements to be covered in the pre-performance meeting are as follows:

- Scope of work and schedule of planned work
- Contractor, contractor's employees, subcontractors and subcontractor employees knowledge of the scope of work.
- Key control and gate/facility combination for entry of gates (if needed).
- All applicable and necessary permits and licenses.
- List of all employees of contractor and subcontractors.
- Superintendents contact information.
- Safety Plan and Safety Exposure reporting - The Contractor shall maintain records of the number of man-hours worked at Lake Mendocino each month. Using these records, the contractor will complete the Safety Exposure Report furnished by the Park Manager.

- 4.7.2. Pre-Performance Meeting: Prior to the beginning of the contract, the Contractor shall meet with the Park Manager, COR or designated Point of Contact to discuss all elements of this contract. At least one week prior to this meeting, the contractor shall submit to the Park Manager all information required as specified in section 1.37. A Certificate of Insurance will be sent to the COR. The date, time and location of this meeting will be determined by the Park Manager or COR. Critical elements to be covered in the pre-performance meeting are as follows:

- 4.7.3. Performance Evaluation Meetings: The Contractor shall meet with the COR and Park Manager as often as determined necessary by the COR to discuss performance.
- 4.7.4. Contract Deficiency Report (CDR): A meeting shall be held no later than one normal workday after a CDR is issued. Written minutes of these meetings shall be

prepared and signed by the COR and the Contractor. Mutual effort will be made to resolve any and all problems identified. Should the Contractor not concur with any decision, etc., the Contractor shall state so, in writing and request a final decision by the Contracting Officer

PART 5

SPECIFIC TASKS

5. Cleaning Services Specifications

- 5.1. REFUSE RECEPTACLES: A refuse receptacle is any garbage can used for the disposal trash or waste. This also includes those receptacles that are intended solely for the disposal of animal waste. Excluded are all large capacity dumpsters.
 - 5.1.1. Services Required: All refuse receptacles (including ‘doggie pots’) will be completely emptied on the days specified. The contractor shall remove all trash and refuse in each receptacle and also any refuse within a 60-foot radius regardless of its volume, type, or source of origin. The cleaning is to obtain a result of no more than three (3) items of litter within that area at all times.
 - 5.1.2. All refuse receptacles will have liners. Each liner will be replaced after emptying the receptacle regardless of its condition.
 - 5.1.3. Each receptacle is to remain in a sanitary and odor free condition. All refuse receptacles will be in good working order. All refuse cans that contain faulty lids/mechanisms or rusted out bottoms will be replaced by the contractor from the government’s designated supply of refuse receptacles.
 - 5.1.4. All refuse collected will be disposed of in areas designated by the COR
 - 5.1.5. Recreation Areas: Refuse cans shall be emptied in the following areas:
 - 5.1.5.1. Coyote Dam Recreation Area
 - 5.1.5.2. Joe Riley Day Use Area
 - 5.1.5.3. Overlook Day Use Area
 - 5.1.5.4. Pomo Day Use Areas (A, B & C)
 - 5.1.5.5. Oak Grove Day Use Area
 - 5.1.5.6. Mesa Day Use Area
 - 5.1.5.7. Inlet Road Area
 - 5.1.5.8. South Boat Ramp
 - 5.1.5.9. North Boat Ramp
 - 5.1.5.10. North Disc Golf Course
 - 5.1.5.11. South Disc Golf Course

5.2. Campground Services

- 5.2.1. A typical campsite consists of a parking pad, a table, a fire ring/grill, and a lantern post. The government reserves the right to upgrade any or all non-typical sites at no additional cost to the government. The Contractor will make every reasonable attempt to clean a campsite or facility even if it is occupied. The Government will only pay for campsites that were cleaned after occupancy. The Contractor is required to submit in writing which sites that were not cleaned for each campground.
 - 5.2.1.1. Each campsite picnic table will be completely cleaned of all refuse, food products and other debris. All graffiti will be removed with graffiti remover. Graffiti that can’t be removed will be reported to the COR within 24 hours. The Contractor will notify any government employee or camp host immediately if there is a faulty table that poses a safety hazard.
 - 5.2.1.2. Each fire ring/grill will be completely cleaned of all ashes, debris, trash, and other refuse. The grills will be scrubbed with a wire brush to ensure there

are no food products. Unused burnable wood products are to be neatly placed next to the fire ring/grill and extinguished if hot. All ashes will be disposed of in a designated area approved by the COR. Ashes that are hot will be completely extinguished with water before disposal. After cleaning fire grills, they will be placed in the upright position.

- 5.2.2. Litter: defined as all refuse including trash, garbage, fishing line, cigarette butts, cans, bottles, bottle caps, fecal matter, and any other debris left by the public. Any piece of litter the size of a cigarette butt or larger will be removed.

- 5.2.2.1. Litter in each campsite will be picked up on each scheduled day, 60 feet in all directions from the campsite's picnic table. If there is no picnic table, litter will be removed 60 feet in all directions from the campsite's fire ring. The cleaning is to obtain a result of no more than 3 items of litter within that area at all times. The Government will only pay for campsites that were cleaned. The Contractor will make every reasonable attempt to clean a campsite or facility even if it is occupied. The Contractor is required to submit weekly, in writing, which sites or facilities that were not cleaned for each campground

- 5.2.3. All refuse collected will be disposed of in areas designated by the COR.

- 5.2.4. Recreation Areas: Campground maintenance will be performed in the following areas:

- 5.2.4.1. Kyen Campground
- 5.2.4.2. Bushay Campground
- 5.2.4.3. Miti Campground

5.3. Picnic & Day-use Area Maintenance Services

- 5.3.1. A typical picnic unit consists of a shelter, concrete pad, picnic table, and a fire grill, although some do not have a shelter roof. The government reserves the right to upgrade any or all non-typical sites at no additional cost to the government. The Government will only pay for picnic units that were cleaned after use. The Contractor will make every reasonable attempt to clean units even if it is occupied. The Contractor is required to submit in weekly, in writing, which units that were not cleaned for each day use area

- 5.3.1.1. Each picnic table will be completely cleaned of all refuse, food products and other debris. All graffiti will be removed with graffiti remover. Graffiti that can't be removed will be reported to the COR within 24 hours. The Contractor will notify any government employee or camp host immediately if there is a faulty table that poses a safety hazard.

- 5.3.1.2. Each fire ring/grill will be completely cleaned of all ashes, debris, trash, and other refuse. The grills will be scrubbed with a wire brush to ensure there are no food products. Unused burnable wood products are to be neatly placed next to the fire ring/grill and extinguished if hot. All ashes will be disposed of in a designated area approved by the COR. Ashes that are hot will be completely extinguished with water before disposal. After cleaning fire grills, they will be placed in the upright position.

- 5.3.1.3. All shelter eaves, steel supports, recesses, and ceilings will be cleaned to remove tape, wrappers, paper, food, ribbon and any other refuse present. The slabs will be swept or air blown and rinsed if necessary to remove any debris or

food. The Contractor will notify any government employee or camp host immediately if there is a faulty shelter that poses a safety hazard.

5.3.2. Litter: defined as all refuse including trash, garbage, fishing line, cigarette butts, cans, bottles, bottle caps, fecal matter, and any other debris left by the public. Any piece of litter the size of a cigarette butt or larger will be removed.

5.3.2.1. Litter will be picked up within 60 feet in all directions of each day use picnic unit on each scheduled day. The cleaning is to obtain a result of no more than 3 items of litter within that area at all times.

5.3.3. Recreation Areas: Picnic/Day use maintenance will be performed in the following areas

5.3.3.1. Joe Riley Day Use Area

5.3.3.2. Overlook Day Use Area

5.3.3.3. Pomo Day Use Areas (A, B & C)

5.3.3.4. Oak Grove Day Use Area

5.3.3.5. Mesa Day Use Area

5.3.3.6. Inlet Road Area

5.3.3.7. Coyote Dam Recreation Area

5.3.4. All refuse will be disposed of in an area approved by the COR.

5.4. UNSCHEDULED SERVICES: At times the Contractor will need to respond to clean the day-use areas, campgrounds or empty refuse cans in the event of an emergency (i.e. excessive visitation/use resulting in prolific refuse in/around the service area(s)).

5.4.1. SERVICE CLEANINGS: As determined necessary by the Park Manager or COR, additional refuse can service(s), campground maintenance, and day-use area maintenance may be requested for the areas previously mentioned in this PWS in addition to ANGELS CAMP (a special-use campground south of Pomo C Day-Use Area) and KAWEYO HORSE STAGING AREA (a seasonal parking area for equestrian trailers and overflow boat trailers).

PART 6
APPLICABLE PUBLICATIONS

6. Applicable Publications:

6.1. The Contractor must abide by all applicable regulations, publications, manuals, and local policies and procedures.

PART 7**ATTACHMENT/TECHNICAL EXHIBIT LISTING****7. Attachment/Technical Exhibit List:**

Attachment 1 – Quality Assurance Surveillance Plan

Attachment 2 – Contract Submissions Table

Attachment 3 – Sample Frequency Schedules

Attachment 1

QUALITY ASSURANCE SURVEILLANCE PLAN

Purpose: This Quality Assurance Surveillance Plan (QASP) is a government developed and applied document used to make sure that systematic quality assurance methods are used in the administration of the Performance Based Service Contract (PBSC) standards included in this contract. The intent is to ensure that the contractor performs in accordance with performance metrics set forth in the contract documents, that the Government receives the quality of services called for in the contract, and that the Government only pays for the acceptable level of services received.

1. Critical performance processes and requirements. Critical to the performance of the contract, the contractor shall provide all personnel equipment, tools, materials, supervision, transportation, other items and services necessary to perform as defined in this Performance Work Statement (PWS). The contractor shall provide accurate transaction processing to ensure that material accountability comply with safety and security requirements, in accordance with this PWS. Additionally, the contractor shall be accountable for all auditable documents, establish/maintain effective quality, and perform required within prescribed timeframes. The performance process is the timely, accurate, and thorough completion of all contract requirements.
2. Performance Standards
 - a. Schedule. The dates for services and the actual accomplishment of the services in accordance with the schedule will be assessed against original dates of services and milestones established for the contract.
 - b. Service. The services required to be performed will be assessed against the PWS detailed in the contract, for the required content, quality, timeliness, and accuracy.
 - c. Past Performance. In addition to schedule and services, and cost aspects of performance discussed above, pursuant to FAR 42.15, the Government will assess the contractor's record of conforming to contract requirements and to standards of good workmanship, the contractor's adherence to contract schedules including the administrative aspects of performance, the contractor's history of reasonable and cooperative behavior and commitment to customer satisfaction, and the contractor's business-like concern for the interest of the customer.
 - d. Quality Assurance Evaluation:
 1. Evaluation Overview
The Government will monitor the Contractor's performance under this contract using the Quality Assurance Surveillance Plan (QASP) detailed herein. The

primary objective of the QASP is to ensure that the Contractor's services meet the performance standards outlined in the contract. This evaluation will be conducted by the Contracting Officer (CO) or a duly appointed Contracting Officer's Representative (COR).

3. Performance Scoring System

The Contractor's performance for each evaluated task or service will be rated according to the five-tiered scoring system below. All evaluations will be formally documented.

- Exceptional (Score: 5): Performance surpasses all contractual requirements, providing a significant benefit to the Government. Any identified deficiencies are minor and were proactively corrected by the Contractor in a highly effective manner.
- Very Good (Score: 4): Performance meets all contractual requirements and exceeds some requirements to the Government's benefit. Any identified deficiencies were minor and promptly corrected.
- Satisfactory (Score: 3): Performance meets all essential contractual requirements. Any identified deficiencies were minor and corrected in a timely manner. This is the expected level of performance.
- Marginal (Score: 2): Performance fails to meet some contractual requirements. Deficiencies are more than minor and impact the Government. The Contractor has failed to identify or implement effective corrective actions for a recurring issue.
- Unsatisfactory (Score: 1): Performance fails to meet most contractual requirements. Deficiencies are serious, significantly impact mission, and/or are repetitive. Contractor's corrective actions have been ineffective.

4. Evaluation Process: The contracting officer or designated representative will conduct regular inspections and evaluations to assess the contractor's performance based on the above scoring system

- a. Frequency: The COR will conduct quality assurance surveillance no less than once (1) per quarter, or more frequently as deemed necessary based on the Contractor's performance. The quarters are defined according to the standard calendar:

Q1: January 1 – March 31

Q2: April 1 – June 30

Q3: July 1 – September 30

Q4: October 1 – December 31

5. Corrective Action Process

- Non-Conforming Service: When a service is rated as Marginal (2) or Unsatisfactory (1), the COR will formally document the deficiency and report to the Project Manager or Contracting Officer.
- Contract Discrepancy Report (CDR): The COR will issue a CDR to the Contractor, detailing the specific deficiency and the contract requirement that was not met.

Resolution of Disagreements: Should the Contractor disagree with the findings of a CDR, the Contractor shall first consult with the COR. If a resolution cannot be reached, the matter shall be elevated in writing to the Contracting Officer, whose decision shall be final. Failure to implement a directed corrective action may be grounds for contract default.

6. Surveillance methods. The primary methods of surveillance used to monitor performance of this contract will include but not be limited to:

- a. 100% Inspection: Used for critical tasks where performance must be flawless.
 - b. Random Sampling: A statistically valid sample of work units is selected for inspection.
 - c. Periodic Inspection: A planned inspection schedule to assess overall performance of a specific area or task.
 - d. Validated Customer Feedback: Formal or informal feedback from Government personnel or facility users, verified by the COR.
- e. Customer Feedback. Customer feedback will be obtained from valid customer complaints. Customer complaints, to be considered valid, must set forth clearly and in writing the detailed nature of the complaint; must be signed and must be forwarded to the COR by the contractor. The contractor shall maintain a log of all customer complaints as well as a copy of each complaint in a documentation file. The COR may request to review the log and/or documentation file at any time.

7. Performance Measurement. Performance will be measured in accordance with the following table:

Performance-Based Matrix

Performance Element	Performance Requirement	Surveillance Method	Frequency	Acceptable Quality Level
Contract Services	Contract Services furnished as prescribed in the PWS as applicable.	Inspection by the COR	Random inspection or sampling of contract services as needed or quarterly.	Over 95% of service elements are rated satisfactory
Overall Contract Performance	Overall contract performance of sufficient quality to earn a Satisfactory (or higher) rating in the COR's annual report on contractor performance	Assessment by the COR	Annual	Over 95% of service elements have been rated as satisfactory, and any identified issues are currently being addressed.
Contractor Self Reporting	Contract Services furnished as prescribed in the PWS as applicable.	Contractor Self Reports	Monthly	Over 95% of services reported performed timely and without rework required.
Customer Feedback	Customer complaints reviewed by COR	Inspection by the COR	Per Occurrence	100% of valid customer complaints resolved
Invoicing	Monthly invoices per contract procedures are timely and accurate.	Review & acceptance of the invoice by COR	Monthly	100% accuracy

8. Incentives/Disincentives:

For each item that does not meet acceptable levels, the Government may issue a Contract Discrepancy Report (CDR). CDRs will be forwarded to the Contracting Officer with a copy sent to the contractor. The contractor must reply in writing within 5 days of receipt identifying how future occurrences of the problem will be prevented. Based upon the contractor's past performance and plan to solve the problem, the Contracting Officer will determine if any further action will be taken.

In accordance with the inspection of services provisions of the contract (52.212-4 (a) Inspection/Acceptance), the contractor will provide quality products in a timely manner since the Government can require the contractor, at no additional cost, to replace or correct work that fails to meet contract requirements.

Attachment 2

Contractor Submittals Prior to Pre-Performance Meeting

1. Certificate of Insurance
2. A typed list of names, phone numbers, and addresses of all persons performing services prior to beginning work. The list shall include a copy of the employees' valid vehicle driver's license. This list shall be maintained during the entire contract period.
3. Name of Supervisor and Alternate Supervisor
4. Safety Plan: The Contractor shall formulate and furnish to the Park Manager and COR a comprehensive program for safe operation and maintenance in accordance with applicable provisions of OSHA and EM 385-1-1. The program shall include equipment maintenance, employee responsibilities for working safely, and training verification of contract employees.
5. Safety Hazard Analysis
6. Quality Control Inspection Plan
7. Uniform Plan
8. Material Safety Data Sheets for each chemical product used by the contractor
9. Composition of paper products used

Monthly Contract Submittals

Required monthly submittals shall be submitted by the 6th business day of each month. The Government reserves the right to increase the frequency of monthly submittals if deemed necessary and requested in writing by the KO or COR.

1. Safety Exposure Report: The Contractor shall maintain records of the number of person-hours worked at Lake Mendocino each month. Using these records, the Contractor will complete the Safety Exposure Report (SPD FORM 94) provided by the Government.
2. Quality Control Inspection Plan
3. Computer-generated invoice, two copies
4. Any deviation from the set schedule

Attachment 3
SAMPLE FREQUENCY SCHEDULES

REC SEASON / PEAK
SEASON
SCHEDULE EXAMPLE

		Refuse Receptacles	Campground Maintenance	Picnic/Day Use Maintenance
SERVICE AREA				
Joe Riley		M,F,S,SU (6 CANS)		M, W (3 SITES)
Overlook		M,F,S,SU (5 CANS)		M, W (4 SITES)
Pomo A		M,F,S,SU (21 CANS)		M, F, SU (21 SITES)
Pomo B		M,F,S,SU (18 CANS)		M, F, SU (17 SITES)
Pomo C		M,F,S,SU (18 CANS)		M, F, SU (20 SITES)
Oak Grove		M,F,S,SU (9 CANS)		M, F, SU (11 SITES)
Mesa		T, TH, SU (9 CANS)		T, TH, SU (10 SITES)
Inlet Road		T, TH, SU (5 CANS)		T, TH (16 SITES)
Coyote Dam Area		M,F,S,SU (10 CANS)		M, W, F (12 SITES)
South Ramp		M,F,S,SU (6 CANS)		
North Ramp		M,F,S,SU (3 CANS)		
South Disc Golf Course		M,F (8 CANS)		
North Disc Golf Course		M, F (3 CANS)		
Miti Campground			M, F (16 SITES)	
Bushay Campground			M, F, S, SU (175 SITES)	
Kyen Campground			M, F, S, SU (100 SITES)	

OFF SEASON
SCHEDULE EXAMPLE

		Refuse Receptacles	Campground Maintenance	Picnic/Day Use Maintenance
SERVICE AREA				
Joe Riley		M (6 CANS)		M (3 SITES)
Overlook		M, F (5 CANS)		M (4 SITES)
Pomo A		M, F (11 CANS)		M (21 SITES)
Pomo B		M (6 CANS)		M (17 SITES)
Pomo C		M (6 CANS)		M (20 SITES)
Oak Grove		M, F (6 CANS)		M (11 SITES)
Mesa		M, F (5 CANS)		F (10 SITES)
Inlet Road		M, F (5 CANS)		F (15 SITES)
Coyote Dam Area		M, F (10 CANS)		M (12 SITES)
South Ramp		M, F (6 CANS)		
North Ramp		M, F (3 CANS)		
South Disc Golf Course		M (8 CANS)		
North Disc Golf Course		M (3 CANS)		
Miti Campground			F (16 SITES)	
Bushay Campground			F (10 SITES)	
Kyen Campground			M (22 SITES)	