

PERFORMANCE WORK STATEMENT (PWS) Feb 2026

ISO 17025 Accredited Calibration Services – Dugway Proving Ground

PART 1

GENERAL INFORMATION

1. **GENERAL:** This is a non-personal service contract under which the personnel rendering the services are not subject, either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. The United States (U.S.) Government shall not exercise supervision or control over the Contractor's employees performing the tasks herein. Such contract employees shall be accountable solely to the Contractor who, in turn shall be responsible to the U.S. Government.

1.1 **Description of Services/Introduction:** The contractor shall provide all personnel, equipment, supplies, transportation, tools, materials, supervision, and other items and non-personal services necessary to perform ISO accredited calibration services for analytical equipment in Chemical Test Division (CTD) at Dugway Proving Ground (DPG) as defined in this PWS except for those items specified as government furnished property (GFP) and government furnished services (GFS). The contractor shall meet the standards in this contract.

1.2 **Background:** To maintain ISO 17025 accreditation, the CTD needs to ensure all lab equipment is regularly calibrated. This includes analytical balances, digital thermometers, flowmeters, flow controllers, and weight sets. CTD currently has a need to establish a calibration service contract to cover the annual calibration of above-mentioned equipment – with the exception of the weight sets, which are calibrated every three years. This regular calibration and maintenance will ensure CTD continues to meet all ISO 17025 standards.

1.3 **Objectives:** The objective of this Performance Work Statement (PWS) is to acquire comprehensive, on-site ISO 17025 accredited calibration services for a range of critical laboratory equipment at DPG. This includes analytical balances, digital thermometers, flow meters, flow controllers and analytical weight sets. The contractor will ensure the continued accuracy and reliability of these equipment to support the Government's ISO 17025 accreditation and maintain the integrity of testing data.

1.4 **Scope:** Contractor shall provide non-personal ISO 17025 accredited calibration services. The contractor shall provide all labor, equipment, materials, and travel necessary to perform these services as outlined below.

- Provide ISO 17025 accredited calibration services four times per year, with each visit potentially spanning multiple days, as scheduled by the Government.
- Provide annual on-site calibration services at CTD for analytical balances, flow meters, and flow controllers, and biennial calibration for digital thermometers, using the contractor's own calibration equipment.
- Provide calibration services for each weight sets every three years, with the flexibility for calibration to be performed either on-site or off-site, including all associated shipping costs in the contract price.
- Deliver a detailed ISO 17025 compliant report of calibration for each instrument, along with a physical stamp indicating the new calibration date and accreditation. Equipment will be calibrated annually, except for digital thermometers (every two years) and weight sets (every three years).
- Offer a flexible contract capable of accommodating changes in the Government's equipment inventory. The contract shall allow for the annual adjustment of the amount of equipment calibrated, through the addition of new equipment and/or removal of obsolete equipment.
- Provide all-inclusive pricing covering calibration services, travel expenses, and shipping costs to and from Dugway for weight sets (if applicable).

The following equipment shall require calibration by the contractor.

Model	Type of equipment	Quantity	Manufacturer	Service Frequency	Location (On Site/Off Site)	Annual Service Count
125 SM	Balance	3	Precisa	Annual	Onsite	3
AB304S	Balance	1	Mettler Toledo	Annual	Onsite	1
BCE 124-S1	Balance	4	Satorius	Annual	Onsite	4
XP205	Balance	8	Mettler Toledo	Annual	Onsite	8
XP504	Balance	7	Mettler Toledo	Annual	Onsite	7
C100L	Flow Controller	86	Sierra	Annual	Onsite	86
FC2901V	Flow Controller	30	Mykrolis	Annual	Onsite	30
MB-10SLPM-D	Flow Controller	6	Alicat	Annual	Onsite	6
MC-5SLPM-D	Flow Controller	46	Alicat	Annual	Onsite	46
2211A	Flow Meter	191	Parker-Porter	Annual	Onsite	191
TR71A	Thermometer	15	T&D Corporation	Two Years	Onsite	8
1mg-200g, Class 1	Weight Set (up to 20 pieces)	12	Troemner	Three years	Onsite/Offsite	4

1.5 Period of Performance: This contract will be a base year with four option years, providing long-term calibration support for essential laboratory equipment. The period of performance shall be for one (1) Base Year (2026) and four (4) 12-month option years. The Period of Performance reads as follows:

Base Year	30 April- 2026 - 29 April 2027
Option Year One (1)	30 April - 2029 – 29 April 2028
Option Year Two (2)	30 April-2028 - 29 April 2029
Option Year Three (3)	30 April -2029 – 29 April 2030
Option Year Four (4)	30 April -2030 - 29 April 2031

The requiring activity for this service contract is the West Desert Test Center's (WDTC) Chemical Test Division

1.6 General Information:

1.6.1 Quality Control Plan (QCP): The contractor shall develop and maintain an effective quality control program to ensure services are performed in accordance with this PWS. The Contractor shall develop, implement, and maintain a QCP and program to ensure all work described in this contract is performed at or above the standard defined in the Performance Requirements Summary (PRS). The QCP is developed by the contractor for its internal use to ensure that it performs and delivers high-quality service. The contractor's QCP is the means by which the contractor ensures all work complies with the requirements of the contract. The QCP identifies and corrects potential and actual problem areas throughout the entire scope of the contract.

1.6.1.1 The contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The QCP shall be submitted within thirty (30) days of contract award. After acceptance of the QCP, the contractor shall receive the contracting officer's (KO) acceptance in writing of proposed changes to the QC procedures. The contractor shall submit QCP changes within five (5) days to the KO and Contracting Officer's Representative (COR) for review and approval prior to implementation.

1.6.1.2 The Quality Control Plan shall address as a minimum:

1.6.1.2.1 Inspection Program. Included shall be a quality control inspection program covering all general and specific tasks included in the contract scope of work. It shall specify tasks or areas to be inspected on a scheduled or

unscheduled basis, the manner in which inspections are to be conducted, the titles of the individuals who will perform the inspections, and the percentage of the work that will be inspected on a recurring basis. In developing this inspection program, the Contractor shall identify the key activities and associated characteristics in each process that have a significant influence on specific services and provide for methods for evaluation of the selected characteristics.

1.6.1.2.2 Deficiency Identification. The QCP shall include a method of identifying deficiencies in the quality of services performed before the level of performance becomes unacceptable as defined in the PRS. This shall contain processes for corrective action without dependence upon Government direction.

1.6.1.2.3 Deficiency Correction. The program shall contain process control and process performance measurement procedures that shall include how the Contractor shall implement preventive corrective actions. The Contractor shall demonstrate that it has designed quality into the delivery of services thereby mitigating the risk(s) associated with delivery of deficient or nonconforming services.

1.6.1.2.4 Documentation and Enforcement. The QCP shall include a method of documenting and enforcing quality control operations of both prime contractor and subcontractor work; including inspection and testing.

1.6.1.2.5 Trend Analysis. The QCP shall include a method of performing trend analysis and assessments through the use of metrics.

1.6.1.2.6 Surveillance Methods. The QCP shall contain specific surveillance techniques for all contract services. The surveillance methods shall be comprehensive and adaptable to the reporting system of the plan.

1.6.2 Quality Assurance (QA): The government shall evaluate the contractor's performance under this contract in accordance with (IAW) the Quality Assurance Surveillance Plan. This plan is primarily focused on what the Government must do to ensure that the contractor has performed IAW the performance standards and contract quality requirements are met. Contract quality requirements" means the technical requirements in the contract relating to the quality of the product or service and those contract clauses prescribing inspection, and other quality controls incumbent on the contractor, to ensure the product or service conforms to the contractual requirements. It defines how the performance standards will be applied, the frequency of surveillance, the performance threshold, and deductions, if applicable.

1.6.3 Recognized Holidays: The contractor is not required to perform services on the following holidays.

New Year's Day	Labor Day
Martin Luther King Jr.'s Birthday	Columbus Day
President's Day	Veteran's Day
Memorial Day	Thanksgiving Day
Independence Day	Christmas Day
Juneteenth	

1.6.4 Hours of Operation: The contractor is responsible for conducting business between the hours of 7:00 to 17:30 Monday through Thursday, except Federal holidays or when the Government facility is closed due to local or national emergencies, administrative closings, or similar Government directed facility closings. For other than firm fixed price contracts, the contractor will not be reimbursed when the government facility is closed for the above reasons. The Contractor must, at all times, maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons.

1.6.5 Place of Performance: The work to be performed under this contract will be performed at the Combined Chemical Test Facility (CCTF) and Bushnell Material Test Facility (BMTF) in the West Desert Test Center (WDCT)/Dugway Proving Ground (DPG).

1.6.6 Type of Contract: Firm Fixed Price (FFP) . The Government anticipates the award of a [FFP] type contract.

1.6.7 Security Requirements:

1.6.7.1 Access and general protection/security policy and procedures: Contractor and all associated subcontractor employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personal identity verification requirements (FAR clause 52.204-9, Personal Identity Verification of Contractor Personnel) as directed by DOD, HQDA and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

1.6.7.2 Physical Security: The contractor shall be responsible for safeguarding all government equipment, information, and property provided for contractor use. At the close of each work period, government facilities, equipment, and materials shall be secured.

1.6.7.3 Escort: The Contractor and all associated sub-contractor employees performing services under this contract shall be escorted at all times by host nation security personnel or by an individual designated by the Contracting Officer Representative (COR) while accessing U.S. facilities or activities.

1.6.7.4 Personnel Security Clearance Requirements: RESERVED

1.6.7.4.1 : The contractor shall follow DOD Federal Acquisition Regulation Supplement (DFARS) clause 252.223-7004, Drug-free Work Force. The contractor shall conduct drug tests, ensuring all top secret cleared contractor employees are tested at least once per year, each year of the contract, as well as when there is a reasonable suspicion that an employee uses illegal drugs. The drug testing shall be at the contractor's expense. Positive drug test results shall be made available to both the KO and COR within 24 hours of known test results. Records of drug testing shall be made available to the COR.

1.6.7.5 Background Checks The Contractor shall ensure contractor employees and subcontractor employees performing services under this contract have passed a security check conducted by the State Police Department of their U.S. residence. Security checks that have been completed as part of a personnel security clearance background investigation, or a previous background check that was a condition of employment, meet this requirement. Documentation of these checks will be made available to the KO or COR upon request. The Government retains the right to exclude any employee from performance of duties under this contract if a background security check reveals an employee is a security risk. The exclusion of an employee for security reasons will not relieve the Contractor from performance of services required under this contract. If the Government determines additional background checks are required, at a minimum, and upon request from the Government, the Contractor shall provide to the KO or COR, the following information on any contractor or subcontractor employee performing services under this contract:

- Full birth name
- Married name (if applicable)
- SSN or local equivalent (ID card number)
- Date of birth
- Place of birth (city, country)

1.6.7.5.1 Background Check Notification Requirements: If a background check on any employee or subcontractor employee performing services under this contract, whether the check was conducted as a condition of employment or as part of the contract with the Government, reveals any information from any source (including host country law enforcement) of criminal activity by Contractor employees, subcontractors, or subcontractor employees, the Contractor shall **immediately** notify the KO and COR of that information. The Contractor shall make notification of:

(1) Traffic violations, other than parking, will be reported to the KO or COR only if the contract is for drivers for the Government;

(2) Any suspicious activity by Contractor employees, subcontractors, or subcontractor employees the Contractor believes may pose a risk to U.S. or host nation national security or imminent risk of deadly bodily harm to any person; and

(3) Any actions taken against Contractor employees, subcontractors, or subcontractor employees pursuant to this requirement.

1.6.7.5.2 Remedies. In addition to other remedies available to the Government, the Contractor's failure to comply with the requirements of this paragraph may result in requiring the Contractor to remove a Contractor employee or employees from the performance of the contract.

1.6.7.5.3 Subcontracts. The Contractor shall include the substance of this paragraph and the preceding paragraph in all subcontracts.

1.6.7.6 Uncleared Contractor Common Access Card (CAC) Credentialing and Access Procedures

1.6.7.6.1 Contractor Common Access Card (CAC) Eligible Requirements RESERVED

1.6.7.6.1.1 Federal Installation/Facility Access Contractor and all associated sub-contractor employees shall comply with applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative). The employees performing services under this contract shall also provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services, Security Office or the host nation equivalent.

1.6.7.6.2. Contractor Non CAC Eligible Requirements for DOD Facility and Installation Access

: Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05/AR 190-13), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative), or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations.

1.6.7.7 Access to Government Information Systems : All Contractor employees and subcontractor employees performing services under this contract who have access to a government information system must be registered in the ATCTS (Army Training Certification Tracking System) at commencement of services and must successfully completed the DoD Information Assurance Awareness training prior to access to the information system and **then annually thereafter**.

1.6.7.8 Key Control: The Contractor shall establish and implement methods of making sure all keys/key cards issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. NOTE: All references to keys include key cards. Contractor shall not duplicate keys provided by the Government. The Contractor shall develop procedures covering key control that shall be included in the Quality Control Plan. Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas.

1.6.7.8.1 The Contractor shall report any occurrences of lost or duplicate keys/key cards to the KO and the COR (and physical property manager, if applicable) within two (2) hours or the next business day if after hours and to request key or lock(s) replacement. This notification and request for key(s) and lock replacement shall be submitted in writing. The total cost of the replacement may be at the Contractor's expense.

1.6.7.8.2. Only authorized Contractor personnel shall use Government issued key(s) and/or key card(s). Contractor personnel shall follow security access requirements when entering secure areas. Contractor shall receive appropriate security clearance approval to allow visitor(s) access in secure areas.

1.6.7.9 Lock Combinations: The Contractor shall establish and implement methods to ensure all lock combinations are protected from unauthorized persons. The Contractor shall ensure lock combinations are changed when

personnel with access to the combinations no longer have a need to know IAW local security procedures and policies. These procedures shall be included in the Contractor's QCP.

1.6.8 Post Award Conference/Contract Periodic Progress Meetings: The Contractor shall attend the post award conference convened by the contracting activity or contract administration office IAW Federal Acquisition Regulation (FAR) Subpart 42.5. The KO, COR, with other Government personnel, as appropriate, may meet periodically with the Contractor to review the Contractor's performance. At these meetings the KO will apprise the contractor of how the government views the Contractor's performance and the Contractor will apprise the Government of problems, if any, being experienced. Appropriate action shall be taken to resolve outstanding issues. These meetings shall be at no additional cost to the government.

1.6.9 Contracting Officer Representative (COR): The COR will be identified by separate letter. The COR monitors all technical aspects of the contract and assists in contract administration. The COR is authorized to perform the following functions: ensure the Contractor performs the technical requirements of the contract; perform inspections necessary in connection with contract performance; maintain written and oral communications with the Contractor concerning technical aspects of the contract; issue written interpretations of technical requirements, including Government drawings, designs, specifications; monitor Contractor's performance and notifies both the KO and Contractor of any deficiencies; coordinate availability of government furnished property; and provide site entry of Contractor personnel. A letter of designation issued to the COR, a copy of which is sent to the Contractor, states the responsibilities and limitations of the COR, especially with regard to changes in cost or price, estimates, or changes in delivery dates. The COR is not authorized to change any of the terms and conditions of the resulting order.

1.6.10 Key Personnel: The follow personnel are considered key personnel by the government: Contract manager or Alternate contract manager and qualified technicians that perform the ISO 17025 calibrations. The contractor shall provide a contract manager who shall be responsible for the performance of the work. The name of this person and an alternate who shall act for the contractor when the manager is absent shall be designated in writing to the contracting officer. The contract manager or alternate shall have full authority to act for the contractor on all contract matters relating to the daily operation of this contract. The qualified technicians must have documented training, experience, and demonstrate proficiency in calibration procedures.

1.6.11 Special Qualifications or Certifications:

- The contractor must operate a laboratory that is formally accredited to ISO/IEC 17025 by a recognized accreditation body (such as ANAB, A2LA, or IAS). This accreditation confirms that the lab meets international standards for competence in testing and calibration
- Qualified performing calibrations must:
 - Have documented education or training, and experience relevant to the ISO 17025 calibration tasks.
 - Be familiar with the specific instruments and ISO 17025 calibration methods used

1.6.11.1 IA/IT Training Certification: All Contractor employees and subcontractor employees supporting IA/IT functions must be certified upon contract award as directed in DoD 8570.01-M, DFARS 252.239.7001, and AR 25-2. Baseline certification as stipulated in DoD 8570.01-M must be completed upon contract award.

1.6.12 Identification of Contractor Employees: Contractor employees shall identify themselves as Contractor personnel and shall avoid representing themselves as Government employees. This identification includes meeting attendance, answering Government telephones, email communications, and working in other situations where Contractor status is not obvious. Contractor personnel identification shall be easily identifiable through the display of badges, name tags, lanyards, etc.

1.6.12.1 Badging of Contractor Employees: If required by the Government, contract personnel and all associated subcontractors employees accessing U.S. facilities or activities, shall present a valid picture ID provided by the Government while accessing Government owned or contracted facilities and shall adhere to facility security policies and restrictions. If applicable, Government issued access badges will not be worn outside designated facility where visible to the general public. Contractor personnel shall return all U.S. Government issued identification to appropriate U.S. Government authorities within five (5) days of the end of their contractual duties.

1.6.12.2 Uniform: The Contractor shall provide a standard uniform for all Contractor and subcontractor employees performing services under this contract, and ensure they wear the uniform during appointed duty hours. The uniform may consist of the same type and color shirt and slacks for all workers. Company logo is optional.

1.6.13 Contractor Travel: Reserved

1.6.14 Other Direct Costs (ODC): Reserved

1.6.15 Data Rights: Reserved.

1.6.16. Non-Disclosure Requirements: Performance under this contract may require the Contractor to access data and information proprietary to a Government agency, another Government Contractor, or of such nature that its dissemination or use other than as specified in this work statement would be adverse to the interests of the Government or others. Neither the Contractor, nor Contractor personnel, shall divulge, nor release data or information developed, or obtained under performance of this work statement, except to authorize Government personnel or upon written approval of the KO. The Contractor shall not use, disclose, or reproduce proprietary data, which bears a restrictive legend, other than as specified in this PWS. All documentation showing individual names or other personal information shall apply, and shall be controlled and protected under the provisions of the Privacy Act of 1974, Public Law 93-579, 5 United States Code (U.S.C.) Section 552a.

1.6.16.1 Non-Disclosure Statements: Reserved.

1.6.16.2 Advertisement and Social Media: The Contractor shall NOT post information to public website or social media locations, personal or professional, that in any way disclose names, locations, hotel data, participants, discussions, pictures, etc. before, during or after the contract period of performance without the express consent of the Government. The use of propaganda violates DOD Commercial Use of Imagery Guidelines stated at (<http://www.defenseimagery.mil/products/DODimagery/commercialuse.html>). The Contractor shall not cite any information (e.g., contract information, pictures, locations, etc.) obtained through this contract on any marketing tools to include its company website.

1.6.16.3 INFORMATION ASSURANCE: At no time will the Contractor or associated sub-contractor employees transmit government documents or information over using methods that do not meet the security requirements specified in the National Institute of Standards and Technology (NIST) Special Publication (SP) 800-171, "Protecting Controlled Unclassified Information in Nonfederal Information Systems and Organizations" such as personal electronic mail accounts, public digital data storage sites (cloud storage), social media platforms or instant messaging. Approved government sites such as U.S. Army Aviation and Missile Research Development and Engineering Center (ARMDEC) Safe Exchange at <https://safe.amrdec.army.mil/SAFE/About.aspx>, or All Partners Access Network (APAN) at <https://community.apan.org/>, or other transmission means determined by the government must be used.

1.6.17 Organizational Conflict of Interest (OCI) Contractor and subcontractor personnel performing work under this contract may receive, have access to, or participate in the development of proprietary or source selection information (e.g., cost or pricing information, budget information or analyses, specifications or work statements, etc.) or perform evaluation services which may create a current or subsequent Organizational Conflict of Interests (OCI) as defined in FAR Subpart 9.5. The Contractor shall notify the KO immediately whenever it becomes aware that such access or participation may result in any actual or potential OCI and shall promptly submit a plan to the KO to avoid or mitigate any such OCI. The Contractor's mitigation plan will be determined to be acceptable solely at the discretion of the KO and in the event the KO unilaterally determines that any such OCI cannot be satisfactorily avoided or mitigated, the KO may affect other remedies as he or she deems necessary, including prohibiting the Contractor from participation in subsequent contracted requirements which may be affected by the OCI.

1.6.18 Phase-in/Phase-Out (PIPO) Period: Reserved.

1.6.19 General Training Requirements:

1.6.19.1 Anti-Terrorism (AT) Level I Training: The Contractor shall complete AT Level I Training within 30 calendar days after contract start date or effective date of incorporation of this requirement into the contract, whichever applies, or 30 calendar days after employment of new personnel, all Contractor employees, including subcontractor employees, who are employed under the contract shall complete AT Level I awareness training within 30 calendar days after contract start date or effective date of incorporation of this requirement into the contract, whichever applies. The contractor shall submit certificates of completion for each affected Contractor employee and subcontractor employee to the COR or KO within ten (10) calendar days after completion of training by all employees and subcontractor personnel. For Common Access Card (CAC) holders, AT Level I awareness training is available at <https://jkodirect.jten.mil>, course number "JS-US007-14". For non-CAC holders, AT Level I awareness training is available at <http://jko.jten.mil/courses/at1/launch.html> (this standalone version is intended for non-CAC users without a JKO account only). Training must have been completed within the last 12 months and **maintained yearly thereafter**. If training cannot be conducted on the website, the Contractor will coordinate with the local AT Officer at their assigned location for classroom training by a Level 2 trained AT Officer and a copy of either the training certificate or the training attendance roster signed by the AT Officer will be maintained by the Contractor. Verification of the training will be provided to the COR or KO within ten (10) calendar days after completion of the training.

1.6.19.2 OPSEC Awareness: If the Contractor, or a subcontractor, or employees of either disclose any information that disrupts or harms the Government's operations or activities, then the Government retains the right to exclude any employee from performance of duties under this contract. The exclusion of an employee for security reasons will not relieve the Contractor from performance of services required under this contract. By way of example, personnel shall not sketch or take photos of government facilities or activities, unless related to service to be provided. All government paper products and removable digital storage material that is received, generated, or stored during the contract will be destroyed completely when no longer needed to preclude recognition of information.

1.6.19.3 Information Assurance (IA) Training :Contractor employees, including subcontractors, requiring access to Government information systems shall complete the DOD IA Cyber Awareness Training. All employees working information technology (IT)/IA functions must comply with DOD and Army training requirements per DOD Directive (DODD) 8570.01, Information Assurance Training Certification and Workforce Management, DOD 8570.01-M, Information Assurance Workforce Improvement Program, and AR 25-2, Information Assurance, within 30 days of employment. Training is available at <https://ia.signal.army.mil/DODIAA/default.asp>.

1.6.19.4 Information Assurance (IA)/Information Technology (IT) Training: All Contractor employees and subcontractor employees requiring access to Government information systems must complete the DoD IA awareness training before issuance of network access and annually thereafter. All employees working IA/IT functions must comply with DoD and Army training requirements in Per DoD 8570.01, DOD 8570.01-M, and AR 25-2, within 30 days of employment. Training is available at <https://ia.signal.army.mil/DoDIAA/default.asp>.

1.6.19.5 Threat Awareness Reporting Program (TARP Training) : RESERVED

1.6.19.6 iWATCH Training: The Contractor will ensure that all Contractor employees and sub-contractor employees performing services under this contract have been briefed on the iWATCH Program, or equivalent for their supporting DoD Agency, within 30 days of employment under the contract. The Contractor will coordinate with the supporting DoD Agency AT Officer through the COR or KO for the briefing. This training will be updated as required by the supporting installation AT policies. A copy of the training attendance will be maintained by the Contractor and made available to the COR or KO upon request.

1.6.19.7 OPSEC Training All Contractor employees and sub-Contractor employees performing services under this contract will complete Level I OPSEC training within 30 calendar days of employment under this contract. OPSEC Level I training is available at <https://jkodirect.jten.mil>, course number "EUC-ECJ6-110-N-LB". Training must have been completed within the last 12 months and maintained yearly thereafter. If training cannot be conducted on the website, the Contractor will coordinate with the local OPSEC Officer at their assigned location for classroom training by a Level 2 trained OPSEC Officer and a copy of either the training certificate or the training attendance roster signed by the OPSEC Officer will be maintained by the Contractor. Verification of the training will be provided to the COR or KO upon request.

PART 2
DEFINITIONS & ACRONYMS

2. DEFINITIONS AND ACRONYMS:

2.1. Definitions:

2.1.1. Contractor. The total contractor organization or a separate entity of it; such as an affiliate, division, or plant that performs its own purchasing.

2.1.2. Contracting officer (KO). A person with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings.

2.1.3. Contracting Officer's Representative (COR). An individual designated and authorized in writing by the contracting officer to perform specific technical or administrative functions.

2.1.4. Defective Service. A service output that does not meet the standard of performance associated with the Performance Work Statement.

2.1.5. Deliverable. Anything that can be physically delivered, but may include non-manufactured things such as meeting minutes or reports.

2.1.6. Key Personnel. Contractor personnel that are evaluated in a source selection process and that may be required to be used in the performance of a contract by the Key Personnel listed in the PWS. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the persons that are listed in the proposal.

2.1.7. Performance Work Statement (PWS). A statement of work for performance-based acquisitions that describes the required results in clear, specific, and objective terms with measurable outcomes.

2.1.8. Physical Security. Protection of the perimeter area, government property, and assets that prevent the loss or damage of Government property.

2.1.9. Quality Assurance. The various functions, including inspection, performed by the government to determine whether a Contractor has fulfilled the contract obligations pertaining to quality and quantity.

2.1.10. Quality Assurance Surveillance Plan (QASP). A plan describing how the agency will survey, observe, test, sample, evaluate and document the Contractor's performance in meeting critical performance standards identified in the contract.

2.1.11. Quality Control (QC). Tasks performed by the Contractor to improve the quality of the organization's output.

2.1.12. Shall. An imperative command; has a duty to or is required to. Denotes that a regulation must be followed unless the contracting officer has obtained a deviation.

2.1.13. Subcontractor. Any supplier, distributor, vendor, or firm that furnishes supplies or services to or for a prime contractor or another subcontractor.

2.1.14. Work Day. The number of hours per day the Contractor provides services in accordance with the contract.

2.1.15. Work Week. Monday through Friday, unless specified otherwise.

2.2 Acronyms:

ALMS	Army Learning Management System
ANSI	American National Standards Institute
AOR	Area of Responsibility
AR	Army Regulation
ATCTS	Army Training Certification Tracking System
AT	Anti-Terrorism
CAC	Common Access Card
CFR	Code of Federal Regulations
CI	Counter Intelligence
CLIN	Contract Line Item Number
CONUS	Continental United States (excludes Alaska and Hawaii)
COR	Contracting Officer Representative
DD Form 254	Department of Defense Contract Security Requirement List
DOD	Department of Defense
DODD	Department of Defense Directive
DODI	Department of Defense Instruction
FAR	Federal Acquisition Regulation
FHP	Force Health Protection
FCG	Foreign Clearance Guide
FY	Fiscal Year
GFE	Government Furnished Equipment
GFP	Government Furnished Property
IA	Information Assurance
IAW	In Accordance With
IT	Information Technology
JPAS	Joint Personnel Adjudication System
JTR	Joint Travel Regulation
KO	Contracting Officer
LOA	Letter of Authorization
NCIC-III	National Crime Information Center Interstate Identification Index
NIST	National Institute of Standards and Technology
ODC	Other Direct Costs
OCI	Organizational Conflict of Interest
OCONUS	Outside Continental United States (includes Alaska and Hawaii)
ODC	Other Direct Costs
OSHA	Occupational Safety and Health Administration
OPSEC	Operation Security
PIPO	Phase In/Phase Out
PRS	Performance Requirements Summary
PWS	Performance Work Statement
QA	Quality Assurance
QASP	Quality Assurance Surveillance Plan
QCP	Quality Control Program
RA	Requiring Activity
SCR	Service Contract Reporting
SOP	Standard Operating Procedures
SPOT	Synchronized Predeployment and Operational Tracker
TE	Technical Exhibit
TSDB	Terrorist Screening Data Base
U.S.C.	United States Code

PART 3
GOVERNMENT FURNISHED PROPERTY AND SERVICES

3.1 Government Furnished Property

The Government will not provide property or services in the performance of this contract

3.2 Emergency and Rescue

3.2.1 The Government will furnish emergency medical and rescue services to prevent loss of life, limb, or undue suffering within the areas serviced by the applicable installation emergency services provider. The Government will seek reimbursement for medical services rendered, as appropriate.

3.2.2 The Government will provide installation fire services to include firefighting, fire prevention inspections and investigations; Installation security services; confined space rescue; and Hazardous Material (HAZMAT) first response.

3.3 Telecommunications/Utilities

The Government will not provide property or services in the performance of this contract

3.4 Government Owned Vehicles

The Government will not provide vehicles in the performance of this contract

3.5 GFE Tools, Hand Tools, Equipment; Test, Measurement and Diagnostic Equipment (TDME) Calibration Services

The Government will not provide property or services in the performance of this contract

3.6 Government Furnished Facilities and Real Property

The Government will not provide property or services in the performance of this contract

3.7 Government Furnished Services

The Government will not provide property or services in the performance of this contract

3.8 The Government will provide available containers at specific contractor occupied facilities for collection of recyclable paper and cardboard, on-hand scrap metal, non-hazardous waste wood and wood by-products, and trash pickup.

PART 4

CONTRACTOR FURNISHED ITEMS AND SERVICES

4. Contractor Furnished Property and Services

4.1 General: NA

4.2 Secret Facility Clearance: NA

4.3 Materials: NA

4.4 Vehicles and Equipment: NA

4.5 Background Checks: The Contractor shall provide Background Checks in accordance with this PWS and as determined by the Government.

PART 5 SPECIFIC TASKS

5. Specific Tasks:

Contractor shall provide non-personal ISO 17025 accredited calibration services.

The contractor shall provide all labor, equipment, materials, and travel necessary to perform these services as outlined below.

- Provide ISO 17025 accredited calibration services four times per year, with each visit potentially spanning multiple days, as scheduled by the Government.
- Provide annual on-site calibration services at CTD for analytical balances, flow meters, and flow controllers, and biennial calibration for digital thermometers, using the contractor's own calibration equipment.
- Provide calibration services for each weight sets every three years, with the flexibility for calibration to be performed either on-site or off-site, including all associated shipping costs in the contract price.
- Deliver a detailed ISO 17025 accredited report of calibration for each instrument, along with a physical stamp indicating the new calibration date and accreditation. Equipment will be calibrated annually, except for digital thermometers (every two years) and weight sets (every three years).
- Offer a flexible contract capable of accommodating changes in the Government's equipment inventory. The contract shall allow for the annual adjustment of the amount of equipment calibrated, through the addition of new equipment and/or removal of obsolete equipment.
- Provide all-inclusive pricing covering calibration services, travel expenses, and shipping costs for weight sets (if applicable).

5.1. Basic Services.

The Contractor shall provide ISO 17025 accredited on-site calibration services at Dugway Proving Ground four times annually for analytical balances, digital thermometers, flow meters, and flow controllers, utilizing their own calibrated equipment; weight sets may be calibrated either on-site or off-site with all associated shipping costs included. This base year contract with four option years requires the Contractor to deliver an ISO 17025 accredited report and calibration stamp for each instrument, while accommodating Government-scheduled service dates and fluctuating equipment quantities – allowing for annual adjustments to the number and type of instruments calibrated – with all travel expenses fully incorporated into the contract price.

5.2. Task Heading. Tasks consist of the following:

5.2.1. Schedule Coordination with the Government: The Contractor will coordinate with the Government to schedule four annual on-site calibration visits to Dugway Proving Ground (DPG), covering all associated travel expenses and providing all necessary calibration equipment. Prior to each visit, the Contractor shall verify that their equipment is fully functional, recently calibrated at an ISO 17025 accredited facility and traceable to NIST or equivalent standards, and appropriate for calibrating the specific DPG equipment scheduled for service.

a) Standard:

- Base Year: Coordinate with the Government to confirm dates and the number/type of equipment available for calibration during each visit.
- Option Years: Utilize a record of the number and type of equipment calibrated in the previous year to proactively propose a calibration schedule to the Government for review and approval. This schedule will be designed to ensure all equipment is calibrated within its annual calibration cycle

and prevent any overdue calibrations, facilitating efficient planning and minimizing scheduling conflicts.

AQL:100% Compliant

5.2.2. On-site support from certified ISO 17025 technician: The contractor shall operate a laboratory that is formally accredited to ISO 17025 by a recognized accreditation body, such as A2LA. This accreditation confirms that the lab meets international standards for competence in testing and calibration. The contractor shall provide service technicians who have documented education or training and experience relevant to the calibration tasks of analytical balances, flow meters, flow controllers, digital thermometers and analytical weight sets.

- a) Standard: The proposal package shall include documentation demonstrating the contractor's ISO 17025 accreditation by a recognized accreditation body, such as A2LA, as well as proof of relevant training and qualifications for each service technician performing calibrations on the specified equipment types.
AQL:100% Compliant
- b) Standard: The contractor shall include in their proposal package a summary of the ISO 17025 calibration procedures intended for use on each equipment type (analytical balances, flow meters, flow controllers, digital thermometers, and analytical weight sets) along with the uncertainty values from their ISO accredited calibration methods. This will provide the Government with visibility into the calibration process, ensuring alignment with ISO 17025 standards and traceability to appropriate standards; detailed technical specifics are not required, but a clear overview of the documented procedures is necessary.
AQL:100% Compliant
- c) Standard: The contractor shall verify US citizenship of their personnel who will perform the service at Dugway. This verification must be sent to the Contracting Officer's Representative (COR) via email within 24 hours after scheduling an onsite service.
The standard doesn't apply if the same person/service technician of the contractor comes to Dugway to perform the service the second time.
AQL:100% Compliant

5.2.3. Prior to performing services at DPG, the contractor shall complete all required training in section 1.6.19 of this PWS.

- a) Standard: Submit training completion documentation to the COR at least 24 hours before the initial on-site service at DPG.
AQL:100% Compliant

5.2.4. Maintain ISO 17025 Accreditation: Continuously maintain valid ISO 17025 accreditation throughout the contract period.

- a) Standard: Provide proof of accreditation upon request.
AQL:100% Compliant

5.2.5. On-Site Calibration Tasks (During Each Site Visit)

5.2.5.1 Analytical Balance Calibration: The contractor shall perform the calibration of analytical balances according to a validated procedure traceable to ISO 17025 standards.

- a) Standard: Verify linearity, repeatability, and eccentricity. Adjust balances as needed.
AQL:100% Compliant

5.2.5.2. Digital Thermometer Calibration:

The contractor shall perform the calibration of thermometers at 4 °C using an ISO 17025 accredited NIST traceable reference

- a) Standard. Confirm both accuracy and resolution.
AQL:100% Compliant

5.2.5.3. Flow Meter & Flow Controller Calibration:

The contractor shall perform the calibration of flow meters and controllers using a flow standard traceable to national or international references. Confirm accuracy, linearity, and repeatability, and conduct calibrations across multiple flow rates in accordance with ISO/IEC 17025 requirements.

a) Standard: Calibration of 0–2 L/min flow devices must be conducted using standards traceable to the International System of Units (SI), such as those certified by a national metrology institute like NIST. Calibration must include an estimation and documentation of measurement uncertainty, which is especially critical at low flow rates where small errors have greater impact. Devices should be tested at five points across their range (e.g., 0.0 to 2.0 L/min) to assess linearity and accuracy.

AQL:100% Compliant

5.2.5.4. Weight Set Calibration (On-Site or Off-Site): The contractor shall perform the calibration of Class1 weight sets either on-site at DPG or at the contractor's facility.

a) Standard: Calibrate weight sets using measurement equipment traceable to national standards, in compliance with ISO17025 requirements.

For off-site: The Government will securely package and ship weight sets to the Contractor's facility for calibration, with the Contractor responsible for all shipping costs to and from Dugway. Calibrated weight sets must be returned to DPG within 14 days of receipt at the Contractor's facility.

AQL:100% Compliant

5.2.6. Deliverables

The Contractor shall provide the following deliverables for each calibration event:

- ISO 17025 Calibration Report: A detailed ISO 17025 compliant report of calibration for each instrument, including all relevant data and traceability information.
- Calibration Stamp: A physical stamp affixed to each calibrated instrument indicating the new calibration date and ISO 17025 accreditation.
- Calibration Cycle: Equipment will be calibrated annually, except for digital thermometers (every two years) and weight sets (every three years).

a) Standards:

- Submit all calibration reports to the COR within five business days of completing the calibration services.
- Apply a new calibration label/stamp to each instrument immediately following calibration.

AQL:100% Compliant

5.2.7. Contractor Manpower Reporting : N/A

5.3. Service Contract Reporting (SCR): Reserved

PART 6
APPLICABLE PUBLICATIONS

6. **APPLICABLE PUBLICATIONS (CURRENT EDITIONS)** The following publications, manuals, regulations, etc. are mentioned in this PWS and are listed below.

6.1. Department Of Defense Contract Security Classification Specification (DD Form 254)

6.1.1 Department of Defense Security Agreement (DD Form 441)

6.1.2 National Industrial Security Program Operating Manual (DoD 5220.22-M)

6.1.3 Installation Access Control (AE Reg 190-16)

6.1.4 The Army Physical Security Program (AR 190-13)

6.1.5 Contractor Identification (AE Reg 27-715)

6.1.6 U.S. Army Corps of Engineers Safety and Health Requirements Manual (EM 385-1-1)

6.1.7 Information Assurance Workforce Improvement Program (DoD 8570-M)

6.1.8 Information Assurance Training Certification and Workforce Management Directive (DoDD 8570.01)

6.1.9 Information Assurance (AR 25-2)

6.1.10 Electromagnetic Compatibility Directive (2004/108/EC)

6.1.11 Policies and Procedures for Property Accountability (AR 735-5)

PART 7
ATTACHMENT/TECHNICAL EXHIBIT LISTING

7. Attachment and Technical Exhibit List

7.1 Technical Exhibit A – Performance Requirements Summary

7.2 Technical Exhibit B – Deliverables Schedule

TECHNICAL EXHIBIT A

Performance Requirements Summary

Performance Objective (The Service required—usually a shall statement)	Standard	Performance Threshold (This is the maximum error rate. It could possibly be “Zero deviation from standard”)	Incentive (Positive and/or Negative)
PRS#1. Schedule Coordination with the Government (PWS para. 5.2.1) Schedule Coordination with the Government: The Contractor will coordinate with the Government to schedule four annual on-site calibration visits to Dugway Proving Ground (DPG), covering all associated travel expenses and providing all necessary calibration equipment. Prior to each visit, the Contractor shall verify that their equipment is fully functional, recently calibrated and traceable to NIST or equivalent standards, and appropriate for calibrating the specific DPG equipment scheduled for service.	Base Year: Coordinate with the Government to confirm dates and the number/type of equipment available for calibration during each visit. Option Years: Utilize a record of the number and type of equipment calibrated in the previous year to proactively propose a calibration schedule to the Government for review and approval. This schedule will be designed to ensure all equipment is calibrated within its annual calibration cycle and prevent any overdue calibrations, facilitating efficient planning and minimizing scheduling conflicts.	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service Non-conforming services will result in Corrective Action Request (CAR) reports issued to Contractor and potential negative CPARS report.
PRS #2. On-site support from certified ISO 17025 technician PWS para. 5.2.2 On-site support from certified ISO 17025 technician: The contractor shall operate a laboratory that is formally accredited to ISO 17025 by a recognized accreditation body A2LA. This accreditation confirms that	The proposal package shall include documentation demonstrating the contractor’s ISO 17025 accreditation by a recognized accreditation body, such as A2LA, as well as proof of relevant training and qualifications for each service technician performing calibrations on the specified equipment types. The contractor shall include in their proposal package a summary of the ISO 17025 calibration procedures intended for use on each equipment type (analytical balances, flow meters, flow controllers, digital thermometers, and analytical weight sets).	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service Non-conforming services will result in Corrective

the lab meets international standards for competence in testing and calibration. The contractor shall provide service technicians who have documented education or training and experience relevant to the calibration tasks of analytical balances, flow meters, flow controllers, digital thermometers and analytical weight sets.	This will provide the Government with visibility into the calibration process, ensuring alignment with ISO 17025 standards and traceability to appropriate standards; detailed technical specifics are not required, but a clear overview of the documented procedures is necessary. The contractor shall verify US citizenship of their personnel who will perform the service at Dugway. This verification must be sent to the Contracting Officer's Representative (COR) via email within 24 hours after scheduling an onsite service. The standard doesn't apply if the same person/service technician of the contractor comes to Dugway to perform the service the second time.		Action Request (CAR) reports issued to Contractor and potential negative CPARS report.
PRS # 3. Training (PWS. 5.2.3) Prior performing services at DPG, the contractor shall complete all required training in section 1.6.19 of this PWS.	Submit training completion documentation to the COR at least 24 hours before the initial on-site service at DPG. Training required are: -Antiterrorism (AT) Level I Training - Information Awareness (IA) Training - Information Assurance (IA)/ Information Technology (IT) Training - iWATCH training - Level I OPSEC Training	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service Non-conforming services will result in Corrective Action Request (CAR) reports issued to Contractor and potential negative CPARS report.
PRS# 4. Certifications (PWS 5.2.4) Maintain ISO 17025 Accreditation: Continuously maintain valid ISO 17025 accreditation throughout the contract period.	On an annual basis, Provide proof of accreditation upon request.	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service Non-conforming services will result in Corrective Action Request (CAR) reports issued to

			Contractor and potential negative CPARS report.
PRS#5. On-site Calibration Tasks – Analytical Balance (During Each Site Visit) (PWS 5.2.5.1) Analytical Balance Calibration: The contractor shall perform the calibration of analytical balances according to a validated procedure traceable to ISO 17025 standards.	. Verify linearity, repeatability, and eccentricity. Adjust balances as needed.	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service Non-conforming services will result in Corrective Action Request (CAR) reports issued to Contractor and potential negative CPARS report.
PRS#6. On-site Calibration Tasks – Digital Thermometer Calibration (During Each Site Visit) (PWS 5.2.5.2) Digital Thermometer Calibration: The contractor shall perform the calibration of thermometers at 4 °C using a traceable reference	Calibrate at 4 degrees Celsius. Confirm both accuracy and resolution.	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service Non-conforming services will result in Corrective Action Request (CAR) reports issued to Contractor and potential negative CPARS report.
PRS#7. On-site Calibration Tasks – Flow Meter and Flow Controller Calibration (During Each Site Visit) (PWS 5.2.5.3) Flow Meter & Flow Controller Calibration:	Calibration of 0–2 L/min flow devices must be conducted using standards traceable to the International System of Units (SI), such as those certified by a national metrology institute like NIST. Calibration must include an estimation and documentation of measurement uncertainty, which is especially critical at low flow rates where small errors have greater impact. Devices should be tested	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service

The contractor shall perform the calibration of flow meters and controllers using a flow standard traceable to national or international references. Confirm accuracy, linearity, and repeatability, and conduct calibrations across multiple flow rates in accordance with ISO/IEC 17025 requirements.	at five points across their range (e.g., 0.0 to 2.0 L/min) to assess linearity and accuracy.		Non-conforming services will result in Corrective Action Request (CAR) reports issued to Contractor and potential negative CPARS report.
PRS#8. On-site Calibration Tasks – Weight Set Calibration (During Each Site Visit) (PWS 5.2.5.4) Weight Set Calibration (On-Site or Off-Site): The contractor shall perform the calibration of Class1 weight sets either on-site at DPG or at the contractor's facility.	Calibrate weight sets using measurement equipment traceable to national standards, in compliance with ISO17025 requirements. For off-site: The Government will securely package and ship weight sets to the Contractor's facility for calibration, with the Contractor responsible for all shipping costs to and from DPG. Calibrated weight sets must be returned to DPG within 14 days of receipt at the Contractor's facility.	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service Non-conforming services will result in Corrective Action Request (CAR) reports issued to Contractor and potential negative CPARS report.
PRS#9. Deliverables (During Each Site Visit) (PWS 5.2.6) The Contractor shall provide the following deliverables for each calibration event: • ISO 17025 Calibration Report: A detailed ISO 17025 compliant report of calibration for each instrument, including all relevant data and traceability information. • Calibration Stamp: A physical stamp affixed to each calibrated instrument indicating the new calibration date and ISO 17025 accreditation.	• Submit all calibration reports to the COR within five business days of completing the calibration services. • Apply a new calibration label/stamp to each instrument immediately following calibration.	Zero deviation from the standard.	Contractor compliance rate shall be utilized as objective evidence of contract compliance and documented into the CPAR system; contractor shall re-perform the service Non-conforming services will result in Corrective Action Request (CAR) reports issued to Contractor and potential negative CPARS report.

• Calibration Cycle: Equipment will be calibrated annually, except for digital thermometers (every two years) and weight sets (every three years).			

TECHNICAL EXHIBIT B
Deliverables Schedule

<u>Deliverable</u>	<u>Frequency</u>	<u># of Copies</u>	<u>Medium/Format</u>	<u>Submit To</u>
On-site support from certified ISO 17025 technician [PWS para. 5.2.2] Proof of relevant training and qualifications for each service technician performing calibrations on the specified equipment types.	The contractor shall annually submit the updated documentation to the COR	The contractor will submit an electronic copy to the COR at the start of each contract year.	Documentation shall be submitted via email	The COR
On-site support from certified ISO 17025 technician [PWS para. 5.2.2] The contractor shall include in their proposal package a summary of the ISO 17025 calibration procedures intended for use on each equipment type (analytical balances, flow meters, flow controllers, digital thermometers, and analytical weight sets). This will provide the Government with visibility into the calibration process, ensuring alignment with ISO 17025 standards and traceability to appropriate standards; detailed technical specifics are not required, but a clear overview of the documented	The contractor shall annually submit the updated documentation to the COR	The contractor will submit an electronic copy to the COR at the start of each contract year.	Documentation shall be submitted via email	The COR

<u>Deliverable</u>	<u>Frequency</u>	<u># of Copies</u>	<u>Medium/Format</u>	<u>Submit To</u>
procedures is necessary.				
Maintain ISO 17025 Accreditation [PWS para. 5.2.4]	The contractor shall annually submit the updated documentation to the COR	The contractor will submit an electronic copy to the COR at the start of each contract year.	Documentation shall be submitted via email	The COR
Deliverables [PWS para. 5.2.5.4] ISO calibration report: A detailed ISO 17025 compliant report of calibration for each instrument, including all relevant data and traceability information.	The contractor shall submit all calibration reports for each equipment to the COR within five business days of completing the calibration services	The contractor shall either submit an electronic copy to the COR or provide access to the company's database to allow the COR to download the record.	Documentation shall be submitted via email	The COR
Deliverables [PWS para. 5.2.5.4] A physical stamp affixed to each calibrated instrument indicating the new calibration date and ISO 17025 accreditation	Apply a new calibration label/stamp to each equipment immediately following calibration.	One label or stamp for each equipment	Sticker	NA