

US Department of Agriculture (USDA)



United States Department of Agriculture

Forest Service

Black Hills National Forest

Black Hills Campground Reconstruction

Comanche Park Campground Statement of Work

Contents

Project.....	3
General Information.....	3
1.0 Scope of Work.....	3
2.0 Background.....	3
Contractor Requirements.....	3
3.0 Technical Requirements / Tasks.....	3
4.0 Government Furnished.....	3
5.0 Deliverables / Schedule.....	4
6.0 Travel.....	9
7.0 Contractor’s Key Personnel.....	9
8.0 Security Requirements.....	9
9.0 Data Rights.....	9
10.0 Section 508 – Electronic and Information Technology Standards.....	9

Project

Comanche Park Campground Reconstruction

General Information

1.0 Scope of Work

Comanche Park Campground is located 6.5 miles west of Custer, SD on US16.

The Campground will be improved from 20 sites to 34 sites. The road will be modified with curve widening and shaping for drainage and new surfacing. The Host Site and Volunteer Site will be relocated and upgraded with power, water and wastewater vaults. 4 new pre-cast vault toilets will replace the five original 1965 stick-built toilets. The Water system work for this project consists of decommissioning the existing pumphouse, installing a new pre-cast concrete treatment building in a new location, with upgraded plumbing and controls, removing the existing aboveground water storage tank and installing a new below ground fiberglass water storage tank, replacing all the distribution piping and installing new hydrants. Work shall start approximately 10 days from the Notice to Proceed (NTP) and be completed 392 days from the NTP.

2.0 Background

The Comanche Park Campground is a seasonal campground operating from approximately mid-May to mid-September annually. To access Comanche CG from downtown Custer, South Dakota, travel west on US Highway 16 for approximately 6.5 miles. Comanche Park Campground is on the left (south) side of the Highway. Comanche CG currently has 20 camping spurs inside the Campground gate and 2 sites outside the gate that are primitive and poorly defined. There are currently five stick-built toilet buildings dating from 1965 at Comanche CG. These toilet buildings will be demolished. This is a Congressionally approved Great American Outdoors project that will include the design and reconstruction of Comanche Park Campground to accommodate modern recreational vehicle sites with modern design and amenities. Work will remove and replace leaking toilets and replace the water system and upgrade host sites. Project may include new trails to connect Campground to nearby motorized trail system.

Contractor Requirements

3.0 Technical Requirements / Tasks

Contractors should demonstrate a thorough understanding of the project requirements and attention to detail is crucial for quality construction. Strong communication skills are essential for coordinating with clients, subcontractors and other stakeholders. Experience in campground construction, general contracting, and road construction is beneficial. Contractors should have the capacity to handle the specific project requirements and deliver within the specified timeline.

A full copy of the Contract Specifications can be found with this solicitation.

A full copy of the Contract Construction Plans can be found with this solicitation.

4.0 Government Furnished

There are no Government Furnished Materials associated with this project.

Key Deliverables

Item No.	Deliverable / Item Title	Description	Frequency	Reference	Delivery Format	Due By
1	Accident Prevention Plan	Design the plan to address Federal, State, and Local Occupational Safety and Health requirements that apply to this project	Once	Specifications General Requirements 2.2.A	Via email to COR	10 days prior to on-site work beginning
2	Action Submittals	Written and graphic information that requires Contracting Officer's(CO's) responsive action.	Prepare and submit Action Submittals required by individual Specification Sections.	Specifications General Requirements 3.4	Submit four copies of each submittal, unless otherwise indicated.	Before beginning work on individual item
3	Informational Submittals	Prepare and submit Informational Submittals required by other Specification Sections.	Prepare and submit Action Submittals required by individual Specification Sections.	Specifications General Requirements 3.5.A	Submit two copies of each submittal, unless otherwise indicated.	Before beginning work on individual item
4	Contractor's Construction Schedule	Provide a construction schedule that incorporates the full contract period.	Once	Specifications General Requirements 3.5.B	Via email to COR	10 days prior to on-site work beginning. Monthly interval
5	Upcoming Work Summary	Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update.	Monthly	Specifications General Requirements 3.5.C	Via email to COR	10 days prior to on-site work beginning. Monthly interval
6	Construction Schedule Updating Report	At monthly intervals, update schedule to reflect actual construction progress and activities.	Submit with Applications for Payment	Specifications General Requirements 3.5.D	Via email to COR	Monthly
7	Daily Construction Reports	Prepare a daily construction report recording information concerning events at Project site	Monthly	Specifications General Requirements 3.5.E	Via email to COR	Monthly
Item No.	Deliverable / Item Title	Description	Frequency	Reference	Delivery Format	Due By

8	Site Condition Reports	Report of differing site conditions	Submit at time of discovery of differing conditions.	Specifications General Requirements 3.5.F	Via email to COR	Before continuation of work on individual item
9	Cost Breakdown	Provide a cost breakdown schedule listing main types of work	Following Award	Specifications General Requirements 3.5.G	Via email to COR	Following Award
10	Project Record Documents	Record Drawings; Record Specifications; Record Product Data	Project Closeout	Specifications General Requirements 5.5, 5.6, 5.7	Digital file Via email to COR	Project Closeout
11	Operation and Maintenance Manual	furnish two complete sets of operation and maintenance (O&M) data	Before scheduling a final inspection	Specifications General Requirements 5.8	Digital file Via email to COR	Within 30 days following receipt of review comments
12	Testing Agency Qualifications	proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.	Once	Specifications Quality Requirements 1.4.A	Digital file Via email to COR	Before beginning work on individual item
13	Permits, Licenses, and Certificates	submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents established for compliance with standards and regulations bearing on performance of the Work.	Once	Specifications Quality Requirements 1.4.B	Digital file Via email to COR	Before beginning work on individual item
14	Test and Inspection Reports	Prepare and submit certified written reports specified in other Sections	Prepare and submit test and inspection reports as required by individual Specification Sections.	Specifications Quality Requirements 1.5.A	Digital file Via email to COR	Submit test and inspection reports as required by individual Specification Sections.
Item No.	Deliverable / Item Title	Description	Frequency	Reference	Delivery Format	Due By

15	Manufacturer's Technical Representative's Field Reports	Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections	Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections	Specifications Quality Requirements 1.5.B	Digital file Via email to COR	Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections
16	Factory-Authorized Service Representative's Reports	Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections.	Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections.	Specifications Quality Requirements 1.5.C	Digital file Via email to COR	Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections.

Key Deliverables

Item No.	Deliverable / Item Title	Description	Frequency	Reference	Delivery Format	Due By
1	Accident Prevention Plan	Design the plan to address Federal, State, and Local Occupational Safety and Health requirements that apply to this project	Once	Specification s General Requirements 2.2.A	Via email to COR	10 days prior to on-site work beginning
2	Action Submittals	Written and graphic information that requires Contracting Officer's(CO's) responsive action.	Prepare and submit Action Submittals required by individual Specification Sections.	Specification s General Requirements 3.4	Submit four copies of each submittal, unless otherwise indicated.	Before beginning work on individual item
3	Informational Submittals	Prepare and submit Informational Submittals required by other Specification Sections.	Prepare and submit Action Submittals required by individual Specification Sections.	Specification s General Requirements 3.5.A	Submit two copies of each submittal, unless otherwise indicated.	Before beginning work on individual item

4	Contractor's Construction Schedule	Provide a construction schedule that incorporates the full contract period.	Once	Specification s General Requirements 3.5.B	Via email to COR	10 days prior to on-site work beginning. Monthly interval
5	Upcoming Work Summary	Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update.	Monthly	Specification s General Requirements 3.5.C	Via email to COR	10 days prior to on-site work beginning. Monthly interval
6	Construction Schedule Updating Report	At monthly intervals, update schedule to reflect actual construction progress and activities.	Submit with Applications for Payment	Specification s General Requirements 3.5.D	Via email to COR	Monthly
7	Daily Construction Reports	Prepare a daily construction report recording information concerning events at Project site	Monthly	Specification s General Requirements 3.5.E	Via email to COR	Monthly
Item No.	Deliverable / Item Title	Description	Frequency	Reference	Delivery Format	Due By
8	Site Condition Reports	Report of differing site conditions	Submit at time of discovery of differing conditions.	Specification s General Requirements 3.5.F	Via email to COR	Before continuation of work on individual item
9	Cost Breakdown	Provide a cost breakdown schedule listing main types of work	Following Award	Specification s General Requirements 3.5.G	Via email to COR	Following Award
10	Project Record Documents	Record Drawings; Record Specifications; Record Product Data	Project Closeout	Specification s General Requirements 5.5, 5.6, 5.7	Digital file Via email to COR	Project Closeout
11	Operation and Maintenance Manual	furnish two complete sets of operation and maintenance (O&M) data	Before scheduling a final inspection	Specification s General Requirements 5.8	Digital file Via email to COR	Within 30 days following receipt of review comments
12	Testing Agency Qualifications	proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.	Once	Specification s Quality Requirements 1.4.A	Digital file Via email to COR	Before beginning work on individual item

13	Permits, Licenses, and Certificates	submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents established for compliance with standards and regulations bearing on performance of the Work.	Once	Specification s Quality Requirements 1.4.B	Digital file Via email to COR	Before beginning work on individual item
14	Test and Inspection Reports	Prepare and submit certified written reports specified in other Sections	Prepare and submit test and inspection reports as required by individual Specification Sections.	Specification s Quality Requirements 1.5.A	Digital file Via email to COR	Submit test and inspection reports as required by individual Specification Sections.
Item No.	Deliverable / Item Title	Description	Frequency	Reference	Delivery Format	Due By
15	Manufacturer's Technical Representative's Field Reports	Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections	Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections	Specification s Quality Requirements 1.5.B	Digital file Via email to COR	Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections
16	Factory-Authorized Service Representative's Reports	Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections.	Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections.	Specification s Quality Requirements 1.5.C	Digital file Via email to COR	Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections.

6.0 Travel

Travel is the responsibility of the contractor.

7.0 Contractor's Key Personnel

The Contractor is to provide name, position title and contact information of company executive responsible for the project. Contractor is to provide an onsite superintendent at all times.

Water system installers must meet all State of South Dakota licensing requirements.

Electricians performing electrical installation must have a South Dakota Electrical License. State Electrical Inspection and approval is required on all electrical work.

8.0 Security Requirements

The Contractor is to install and maintain suitable barriers to ensure the protection of the public, employees, and facilities. Protect persons, motor vehicles, surrounding buildings, plants, and surrounding surfaces or buildings from harm resulting from Contractor's work.

Site gate lockout procedures will be established if applicable.

9.0 Data Rights

Data will not be produced with this construction contract.

10.0 Section 508 – Electronic and Information Technology Standards

Information technology will not be acquired with this construction contract.