

Hazard Tree Removal – 16 Trees



Hazard Tree Removal
Hazard Tree Mitigation
16 Tree & Stump Removal
Package name: **HTM-001 FY-26**

PART 1: GENERAL

1.1 PROJECT DESCRIPTION:

1. The contractor shall provide all labor, supervision, materials, tools, supplies, transportation, barricades, signs, traffic control measures/coordination and equipment incidental to the removal of a tree in accordance with industry standards and best management practices (BMPs) as identified around the National Mall and Memorial Parks.

1.2 SCOPE OF WORK:

Task: *Tree removal of tree identified in associated SOW.*

- a All work performed in accordance with the most up to date ANSI and OSHA standards.
- b Take down 16 trees in a controlled and safe fashion. Remove all resulting debris from site and dispose of off campus by following all local, state, and federal DOT and dumping laws.
- c Grind the associated 16 stumps completely and backfill with NAMA approved topsoil.
Grind stumps completely through bottom of stump. Grind all roots 1" diameter and larger throughout root mat. Backfill stump hole with NAMA approved topsoil.

Technical Requirements:

- 1) Grind depth shall be 24" inches below grade or once through the bottom of the stump. The contractor is responsible for coordinating utility markings for each stump.
- 2) ALL (100%) shavings/grinded stump and root material shall be removed from the stump hole! All roots 1" diameter and larger shall be ground. The stump site shall be backfilled with a soil mixture to meet the following specifications in "Soil Requirements" below. A certificate from the topsoil provider shall be supplied to the COR prior to installation. Examples of topsoil providers, in no particular order are:
 - [Stancills](#),

- TE Woods,
- Egypt Farms,
- JK Enterprises

Soil Requirements:

- a) Shall be a screened, natural, surface soil, in a friable condition and contain less than 3 percent subsoil. The topsoil shall be free of hardpan material, stones and clods larger than 1/2 inch in diameter, sticks, tree or shrub roots, debris, toxic substances (i.e. residual herbicides) and other material detrimental to plant growth. The area and the topsoil shall be free of undesirable plants or plant parts such as, but not limited to, bermudagrass, nut sedge, mugwort, Johnson grass, quack grass, Canada thistle or noxious weeds as set forth in the Federal Seed Act.
- b) Contractor shall notify NPS of location of all sources of the topsoil and furnish the NPS a certified report from the agricultural experiment station or approved agricultural laboratory of an analysis performed not more than 60 days prior to the date of submission. The topsoil shall be certified to meet the following requirements:
 - (1) Shall be a natural, original surface soil of a sandy loam texture with a mechanical analysis of 50%-65% sand, 15-25% silt and 10-35% clay.
 - (2) Shall have at least 2%, but not more than 5%, organic matter.
 - (3) Soil pH shall 5.5 to pH 7.2 inclusive unless otherwise specified.
 - (4) Soil salinity by electrical conductivity measurement shall not exceed 600 parts per million (ppm) as determined by Black, Editor "Method of Soil Analysis", Part 2, published by the American Society of Agronomy, 1965.
 - (5) The soil nutrient level shall be between 70-265 lbs. /acre of magnesium, 65-205 lbs./acre of phosphorous (P₂O₅), and 85-320 lbs./acre of potassium (K₂O).
 - (6) Agricultural limestone at not more than 5 pounds per cubic yard of topsoil may be used to adjust an acidic condition and shall be thoroughly mixed by volume.
 - (7) Topsoil which has been synthesized by blending materials which individually do not meet the requirements of this specification will not be accepted even though the resulting blend meets the organic matter, mechanical analysis, Ph and soluble salts requirements.
 - (8) Topsoil shall not be delivered or handled in a frozen or muddy condition.

Areas of Operation:

- Ash Woods (flanking both sides of the DC War Memorial) Trees #1 - 12
- West Basin Dr. – Tree #13
- Independence Ave. (west of West Basin Dr.) Trees #14 – 16

* See associated Areas of Operation Power Point

1.3 PERIOD OF PERFORMANCE:

From May 4, 2026 – July 20, 2026, or within 75 days of awarded date.

Expect blackout dates surrounding the 4th of July.

1.4 PROTECTION OF GOVERNMENT PROPERTY:

1. The Contractor shall assume full liability and responsibility for any loss or damage to Government property caused by his operations and shall assume full responsibility for any and all damages or claims for damage for injury to persons, property or equipment which might result from any service performed under this contract. The Contractor shall be responsible for the repair or replacement of all damaged government property caused by his operations.

2. **Tree and Turf Protection:** All motorized and non-motorized equipment used shall be conveyed and staged on industry appropriate turf protection mats (e.g. Alturna mats, Trak-Mats, ½" plywood, etc.) designed for the purpose of protecting soil, turf and Critical Root Zones (CRZ's) when operating off paved surfaces. At no time shall motor vehicles or heavy equipment be in direct contact with soil, turf or critical root zones. At no time shall "over-the-road" DOT tires be in direct contact with soil, turf, or critical root zones. Extra wide, low PSI "floatation tires" made for the purpose are exempt (e.g., golf carts, ATV's)

1.5 PERMITS AND RESPONSIBILITIES:

1. The contractor shall, without additional expense to the Government, be responsible for obtaining and renewing all necessary licenses and permits.

2. The contractor shall be responsible for all damages to persons or property that occur as a result of the contractor's negligence and shall take proper safety and health precautions to protect the work, the workers, the public and the property of others.

3. The contractor shall be responsible for all materials delivered and work performed until completion and acceptance of the entire work.

1.6 ON-SITE SUPERVISOR:

1. As a minimum, the contractor must provide one on-site supervisor to direct all contract personnel and maintenance operations.
2. The on-site supervisor shall be fluent in the English language in order to effectively communicate with the contractor's employees and/or subcontractors as well as the COR and other Government personnel.
3. If the on-site supervisor is not present or otherwise absent, the contractor shall provide an alternate supervisor to manage and direct all contract personnel and operations. The alternate supervisor shall possess the same qualifications as the on-site supervisor.
4. The onsite supervisor shall be available for phone calls during all working hours.
5. A current ISA Certified Arborist shall be on the job site at all times and shall be the primary contact with the Government's technical representative responsible for controlling the quality of work and inspecting all completed work in order to ensure that contract performance requirements are met. The contractor shall provide the arborist's certification ID for verification before work begins, and any time there is a change in the onsite arborist. Certification and currency will be subject to verification by the government utilizing the ISA database.

1.7 CONDUCT:

1. The contractor's employees shall, at all times while on the job site, whether on or off duty, conduct themselves in a professional, orderly and safe manner. Rudeness, fighting, being under the influence of alcohol and/or drugs or bringing and/or consuming alcohol and/or drugs, gambling, soliciting, stealing, and any immoral or otherwise undesirable conduct shall not be permitted on the job site and shall result in immediate and permanent removal from the job site of any employee engaging in such conduct.

2.1 SITE MAINTENANCE:

1. The contractor shall maintain the work site in a safe, neat and orderly manner. All supplies and equipment on the project site shall be stored to preclude any damage.
2. Limited space may be provided for the storage of materials, which shall be stored in a clean and neat condition as approved by the COR. This is not guaranteed; thus, the contractor must be prepared to transit the entire operational footprint daily.
3. All mud, dirt, debris, foreign objects or spills of any kind from the contractor's operations shall be cleaned up daily or as requested by the COR.

4. All contractor generated refuse and waste shall be hauled from the work site daily. Refuse and waste material shall be hauled in trucks with tight fitting covers to prevent spillage on roadways.
5. It shall be the contractor's responsibility to take whatever measures are necessary to assure the protection of the Government assets and to perform the work so as to cause minimal disruption of ongoing activities near occupied areas.
6. The contractor assumes the risk and responsibility for the loss or damage to the Government furnished property.
7. Any/all turf protection mats shall be removed from turf nightly. No mats to remain on soil/turf overnight.

2.2 ENVIRONMENTAL CONCERNS AND SAFETY STANDARDS:

1. The contractor and each of his employees shall work in compliance with all applicable OSHA, Federal, state and local safety laws and regulations (e.g. CFR29, etc).
2. The contractor will be in compliance with ANSI Z133.1 standards.
3. The contractor shall provide and ensure that all personnel at the work site use the proper Personal Protective Equipment (PPE) required by OSHA regulations and ANSI standards.
4. The contractor shall take all necessary precautions for safety and shall provide reasonable protection to prevent damage, injury or loss to people, properties, equipment and vehicles.
5. In the event of an emergency the contractor should first call **911**. For other nonemergency issues requiring a law enforcement officer, the US Park Police watch desk may be reached at **(202) 438-1617**.
6. Damage caused by the contractor to any properties shall be repaired or replaced to the satisfaction of the Government at the expense of the contractor. The Government, at its sole direction, may elect to repair or replace the damaged property, and deduct such costs from monies due the contractor.
7. The contractor shall not leave any tools, parts and/or supplies unattended in the public area at any time while performing work.
8. The contractor shall report damage caused to US Government trees or landscape immediately to the COR or NAMA staff Arborist.

2.3 VEHICLE OPERATIONS

Contractor personnel operating motor vehicles used in performance of this contract shall have a valid state operator's license and shall operate all motor vehicles in

accordance with applicable laws. The contractor's vehicles shall have an identification tag clearly visible while on site.

3.1 QUALITY ASSURANCE:

1. When the contractor considers work is acceptable to the Government and complete, the contractor shall inform the COR that the work is complete and ready for inspection. The COR will inspect the work on-site in consultation with the staff arborist. In the event that the work is not acceptable, the contractor shall record a list of items noted by the Government to be corrected. A subsequent inspection may take place in order to review the corrected items.

Upon completion, the contractor shall provide the government with a work/treatment log denoting the work performed by specimen. The work log shall utilize standard industry terms and include any tree health or hazard concerns noted during work performance. Contractor work log entries will be used to build historical tree health data archives and better inform urban forest management decisions within the park.

The Contractor shall submit all invoices through www.ipp.gov within 30 days of work performed or on a monthly basis. All Invoices will have the work performed broken out on them along with the location site clearly defined. Failure of the contractor to upload an attached copy of the invoice and any requested documentation through IPP.gov will result in invoice being rejected.