

STATEMENT OF WORK
Project Number 202500184
Installation of Exhaust System
FACILITY 420

1. **SCOPE:** The proposed work on this project consists of providing and installing a fully automatic Diesel Exhaust Extraction System at Building 420, Fire Department of The West Virginia Air National Guard (ANG) at McLaughlin Air National Guard Base.

2. **LOCATION:** West Virginia Air National Guard, 1679 Coonskin Drive, Charleston, West Virginia, 25311-5000.

3. **WORK TO BE ACCOMPLISHED:** The work to be performed includes the following principal features:

A. Special Notes -

1) Daily removal of debris shall be accomplished at the end of each workday. No materials may be left on the work site that may be blown by wind or present a hazard to vehicle or pedestrian traffic.

2) Welding, cutting and burning operations may be anticipated in this project. The Contractor shall contact the Base Fire Department at 341-6220 to receive the Burning and Welding Permit prior to starting any operations that produce a spark or flame such as burning, welding, grinding, cutting or drilling.

B. Waste Disposal and Site Clean Up -

1) The Contractor shall dispose of all demolition debris or materials at off Base location(s) in compliance with all State and Federal and local regulatory guidelines. The Contractor shall submit dump receipts or tickets to the Base Civil Engineer.

2) The Contractor is encouraged to recycle materials recovered during the demolition process whenever possible. The Contractor shall provide the BCE with a list of recycled materials. Documentation of recycled materials should include the approximate weight and cubic feet of each material.

C. New Work –

1) The Contractor shall install a custom-configured, ceiling-mounted vehicle exhaust removal system designed to accommodate up to 12 different fire apparatus in the station.

2) The system shall include a magnetic nozzles that connect directly to the tailpipes of the vehicles to remove 100% of toxic diesel exhaust gases and particulates directly at the source, preventing them from entering the breathing area of the firehouse.

- 3) The system shall include an automatic release. When a vehicle leaves on an emergency run, the nozzle stays connected to the tailpipe until the apparatus reaches the bay door, at which point it automatically releases.
- 4) The system shall include an exhaust fan that is an automatic, high-efficiency, spark-resistant exhaust fan that runs to pull the exhaust through the ductwork and outside.
- 5) The system shall include an auto-start control panel that provides auto start/stop operation with adjustable timer, manual override switch, and wireless capability.

4. **TIME FOR COMPLETION:** The entire work shall be accomplished within 14 days after date of issuance of the Notice to Proceed.

5. **TOUR OF THE JOB SITE:** Site visit will be announced in the solicitation on SAM.gov

6. **PERFORMANCE:**

a. Submission of a bid by a Contractor shall be accepted as prima-facie evidence that he has examined the specifications and has satisfied himself as to the nature and location of the work and all other matters which can in any way effect the work or cost thereof under this contract. Any failure of the Contractor to acquaint himself with all available information, including a physical survey of the site of the proposed work, will not relieve him from successfully performing all the work required for a complete finished job.

b. The above brief outline of principal features of the work in no way limits the responsibility of the Contractor to perform all work and furnish all plant, labor, and materials required by the specifications and plans referred to herein.

c. Installation, workmanship, and all materials shall be guaranteed in writing by the Contractor to be free from defect under normal use for a period of at least one year. All repairs by the Contractor shall be performed at no expense to the Government.

d. Material submittals shall be accomplished in accordance with instructions pertaining to AF Form 3000, "Material Approval Submittal". Contractor is to submit all shop drawings and material submittals for this contract within ten (10) calendar days of issue of the Notice to Proceed, or as directed by the Contracting Officer, to the Contracting Officer Representative. All submittals shall consist of one completed AF Form 3000 and four copies of material specifications and Material Safety Data Sheets MSDS".

e. Contractor is to submit shop drawing in four copies to the Contracting Officer Representative. Two copies will be returned to the Contractor indicating approval or disapproval and the date of such action. The Contractor will not proceed with work that is detailed on shop drawings until the drawings are approved.

f. The contractor shall provide all safety equipment and instructions for use by his/her employees, and ensure that a copy is provided to the Contracting Officer Representative prior to commencing work.

g. Material Safety Data Sheets – A copy shall be submitted with the AF Form 3000 Material Approval Submittal form and the Contractor shall have a copy on display at the job site for all materials brought to and or stored at the job trailer, site office or at the site storage location. The Contractor shall ensure that copies have been provided to the Contracting Officer Representative prior to transporting any materials on to the Base.

h. All construction materials and chemical compounds shall be stored in the original container or properly marked containers and approved storage containers supplied by the Contractor. All hazardous or flammable compounds shall be stored in approved lockable storage boxes that shall be locked when not in the Contractors' or his employee's direct supervision. All surplus materials and or compounds shall be removed from the Base when work on the project is complete.

i. Contractor must coordinate with the fire department leadership to schedule which bays will need to be open when installing the exhaust ventilation system. Fire trucks can be parked outside to create a clear and safe workspace.

j. Contractor will be required to provide any lifts or scaffolding that may be required for this project.

k. The installed exhaust capture system must follow all applicable guidelines in Chapter 10 of NFPA 1500.

7. SECURITY:

7.1 CONTRACTOR shall comply with all applicable installation/facility access and local security policies and procedures, which may be obtained from the COR. CONTRACTOR shall also provide all information required for background checks to meet installation access requirements to be accomplished by the local installation's Security Forces, Director of Emergency Services or local Security Office. CONTRACTOR shall ensure compliance with all personal identity verification requirements as directed by DoD, HAF and/or local policy. Should the Force Protection Condition (FPCON) change, the Government may require changes in contractor security matters or processes.

7.2 CONTRACTOR and all associated subcontractor employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personal identity verification requirements (FAR clause 52.204-9, Personal Identity Verification of Contractor Personnel) as directed by DOD, HQDA and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

7.3 CONTRACTOR personnel shall comply with McLaughlin Air National Guard Base CONTRACTOR Escort and Security policies per this SOW. Violations of these policies may

result in termination of the contract. Compliance with security requirements shall not be a basis for failing to complete work in the required PoP.

8. GOVERNMENT FURNISHED EQUIPMENT / PROPERTY:

8.1 The GOVERNMENT shall provide basic/minimal documents describing the work required in this SOW.

8.2 The GOVERNMENT shall provide the CONTRACTOR access to the site to include all areas of work described in this SOW.

8.3 The GOVERNMENT shall provide no other equipment, services, or property.

8.4 CONTRACTOR shall ensure all Government Provided Equipment in work area remain protected, operational, and dust free throughout the project.

9. PERIOD OF PERFORMANCE:

9.1 **NO MATERIAL SHALL BE ORDERED AND NO WORK SHALL BE PERFORMED PRIOR TO ISSUANCE OF NTP BY THE KO.**

9.2 CONTRACTOR shall have a maximum of 14 calendar days from the initial Notice to Proceed (NTP) to complete the project including any design and construction. Any changes or extensions to this time period need prior approval from the CONTRACTING OFFICER.

9.3 CONTRACTOR shall have access to the site from 7:30 am - 4:00 pm Monday through Friday. CONTRACTOR will not have access to the site on Weekends, Off Mondays and Government Holidays unless approved by COR prior.

10. COMPLETION AND CLOSEOUT DOCUMENTS

10.1 The COR shall certify performance and final completion of this contract.

10.2 The CONTRACTOR shall schedule a Pre-Final Inspection with KO and COR at least 3 days prior to end of PoP. Any Punch List items will be identified and recorded at this time. CONTRACTOR shall have 10 days to address these items.

10.4 CONTRACTOR shall schedule a Final Inspection with KO and COR upon completion of all Punch List and within 10 days of the Pre-Final Inspection. This inspection will confirm that all Punch List items have been corrected. Upon completion of the Final Inspection the GOVERNMENT shall take over ownership of the project.

10.5 CONTRACTOR shall submit Release of Claims to COR within 10 days of project completion.

10.6 CONTRACTOR shall submit any Red Line Drawings to COR within 10 days of project completion.

10.7 CONTRACTOR shall recover all base passes/badges upon job completion and return to COR within 5 days after project completion.