

Schedule of Items

USFS Southern Region
Francis Marion and Sumter National Forests
Buck Hall Recreation Area Renovations

AQ: ACTUAL QUANTITY, DQ: DESIGNED QUANTITY, LSQ: LUMP SUM QUANTITY

BASE BID

Item No.	Description	Method of Measure	Unit	Quantity	Unit Price	TOTAL
1.00	General Conditions					
1.01	Mobilization/Demobilization	LSQ	LS	1		
1.02	Supervision and Management	DQ	MOS	18		
1.03	Site Office	DQ	MOS	18		
1.04	Bonds and Insurance	LSQ	LS	1		
2.00	Reach 1 - Rock Revetment					
2.01	Partial Bulkhead Demolition	DQ	LF	1,350		
2.02	Rock Revetment Construction	AQ	LF	1,350		
3.00	Reach 2 - Boat Launch Improvements and Floating Dock Repairs					
3.01	Concrete Repair	LSQ	LS	1		
3.02	Pile Replacement	LSQ	EA	8		
3.03	Floating Dock Repair	LSQ	LS	1		
4.00	Reach 3 - Bulkhead					
4.01	Partial Bulkhead Demolition	DQ	LF	155		
4.02	Bulkhead Construction	DQ	LF	155		
5.00	Boat Launch Circulation and Parking Improvements					
5.01	Demolition	LSQ	LS	1		
5.02	Asphalt Pavement Heavy	AQ	SY	5,500		
5.03	Striping	LSQ	LS	1		
5.04	Wheel Stops	AQ	EA	27		
5.05	Dumpster Pad and Dumpster	LSQ	LS	1		
5.06	Information Kiosk	LSQ	EA	1		
6.00	Storm Drainage					
6.01	12" RCP	AQ	LF	270		
6.02	12" HDPE (PERF.)	AQ	LF	704		
6.03	12" HDPE	AQ	LF	41		
6.04	15" RCP	AQ	LF	153		
6.05	18" RCP	AQ	LF	34		
6.06	6" HDPE	AQ	LF	12		
6.07	Flared End Section	AQ	EA	4		
6.08	Wier Structure	AQ	EA	15		
6.09	Sediment Basin Construction	AQ	SY	6,170		
7.00	Campground Loop A Improvements					
7.01	Selective Tree Clearing	AQ	EA	65		

7.02	Grading	DQ	AC	8		
7.03	Asphalt Demolition	DQ	SY	7,810		
7.04	Existing RV Site Demolition	DQ	EA	15		
7.05	Asphalt Pavement Light	AQ	SY	8,390		
7.06	Striping	LSQ	LS	1		
7.07	Seeding	AQ	SY	13,890		
7.08	RV Sites	AQ	EA	18		
7.09	Primitive Sites	AQ	EA	7		
7.10	Site Furnishings (picnic table)	AQ	EA	25		
7.11	Site Furnishings (fire ring)	AQ	EA	25		
7.12	Conc. Sidewalk	AQ	SY	1,585		
7.13	Hose bibb	AQ	EA	21		
7.14	RV Electrical Pedestals	AQ	EA	18		
7.15	Host Site Sewer Connection (CO)	DQ	EA	1		
7.16	Information Kiosk by Host Site	LSQ	LS	1		
8.00	Water System Improvement					
8.01	Well	DQ	EA	2		
8.02	Pump	DQ	EA	2		
8.03	2" Waterline	AQ	LF	3,000		
8.04	1" Waterline	AQ	LF	1,080		
8.05	3/4" Waterline	AQ	LF	1,850		
9.00	Wastewater System					
9.01	Lift Station	LSQ	LS	1		
9.02	Septic Tanks	LSQ	LS	1		
9.03	Distribution Boxes	LSQ	LS	1		
9.04	Septic Field	LSQ	LS	1		
9.05	2" Force Main	AQ	LF	3,304		
9.06	4" PVC	AQ	LF	149		
9.07	6" PVC	AQ	LF	1,826		
10.00	Electrical Utilities Replacement					
10.01	Lump Sum	LSQ	LS	1		
11.00	Fill and Dump Station					
11.01	Heavy Duty Asphalt	AQ	SY	1,400		
11.02	Dump Station	DQ	EA	2		
11.03	Hose Bibb	AQ	EA	4		
11.04	Wheel Stops	AQ	EA	12		
11.05	Signage	LSQ	LS	1		
11.06	Dumpster Pad and Dumpster	LSQ	LS	1		
12.00	Signage					
12.01	Lump Sum	LSQ	LS	1		
13.00	Landscape					
13.01	Nyssa sylvatica 'Wildfire'	AQ	EA	3		
13.02	Pinus palustris	AQ	EA	3		
13.03	Quercus bicolor 'JFS-KW12'	AQ	EA	5		

13.04	Quercus virginiana	AQ	EA	4		
13.05	Sabal palmetto	AQ	EA	6		
13.06	Serenoa repens	AQ	EA	26		
13.07	Native seed mix	DQ	SY	5,030		
14.00	Erosion Control					
14.01	Silt fence	AQ	LF	9,700		
14.02	Tree protection fencing	AQ	LF	8,650		
14.03	Construction entrance	AQ	EA	1		
14.04	Temporary seeding	AQ	SY	37,920		
14.05	Permanent seeding	AQ	SY	37,920		
14.06	Inlet protection	AQ	EA	11		
14.07	Sediment tubes	AQ	EA	17		
14.08	Outlet stabilization structure	AQ	EA	3		
14.09	Concrete waste management	AQ	EA	1		
14.10	Turbidity curtain	AQ	LF	1,900		
15.00	Building 200 (Loop A Well House)					
15.01	Lump Sum	LSQ	LS	1		
16.00	Building 300 (Loop A Bath House)					
16.01	Lump Sum	LSQ	LS	1		
17.00	Building 700 (Dump Station Well House)					
17.01	Lump Sum	LSQ	LS	1		
						TOTAL BASE BID
OPTIONAL BID ITEMS						
18.00	Reach 4 - Rock Revetment					
18.01	Partial Bulkhead Demolition	DQ	LF	200		
18.02	Erosion Control	AQ	LF	200		
18.03	Rock Revetment Construction	AQ	LF	200		
19.00	Fishing Pier Improvements					
19.01	Selective Demolition	LSQ	LS	1		
19.02	Prepare Existing Piles & Install Vinyl Wrap @ Tidal Zone	DQ	EA	20		
19.03	Replacement Cross-Bracing	DQ	EA	6		
19.04	Placement Over-Framing, & Decking	AQ	SF	925		
19.05	Replacement Railings (Standard & ADA Fishing Rails)	AQ	LF	230		
20.00	Fishing Pier Extension					
20.01	Piles	AQ	EA	10		
20.02	Bents, Cross-Bracing, Over-Framing, and Decking	AQ	SF	460		
20.03	Railings (Standard & ADA Fishing Rails)	AQ	LF	110		
20.04	Existing Railing Modification @ Pier Extension Connection	LSQ	LS	1		
21.00	Kayak Launch					
21.01	ADA Gangway	LSQ	LS	1		
21.02	Fixed Access Pier	LSQ	LS	1		
21.03	Floating Dock	LSQ	LS	1		
21.04	Asphalt Paving	AQ	SY	560		
22.00	Day Use Area					

22.01	Selective Tree Clearing	DQ	EA	22		
22.02	Concrete Sidewalk	AQ	SY	1,000		
22.03	Striping	LSQ	LS	1		
22.04	Asphalt Paving	AQ	SY	2,500		
22.05	Wheel Stops	AQ	EA	41		
22.06	Site Furnishings (picnic tables at pavilion)	AQ	EA	6		
22.07	Site Furnishings (picnic tables along walking trail)	AQ	EA	2		
22.08	Site Furnishings (grill stations)	AQ	EA	2		
22.09	Information Kiosk	LSQ	LS	1		
23.00	Overflow Parking Lot Improvement					
23.01	Gravel Driveway	AQ	SY	3,350		
23.02	Selective Tree Clearing	AQ	EA	6		
24.00	Telecommunications System					
24.01	Lump Sum	LSQ	LS	1		
25.00	Building 100 (Day Use Toilet Building)					
25.01	Lump Sum	LSQ	LS	1		
26.00	Building 400 (Storage Building)					
26.01	Lump Sum	LSQ	LS	1		
27.00	Building 500 (Picnic Shelter)					
27.01	Lump Sum	LSQ	LS	1		
TOTAL OPTIONAL BID ITEMS						
TOTAL BASE BID + OPTION ITEMS						