

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		PAGE 1 OF 3 PAGES	
2. AMENDMENT/MODIFICATION NUMBER A00004		3. EFFECTIVE DATE 05/07/2026		4. REQUISITION/PURCHASE REQUISITION NUMBER		5. PROJECT NUMBER (If applicable) BI25NC201C06	
6. ISSUED BY Division of Eng. Services Seattle 701 Fifth Avenue, Suite 1600 Seattle WA 98104		CODE		7. ADMINISTERED BY (If other than Item 6) See block 6		CODE	
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)				(X)		9A. AMENDMENT OF SOLICITATION NUMBER	
				(X)		75H70126R00019	
				()		9B. DATED (SEE ITEM 11) 04/01/2026	
						10A. MODIFICATION OF CONTRACT/ORDER NUMBER	
CODE				FACILITY CODE		10B. DATED (SEE ITEM 13)	

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
()	
()	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
()	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
()	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

The reason for this amendment on this solicitation is to answer questions from vendors.

See Q&A below.


Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

QUESTIONS AND ANSWERS

Q1. Note 5 on E101 indicates to go to sheet E702 to see the detail for the photo sensor. Sheet E702 has not been provided. Please provide E702 or clarify.

A1. Keynote 5 on E101 references the incorrect sheet. This detail was moved and the reference should be to sheet C401. The detail is titled "SUPPLEMENTAL WIND CONE – TYPE L-806." I have included a snip below. The detail is not specifically for the photo sensor control. It is intended to show the obstruction light on top of the wind cone.



SUPPLEMENTAL WIND CONE - TYPE L-806
NTS

Q2. Can you provide a structural section detail through approximately grid line 5 detailing the structural requirements to splice the new metal form pan and concrete slab / reinforcement to the existing? Can the last floor truss in the garage closest to the common wall with room 315 be left in place with a new truss added adjacent to it to? Allowing it to be used as a splice area and aid in shoring up the common wall. Per as built plans, the wall currently appears to be between two joists.

A2. The proposed solution of leaving the last truss as a splice location will have to be reviewed in construction based on the conditions of the existing floor trusses. If the truss is in poor condition, additional shoring will be required. A detail can be provided once the final configuration is determined by the contractor.

Solicitation: 75H70126R00019

Amendment 00004

Q3. Can you provide a cut / demo line for the existing garage slab preferably within the garage limits to reduce the amount of work required in adjacent areas to allow required beam, joist and decking replacement?

A3. The entire garage slab is required to be removed up to Gridline N, as the main beam on gridline 5 is being replaced